This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

UC-NRLF
$B 72 219

UNITED STATES COAST PILOT

ATLANTIC COAST

SECTION A

ST. CROIX RIVER TO CAPE COD

GIFT OF

SIGILLVM · VNIVERSITATIS · CALIFORNIENSIS
MDCCCLXVIII
LVX
FIAT
EX LIBRIS

Digitized by Google

Digitized by Google

Digitized by Google

Serial No. 99

DEPARTMENT OF COMMERCE
U. S. COAST AND GEODETIC SURVEY
E. LESTER JONES, SUPERINTENDENT

UNITED STATES COAST PILOT

ATLANTIC COAST

SECTION A

ST. CROIX RIVER TO CAPE COD

UNIVERSITY OF CALIFORNIA

PRICE, 50 CENTS

WASHINGTON
GOVERNMENT PRINTING OFFICE
1918

Digitized by Google

VK721
A6
Sect.A
1918

Gift

Digitized by Google

M. N. W.

CONTENTS.

	Page.
Introductory	5
Note	6
Index map	Facing 7
Navigational aids and the use of charts	7
Use of sounding tubes	17
General information, St. Croix River to Cape Cod	22
Largest dry docks and marine railways	28
Hours of operation of fog signals	29
Radio service	30
United States Coast Guard stations	31
Variation of the compass	33
Tides	33
Inland waterways	35
Gulf of Maine	37
Currents, Gulf of Maine	39
Approaching or standing along the coast of Maine eastward of Portland	41
Approaching or standing along the coast between Portland and Cape Cod	43
Directions, Coast of Maine, offshore	45
Directions, Portland to Boston and Cape Cod	45
Directions, Inside passages, West Quoddy Head to Portland	47
St. Croix River and approaches	54
Currents, St. Croix River and approaches	59
Directions, Eastport Harbor and St. Croix River	61
Coast from West Quoddy Head to Machias Bay	62
Machias Bay and River	64
Englishman and Chandler Bays	68
Chandler Bay to Pleasant Bay	71
Pleasant, Narraguagus, and Pigeon Hill Bays	75
Coast from Petit Manan to Frenchman Bay	82
Frenchman Bay	87
Winter Harbor	89
East side, Winter Harbor to Sullivan Harbor	90
Sullivan Harbor	92
Sullivan Harbor to Mount Desert Narrows	93
Bar Harbor	95
Bar Harbor to South West Harbor	96
South West Harbor and approaches	96
Islands off Blue Hill Bay	100
Blue Hill Bay	103
Blue Hill Bay, east side	103
Blue Hill Bay, west side	105
Blue Hill Harbor	108
Union River Bay	109
Directions, Blue Hill Bay	110
Jerico Bay	112
Eggemoggin Reach	113
Deer Island Thoroughfare	117
Merchants Row	119
Fox Islands Thoroughfare	120
Penobscot Bay	122
Islands and rocks off Penobscot Bay	123
East Penobscot Bay	126
Directions, East Penobscot Bay	129
Bagaduce River and Castine Harbor	131
Vinal Haven and North Haven Islands	132
Directions, Carvers Harbor	134
Long Island (Islesboro)	136

386029

Digitized by Google

	Page.
Penobscot Bay—Continued.	
Two Bush and Muscle Ridge Channels	139
Rockland Harbor	141
West Penobscot Bay, Rockland to Belfast	142
Belfast Bay and River	145
Searsport and Stockton Harbors	145
Directions, West Penobscot Bay	147
Penobscot River	149
Directions, Penobscot River	151
Coast from Muscle Ridge Channel to Port Clyde	152
Monhegan Island	154
St. George River and Thomaston Harbor	155
Muscongus Bay	158
Johns Bay	164
Damariscotta River	165
Boothbay Harbor and Linekin Bay	168
Inside passage from Boothbay Harbor to Bath	172
Sheepscot River	175
Kennebec River	180
Casco Bay, eastern part	189
Casco Bay, western part	194
Directions, Casco Bay	198
Portland Harbor	199
Coast from Portland to Portsmouth	205
Portsmouth Harbor	212
Isles of Shoals	216
Coast from Portsmouth to Newburyport	217
Merrimack River and Newburyport Harbor	218
Merrimack River to Cape Ann	221
Cape Ann	222
Gloucester Harbor	226
Gloucester Harbor to Salem Harbor	229
Salem, Beverly, and Marblehead Harbors	231
Coast from Marblehead to Boston	239
Boston Harbor	241
Outer Harbor and channels	242
Boston Inner Harbor	245
General information	249
Bridge regulations	254
Currents, Boston Harbor	257
General remarks in approaching Boston Harbor	258
Directions, Boston Harbor	259
Dorchester Bay	261
Quincy Bay	263
Hingham Bay	263
Coast from Boston to Plymouth	266
Plymouth Harbor	269
Cape Cod Bay	273
Provincetown Harbor	277
Cape Cod Canal	281
Appendix:	
Coast Pilots, sailing directions (Philippine Islands), and suboffices of the Coast and Geodetic Survey	285
Coast Pilots	285
Sailing Directions, Philippine Islands	285
Suboffices	285
Meteorological Tables	286
Index	289

Digitized by Google

INTRODUCTORY.

DEPARTMENT OF COMMERCE,
U. S. COAST AND GEODETIC SURVEY,
Washington, D. C., August 23, 1918.

This publication covers the coast from St. Croix River to Race Point, Cape Cod, including Cape Cod Bay. It is based mainly upon the work of the United States Coast and Geodetic Survey, including the results of a special examination in 1917.

This volume covers all of the territory formerly included in Atlantic Coast Pilot, Part I–II, St. Croix River to Cape Ann; and a part of the territory formerly included in Atlantic Coast Pilot, Part III, Cape Ann to Point Judith. Three editions of each were published. The present edition has been prepared by L. A. Potter, junior hydrographic and geodetic engineer, under the direction of Herbert C. Graves, Chief of Division of Hydrography and Topography, Coast and Geodetic Survey.

Great courtesy has been shown by the United States Engineers, the Lighthouse Service, and local authorities in furnishing information for use in this publication.

The aids to navigation are corrected to August 23, 1918.

Navigators are requested to notify the Superintendent of the Coast and Geodetic Survey of any errors or omissions they may find in this publication, or of additional matter which they think should be inserted for the information of mariners.

E. LESTER JONES,
Superintendent.

Digitized by Google

NOTE.

The courses and bearings given in degrees are *true*, reading clockwise from 0° at north to 360°, and are followed by the equivalent *magnetic* value in points in parentheses. General directions, such as northeastward, west-southwestward, etc., are magnetic.

Distances are in *nautical miles*, and may be converted approximately to statute miles by adding 15 per cent to the distances given.

Currents are expressed in knots, which are nautical miles per hour.

Except where otherwise stated, all depths are at *mean low water*.

The chart numbers mentioned in the descriptions are the largest scale charts covering the locality. For the numbers of smaller scale charts covering the same locality, see the index map facing page 7.

Supplements and other corrections for this volume are issued from time to time, and will be furnished free of charge on application to the Coast and Geodetic Survey, Washington, D. C., provided the volume itself has not been superseded by a subsequent edition.

For the period of the war, mariners are warned that certain aids to navigation may be removed or discontinued without notice. Special regulations are also prescribed, limiting or forbidding anchorage, temporarily closing certain channels and ports, and establishing rules for entering others. The information contained in this volume is for normal conditions and does not take into account these special regulations.

The area covered by this volume is almost entirely a region of ledges and bowlders. In areas of broken ground, not examined by means of a wire drag, there is no certainty that the least depths have been found and charted. See a discussion of the "character of the bottom" and "wire-drag surveys" on page 22.

Digitized by Google

Digitized by Google



Digitized by Google

UNIV. OF CALIFORNIA

UNITED STATES COAST PILOT.

ATLANTIC COAST—SECTION A—ST. CROIX RIVER TO CAPE COD.

NAVIGATIONAL AIDS AND THE USE OF CHARTS.

The Coast and Geodetic Survey is charged with the survey of the coasts, harbors, and tidal estuaries of the United States and its insular possessions and issues the following publications relating to these waters as guides to navigation: Charts, Coast Pilots, Tide Tables, a catalogue of these publications, and Notice to Mariners, the last named published weekly by the Bureau of Lighthouses and Coast and Geodetic Survey.

CHARTS bear three dates, which should be understood by persons using them: (1) The date (month and year) of the edition, **printed** on the late charts below the border in a central position, and on the older ones on the face of the chart; (2) the date of the latest correction to the chart plate, **printed** in the lower left-hand corner below the border; (3) the **date of issue, stamped** below the border and just to the left of the subtitle.

Charts show all necessary corrections as to lights, beacons, buoys, and dangers, which have been received to the **date of issue**, being hand corrected since the latest date printed in the lower left-hand corner. All small but important corrections occurring subsequent to the **date of issue** of the chart are published in Notice to Mariners, and should be applied by hand to the chart immediately after the receipt of the notices.

The date of the edition of the chart remains unchanged until an extensive correction is made on the plate from which the chart is printed. The date is then changed and the issue is known as a new edition.

When a correction, not of sufficient importance to require a new edition, is made to a chart plate, the year, month, and day are noted in the lower left-hand corner.

All the notes on a chart should be read carefully, as in some cases they relate to the aids to navigation or to dangers that can not be clearly charted.

The charts are various in character, according to the objects which they are designed to subserve. The most important distinctions are the following:

1. Sailing charts, mostly on a scale of approximately $\frac{1}{1200000}$, which exhibit the approaches to a large extent of coast, give the

Digitized by Google

offshore soundings and enable the navigator to identify his position as he approaches from the open sea.

2. General charts of the coast, on scales of $\frac{1}{400000}$ and $\frac{1}{200000}$, intended especially for coastwise navigation.

3. Coast charts, on a scale of $\frac{1}{80000}$, by means of which the navigator is enabled to avail himself of the channels for entering the larger bays and harbors.

4. Harbor charts, on larger scales, intended to meet the needs of local navigation.

COAST PILOTS, relating to the surveyed waters of the United States, Porto Rico, and Alaska, and Sailing Directions of the Philippine Islands, contain full nautical descriptions of the coast, harbors, dangers, and directions for coasting and entering harbors. Similar information relating to Hawaii is published in Coast Pilot Notes.

Coast Pilots are corrected for important imformation received to the date of issue, which is given on the correction sheets accompanying the volume. From time to time, as the material accumulates, supplements are issued containing the more important corrections since the publication of the volume. The supplements are printed on one side of the paper only, so that they may be cut and pasted in the appropriate places in the volume. Supplements and other corrections for any volume can be furnished free of charge on application to the Coast and Geodetic Survey, Washington, D. C., provided the volume itself has not been superseded by a subsequent edition.

TIDE TABLES.—The Coast and Geodetic Survey Tide Tables are issued annually in advance of the year for which they are made, and contain the predicted time and height of the tides for each day in the year at the principal ports of the world, including the United States and its possessions. A table of tidal differences is given, by means of which the tides at more than 3,000 intermediate ports may be obtained. Separate reprints from the general Tide Tables are issued for the Atlantic and Pacific coasts of the United States and its dependencies.

AGENCIES for the sale of the Charts, Coast Pilots, and Tide Tables of the Coast and Geodetic Survey are established in many ports of the United States and in some foreign ports. They can also be purchased in the office of the Coast and Geodetic Survey, Washington, D. C., or any of the suboffices. If ordered by mail, prepayment is obligatory. Remittances should be made by postal money order or express order, payable to the "Coast and Geodetic Survey." Postage stamps, checks, and drafts can not be accepted. The sending of money in an unregistered letter is unsafe. Only catalogue numbers of charts need be mentioned. The catalogue of charts and other publications of the Survey can be obtained free of charge on application at any of the sale agencies or to the Coast and Geodetic Survey Office, Washington, D. C.

OTHER PUBLICATIONS.—Lists of Lights, Buoys, and other Daymarks of the United States, its insular possessions, and the Great Lakes, are published by the Bureau of Lighthouses. Notice to Mariners, relating to the same waters, are published weekly by the Bureau of Lighthouses and Coast and Geodetic Survey. These publications can be obtained free of charge on application to the Division of Publications, Department of Commerce, Washington, D. C.

Digitized by Google

USE OF CHARTS.

ACCURACY OF CHART.—The value of a chart depends upon the character and accuracy of the survey on which it is based, and the larger the scale of the chart the more important do these become. In these respects the source from which the information has been compiled is a good guide.

This applies particularly to the charts of the Alaska Peninsula, Aleutian Islands, Arctic Ocean, and part of Bering Sea and the Philippine Islands. The early Russian and Spanish surveys were not made with great accuracy, and until they are replaced by later surveys these charts must be used with caution.

With respect to these regions the fullness or scantiness of the soundings is another method of estimating the completeness of a chart. When the soundings are sparse or unevenly distributed it may be taken for granted that the survey was not in great detail.

A wide berth should therefore be given to every rocky shore or patch, and this rule should invariably be followed, viz, that instead of considering a coast to be clear unless it is shown to be foul, the contrary should be assumed.

With respect to a well-surveyed coast only a fractional part of the soundings obtained are shown on the chart, a sufficient number being selected to clearly indicate the contour of the bottom. When the bottom is uneven the soundings will be found grouped closely together, and when the slopes are gradual fewer soundings are given. Each sounding represents an actual measure of depth and location at the time the survey was made.

Shores and shoals where sand and mud prevail, and especially bar harbors and the entrances of bays and rivers exposed to strong tidal currents and a heavy sea, are subject to continual change of a greater or less extent, and important ones may have taken place since the date of the last survey. In localities which are noted for frequent and radical changes, such as the entrance to a number of estuaries on the Atlantic, Gulf, and Pacific coasts, notes are printed on the charts calling attention to the fact.

It should also be remembered that in coral regions and where rocks abound it is always possible that a survey with lead and line, however detailed, may have failed to find every small obstruction. For these reasons, when navigating such waters the customary sailing lines and channels should be followed, and those areas avoided where the irregular and sudden changes in depth indicate conditions which are associated with pinnacle rocks or coral heads.

DREDGED CHANNELS.—These are generally shown on the chart by two broken lines to represent the side limits of the improvement. Before completion of the project the depth given is that shown by the latest survey received from the engineer in charge. After completion the depth given is the one proposed to be maintained by redredging when necessary.

The actual depth of a completed channel may be greater than the charted depth shortly after dredging, and less when shoaling occurs as a result of storms or other causes. These changes are of too frequent occurrence and uncertain duration to chart. Therefore when a vessel's draft approximates the charted depth of a dredged channel the latest information should be obtained before entering.

Digitized by Google

DANGER CURVES.—The curves of depth will be found useful in giving greater prominence to outlying dangers. It is a good plan to trace out with a colored pencil the curve next greater than the draft of the vessel using the chart, and regard this as a "danger curve," which is not to be crossed without precaution.

Isolated soundings shoaler than surrounding depths should be avoided, as there is always the possibility that the shoalest spot may not have been found.

CAUTION IN USING SMALL-SCALE CHARTS.—It is obvious that dangers to navigation can not be shown with the same amount of detail on small-scale charts as on those of larger scale, therefore in approaching the land or dangerous banks regard should be had to the scale of the chart used. A small error in laying down a position means only yards on a large-scale chart, whereas on a small scale the same amount of displacement means large fractions of a mile.

For the same reason, bearings to near objects should be used in preference to objects farther off, although the latter may be more prominent, as a small error in bearing or in laying it down on the chart has a greater effect in misplacing the position the longer the line to be drawn.

DISTORTION OF PRINTED CHARTS.—The paper on which charts are printed has to be dampened. On drying, distortion takes place from the inequalities in the paper, which varies with the paper and the amount of the original dampening; but it is not sufficient to affect ordinary navigation. It must not, however, be expected that accurate series of angles taken to different points will always exactly agree, when carefully plotted upon the chart, especially if the lines to objects be long. The larger the chart the greater the amount of this distortion.

BUOYS.—Too much reliance should not be placed on buoys always maintaining their exact position, especially when in exposed positions; it is safer, when possible, to navigate by bearings or angles to fixed objects on shore and by the use of soundings.

Gas buoys and other unwatched lights can not be implicitly relied on; the light may be altogether extinguished, or, if intermittent, the apparatus may get out of order.

LIGHTS.—The distances given in the light lists and on the charts for the visibility of lights are computed for a height of 15 feet for the observer's eye. The table of distances of visibility due to height, published in the light list, affords a means of ascertaining the effect of a greater or less height of the eye. The glare of a powerful light is often seen far beyond the limit of visibility of the actual rays of the light, but this must not be confounded with the true range. Again, refraction may often cause a light to be seen farther than under ordinary circumstances.

When looking for a light the fact may be forgotten that from aloft the range of vision is increased. By noting a star immediately over the light a bearing may be afterwards obtained from the standard compass.

The actual power of a light should be considered when expecting to make it in thick weather. A weak light is easily obscured by haze, and no dependence can be placed on its being seen.

The power of a light can be estimated by its candlepower as given in the light lists and in some cases by noting how much its visibility

Digitized by Google

in clear weather falls short of the range due to the height at which it is placed. Thus a light standing 200 feet above the sea and recorded as visible only 10 miles in clear weather is manifestly of little brilliancy, as its height would permit it to be seen over 20 miles if of sufficient power.

Fog Signals.—Sound is conveyed in a very capricious way through the atmosphere. Apart from the wind, large areas of silence have been found in different directions and at different distances from the origin of the sound signal, even in clear weather. Therefore too much confidence should not be felt as to hearing a fog signal. The apparatus, moreover, for sounding the signal may require some time before it is in readiness to act. A fog often creeps imperceptibly toward the land and is not observed by those at a lighthouse until it is upon them, whereas a vessel may have been in it for many hours while approaching the land. In such a case no signal may be sounded. When sound travels against the wind it may be thrown upward; in such a case a man aloft might hear it when it is inaudible on deck. The conditions for hearing a signal will vary at the same station within short intervals of time; mariners must not, therefore, judge their distance from a fog signal by the force of the sound and must not assume that a signal is not sounding because they do not hear it.

Taken together, these facts should induce the utmost caution when nearing the land or danger in fog. The lead is generally the only safe guide and should be faithfully used.

Submarine Bells have an effective range of audibility greater than signals sounded in air, and a vessel equipped with receiving apparatus can determine the approximate bearing of the signal. These signals can be heard also on vessels not equipped with receiving apparatus by observers below the water line, but a bearing of the signal can not then be readily determined.

Tides.—A knowledge of the tide, or vertical rise and fall of the water, is of great and direct importance whenever the depth at low water approximates to or is less than the draft of the vessel and wherever docks are constructed so as to be entered and left near the time of high water. But under all conditions such knowledge may be of indirect use, as it often enables the mariner to estimate in advance whether at a given time and place the current will be running flood or ebb. In using the tables slack water should not be confounded with high or low tide nor a flood or ebb current with flood or ebb tide. In some localities the rise or fall may be at a stand while the current is at its maximum velocity.

The Tide Tables published by the Coast and Geodetic Survey give the predicted times and heights of high and low waters for most of the principal ports of the world and tidal differences and constants for obtaining the tides at all important ports.

Plane of Reference for Soundings on Charts.—For the Atlantic coast of the United States and Porto Rico the plane of reference for soundings is the mean of all low waters; for the Pacific coast of the United States and Alaska, with the exception noted below, and for the Hawaiian and Philippine Islands, it is the mean of the lower low waters. For Wrangell Strait, Alaska, it is 3 feet below mean lower low water.

Digitized by Google

For the Atlantic coast of the Canal Zone, Panama, the plane of reference for soundings is mean low water, and for the Pacific coast of the same it is low-water springs.

For foreign charts many different planes of reference are in use, but that most frequently adopted is low-water springs.

It should be remembered that whatever plane of reference is used for a chart there may be times when the tide falls below it. When the plane is mean low water or mean lower low water there will generally be as many low waters or lower low waters below those planes as above them. Also the wind may at times cause the water to fall below the plane of reference.

TIDAL CURRENTS.—In navigating coasts where the tidal range is considerable special caution is necessary. It should be remembered that there are indrafts into all bays and bights, although the general set of the current is parallel to the shore.

The turn of the tidal current offshore is seldom coincident with the time of high and low water on the shore.

At the entrance to most harbors without important tributaries or branches the current turns at or soon after the times of high and low water within. The diurnal inequality in the velocity of current will be proportionately but half as great as in the height of the tides. Hence, though the heights of the tide may be such as to cause the surface of the water to vary but little in level for 10 or 12 hours, the ebb and flow will be much more regular in occurrence.

A swift current often occurs in narrow openings between two bodies of water, because the water at a given instant may be at different levels.

Along most shores not seriously affected by bays, tidal rivers, etc., the current usualy turns soon after high and low waters.

When there is a large tidal basin with a narrow entrance, the strength of the current in the entrance may occur near the time of high and low water, and slack water at about half tide, outside.

The swiftest current in straight portions of tidal rivers is usually in the mid-channel, but in curved portions the strongest current is toward the outer edge of the curve.

Counter currents and eddies may occur near the shores of straits, especially in bights and near points.

TIDE RIPS AND SWIRLS occur in places where strong currents occur, caused by a change in the direction of the current, and especially over shoals or in places where the bottom is uneven. Such places should be avoided if exposed also to a heavy sea, especially with the wind opposing the current; when these conditions are at their worst the water is broken into heavy choppy seas from all directions, which board the vessel, and also make it difficult to keep control, owing to the baring of the propeller and rudder.

CURRENT ARROWS on charts show only the usual or mean direction of a tidal stream or current. It must not be assumed that the direction of the current will not vary from that indicated by the arrow. In the same manner the velocity of the current constantly varies with circumstances, and the rate given on the chart is a mean value, corresponding to an average range of tide. At some stations but few observations have been made.

FIXING POSITION.—The most accurate method available to the navigator of fixing a position relative to the shore is by plotting with

Digitized by Google

a protractor sextant angles between well-defined objects on the chart: this method, based on the "three-point problem" of geometry, should be in general use.

In many narrow waters, also, where the objects may yet be at some distance, as in coral harbors or narrow passages among mud banks, navigation by sextant and protractor is invaluable, as a true position can in general be obtained only by its means. Positions by bearings are too rough to depend upon, and a small error in either taking or plotting a bearing might under such circumstances put the ship ashore.

For its successful employment it is necessary, first, that the objects be well chosen, and, second, that the observer be skillful and rapid in his use of the sextant. The latter is only a matter of practice.

Near objects should be used either for bearings or angles for position in preference to distant ones, although the latter may be more prominent, as a small error in the bearing or angle or in laying it on the chart has a greater effect in misplacing the position the longer the line to be drawn.

On the other hand, distant objects should be used for direction because less affected by a small error or change of position.

The three-arm protractor consists of a graduated circle with one fixed and two movable radial arms. The zero of the graduation is at the fixed arm and by turning the movable arms each one can be set at any desired angle with reference to the fixed arm.

To plot a position, the two angles observed between the three selected objects are set on the instrument, which is then moved over the chart until the three beveled edges in case of a metal instrument, or the radial lines in the case of a transparent or celluloid instrument, pass respectively and simultaneously through the three objects. The center of the instrument will then mark the ship's position, which may be pricked on the chart or marked with a pencil point through the center hole.

The tracing-paper protractor, consisting of a graduated circle printed on tracing paper, can be used as a substitute for the brass or celluloid instrument. The paper protractor also permits the laying down for simultaneous trial of a number of angles in cases of fixing important positions. Plain tracing paper may also be used if there are any suitable means of laying off the angles.

The value of a determination depends greatly on the relative positions of the objects observed. If the position sought lies on the circle passing through the three objects it will be indeterminate, as it will plot all around the circle. An approach to this condition, which is called a revolver, must be avoided. In case of doubt select from the chart three objects nearly in a straight line, or with the middle object nearest the observer. Near objects are better than distant ones, and, in general, up to 90° the larger the angles the better, remembering always that large as well as small angles may plot on or near the circle and hence be worthless. If the objects are well situated, even very small angles will give for navigating purposes a fair position, when that obtained by bearings of the same objects would be of little value.

Accuracy requires that the two angles be simultaneous. If under way and there is but one observer, the angle that changes less rapidly

Digitized by Google

may be observed both before and after the other angle and the proper value obtained by interpolation.

A single angle and a range give in general an excellent fix, easily obtained and plotted.

THE COMPASS.—It is not intended that the use of the compass to fix the position should be given up; there are many circumstances in which it may be usefully employed, but errors more readily creep into a position so fixed. Where accuracy of position is desired, angles should invariably be used, such as the fixing of a rock or shoal, or of additions to a chart, as fresh soundings or new buildings. In such cases angles should be taken to several objects, the more the better; but five objects is a good number, as the four angles thus obtained prevent any errors.

When only two objects are visible, a sextant angle can be used to advantage with the compass bearings and a better fix obtained than by two bearings alone.

DOUBLING THE ANGLE ON THE BOW.—The method of fixing by doubling the angle on the bow is invaluable. The ordinary form of it, the so-called "bow and beam bearing," the distance from the object at the latter position being the distance run between the times of taking the two bearings, gives the maximum of accuracy, and is an excellent fix for a departure, but does not insure safety, as the object observed and any dangers off it are abeam before the position is obtained.

By taking the bearings at two points and four points on the bow, a fair position is obtained before the object is passed, the distance of the latter at the second position being, as before, equal to the distance run in the interval, allowing for current. Taking afterwards the beam bearing gives, with slight additional trouble, the distance of the object when abeam; such beam bearings and distances, with the times, should be continuously recorded as fresh departures, the importance of which will be appreciated in cases of being suddenly shut in by fog.

A graphic solution of the problem for any two bearings of the same object is frequently used. The two bearings are drawn on the chart, and the course is then drawn by means of the parallel rulers so that the distance measured from the chart between the lines is equal to the distance made good by the vessel between the times of taking the bearings.

DANGER ANGLE.—The utility of the danger angle in passing outlying rocks or dangers should not be forgotten. In employing the horizontal danger angle, however, charts compiled from early Russian and Spanish sources, referred to in a preceding paragraph, should not be used.

SOUNDINGS.—In thick weather, when near or approaching the land or danger, soundings should be taken continuously and at regular intervals, and, with the character of the bottom, systematically recorded. By marking the soundings on tracing paper, according to the scale of the chart, along a line representing the track of the ship, and then moving the paper over the chart parallel with the course until the observed soundings agree with those of the chart, the ship's position will in general be quite well determined.

SUMNER'S METHOD.—Among astronomical methods of fixing a ship's position the great utility of Sumner's method should be well

Digitized by Google

understood, and this method should be in constant use. The Sumner line—that is, the line drawn through the two positions obtained by working the chronometer observation for longitude with two assumed latitudes, or by drawing through the position obtained with one latitude a line at right angles to the bearing of the body as obtained from the azimuth tables—gives at times invaluable information, as the ship must be somewhere on that line, provided the chronometer is correct. If directed toward the coast, it marks the bearing of a definite point; if parallel with the coast, the distance of the latter is shown. Thus the direction of the line may often be usefully taken as a course. A sounding at the same time with the observation may often give an approximate position on the line. A very accurate position can be obtained by observing two or more stars at morning or evening twilight, at which time the horizon is well defined. The Sumner lines thus obtained will, if the bearings of the stars differ three points or more, give an excellent result. A star or planet at twilight and the sun afterwards or before may be combined; also two observations of the sun with sufficient interval to admit of a considerable change of bearing. In these cases one of the lines must be moved for the run of the ship. The moon is often visible during the day and in combination with the sun gives an excellent fix.

Change of Variation of the Compass.—The gradual change in the variation must not be forgotten in laying down positions by bearings on charts. The magnetic compasses placed on the charts for the purpose of facilitating plotting become in time slightly in error, and in some cases, such as with small scales, or when the lines are long, the displacement of position from neglect of this change may be of importance. The compasses are reengraved for every new edition if the error is appreciable. Means for determining the amount of this error are provided by printing the date of constructing the compass and the annual change in variation near its edge.

The change in the magnetic variation in passing along some parts of the coast of the United States is so rapid as to materially affect the course of a vessel unless given constant attention. This is particularly the case in New England and parts of Alaska, where the lines of equal magnetic variation are close together and show rapid changes in magnetic variation from place to place, as indicated by the large differences in variation given on neighboring compass roses.

Local Magnetic Disturbance.—The term "local magnetic disturbance" or "local attraction" has reference only to the effects on the compass of magnetic masses external to the ship. Observation shows that such disturbance of the compass in a ship afloat is experienced only in a few places.

Magnetic laws do not permit of the supposition that it is the visible land which causes such disturbances, because the effect of a magnetic force diminishes in such rapid proportion as the distance from it increases that it would require a local center of magnetic force of an amount absolutely unknown to affect a compass half a mile distant.

Such deflections of the compass are due to magnetic minerals in the bed of the sea under the ship, and when the water is shallow, and the force strong, the compass may be temporarily deflected when passing over such a spot, but the area of disturbance will be small, unless there are many centers near together.

Digitized by Google

The law which has hitherto been found to hold good as regards local magnetic disturbances is that north of the magnetic equator the north end of the compass needle is attracted toward any center of disturbance; south of the magnetic equator it is repelled.

It is very desirable that whenever an area of local magnetic disturbance is noted, the position should be fixed, and the facts reported as far as they can be ascertained.

USE OF OIL FOR MODIFYING THE EFFECT OF BREAKING WAVES.—Many experiences of late years have shown that the utility of oil for this purpose is undoubted and the application simple.

The following may serve for the guidance of seamen, whose attention is called to the fact that a very small quantity of oil skillfully applied may prevent much damage both to ships (especially of the smaller classes) and to boats by modifying the action of breaking seas.

The principal facts as to the use of oil are as follows:

1. On free waves, i. e., waves in deep water, the effect is greatest.

2. In a surf, or waves breaking on a bar, where a mass of liquid is in actual motion in shallow water, the effect of the oil is uncertain, as nothing can prevent the larger waves from breaking under such circumstances, but even here it is of some service.

3. The heaviest and thickest oils are most effectual. Refined kerosene is of little use; crude petroleum is serviceable when nothing else is obtainable; but all animal and vegetable oils, such as waste oil from the engines, have great effect.

4. A small quantity of oil suffices if applied in such a manner as to spread to windward.

5. It is useful in a ship or boat, either when running or lying-to, or in wearing.

6. No experiences are related of its use when hoisting a boat at sea or in a seaway, but it is highly probable that much time would be saved and injury to the boat avoided by its use on such occasions.

7. In cold water the oil, being thickened by the lower temperature and not being able to spread freely, will have its effect much reduced. This will vary with the description of oil used.

8. For a ship at sea the best method of application appears to be to hang over the side, in such a manner as to be in the water, small canvas bags, capable of holding from 1 to 2 gallons of oil, the bags being pricked with a sail needle to facilitate leakage of the oil. The oil is also frequently distributed from canvas bags or oakum inserted in the closet bowls.

The positions of these bags should vary with the circumstances. Running before the wind, they should be hung on either bow—e. g., from the cathead—and allowed to tow in the water.

With the wind on the quarter the effect seems to be less than in any other position, as the oil goes astern while the waves come up on the quarter.

Lying-to, the weather bow, and another position farther aft, seem the best places from which to hang the bags, using sufficient line to permit them to draw to windward while the ship drifts.

9. Crossing a bar with a flood tide, to pour oil overboard and allow it to float in ahead of the boat, which would follow with a bag towing astern, would appear to be the best plan. As before remarked, under these circumstances the effect can not be so much trusted.

Digitized by Google

On a bar, with the ebb tide running, it would seem to be useless to try oil for the purpose of entering.

10. For boarding a wreck, it is recommended to pour oil overboard to windward of her before going alongside. The effect in this case must greatly depend upon the set of the current and the circumstances of the depth of water.

11. For a boat riding in bad weather from a sea anchor, it is recommended to fasten the bag to an endless line rove through a block on the sea anchor, by which means the oil can be diffused well ahead of the boat and the bag readily hauled on board for refilling, if necessary.

USE OF SOUNDING TUBES.

Although of undoubted value as a navigational instrument, the sounding tube is subject to certain defects which, operating singly or in combinations, may give results so misleading as to seriously endanger the vessel whose safety is entirely dependent upon an accurate knowledge of the depths.

Efforts have been made from time to time by the Coast and Geodetic Survey to utilize tubes for surveying operations. The results obtained, however, have been so unsatisfactory that the general use of such tubes for surveying work has been discouraged.

In practical tests, carefully made by surveying parties, where up-and-down casts of the lead were taken with tubes attached to the lead, errors in the tube amounting at times to as much as 25 per cent of the actual depths have been noted. Errors of 10 to 12 per cent of the actual depth were quite common.

It is also worthy of note that in the great majority of cases the tubes gave depths greater than the true depths, which, in actual use in coastwise navigation, would usually have resulted in the conclusion that the ship was farther offshore than was really the case.

There are various types of tubes in common use which are too well known to require detailed description here. They are all based on the general principle that air is elastic and can be compressed, and that if a column of air in a tube be lowered into the water in such a way that the air can not escape, yet at the same time the pressure of the water can be transmitted to it, the amount by which the air is compressed furnishes a measure of the depth to which it was lowered.

Theoretically this principle is sound, but when we come to apply the theory to actual practice certain elements enter which result in errors in the depth determination. It is important to note that the amount of these errors depends on the depth; the greater the depth the greater the numerical value of the error.

The causes which produce these errors are as follows:

1. In order to give correct results, the bore of the tube must be exactly cylindrical; in other words, the volume of air in any one inch of length of the tube must be exactly the same as in an inch in any other part. But because of the way in which glass tubes are made, it is very difficult to accomplish this. The bore may taper slightly, or vary in other ways from a true cylinder. If tapering, the minimum diameter of bore may be at the top, middle, or bottom

Digitized by Google

of the tube as submerged. If the minimum diameter be at the top, the tube will register depths less than the actual depths of water, and if at the bottom, the registered depth will be greater than the true depth.

This defect may be detected in a suspected tube by introducing a small quantity of mercury into the tube and comparing its length at different points along the bore. For satisfactory results, the length of this column should not vary more than 5 per cent.

2. In order that even a perfect tube should give accurate results, the conditions of barometric pressure and air and water temperatures under which the sounding is being taken must be the same as those under which the scale for reading the depths was made.

In making the scale a barometric pressure of 29 inches is usually assumed as normal.

Then, if in actual use the barometer registers above normal, the air in the tube is already partly compressed, and when lowered to any given depth the amount of compression due to water pressure is correspondingly diminished. With a barometer below normal, the reverse is true, and it therefore follows that when the barometer reads above normal the tubes will register less than the true depths, whereas if the barometer reads below normal, the registered depths will be greater than the true. The amount of error introduced from this cause is about 3 per cent of the depth for each inch of barometric pressure above or below normal.

The density of the air in the tube also depends directly upon its temperature. Therefore, the difference between the temperature of the air in the tube before and after submergence will affect the accuracy of the sounding. Where the temperature of the tube in the air is greater than that of the tube in the water, the depth recorded will be greater than the actual depth, and, conversely, when the temperature of the air is lower than that of the water the depth recorded will be less than the true depth. Also, the temperature of the water may vary at different depths, so that the actual amount of this error depends on the difference between the temperatures of the tube in the air and at the bottom.

The amount of error introduced from this cause is about 1 per cent of the depth for each 3 degrees Fahrenheit difference in temperature.

3. While the tubes are usually 24 inches long, and the scales are designed for that length of tube, the manner of closing the upper end of the tube may introduce an eror. The thickness of the caps used for this purpose varies considerably in different makes of tubes, even when such caps are made of the same material. This variation in thickness results in moving the tube slightly up or down in the scale. Thus, with a thin cap the sounding read from the scale will be too deep, with a thick cap the sounding read will be less than the true depth.

Copper caps put on with sealing wax have been found to vary sufficiently to produce errors of about 5 per cent of the depth in depths of 50 to 70 fathoms. Rubber caps seem to be more nearly uniform and to give better results when new. Rubber, however, deteriorates, and when used too long there is apt to be leakage of air.

When removable caps are used care should be taken to see that they are pushed home thoroughly before sounding.

Digitized by Google

4. The integrity of the air in the tube should be carefully preserved. Even a slight leakage of air will result in showing a sounding considerably in excess of the true depth.

Vessels sometimes approach dangers coming from depths of over 100 fathoms. As they approach, they begin feeling for the bottom, sounding at infrequent intervals to pick up depths of 75 to 100 fathoms. So long as they get no bottom in such depths navigators feel secure. But a leaky tube may show no bottom at 100 fathoms when the ship is actually in much less depths, possibly resulting in disaster before the error is discovered.

Special precautions should, therefore, be taken on this point. Copper caps should be sealed in place with sealing wax, and rubber caps should be supplied with wire clamps giving a tight fit.

5. Accumulated salt on the inner surface of the tube will cause the watermark to creep up and register greater than true depths.

The type of tube exemplified by the well-known Bassnett sounder is based on the same principle as the ordinary glass tube, but is more complicated in design. It consists essentially of a metal case containing a glass tube closed at the upper end. Inside the glass tube is a metal tube through which the water enters and is trapped by a valve at the top of the metal tube.

In this device the scale is graduated directly on the glass tube, thus eliminating those errors due to thickness of cap; but, on the other hand, the possibility of errors increases directly with the number of working parts of which the sounder is made.

In using sounders of this type care should be exercised to preserve perfectly gasketed joints between the bottom of the glass tube and the metal case and to keep the outlet valve well oiled and water-tight.

Leaking valves and water remaining in the tube before a sounding is taken will give increased depths, while deficient depths may be recorded as a result of loss of water through suction at the inlet as the tube is being reeled in.

The Bassnett type, in common with all other forms of pressure tube, is subject to the above-described errors due to variations in temperature and barometric pressure.

It will be noted that wherever the amount of the various errors can be stated they are all small. Their importance lies in the fact that two or more of them, acting together, may result in considerable errors. As already stated, actual experiments show that errors of 10 to 12 per cent are not uncommon and that considerably greater errors may occur.

There are certain precautions which can be taken to eliminate or reduce these errors:

1. In purchasing tubes a type should be selected which can be used until broken or lost. The navigator can then make a study of the results obtained from each individual tube and thus gain a fair idea of its accuracy under known conditions. This necessitates some permanent means of identifying the various tubes used, which may readily be accomplished in the case of the glass tubes by means of various colored paints or threads.

2. Before undertaking the sounding necessary to make any particular landfall the vessel should be stopped for an up-and-down cast of the lead in order to test the accuracy under the prevailing conditions of the tubes which are to be used. For this purpose it is not

Digitized by Google

necessary to get bottom; simply run out 60 to 80 fathoms of wire and then see how closely the tubes register that amount. A number of tubes can be sent down at one time and it is then possible to select one or two which register most nearly correct.

It is well to keep a permanent record of the results of each tube tested. By so doing the navigator will soon obtain valuable information as to the performance of the various tubes and the degree to which they may be trusted. Such a record should, of course, take into account the various conditions affecting the result.

It will be noted that the factors which produce errors may be divided roughly into three groups:

(*a*) Inherent: Those which occur as a result of permanent defects in the tube, such as the variation of the bore from a true cylinder, variation in the thickness of the cap, etc.

(*b*) External: Those which occur as a result of the conditions under which the sounding was taken, variations of temperature or barometric pressure from the normal, etc.

(*c*) Accidental: Those which affect a single sounding, due to the failure of the tube to register properly, leakage of air, loss of water from leaky valves, errors due to the presence of salt in the tube, etc.

These accidental errors are probably the most serious of the three types, both because they are apt to be larger in amount and because it is impossible to foresee when they will occur. But, on the other hand, they occur only as a result of a few known causes, already enumerated, and therefore by the exercise of proper caution in the use of the tubes they may be to a large extent eliminated. If the ordinary glass tube is used, see that the bore is thoroughly dry and free from salt and that the cap makes a tight fit. If using a sounder, see that the tube is free from water and that the valves are tight and well oiled.

And, above all, during the course of the sounding take an occasional up-and-down cast as a check, for by that means alone can one be sure that the proper results are being obtained.

The smallest possible number of tubes should be used. It is obviously much better to use over and over again one tube which is giving good results than to use a number whose errors are uncertain. This is particularly desirable where sounders involving valves are used.

If a tube shows no bottom at 100 fathoms, examine the arming to make sure that the lead actually failed to find bottom.

Finally, beware of overconfidence. Tubes which have been working properly for a number of soundings suddenly develop errors. It is chiefly for this reason that they have been discarded for surveying operations.

Assuming that the accidental errors can be reasonably controlled, the inherent and external errors present no serious difficulty.

As already indicated, the bore of a tube (or at least of any tube which is capable of constant use) can be tested with mercury and those tubes rejected which show variations in bore greater than about 5 per cent.

Errors due to variations in the thickness of caps can be eliminated by using a scale graduated for a true length of 24 inches (the length of the glass tube) and removing the cap before the sounding is read.

Errors due to differences between air and water temperatures can be reduced to a minimum which can usually be neglected by immers-

Digitized by Google

ing the tube before using in a bucket of sea water, newly drawn, so that its temperature has not had time to change. Care should, of course, be taken to see that no water enters the tube. When this is done there may still remain an error due to the difference in temperature of the water at the surface and at the bottom. This may, if desired, be corrected by sending down a self-registering thermometer with the lead, but for the ordinary purposes of navigation this is a refinement which may be ignored.

There is no ready method available for correcting the error due to variations in the barometric pressure. The correction should be applied to the sounding recorded.

It is interesting to note that sounding tubes which give good results can readily be made from plain glass or metal tubes aboard ship—gauge glasses, for instance. One end of the tube is closed with a cork and sealing wax. A narrow strip of chart paper of uniform width, on which a line has been ruled with an indelible pencil, is inserted the entire length of the tube. The paper is held in place by bending the projecting lower end upward along the outside of the tube and securing it with a rubber band. The height to which the water rises in the tube will be indicated by the blurring of the pencil line.

If the air column in the tube is 24 inches long, the sounding may be read from any scale graduated for tubes of that length. If of a different length, a special scale must be prepared; its graduations, compared to those of the 24-inch scale, will be proportional to the comparative lengths of the two tubes.

If certain precautions are taken, these tubes will give results which compare favorably with commercial tubes. The paper should be inserted uniformly in the tube, and its upper end, or a mark from which the measurement is taken, should coincide with the top of the air column. Metal tubes have the advantage of uniform bore; but if metal tubes are used, the paper, in order to insure uniformity, should be fastened at the upper end when that end is being sealed and then stretched lightly at the bottom. The depth should always be read from the dry portion of the paper, as the wet portion is subject to considerable change in length.

Digitized by Google

ATLANTIC COAST—ST. CROIX RIVER TO CAPE COD.

GENERAL INFORMATION.

The information contained in this volume, section A of the "United States Coast Pilot, Atlantic Coast," relates to the coast and inland waters from St. Croix River, forming the boundary between Maine and New Brunswick, to Race Point, Cape Cod, including Cape Cod Bay. It embraces all of the coast of Maine and New Hampshire and part of the coast of Massachusetts.

Character of the bottom.—The entire area within the limits of this volume is a region of ledges and bowlders. The ledges rise abruptly from deep water and the bowlders ordinarily lie singly or in clusters on an otherwise flat bottom, so that the navigator can not depend on the lead to avoid them. **As a measure of safety, vessels should avoid broken ground where abrupt changes in depth are indicated by the chart to depths less than 10 or 12 fathoms; and in places dangers have been found where least depths of as much as 20 fathoms were the only indications found by the lead line survey. It is always safest, therefore, to select a sailing line from the chart which leads in the deepest water and well clear of broken ground.** There is little natural change in the shore or shoals, except in places in Cape Cod Bay, where the shores are generally sandy and sand shoals extend off from them in places. Bowlders also occur in places, however, in Cape Cod Bay.

Wire-drag surveys.—In all areas mentioned above as rocky or regions of bowlders the ordinary survey with the lead line can not be relied upon to locate all dangers. In such areas a wire-drag survey, in which a horizontal wire is suspended at a known depth below the surface and dragged across the area, is the only means of locating all dangers.

At the end of 1917 the areas examined by means of a wire drag were as follows:

Winter Harbor; the main part of Frenchman Bay from just southward of Egg Rock lighthouse to the entrance of the tributaries at the head; parts of Blue Hill and Jerico Bays; the main channels through Eggemoggin Reach, Deer Island Thoroughfare, and Merchants Row; Penobscot Bay from southward of Matinicus Island to the entrance of Penobscot River, including the main channel through Fox Islands Thoroughfare; Muscle Ridge and Two Bush Channels and the channel westward from them to Mosquito and Metinic Islands; Portland Harbor and approaches, from Fort Gorges out to the general 18-fathom curve in the approach, the eastern limit being 3 miles eastward of Halfway Rock; the main channel of Portsmouth Harbor and the broken ground off the entrance, from about 3 miles

Digitized by Google

northward of Boon Island lighthouse southwestward to about 7 miles southwestward of Isles of Shoals; and the broken ground along the coast from Cape Ann to the entrance of Cape Cod Canal, out to a distance varying from 4½ to 7 miles from the shore. The broken ground close along the shores was not usually covered with the drag. These limits are general and are given more in detail under the descriptions of the tributaries.

The coast from West Quoddy Head to Penobscot Bay is generally rocky and indented by numerous large bays and many excellent harbors. Numerous islands lie along the shore, among which are passages that are much used by vessels, usually of less than 12 feet draft, as they afford anchorage in a head wind, or in thick weather. The many bowlders, rocks, and ledges which lie along and off this coast require the closest attention of the navigator, as in many cases they rise abruptly from deep water and the lead does not generally give indication of their proximity until too late to avoid them. The navigator should also remember that the average rise of spring tide at Rockland is 11 feet, at Millbridge 13 feet, and at Eastport 21 feet, and that a vessel may sometimes pass over places at high water on which she would bring up at low water.

Between Penobscot Bay and Cape Elizabeth the coast is rocky and very much broken by numerous bays and rivers, many of which are excellent harbors. In Muscongus and Casco Bays good channels lead between the islands, affording inside passages that are much used by the smaller class of vessels passing along the coast. Great caution is necessary when standing along this stretch of the coast in thick weather, on account of the numerous dangers which in some cases lie nearly 10 miles offshore.

Between Cape Elizabeth and Portsmouth there are fewer harbors and marked indentations. The shore is more thickly settled than farther eastward, several of the beaches being popular summer resorts. The outlying dangers are well marked and fewer in number. **Southward of Portsmouth** the coast is low and generally a sandy beach, with a few outcropping ledges and outlying dangers, but the northern shore of Cape Ann is high and rocky.

Between Cape Ann and Plymouth entrance the coast is rocky, generally bold, with numerous islands, dry rocks, bowlders, and sunken ledges lying near the shore, with deep channels between. The shores of **Cape Cod Bay** are generally sandy with extensive sand shoals extending out well from the shore in many places. Bowlders also occur in places in Cape Cod Bay.

Harbors and ports.—The most important places, either commercially or as harbors of refuge are Calais; Eastport; Little River; Machias Bay; Narraguagas Bay; Winter Harbor; Bar Harbor; Southwest Harbor; Bass Harbor; Castine, Belfast, Camden, Rockport, and Rockland in Penobscot Bay; Bangor and Bucksport on Penobscot River; Tenants Harbor; Port Clyde; Boothbay; Bath and Augusta on Kennebec River; Portland; Portsmouth; Gloucester; Salem; Boston; Plymouth; and Provincetown. These and many other harbors are described under the different headings following:

Anchorages.—Between West Quoddy Head and Portland, anchorages are numerous, those most frequently used by coasting vessels

Digitized by Google

being Little River, Starboard Cove, Englishman Bay, Narraguagus Bay, Winter Harbor, Southwest Harbor, Rockland Harbor, Port Clyde, Boothbay Harbor, and Portland Harbor. Southward of Portland the only anchorages available for large vessels are in the harbors of Portsmouth, Gloucester, Salem, Boston, Plymouth, and Provincetown. There are other harbors available for small vessels and motor boats, as mentioned under the description.

Prominent features.—The coast between West Quoddy Head and Little River presents no special features; westward of Little River the shore is broken by bays and islands, and continues to be so to Whitehead. Grand Manan Island has nearly perpendicular, dark, rocky faces about 200 feet high on its western side. Pigeon Hill on the western side of Pigeon Hill Bay, near the head, is 307 feet high. Schoodic Mountain, near the south end of Schoodic Peninsula, the eastern point at entrance to Frenchman Bay, is 437 feet high. Green Mountain, the highest on Mount Desert Island, is 1,532 feet high and the most prominent landmark on this part of the coast; there are other mountains near it nearly as high. Isle au Haut is 556 feet high near its northern end and is on the eastern side of the entrance to East Penobscot Bay. The Camden Hills (Mount Megunticook, 1,320 feet) are on the western side of Penobscot Bay, above the town of Camden. Monhegan Island, lying 9¼ miles from the mainland, is 160 feet high and a mark for all vessels bound into Penobscot Bay from westward. Seguin Island lies about 2¼ miles from the mainland off the mouth of the Kennebec River; the island is about 145 feet high and a mark for vessels bound into the river or standing along the coast.

Cape Elizabeth, the southern point at the entrance to Portland Harbor, is about 90 feet high and marked by two lighthouses. Agamenticus Mountain is 728 feet high and the most prominent landmark between Portland and Cape Ann. It is about 4½ miles inland and 9 miles northeastward of Portsmouth. The Isles of Shoals, lying about 5½ miles from the coast and southeastward of Portsmouth Harbor entrance, can be seen a long distance, the large hotels being conspicuous marks. Boon Island lighthouse is about 9 miles northeastward of the Isles of Shoals and about 6½ miles offshore. Cape Ann, at its northern end, is high, but its eastern end is comparatively low. The two light towers on Thatcher Island are the most conspicuous marks seen when approaching the cape.

The land southward of Cape Ann is comparatively low, well settled, and has numerous artificial marks. The prominent objects visible in approaching Cape Cod are described on page 278.

System of buoyage.—In conformity with section 4678 of the Revised Statutes of the United States, the following order is observed in coloring and numbering buoys in United States waters, viz:

In approaching the channel, etc., from seaward, red buoys, with even numbers, will be found on the starboard side.

In approaching the channel, etc., from seaward, black buoys, with odd numbers, will be found on the port side.

Buoys painted with red and black horizontal stripes will be found on obstructions, with channel ways on either side of them, and may be left on either hand in passing in.

Digitized by Google

Buoys painted with white and black perpendicular stripes will be found in midchannel, and must be passed close-to to avoid danger.

All other distinguishing marks to buoys will be in addition to the foregoing and may be employed to mark particular spots.

Perches, with balls, cages, etc., will, when placed on buoys, be at turning points, the color and number indicating on what side they shall be passed.

Nun buoys, properly colored and numbered, are usually placed on the starboard side and can buoys on the port side of channels.

Day beacons (except such as are on the sides of channels, which will be colored like buoys) are constructed and distinguished with special reference to each locality, and particularly in regard to the background upon which they are projected.

Aids to navigation.—The lighthouses and other aids to navigation are the principal guides, and mark the approach and channels to the important ports. The buoyage accords with the system adopted in United States waters. The principal coast lights are described in the text of this volume. For a complete description of all lighted aids see the Light List, Atlantic and Gulf Coasts of the United States, published by the Lighthouse Service, which can be obtained, free of charge, from the Division of Publications, Department of Commerce, Washington, D. C.

Pilots.—Pilotage is not compulsory for ports in the State of Maine. Fishermen and others competent to take vessels into the ports of the state can usually be found along the coast. There are licensed pilots for the port of Portland. (See "Pilots" under heading Portland Harbor.)

Pilotage is not compulsory for enrolled or registered vessels of the United States in the ports of New Hampshire, and only for other vessels when a pilot offers his services.

Pilotage is compulsory for ports in Massachusetts, except coastwise steam vessels not sailing under register, vessels regularly employed in the coasting trade, fishing vessels other than whalers, and vessels of less than 7 feet draft. All other vessels are obliged to pay pilotage. (See also "Pilots," under different headings.) Pilots are always available at Gloucester, Boston, and Cape Cod Canal.

Towboats are stationed at Calais, Machiasport, Ellsworth, Stonington, Rockland, Bangor, Bath, Portland, Portsmouth, Newburyport, Gloucester, Boston, and Cape Cod Canal.

Harbor masters are appointed for the principal ports, and they have charge of the anchorage and berthing of vessels in their respective harbors. The anchorage regulations for the port of Boston are given on page 249. The laws prohibit the dumping of ashes or other materials in the channels.

Navigation laws of the United States are published by the Bureau of Navigation, Department of Commerce, at intervals of four years, the present edition being that of 1915. A supplement is issued after every session of Congress. The volume and supplements can be obtained from the Superintendent of Documents, Government Printing Office, Washington, D. C., price $1 for the volume and 5 cents each for the supplements.

Rules of the road.—International and inland "Rules to prevent collisions of vessels," lines within which the inland rules apply, and

Digitized by Google

"Regulation of motor boats" are published by the Bureau of Navigation, Department of Commerce.

Pilot rules for certain inland waters of the Atlantic and Pacific coasts and of the coast of the Gulf of Mexico are published by the Steamboat-Inspection Service in Form 804.

Copies of these pamphlets are furnished by the officers of the Steamboat-Inspection Service, and can also be had from the Division of Publications, Department of Commerce, Washington, D. C.

Quarantine.—Quarantine for all ports within the limits of this volume is enforced in accordance with the regulations of the United States Public Health Service. There are United States quarantine officers at Eastport, Portland, and Boston. Health officers of the State of New Hampshire have authority to make regulations respecting quarantine for ports in the State. At Portsmouth, the only port in New Hampshire, quarantine regulations are prescribed but have become obsolete, as no vessels subject to quarantine enter at present.

National quarantine regulations will be found at the stations of the service and at American consulates, and will be furnished to vessels upon application, either by officers of the service or by the bureau in Washington, D. C. Every vessel should be provided with the quarantine regulations.

Marine hospital.—Information as to relief furnished seamen will be found in the regulations of the United States Public Health Service, which can be consulted at all stations of the service. Such stations are located at ports of any importance, and if not in charge of a service officer, relief will be provided by collectors of customs upon application.

The following stations are in charge of a service officer:

Eastport, Me.	Boothbay Harbor, Me.
Machias, Me.	Portland (marine hospital), Me.
Bangor, Me.	Gloucester, Mass.
Rockland, Me.	Boston (marine hospital), Mass.

Bridge regulations.—Regulations for lighting bridges over navigable waters, also for lights on sheer booms, peirs, dams, and similar obstructions to navigation are prescribed by the Department of Commerce. A copy of these regulations will be sent free of charge to any shipmaster, pilot, or bridge owner on application to the Division of Publications, Department of Commerce, Washington, D. C. The lighthouse inspectors have immediate authority over lighting of structures in their respective districts and are charged with the enforcement of the regulations.

Regulations for the operation of drawbridges are prescribed by the Secretary of War, and extracts from these regulations are given in the description of the waters affected under the heading "Bridge regulations."

Fish weirs.—Regulations prescribe that fishing structures and appliances in navigable waters of the United States shall be lighted for the safety of navigation, as follows:

The lights shall be displayed between sunset and sunrise. They shall be placed at each end of the structure excepting where the inner end terminates in such situation that there is no practicable navigation between it and the high-

Digitized by Google

water line of the adjacent coast, in which case no inner light shall be displayed. The outer light shall be white and the inner light shall be red. The size, capacity, and manner of maintenance of the lights shall be such as may be specified in the War Department permit authorizing the erection of the structure or appliance.

When several structures or appliances are placed on one line with no navigable passage between them, they will be considered, for lighting purposes, as one structure.

The following special **signals for surveying vessels** of the United States employed in hydrographic surveying have been prescribed:

A surveying vessel of the United States, under way or at anchor in a fairway and employed in hydrographic surveying, may carry where they can best be seen, but in any case well above the rigging lights prescribed by law for preventing collisions, three lights in a vertical line one over the other and not less than 6 feet apart. The highest and lowest of these lights shall be green, and the middle light shall be white, and they shall be of such a character as to be visible all around the horizon at a distance of at least 2 miles. In the case of a small vessel the distance between the lights of such private code may be reduced to 3 feet if necessary.

By day such surveying vessel may carry in a vertical line, not less than 6 feet apart, where they can best be seen, three shapes of not less than 2 feet in diameter, of which the highest and lowest shall be globular in shape and green in color, and the middle one diamond in shape and white.

Lighthouse tenders when working on buoys in channels or other frequented waters may display a red flag (international signal-code letter B) and a black ball at the fore as a warning to other vessels to slow down in passing.

The wire drags, some of which are over 2 miles long, used by the Coast and Geodetic Survey in sweeping for dangers to navigation, may be crossed by vessels without danger of fouling at any point except between the towing launches and the large buoys near them, where the towline approaches the surface of the water. Steamers passing over the drag are requested to change course so as to cross it approximately at right angles, as a diagonal course may cause the propellor to foul the supporting buoys and attached wires.

Supplies.—All kinds of supplies in unlimited quantities are obtainable at Boston and Portland. Coal, gasoline, water, and ordinary ship supplies are obtainable at Eastport, Rockland, Bangor, Bath, Portsmouth, Gloucester, Salem, Beverly, and Plymouth. Coal in limited quantities, water, gasoline, and provisions are also usually obtainable at Calais, Winter Harbor, Bar Harbor, Camden, Belfast, Boothbay Harbor, Newburyport, and Rockport, Mass. Gasoline and provisions are obtainable at all of the towns and villages and on some of the off-lying islands, as mentioned under the descriptions.

Repairs.—Boston is the principal place at which extensive repairs to the hulls and machinery of large vessels can be made. There are good facilities for repairs to machinery of steamers at Bath, and to the hulls of wooden vessels and ordinary repairs to machinery at Portland. Small vessels and motor boats can be hauled out, and ordinary repairs to machinery can be made at many other places,

Digitized by Google

as mentioned under the descriptions of the towns and in the following table:

LARGEST DRY DOCKS AND MARINE RAILWAYS.

Port.	Name.	Length over blocks.	Depth on sill at high water.	Capacity.
Maine:		*Feet.*	*Feet.*	*Tons.*
Calais	Dry dock	[1] 130	10	.....
Ellsworth	Railway	[1] 130	7, 9	100
Rockland	do	[1] 126	8, 9½	600
Portland	do	.....	13, 16	1,300
Massachusetts:				
Gloucester	do	[1] 125	16	200
Manchester	Railway (for yachts)	[1] 90	9	.....
Marblehead	Railway	[1] 100	10½	75
Boston	do	260	15, 17	2,300
Charlestown (navy yard)	Dry dock	729	30. 6	.....
	do	368	25. 8	.....
East Boston	do	462	17. 6	.....
	Railway	250	12, 15	2,000
Neponset	do	120	15	.....
Quincy	do	175	15 to 17	700

[1] Length of vessel that can be hauled.

Prevailing winds.—The prevailing winds are southwesterly during the summer and northerly during the winter. At all seasons the heaviest gales are generally from northeastward or eastward.

Fogs are the dread of the navigator on this coast in summer and may occur at any season. They are liable to set in at any time, often with almost no warning. They are of frequent occurrence during June, July, and August, and the months of May and September are not free from them. Some portion of this period invariably has much thick weather, while other portions may be free from it. Fogs have been known to last three weeks, almost without intermission. At the heads of the bays and within the rivers it is often comparatively clear when thick outside. The fog of such interior waters usually "scales up" (clears) throughout the middle of the day. Winds from east to southwest, by the way of south, are those which bring in fog; westerly and northerly winds clear it away.

Under this heading scarcely any rule can be made that is not subject to frequent exceptions, and those who have the most experience in the matter are the least apt to make predictions. It is usually the case, however, that a fall of the barometer below 30 inches during a fog will be followed by the lifting of the fog. If a wisp of mist is to be seen hanging over Mount Desert or over the Camden Hills, whether otherwise clear or not, the following day is usually foggy. When calm during the ebb tide, if the fog is seen in a bank offshore, provided it remains calm, the fog will come in with the following flood.

The following table shows the average number of hours per month, from a record of about six years, that the fog signals were operated, on account of fog and snow, at the stated light stations of the United States:

Digitized by Google

HOURS OF OPERATION OF FOG SIGNALS.

	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
West Quoddy Head	76	92	63	99	135	156	321	235	176	59	22	55	1,489
St. Croix River	12	24	10	47	17	48	86	115	66	12	8	10	455
Little River	77	92	63	93	112	128	274	203	150	62	21	58	1,333
Libby Islands	105	126	85	108	133	137	288	226	181	79	41	72	1,581
Nash Island	71	89	56	89	118	95	211	199	136	61	24	47	1,196
Petit Manan	74	101	64	89	113	109	248	173	144	55	26	58	1,254
Mount Desert	101	112	64	105	136	143	257	200	158	56	29	49	1,410
Egg Rock	121	133	99	125	127	122	236	172	166	74	40	85	1,500
Blue Hill Bay	48	63	46	60	73	56	156	115	97	29	13	34	790
Saddleback Ledge	59	58	46	87	76	85	188	135	115	41	10	28	928
Matinicus Rock	115	115	110	131	165	166	302	220	192	94	29	79	1,718
Whitehead	155	149	137	173	163	144	263	203	193	109	109	122	1,920
Fort Point	33	23	22	48	51	37	116	86	75	29	19	27	566
Manana Island fog signal	76	91	78	103	104	95	163	122	122	56	38	49	1,097
Perkins Island	47	44	30	47	33	35	72	55	58	37	21	25	504
Seguin	176	148	141	142	149	138	239	198	182	93	92	131	1,829
Halfway Rock	76	80	53	78	63	53	104	94	96	48	32	52	829
Portland light vessel	57	75	49	78	56	62	88	79	99	46	37	57	783
Portland Head	73	87	56	78	63	59	122	83	98	48	40	55	862
Cape Neddick	82	83	65	79	69	60	91	69	97	59	45	65	864
Portsmouth Harbor	78	82	55	59	45	46	80	64	69	48	38	63	727
Isles of Shoals	69	66	48	65	47	43	62	60	71	45	33	41	650
Cape Ann	85	71	68	93	72	71	120	86	71	62	28	52	879
Bakers Island	100	71	85	65	65	49	100	87	67	73	30	59	851
Boston light vessel	88	74	81	77	61	65	90	76	70	66	36	65	849
The Graves	75	62	71	59	53	47	85	69	62	68	31	56	738
Boston	82	64	75	55	51	48	76	63	55	65	38	62	734
Castle Rocks fog signal	45	54	69	41	22	46	58	42	30	68	13	47	535
Plymouth (Gurnet)	62	63	66	65	62	51	66	54	43	41	25	30	628
Race Point	90	87	81	69	68	58	66	47	67	53	31	34	751
Cape Cod	92	83	91	78	94	78	96	68	77	72	34	29	892
Pollock Rip Slue light vessel	88	102	84	70	118	116	212	145	126	73	37	44	1,215
Great Round Shoal light vessel	105	109	90	92	99	124	181	111	94	70	33	50	1,158
Nantucket Shoals light vessel	50	59	63	83	141	168	184	80	71	63	11	10	893

Ice.—The extent to which the harbors of Maine are closed to navigation by ice varies greatly in different years. During some winters most of the harbors are open, while in others the only harbors available for anchorages are Quoddy Roads, Eastport, Little River, Machias Bay (above Avery Rock lighthouse), Mistake Harbor (not much used), Winter Harbor, and Boothbay Harbor. Portland Harbor generally has an open channel in winter, kept so by steamers and tugs. The mouths of the rivers are generally avoided for anchorage in winter and early spring, on account of running ice. In the bays and harbors the ice formation is mostly local; beginning at the head, in sheltered places along the shore, it extends outward. During a calm or light winds from northward the local formations rapidly increase, while strong winds break them up and force them as drift ice onto the lee shore. The tidal currents do not prevent the forma-

Digitized by Google

tion of ice or influence its movement in strong winds except in the larger rivers.

In severe winters some of the harbors south of Cape Ann are closed to navigation by ice, and there is more or less drift ice in all the harbors, in Cape Cod Bay, and on Monomoy and Nantucket Shoals. In the principal harbors steamers and tugs usually keep a channel open. See "Ice" under the different headings.

Storm-warning displays.—Storm warnings are displayed by the United States Weather Bureau on the coasts of the United States and the Great Lakes.

SMALL-CRAFT WARNING.—A red pennant indicates that moderately strong winds are expected.

STORM WARNING.—A red flag with a black center indicates that a storm of marked violence is expected.

The pennant displayed with the flag indicates the direction of the wind—white, westerly; red, easterly. The pennant above the flag indicates that the wind is expected to blow from the northerly quadrants; below, from the southerly quadrants.

BY NIGHT, a red light indicates easterly winds, and a white light below a red light, westerly winds.

HURRICANE WARNING.—Two red flags with black centers, displayed one above the other, indicate the expected approach of a tropical hurricane, or of one of those extremely severe and dangerous storms which occasionally move across the Great Lakes and northern Atlantic coast. These warnings are displayed at all stations on the Atlantic and Gulf coasts of the United States and on the following islands in the Atlantic: Jamaica, Santo Domingo, Turks Island, Bermuda, Haiti, Curacao, Porto Rico, St. Kitts, Dominica, Barbados, Trinidad, and Cuba. Neither small-craft nor hurricane warnings are displayed at night.

The following are the storm-warning display stations within the limits covered by this volume:

MAINE:
- Eastport.
- Machiasport.
- Vinal Haven.
- Bangor.
- Whitehead.
- Marshall Point lighthouse.
- Boothbay Harbor.
- Portland.

NEW HAMPSHIRE:
- Isles of Shoals.
- Portsmouth.
- Portsmouth (Wood Island).
- Portsmouth (navy yard).
- Wallis Sands.
- Rye Beach.

MASSACHUSETTS:
- Newburyport.
- Rockport.
- Gloucester.
- Marblehead.
- Marblehead (Boston Yacht Club).
- Boston (post office building).
- Charlestown (navy yard).
- South Boston (city coast guard station).
- City Point (Boston Yacht Club).
- Dorchester (Boston Yacht Club).
- Dorchester (Savin Hill Yacht Club).
- Hull.
- Hull (Boston Yacht Club).
- Sandwich.
- Wellfleet.
- Provincetown.
- Race Point.
- Cape Cod Lighthouse.

RADIO SERVICE.

The United States naval coastwise radio stations and all ships of the United States Navy equipped with radio apparatus are open for commercial business. Information concerning regulations, rates, and

Digitized by Google

the commercial work of the stations may be obtained by addressing the Director of Naval Communications, Radio, Va. Hydrographic information, weather reports, storm warnings, and time signals are sent out from the stations for the benefit of shipping.

Time signals.—In connection with the service over the land telegraph lines, time signals by radio are sent daily, Sundays, and holidays excepted, from certain United States naval coastwise radio stations at noon of the seventy-fifth meridian time on the Atlantic coast and at noon of the one hundred and twentieth meridian time on the Pacific coast. The signals begin at 11.55 and continue for 5 minutes. During this interval every tick of the clock is transmitted, except the twenty-ninth second of each minute, the last 5 seconds of each of the first 4 minutes, and finally the last 10 seconds of the last minute. The noon signal is a longer contact after this long break. Similar time signals are also sent at 10 p. m. from some of the stations.

The supervision of radio communication in the United States is controlled by the Bureau of Navigation, Department of Commerce. A list of the radio stations of the United States, including shore stations, merchant vessels, vessels of the United States Navy, Coast Guard cutters, and amateurs; and the radio laws and regulations of the United States are published by that bureau, and either publication can be obtained from the superintendent of documents, Government Printing Office, Washington, D. C., price 15 cents each. Changes or additions to the stations are published in bulletins issued monthly, price 5 cents per copy or 25 cents per year. (These bulletins have been temporarily discontinued.)

The International List of Radio Stations of the World includes the stations of the United States, excepting amateurs, and contains additional information, such as geographical location, normal range in nautical miles, radio system, and rates. Persons desiring this list should communicate direct with the International Bureau of the Telegraphic Union (Radiotelegraphic Service), Berne, Switzerland. The price is 60 cents per copy, not including postage. The rates of postage are: One copy, 24 cents; 2 copies, 36 cents; 3 copies, 48 cents.

UNITED STATES COAST GUARD STATIONS.

Coast Guard stations are maintained at the places named in the following table. The stations are manned throughout the year, and are supplied with boats, wreck guns, beach apparatus, and all other appliances for affording assistance in case of shipwreck. Instructions to enable mariners to avail themselves fully of the assistance thus afforded will be sent free of charge upon application to the United States Coast Guard, Washington, D. C.

The Coast Guard stations are provided with the International Code of Signals. Where telephone or telegraph facilities are available, messages of passing vessels will be received and promptly forwarded.

Signals.—The following signals have been adopted by the United States Coast Guard:

Upon the discovery of a wreck by night the Coast Guard force will burn a red pyrotechnic light or a red rocket to signify "You are seen; assistance will be given as soon as possible."

Digitized by Google

A red flag waved on shore by day or a red light, red rocket, or red Roman candle displayed by night will signify "Haul away."

A white flag waved on shore by day or a white light slowly swung back and forth or a white rocket or white Roman candle fired by night will signify "Slack away."

Two flags, a white and a red, waved at the same time on shore by day, or two lights, a white and a red, slowly swung at the same time, or a blue pyrotechnic light burned by night will signify "Do not attempt to land in your own boats; it is impossible."

A man on shore beckoning by day or two torches burning near together by night will signify "This is the best place to land."

Any of these signals may be answered from the vessels as follows: In the daytime by waving a flag, a handkerchief, a hat, or even the hand; at night by firing a rocket, a blue light, or a gun, or by showing a light over the ship's gunwale for a short time and then concealing it.

Cautions.—Masters are particularly cautioned, if they should be driven ashore anywhere in the neighborhood of the stations, to remain on board until assistance arrives, and under no circumstances should they attempt to land through the surf in their own boats until the last hope of assistance from the shore has vanished. Often when comparatively smooth at sea a dangerous surf is running which is not perceptible 400 yards offshore, and the surf when viewed from a vessel never appears as dangerous as it is. Many lives have been lost unnecessarily by the crews of stranded vessels being thus deceived and attempting to land in the ship's boats.

The difficulties of rescue by operations from the shore are greatly increased in cases where the anchors are let go after entering the breakers, as is frequently done, and the chances of saving life correspondingly lessened.

Official designation.	State.	Locality.
1	Maine.....	West Quoddy Head, Carrying Place Cove.
2	.....do.....	Cross Island, Machias Bay.
4	.....do.....	Great Wass Island, off Jonesport.
5	.....do.....	Little Cranberry Island, off Mount Desert.
6	.....do.....	Whitehead, on southwest end of Whitehead Island.
7	.....do.....	Burnt Island, off mouth of St. George River.
8	.....do.....	Damiscove Island, Damiscove Harbor.
9	.....do.....	Popham Beach, on west side mouth of Kennebec River.
10	.....do.....	Cape Elizabeth, near the lights.
11	.....do.....	Biddeford Pool, Fletchers Neck.
12	New Hampshire.	Wood Island, Portsmouth Harbor.
13	.....do.....	Wallis Sands.
14	.....do.....	Appledore Island, Isles of Shoals.
15	.....do.....	Rye Beach, north end.
16	.....do.....	Hampton Beach, 1½ miles north of Great Boars Head.
19	Massachusetts...	Salisbury Beach, ⅔ mile south of State line.
20	.....do.....	North end of Plum Island, mouth of Merrimac River.
21	.....do.....	Plum Island, 2¼ miles from south end.
22	.....do.....	Rockport, ½ mile west of Straitsmouth light.
23	.....do.....	Gloucester, westerly side of Gloucester Harbor.
24	.....do.....	Nahant, on Nahant Neck.
25	.....do.....	South Boston, floating station in Dorchester Bay.

Digitized by Google

Official designation.	State.	Locality.
26	Massachusetts..	Hull Bay, 1 mile west of Point Allerton.
27	.....do.....	Minot, 2½ miles south of Minots Ledge light.
28	.....do.....	Fourth Cliff, south end.
29	.....do.....	Brant Rock, on Green Harbor Point.
30	.....do.....	Gurnet, 4½ miles northeast of Plymouth.
31	.....do.....	Manomet Point, 6½ miles southeast of Plymouth.
32	.....do.....	Provincetown, ⅛ mile east of Wood End light.

VARIATION OF THE COMPASS.

The magnetic variation for 1921 and annual increase at points mentioned are as follows:

Locality.	Variation.	Annual increase.
	° ′	′
Eastport	20 25 W	6
Little River	20 00 W	6
Jonesport, Moosabec Reach	19 35 W	6
Petit Manan	19 00 W	6
Mount Desert Rock	18 20 W	6
Bar Harbor	18 35 W	6
Blue Hill	18 25 W	6
Stonington, Deer Island Thoroughfare	18 00 W	6
Matinicus Rock	17 30 W	6
Belfast	18 00 W	6
Monhegan	17 15 W	6
Kennebec River entrance	17 00 W	6
Cape Elizabeth	16 35 W	6
Cape Porpoise	16 20 W	6
Isles of Shoals	15 30 W	6
Gloucester	15 30 W	6
Salem	15 30 W	6
Boston light vessel	15 00 W	6
Cape Cod Canal	14 25 W	6
Cape Cod lighthouse	15 15 W	6

TIDES.

Locality.	Lunitidal interval, high water.	Mean range.	Lowest tide.
	H. *m.*	*Feet.*	*Feet.*
Eastport	11 09	18.2	−5.0
Cutler, Little River	10 56	13.9	−3.5
Starboard Island, Machias Bay	10 54	12.9	−3.5
Jonesport, Moosabec Reach	10 58	11.5	−3.5
Trafton Island, Narraguagus Bay	10 57	11.1	−4.0
Bar Harbor, Mount Desert Island	10 58	10.5	−4.0
Union River, Blue Hill Bay	11 09	10.4	−4.0
Bass Harbor, Mount Desert Island	11 02	10.2	−3.5
Naskeag Harbor, Eggemoggin Reach	11 01	10.2	−3.5
Stonington, Deer Isle	10 59	9.7	−3.5

Digitized by Google

TIDES—continued.

Locality.	Lunitidal interval, high water.	Mean range.	Lowest tide.
	H. m.	*Feet.*	*Feet.*
Iron Point, North Haven Island	11 03	9.5	−3.5
Rockland, Penobscot Bay	11 08	9.7	−4.0
Fort Point, Penobscot River	11 10	10.3	−3.5
Bangor, Penobscot River	11 20	13.1	−4.5
Port Clyde	11 00	9.3	−3.5
Boothbay Harbor	11 05	8.8	−3.5
Wiscasset, Sheepscot River	11 23	9.4	−3.5
Hunniwell Point, Kennebec River	11 11	8.3	−3.5
Bath	12 15	6.4	−3.5
Augusta	2 50	4.1	−4.5
Portland Harbor	11 11	8.9	−4.5
Wood Island Harbor	11 12	9.1	−3.5
Portsmouth Harbor light	11 21	8.7	−4.0
Newburyport, Merrimack River	11 40	7.8	−3.5
Rockport Harbor	11 13	8.8	−3.5
Gloucester Harbor	11 14	8.9	−3.5
Salem Harbor	11 16	9.0	−4.0
Boston lighthouse	11 18	9.0	−3.5
Boston Navy Yard	11 28	9.6	−4.0
Plymouth Harbor	11 21	9.6	−4.0
Sandy Neck light, Barnstable Harbor	11 27	9.4	−4.0
Provincetown Harbor	11 22	9.2	−4.0

The effect of strong winds, in combination with the regular tidal action, may at times cause the water to fall below the plane of reference of the chart, mean low water; the lowest level observed below the plane of reference is given under the column headed "Lowest tide." The water has been known also to rise about the same amounts above mean high water, due to similar causes.

Tide Tables for the Atlantic coast of the United States, including Canada and the West Indies, are published annually in advance by the United States Coast and Geodetic Survey. This volume furnishes, at the nominal cost of 10 cents, full tidal data for the Atlantic and Gulf coasts of North America.

It contains a table of full daily predictions of the times and heights of high and low waters for certain standard or principal ports along the coast; full explanations for the use of this table are given on page 8. The use of Table 2 of the Tide Tables should be known to every navigator. By means of this table the predictions given for the standard ports are extended so as to enable one to obtain complete tidal data for each day for stations only a few miles apart for the greater part of the coast, and with almost the same accuracy as though full predictions were given for all these points.

Instead of using the height differences of Table 2, however, a more accurate method is that of multiplying both high and low water heights at the standard port by the ratio of ranges for the given port to obtain the heights of the corresponding high and low waters. The ratio of ranges is given in Table 2 of the Tide Tables. The minus sign before the predicted heights in the tide tables indicates that the water is below the plane of reference, which is mean low water.

Digitized by Google

The time of high or low water at any given port in Table 2 is found by taking the time of the corresponding tide for that day from the standard port for reference and applying to it the time difference for the given port from the third column of Table 2, adding it if the sign is plus and subtracting if minus.

Caution.—In using the Tide Tables, slack water should not be confounded with high or low water. For ocean stations there is usually but little difference between the time of high or low water and the beginning of ebb or flood current; but for places in narrow channels, landlocked harbors, or on tidal rivers the time of slack current may differ by 2 or 3 hours from the time of high or low water stand, and local knowledge is required to enable one to make the proper allowance for this delay in the condition of tidal currents.

The figures given in Tables 1 and 2 of the Tide Tables are the times of high and low water, and these times are not necessarily the times of slack water.

To obtain the times of slack water, reference should be made either to figures given for various places in this volume of the Coast Pilot or to Table 4 of the Tide Tables, where the predicted times of slack water are given for Cape Cod Canal, Pollock Rip Slue, The Race, and Hell Gate. Numerous other stations are referred to these standard stations, so as to enable one to obtain the times of slack water for stations only a few miles apart for the greater part of the coast, and with almost the same accuracy as though full predictions were given for all of these points.

INLAND WATERWAYS.

The following data about the inland waterways are included for ready reference:

The inland waters extending eastward from New York include Long Island Sound, Narragansett Bay, Buzzards Bay, and Vineyard and Nantucket Sounds. From the head of Buzzards Bay there is an available passage through Cape Cod Canal (see p. 281), from which the passage to the New England coast must be made mostly outside, although there are harbors at short intervals.

Long Island Sound has harbors at short intervals on both sides from its west end to Eatons Neck, and thence on its north side to and including Fishers Island Sound. From Watch Hill boats must go outside to the bays and sounds eastward, but Point Judith Harbor of Refuge is available, and shortens the distance between harbors.

On the south coast of Long Island there is at present no inside route between Jamaica Bay and the inland waters eastward. Boats must go outside from New York to East Rockaway Inlet, and the latter requires local knowledge, because of frequent changes. But from East Rockaway Inlet boats of 5 feet draft can be taken inside through Great South Bay and 3 feet draft through Moriches and Shinnecock Bays and Shinnecock Canal to Great Peconic Bay. Masted boats are limited to a height of less than 20 feet above the water by the fixed bridges over Shinnecock Canal, and otherwise all bridges have draw openings. This route is described in Atlantic Coast Pilot, Section B, under the heading "Inland waters, south coast of Long Island."

By the Hudson River and Erie (New York State Barge) Canal, or Hudson River, Champlain Canal, and Richelieu River, boats can be

Digitized by Google

taken through to the Great Lakes or St. Lawrence River, respectively. The dimensions of vessels that can be taken through to the Great Lakes or to Lake Champlain are, draft 10 feet, length 311 feet, width 45 feet, and overhead clearance 15.5 feet above water level.

The nearest inlet connecting with the inside waters on the **coast of New Jersey** is nearly 45 miles southward of Sandy Hook, and boats must pass outside between these points, unless taking the route through the Delaware & Raritan Canal. But from the head of Barnegat Bay to Cold Spring Inlet at Cape May there is an inside route for boats of 5 feet draft by taking advantage of the tide in places.

There is an inside route, good for small boats, along the **coast of Delaware, Maryland, and Virginia,** from Rehoboth Bay southward to Cape Charles. The nearest inlet connecting with the inside waters is 64 miles southward of Cape Henlopen, but a canal connects Rehoboth Bay with Delaware Bay.

New York to Key West.—Vessels of 7 feet draft can pass inside from New York Bay to Delaware River through the Delaware & Raritan Canal. Masted vessels are limited to a height of 50 feet above canal level by a bridge without draw at New Brunswick, N. J.

Vessels of 9 feet draft can pass inside from Delaware River to Beaufort, N. C., through the Chesapeake & Delaware Canal, Chesapeake Bay, Elizabeth River, Dismal Swamp Canal or Albemarle & Chesapeake Canal, Albemarle and Pamlico Sounds, Neuse River, Adams Creeks, canal to Core Creek, and Newport River. A draft of 3 feet can be taken inside about 40 miles southward from Beaufort, N. C., to New River Inlet. All bridges have draw openings.

There is no inside passage from Beaufort, N. C., to Winyah Bay, a distance of about 160 nautical miles, and vessels must pass outside between these points. Cape Fear River, halfway between them, is available as a harbor.

Vessels of 5 feet draft can pass inside from Winyah Bay, S. C., to St. Johns River, Fla. All bridges have draw openings.

Vessels of 4 feet draft can pass inside from St. Johns River to Miami, Fla., through Pablo Creek, North, Matanzas, Halifax, and Hillsborough Rivers, Mosquito Lagoon, Indian River, South Jupiter Narrows, Hobe and Jupiter Sounds, Lake Worth, Key Biscayne Bay, and the canals connecting them. All bridges have draw openings.

From Miami to Key West, Fla., there is practically an inside route through the Hawk Channel that can be used by vessels of 10 feet draft. Cuts with a depth of 5 feet have been made in places so that vessels of 4 feet draft can go from Miami through Key Biscayne Bay, Card Sound, Barnes Sound, railroad drawbridge at Cross Key, Blackwater Sound, Tarpon Basin, Florida Bay along the north side of the keys to Long Key, and thence northwestward into the Gulf of Mexico at Cape Sable, or can continue in Florida Bay along the north side of the keys, through Big Spanish Key Channel, and thence in the Gulf of Mexico to Key West.

Boats of 1½ to 4 feet draft (depending on the rainfall) have been taken across Florida by way of some of the drainage canals, Lake Okeechobee, and Caloosahatchee River, but the route is at present impracticable.

Gulf of Mexico.—From Key West to New Orleans there are several detached stretches of inside waters, available for a draft of 4 to 5

Digitized by Google

feet, and a partially sheltered route with frequent harbors for small craft along the entire coast.

From New Orleans westward through Louisiana there is a network of inside waters affording a through route, for drafts of 3 to 5 feet, to Sabine Pass. From Sabine Pass to Galveston there is no inside route.

From Galveston southwestward to Corpus Christi there is an inside route for a draft of 4 feet by way of several extensive bays and dredged canals connecting them. Beyond Corpus Christi there is no inside route available.

Charts covering the routes along the Atlantic coast and Gulf of Mexico are published by the United States Coast and Geodetic Survey. Charts of the Erie Canal, Champlain Canal, Lake Champlain, and Great Lakes are published by the United Staes Lake Survey Office, Detroit, Mich.

A catalogue showing the charts of the route along the Atlantic and Gulf coasts can be obtained free of charge on application to the Coast and Geodetic Survey, Washington, D. C., or to any of its agents. A list of agents for the sale of charts and other publications of the Coast and Geodetic Survey is given in the catalogue and in the first notice each month of the Notice to Mariners, published weekly by the Bureau of Lighthouses and the Coast and Geodetic Survey.

The inland waters are covered in the following publications of the Coast and Geodetic Survey:

United States Coast Pilot, Section B, covering the coast and inland waters from Race Point, Cape Cod, to Sandy Hook, including Long Island Sound, and New York Harbor and tributaries.

United States Coast Pilot, Section C, covering the coast and inland waters from Sandy Hook to Cape Henry, including Delaware and Chesapeake Bays, and the inside route from New York to Norfolk.

Inside Route Pilot, coast of New Jersey.

United States Coast Pilot, Section D, covering the coast and inland waters from Cape Henry to Key West.

Inside Route Pilot, New York to Key West.

United States Coast Pilot, Section E, covering the coast and inland waters of the Gulf of Mexico.

Inside Route Pilot, Key West to New Orleans.

GULF OF MAINE.

The great indentation of the coast between the British Province of Nova Scotia on the northeast and Massachusetts on the southwest, which includes the Bay of Fundy and Massachusetts Bay as subsidiary features, has received the general designation "Gulf of Maine." It is shown on charts 1000, 1106, and 1107.

On account of its changeable weather, frequent fogs, and strong tidal currents, this locality has a bad reputation among mariners. (For offshore current observations see p. 39.)

The bottom in the Gulf of Maine is irregular, and the depths are so variable that it is quite impossible to determine a vessel's position by soundings alone, but the navigator will find a frequent use of the lead of the greatest assistance in approaching both Georges and Brown Banks from southward and eastward, the bottom slope on that side being well defined.

Digitized by Google

The principal offshore dangers are Nantucket Shoals, Georges and Cutivator Shoals, both a part of Georges Bank; and Ammen Rock, a part of Cashes Ledge.

Brown Bank, with 14 to 50 fathoms over it, is about 40 miles south of Cape Sable, between latitude 42° 17′ and 42° 54′ N and longitude 65° 12′ and 66° 28′ W. The bank is about 50 miles long in a west-northwest direction, and its greatest width is nearly 30 miles. The least depth (14 fathoms) is near the westerly end of the bank.

Georges Bank is the extensive shoal (depth less than 50 fathoms) lying off the coast of Massachusetts eastward of Nantucket Shoals. The northeastern point of this bank is in latitude 42° 05′ N and longitude 66° 05′ W; from this the eastern edge trends in a general southwesterly direction to latitude 40° 48′ N and longitude 67° 00′ W; the edge of the bank then takes a general westerly direction and joins the 50-fathom curve southward of Nantucket Shoals. The greatest width north and south is about 80 miles.

That part of the bank where depths of less than 20 fathoms will be found, including Georges and Cultivator Shoals, is an area 30 to 40 miles wide and about 75 miles long in a west-southwesterly direction, lying approximately between latitude 40° 45′ and 42° 00′ N and longitude 67° 10′ and 68° 40′ W, and has several spots with 5 to 10 fathoms over them. Depths of less than 20 fathoms, however, extend farther southwestward. A sounding of 8 fathoms, fine gray sand and black specks, is reported in (approximately) latitude 40° 44′ N, longitude 68° 45′ W; deeper water was found immediately southward, and subsequent soundings proved that the vessel was, if anything, southward of the position given.

Georges Shoal is a dangerous shoal, with less than 10 fathoms over it, between latitude 41° 33′ and 41° 47′ N and longitude 67° 38′ and 67° 53′ W. The least-known depth within these limits is 12 feet; in heavy weather the sea breaks here in 10 fathoms, and tide rips are found near the shoalest place, which extends about 9 miles in a north and south direction.

Cultivator Shoal is about 7 miles long in a north-northeast direction, with least found depths of 3 to 8 fathoms. It lies between latitude 41° 32′ and 41° 39′ N and longitude 68° 10′ and 68° 14′ W, and is about 19 miles westward of the shoalest part of Georges Shoal.

A detached shoal, with 5¼ fathoms over it, lies in latitude 41° 11′ N, longitude 68° 26′ W; and another, with 5 fathoms over it; lies in latitude 41° 14′ N, longitude 68° 00′ W. Between these and Cultivator Shoal are several shoal spots with 8 and 10 fathoms over them.

Nantucket Shoals is the general name of the numerous different broken shoals which lie southeastward of Nantucket Island and make this one of the most dangerous parts of the coast of the United States for the navigator. These shoals extend 23 miles eastward and 39 miles southeastward from Nantucket Island, are shifting in their nature, and the depths vary from 3 and 4 feet on some to 4 and 5 fathoms on others, while sloughs with depths of 10 fathoms or more lead between those farthest offshore. The easterly edge of the shoals has depths of 4 and 4½ fathoms in places, and trends 166° true (S mag.) from latitude 41° 18′ N, longitude 69° 29′ W, to latitude 40° 57′ N, longitude 69° 22′ W. **Asia Rip**, the southeasternmost danger, has a least depth of 6 fathoms in latitude 40° 48′ N, longi-

Digitized by Google

tude 69° 22′ W. Deep-draft vessels should pass southward and eastward of Asia Rip, and eastward of the easterly edge of the shoals as defined above. For a distance of 15 miles eastward and southeastward and 17 miles southward from Nantucket Island, the shoals have depths less than 16 feet, and this area should be avoided by all vessels. The tidal currents are strong, and variable in direction, forming extensive rips and broken water over the shoals.

Nantucket Shoals light vessel, the leading mark for vessels passing southward of Nantucket Shoals, is moored in 30 fathoms off the southern end of the shoals.

Cashes Ledge, with depths less than 30 fathoms, is about 6 miles long in a north-northeast direction. **Ammen Rock**, with 4¼ fathoms over it, is near the middle of the ledge in latitude 42° 53′ N, longitude 68° 55′ W. There is a whistling buoy on the east side. The sea breaks over this rock in heavy weather.

Jeffreys Bank, locally known as **Monhegan Fall**, has a least found depth of 46 fathoms, and lies about 26 miles southward of Matinicus Rock lighthouses. Less depths have been reported by fishermen.

Platts Bank has a least found depth of 29 fathoms.

Banks with depths of 45 to 50 fathoms have been reported by fishermen about 10 miles northwestward, 10 miles northeastward, and 15 miles eastward of the shoalest part of Platts Bank.

Jeffreys Ledge makes northeastward from Cape Ann, and has a least found depth of 18 fathoms over it. The northeastern point of the ledge is 22 miles eastward of Boon Island lighthouse.

Stellwagen Bank lies northward of Cape Cod and off the entrance to Massachusetts Bay; the least found depth over it is from 9½ to 20 fathoms, but fishermen have reported a depth of 7 fathoms at the north end.

Grand Manan Channel.—This channel leads along the coast of Maine, between it and Grand Manan Island, and is an approach from westward to Quoddy Roads and Passamaquoddy Bay, and the most direct passage for vessels bound up the Bay of Fundy from along the coast of Maine. The channel varies in width from 5½ miles abreast Campobello Island to 10 miles abreast Southwest Head, the southwestern point of Grand Manan Island. Its western approach is marked by Machias Seal Island lighthouses, which also mark the westernmost of the rocks and ledges which lie southwestward of Grand Manan Island. With the exception of the dangers between Machias Seal Islands and Grand Manan Island, the channel is free and has a good depth of water. The tidal currents have a velocity of 2½ to 3 knots, and follow the general direction of the channel. Off West Quoddy Head the currents set in and out of the roads, forming strong rips. Sailing vessels should not approach West Quoddy Head too closely with a light wind.

CURRENTS, GULF OF MAINE.

Offshore.—The time of turning and strength of the current over the region extending westward and northward of a line from Georges Bank to Lurcher Shoal is very nearly simultaneous. The flood current sets northward, the strength of the flood over the eastern portion of this region occurring about 3 hours after the time of Boston

Digitized by Google

low water, and over the western portion about ½ hour later. The ebb current sets southward, the strength of the ebb over the eastern portion occurring about 3 hours after the time of Boston high water, and over the western portion about ½ hour later. Slack water over the eastern portion occurs about the time of high and low water at Boston, and over the western portion about ½ hour later.

Off Nova Scotia, outside the 50-fathom line, the velocity at time of strength is about 1½ knots; inside the 50-fathom line the velocity is between 1½ and 2 knots.

At the Entrance of the Bay of Fundy, 5 miles southeastward of Gannet Rock, the strength of the flood current occurs about 3 hours before high water at St. John, New Brunswick, has an average velocity of 2.7 knots, and sets 36° true (NE by E mag.). The strength of the ebb occurs 3 hours before low water at St. John, has an average velocity of 3.9 knots, and sets 228° true (WSW mag.). Slack water before the flood occurs about 35 minutes after low water at St. John, and slack water before the ebb at about the time of high water at St. John.

In the Bay of Fundy, slack water before the flood occurs about ¾ hour after low water at St. John, and slack water before the ebb about ¾ hour after high water at St. John. The velocity at strength is between 1½ and 2½ knots, the flood setting northeastward and ebb southwestward.

In Grand Manan Channel the average velocity at strength is about 2½ knots, the flood setting northeastward and ebb southwestward, approximately parallel to the channel. Slack water before the flood occurs at about the time of low water at St. John, and slack water before the ebb about ½ hour after high water at St. John.

Over Georges Bank the velocity at strength is about 2 knots.

Between Georges Bank and Brown Bank the velocity at strength is about 1½ knots, with a like velocity between Brown Bank and Cape Sable Bank.

Over Stellwagen Bank, and in the channel between it and Cape Cod, the flood current sets westward and ebb northeastward to eastward. The flood current begins about ¾ hour before the time of low water at Boston, and the ebb current begins about ¾ hour before high water. The velocity at strength is about ¾ knot.

A current diagram, showing the state of the current along a curved line extending from Nantucket Shoals light vessel to Nova Scotia is given in the tide tables, published annually by the Coast and Geodetic Survey.

Alongshore.—On the coast of Maine eastward of Portland the flood sets eastward and has greater velocity than the ebb, which sets westward. In passing from one headland to another it is always necessary to make allowance for the current setting into or out of the bays or rivers, according to the stage of the tide; such allowance frequently amounts to as much as ½ point.

Eastward of Mount Desert the currents have a greater velocity than farther west, but are more regular in their ebb and flow, conforming more exactly to the rise and fall of the tides. Along the coast between Mount Desert and Portland the effect of the westerly (ebb) set is more marked as compared with the flood than is the case farther east.

Digitized by Google

With easterly or southeasterly winds the currents have more of a tendency on shore than at other times, but they are not affected much by northerly, westerly, or southerly winds.

No systematic current observations have been made along the coast of Maine, except at Portland light vessel.

PORTLAND LIGHT VESSEL.—The tidal current is weak, being on the average less than ¼ knot at time of strength. During October, November, and December there is a southerly set of about ½ knot. Southerly winds, however, tend to reverse this set. The greatest velocity observed during October, November, and December, 1913, was 1.2 knots southerly, accompanied by a northerly wind of 30 to 35 miles an hour.

BOSTON LIGHT VESSEL.—The tidal current is small, averaging about ¼ knot at time of strength. Strength of flood occurs about 2¾ hours before high water and sets 265° true (W ⅞ N mag.). Strength of ebb occurs about 2¾ hours before low water and sets 85° true (E ⅞ S mag.). Because of the weak character of the tidal currents the winds greatly influence the direction of the current. The greatest velocity observed during three months in autumn was less than 1 knot.

The currents along the eastern side of Cape Cod and across Monomoy and Nantucket Shoals are described in Atlantic Coast Pilot, Section B.

APPROACHING OR STANDING ALONG THE COAST OF MAINE EASTWARD OF PORTLAND.

This section of the coast is a dangerous one for navigators on account of the strong tidal currents, frequent fog, and numerous offlying dangers. For information concerning currents see page 40, and for information concerning fog see page 28 and the meteorological tables in the appendix. The lead is of little assistance to locate the position, but should be in constant use to prevent too close an approach to dangers. See a discussion of the character of the bottom on page 22.

Wrecks.—An examination of the record of wrecks occurring on the coast of Maine eastward of Portland shows that wrecks have occurred on practically all of the offlying islands and rocks between Portland and Machias Bay, most of them in thick weather, either fog or snow. Many of the wrecks could have been prevented if frequent soundings had been taken.

During thick weather great caution is necessary when approaching the coast, especially eastward of Petit Manan, where the tidal currents have considerable velocity. If one of the offshore lighthouses has not been made and the position accurately determined before the fog shuts in, it is advisable to keep well outside until it clears. East of Seguin Island, except southward and eastward of Grand Manan Island, in clear weather the land will always be made before any of the outlying dangers are encountered, and by keeping 3 miles outside of the headlands and outlying islands vessels will clear all unmarked dangers.

Coming from the vicinity of Cape Sable.—Vessels bound to Machias or ports eastward of it should make Machias Seal Island lighthouses and pass westward of them. If bound to Eastport or Calais, the route through Grand Manan Channel is preferable to passing east-

Digitized by Google

ward of Grand Manan, as in case of bad weather coming on an anchorage may be made either at Little River or in Machias Bay.

It is not advisable for a stranger to pass eastward of the Machias Seal Islands or between them and Grand Manan, where there are a number of ledges on which the sea breaks in heavy weather, including Bull Rock, an unmarked danger with 2 feet over it.

If bound to ports in Penobscot Bay, vessels should steer so as to make either Mount Desert lighthouse or Matinicus Rock lighthouses. In the former case, on a clear day, Green Mountain, the highest part of Mount Desert Island, may be sighted before the lighthouse. When steering for Matinicus Rock lighthouses, Isle au Haut, 556 feet high, on a clear day may be sighted about the same time as the rock.

Coming from the vicinity of Cape Cod or Cape Ann.—Vessels, both steamers and large tows, bound into Penobscot Bay, including those coming from Boston and Cape Cod Canal, and also those passing eastward of Cape Cod, usually make the gas and whistling buoy off Cape Ann and then shape the course for Manana Island gas, whistling, and submarine bell buoy and enter through Two Bush or Muscle Ridge Channels. In the winter and in bad weather the smaller class of vessels follow the coast, sighting the principal lighthouses, and making an anchorage on approach of bad weather. Vessels bound from Cape Cod or Cape Ann to points eastward of Penobscot Bay usually shape the course from Cape Ann to either Monhegan Island or Matinicus Rock lighthouses.

On all the banks in or near the Gulf of Maine a number of fishing vessels may be found at anchor. They are sometimes very numerous in the South Channel, on the Georges Bank, and Jeffrey Ledge. In the summer a large fleet of mackerel fishermen will often be met near the coast between Mount Desert Rock and Cape Ann.

Standing along the coast.—In clear weather, vessels stand along the coast close enough to make the lighthouses and to recognize the principal landmarks on shore. In thick weather they aim to make the fog signals or the whistling or bell buoys; these buoys are placed close enough to one another and to the fog signals to be readily followed up by vessels if not set too much off their course by the tidal currents. When running in thick weather a vessel should verify her position as often as possible by the aids, and when approaching a fog signal or buoy should proceed slowly, using the lead, and if necessary stop until the looked-for aid is found and recognized before she continues for the next aid. There are three good harbors for which a stranger standing along the coast in their vicinity can make in thick weather and enter with ordinary precaution—Machias Bay, Winter Harbor, and Boothbay Harbor.

Inside passages and thoroughfares.—The numerous islands along the stretch of coast from Mount Desert Island to Portland, Me., make it possible for vessels of limited draft to avoid a heavy sea and find convenient anchorages, for a great part of this distance, by using the thoroughfares and passages inside and among the islands. The principal and most frequented route is from South West Harbor across Cranberry Island Bar, Bass Harbor Bar, and Blue Hill Bay, through Casco Passage or York Narrows, across Jericho Bay, through Deer Island Thoroughfare or Merchants Row, across East Penobscot Bay, through Fox Islands Thoroughfare, across West Penobscot Bay, and through Fisherman Island Passage and Muscle Ridge Channel. This

Digitized by Google

is practically a continuous inside passage, good, with the exception of Deer Island Thoroughfare, for a draft of 12 feet at low water and 18 feet at ordinary high water. A continuation westward is through Davis Straits, through Fisherman Island Passage (near Boothbay), and among the islands in the western part of Casco Bay.

APPROACHING OR STANDING ALONG THE COAST BETWEEN PORTLAND AND CAPE COD.

Approaching Massachusetts Bay from sea.—The approach to the coast of Massachusetts north of Cape Cod is through the Gulf of Maine, the body of water lying westward of a line drawn from Cape Cod to Cape Sable. Between these points, and forming the southeastern limit of the gulf, lie Nantucket Shoals, Georges Bank, and Brown Bank, areas over which there is a depth of less than 50 fathoms. Nantucket Shoals and Georges Bank, on account of their many shoal spots and the strong tidal currents setting over them, are a menace to navigators approaching the coast or standing from Canadian ports to New York.

As far as the navigator is concerned Brown Bank need not be avoided; it may even assist, from soundings, to approximately locate a vessel's position.

The part of Georges Bank lying between latitude 41° 05′ N and 42° 00′ N and longitude 67° 17′ W and 68° 35′ W should be avoided; in heavy weather the sea breaks on the spots with 10 fathoms or less, and strong tide rips are encountered, the latter, however, not always indicating shoal water. For current information see page 40.

Vessels passing south of the dangerous part of Georges Bank should not shoal the water to less than 25 fathoms. Approaching this part of the bank from eastward or southward, the water shoals gradually. Approaching from westward, the depths are irregular and the water shoals abruptly in places to 20 fathoms or less. On the north side of Georges Bank, between longitude 66° 00′ W and 68° 00′ W, the 100-fathom and 50-fathom curves are but a few miles apart, and when approaching the dangerous part of the bank from northward 50 fathoms may be taken as a good depth to avoid the shoals.

The only known outlying danger in the Gulf of Maine to be avoided by vessels bound to ports in Massachusetts is **Ammen Rock**, with 4¼ fathoms, in latitude 42° 53′ N and longitude 68° 55′ W. It is a part of **Cashe Ledge**, which is about 6½ miles long in a north-northeast direction, with depths less than 30 fathoms.

Vessels from ports in northern Europe or the British Provinces and bound to ports in the United States north of Cape Cod approach the coast passing between Cape Sable and Georges Bank, between latitude 42° 00′ N and 43° 10′ N. If bound to Boston, they cross Brown Bank and shape the course for Boston light vessel. See page 258.

Vessels approaching the Gulf of Maine from southward sometimes endeavor to make the 50-fathom curve on the southern edge of Georges Bank, in latitude 40° 20′ N and longitude 69° 00′ W, then stand 0° true (N by E ¼ E mag.) on soundings of over 30 and less than 50 fathoms for about 50 miles, and then shape a 323° true (NNW mag.) course, taking care to keep in a greater depth than

Digitized by Google

20 fathoms until the course is laid to sight Cape Cod lighthouse. This lighthouse, the skeleton radio towers about 9 miles southward of it, and the Pilgrim Monument at Provincetown are the most prominent marks on Cape Cod.

The passage across Georges Bank between the easternmost of the Nantucket Shoals and the westernmost shoal spots of Georges Bank, about 30 miles wide, has been called **Great South Channel.**

VESSELS COMING FROM CAPE HATTERAS, CHESAPEAKE BAY, DELAWARE BAY, OR NEW YORK make Nantucket Shoals light vessel.

VESSELS OF LESS THAN 24 FEET DRAFT may, when coming from southward or alongshore, enter the Gulf of Maine through Vineyard and Nantucket Sounds. This route avoids Nantucket Shoals, and is the one followed by vessels in the coasting trade. Vessels of 22 feet draft or less can also enter through Cape Cod Canal (see page 281).

Directions for all of the various routes from southward to the north end of Cape Cod are given in Atlantic Coast Pilot, section B, Cape Cod to Sandy Hook.

Standing along the coast between Portland and Cape Cod.—The lighthouses and other aids to navigation are sufficiently numerous to enable a stranger to run either at night or the daytime in clear weather. There are numerous anchorages where a vessel with good ground tackle can ride out any gale (see p. 23). Of these, Provincetown Harbor is the harbor of refuge most frequently used by vessels approaching Massachusetts Bay from seaward. The navigator, when crossing the banks and when approaching the coast, should not neglect to take soundings at frequent intervals.

Wrecks.—South of Portland the wrecks have occurred most frequently on the prominent headlands or the shoals off them, viz., Cape Elizabeth, Cape Ann, and the north side of Cape Cod, with less frequent wrecks on the less prominent headlands. Numerous wrecks have also occurred on the dangers in the approaches to Boston Harbor, more frequently on the south side, from Scituate to Point Allerton. Most of the wrecks have occurred during thick weather.

Between Portland and Boston the most dangerous points for coasting vessels are the dangers off Cape Elizabeth, Boon Island, Isles of Shoals, Cape Ann, and the dangers in the entrance of Boston Harbor. Vessels must depend upon making the fog signals or the whistling and bell buoys, and when approaching them should proceed slowly, using the lead, and if necessary stop until the looked-for aid is found and recognized before continuing for the next aid. The soundings in the vicinity of Cape Ann are very irregular and can not be depended upon to locate even approximately the vessel's position.

The numerous strandings on the north end of Cape Cod, between Cape Cod lighthouse and Race Point lighthouse, have usually occurred to vessels approaching Massachusetts Bay or Cape Cod Bay from southward or eastward in thick weather. Keeping in a greater depth than 20 fathoms will insure giving the eastern side of Cape Cod a berth of 2½ miles, and if this depth is followed will lead to Peaked Hill Bar gas, whistling, and submarine bell buoys, northward of the end of the cape.

The precautions to be taken in approaching Boston Harbor from Cape Cod or Cape Ann are given on page 258.

Digitized by Google

DIRECTIONS, COAST OF MAINE, OFFSHORE.

The following are approximately the courses followed by most of the large vessels and the larger tows bound between Eastport and Portland and of too deep draft to follow the inside route. Vessels bound to points south of Cape Ann follow these courses to Matinicus Rock or Monhegan Island lighthouses and then shape the course to the gas and whistling buoy off Cape Ann. In winter or in bad weather they often follow the coast more closely between Monhegan and Cape Ann.

From a position 1¼ miles southeastward of West Quoddy Head lighthouse and ½ mile southeastward of Sail Rock whistling buoy steer 226° true (SW by W ⅞ W mag.) for 14 miles to a position 1⅜ miles southeastward of Little River lighthouse and ½ mile southeastward of Little River whistling buoy.

Then make good a 230° true (WSW ¼ W mag.) course for 18½ miles, passing 2¼ miles off Libby Islands lighthouse and to a position 2½ miles off Moose Peak lighthouse and ½ mile southward of Moose Peak whistling buoy.

Then make good a 235° true (WSW ½ W mag.) course for 71½ miles, passing 5¾ miles southward of Petit Manan lighthouse, 4¼ miles southward of Great Duck Island lighthouse, 7 miles northward of Mount Desert (Rock) lighthouse, and to Matinicus Rock whistling buoy, lying 2 miles 168° true (S ½ W mag.) from Matinicus Rock lighthouses.

From the whistling buoy a 264° true (W by N mag.) course, made good for 34 miles, will lead 3 miles southward of Monhegan Island lighthouse and to a position ½ mile southward of Bantam Rock gas and whistling buoy. From this position a 260° true (W ⅝ N mag.) course, made good for 18 miles, will lead close to Seguin Island whistling buoy and to Halfway Rock whistling buoy. See directions for Portland Harbor, page 204.

Or, from Matinicus Rock whistling buoy, a 256° true (W ¼ N mag.) course, made good for 56 miles, will lead to Portland light vessel.

DIRECTIONS, PORTLAND TO BOSTON AND CAPE COD.

Coasting vessels and the larger tows bound between Portland and Boston usually make one course between Portland light vessel and Cape Ann. Small craft and the smaller tows usually pass westward of Isles of Shoals and Boon Island, and the larger vessels often use this route in heavy westerly weather; the least depth crossed is about 5 fathoms. At night or in thick weather it is safer to pass eastward of Boon Island and Isles of Shoals.

To pass eastward of Boon Island.—From Portland light vessel a 199° true (SW by S mag.) course made good for 57 miles will lead to Cape Ann gas and whistling buoy, passing 5¼ miles eastward of Boon Island Ledge gas and whistling buoy and 7¾ miles eastward of Boon Island lighthouse.

Or, from Old Anthony gas and whistling buoy, a 195° true (SSW ⅝ W mag.) course made good for 56 miles will lead to Cape Ann gas and whistling buoy, passing 5 miles eastward of Wood Island lighthouse, 3¼ miles eastward of Boon Island Ledge gas and whistling buoy, and 5¾ miles eastward of Boon Island lighthouse.

Digitized by Google

To pass westward of Boon Island.—From Cape Elizabeth light vessel a 218° true (SW ¾ W mag.) course made good for 34 miles will lead to York Ledge whistling buoy. The course leads 5¼ miles southeastward of Goat Island lighthouse, 1¾ miles northwestward of Boon Island lighthouse, and 1 mile southeastward of York Ledge. It leads about ½ mile southeastward of a reported depth of 5 fathoms, undeveloped, 5⅜ miles north-northeastward of Boon Island lighthouse.

Or, from Old Anthony whistling buoy, make good a 217° true (SW ¾ W mag.) course for 15 miles, passing 2 miles southeastward of Wood Island lighthouse, and to Cape Porpoise whistling buoy, which lies 1¾ miles southeastward of Goat Island lighthouse. Then make good a 206° true (SW ¼ S mag.) course for 17½ miles, passing 2½ miles northwestward of Boon Island lighthouse, nearly 1 mile eastward of York Ledge, and to York Ledge whistling buoy. This course leads about 1 mile northwestward of a reported depth of 5 fathoms, undeveloped, 5⅜ miles north-northeastward of Boon Island lighthouse.

From York ledge whistling buoy steer 210° true (SW mag.) for 7 miles, passing 1 mile northwestward of Isles of Shoals, and to a position 1½ miles west-northwestward of Isles of Shoals lighthouse. Then steer 164° true (S mag.) for 21½ miles, passing close to White Island whistling buoy, 1¼ miles eastward of Dry Salvages beacon, and to Cape Ann gas and whistling buoy.

Cape Ann to Boston.—From Cape Ann gas and whistling buoy a 228° true (SW by W ⅝ W mag.) course for 23½ miles will lead to the buoys at the entrance of Broad Sound North Channel. Directions from a position 1 mile southeastward of Cape Ann lighthouses to the different entrances of Boston Harbor and into the harbor are given on page 259.

Cape Ann to Cape Cod Canal.—From Cape Ann gas and whistling buoy a 177° true (S by W mag.) course for 48 miles will lead to the perpendicularly striped gas and bell buoy off the canal. Or, from Cape Ann gas and whistling buoy a 211° true (SW ⅛ W mag.) course for 20½ miles will lead to Boston light vessel; then a 147° true (S by E ⅝ E mag.) course for 4½ miles will lead to a position ⅛ mile northeastward of buoy No. 1, which marks a 3½-fathom spot. Vessels can then follow the direction from Boston to Cape Cod Canal, given on page 283.

Cape Ann to Cape Cod.—From Cape Ann gas and whistling buoy a 147° true (S by E ⅜ E mag.) course for 39½ miles will lead to a position 3 miles northeastward to Cape Cod lighthouse. Care should be taken in approaching Cape Cod, especially in thick weather, not to be set on Peaked Hill Bar or the end of the cape.

Boston to Cape Cod.—Directions from Cape Cod to Boston are given on page 258. From Boston light vessel, a 115° true (SE ½ E mag.) course made good for 36 miles will lead close to the gas, whistling, and submarine bell buoys off Peaked Hill Bar and to a position 3 miles northeastward of Cape Cod lighthouse. The tidal currents may be expected to cause a slight westerly set on this course for the greater part of the flood and a stronger northerly and easterly set on the last of the flood and greater part of the ebb.

Digitized by Google

DIRECTIONS, INSIDE PASSAGES, WEST QUODDY HEAD TO PORTLAND.

Small craft.—Small craft of 6 feet or less draft, running along this section of the coast in the daytime, in clear weather, can find a partially protected route throughout most of the distance from West Quoddy Head to Portland. The route is fringed with numerous dangers, and extreme caution and close attention to the charts are necessary.

The most frequently used route for boats of this class leads close along the coast from West Quoddy Head to Cross Island, through Cross Island Narrows, across the mouth of Machias Bay, through Foster Channel, Brothers Passage, Moosabec Reach, and Tabbott Narrows, across Petit Manan Bar close to the perpendicularly striped buoy (navigable only with a smooth sea), through the buoyed channel northward of Schoodic Island, through Western Way, across Bass Harbor Bar, through Casco Passage, Deer Island Thoroughfare, Fox Islands Thoroughfare, Owlshead Bay, and Muscle Ridge Channel, and thence by the route used by vessels of 12 feet or less draft, described following.

Directions through Cross Island Narrows, Foster Channel, Petit Manan Bar, and Deer Island Thoroughfare are given under their descriptions. Directions through most of the other passages are given following. Strangers in small craft can follow the directions given following for vessels of 12 feet or less draft if desired.

Vessels of 12 feet or less draft.—Vessels of this draft at low water and about 18 feet draft at high water, bound along the coast of Maine, generally use the thoroughfares and passages inside and between the islands. The most frequently used route leads southward of Cross and Libby Islands, through Moosabec Reach and Tabbott Narrows, southward of Petit Manan lighthouse and Schoodic Island, across Bass Harbor Bar, through Casco Passage, Deer Island Thoroughfare or Merchants Row, Fox Islands Thoroughfare, Muscle Ridge Channel, Davis Straits, Fisherman Island Passage (near Boothbay Harbor), and between Seguin and Pond Island. Vessels of this draft can then pass southward of the islands in Casco Bay or can find a more protected route inside the islands as described in the directions following; the most frequently used route in good weather is southward of the islands in Casco Bay.

This inside route is very narrow in places and leads close to many dangers, but the principal dangers for vessels of 12 feet draft are marked, and it can be used by vessels of that draft in the daytime and with clear weather, by a close attention to the charts and the following directions. Most of the route is used by local vessels up to 18 feet draft, but strangers in vessels of over 12 feet draft seldom use it. There are anchorages at frequent intervals, as mentioned under the descriptions of the bays and thoroughfares, and vessels caught in a fog anchor until the weather clears. Pilots for the route can be obtained at most of the cities and towns along it, and strangers often take pilots.

1. West Quoddy Head to Moosabec Reach (charts 301, 303, and 304), 32 miles.—From Sail Rock whistling buoy (nearly ¾ mile southeastward of West Quoddy Head lighthouse), steer 226° true (SW by W ⅞ W mag.) for 14 miles to Little River whistling buoy (1 mile

Digitized by Google

southeastward of Little River lighthouse). Then steer 233° true (WSW ½ W mag.) for 4¾ miles, and pass about ½ mile southward of Old Man and Double Shot Islands. Then steer 245° true (W ½ S mag.) for 5 miles to a position ½ mile southward of Libby Islands lighthouse.

Then steer 272° true (WNW mag.) for 2¾ miles to a position 100 yards northward of the black bell buoy lying 300 yards northeastward of the eastern end of The Brothers (grassy). Then steer 257° true (W ⅝ N mag.) through Brothers Passage for 1⅝ miles, passing 250 yards southward of Green Island, and to a position 200 yards northward of Pulpit Rock (bare). Then steer 249° true (W mag.) for 3¼ miles to a position about ¼ mile northward of Mark Island (thickly wooded). Then follow the directions in section 2.

Or, from a position ½ mile southward of Libby Islands lighthouse, steer 260° true (W ⅞ N mag.) for 3¼ miles to a position ¼ mile southward of the western end of The Brothers. Then steer 268° true (WNW ½ W mag.) for 1¼ miles to a position ¼ mile southward of Pulpit Rock. Then steer 255° true (W ½ N mag.) for 3 miles, with the south side of The Brothers astern, to a position ¼ mile northward of Mark Island.

2. Through Moosabec Reach to Petit Manan (charts 304 and 305), 18 miles.—These directions are good for vessels of 12 feet draft at low water. The least depth is about 13 or 14 feet. Passing 400 yards northward of Mark Island, steer 253° true (W ¼ N mag.) for 1⅛ miles, passing 300 yards southward of Bay Ledges red buoy, 150 yards northward of Gilchrist Rock spindle, and 50 yards southward of three red buoys. From buoy No. 6 steer 266° true (WNW ⅝ W mag.) through the dredged channel, which is 300 feet wide and 14 feet deep; on this course pass 25 yards southward of two red buoys and about 50 yards northward of a light on a stone beacon. This light is on the northerly end of a stone jetty, which shows at low water. From the light continue the 266° true (WNW ¾ W mag.) course, and pass about 30 yards northward of Horse Ledge black buoy.

From Horse Ledge buoy steer 260° true (W ⅞ N mag.) for 3 miles, and pass about 100 yards southward of red buoy No. 12 and about 400 yards northward of Pomp Island. Fessenden Ledge spindle should be made a very little on the starboard bow, nearly ahead. When about ½ mile from the spindle and the eastern side of Hardwood Island bears 206° true (SW mag.), steer 251° true (W mag.), pass midway between the spindle and the bare rock close to the northwest side of Hardwood Island, and pass about 100 yards northward of Shabbit Island Ledge black buoy.

When Nash Island lighthouse shows between the red and black buoys at the northern end of Tabbott Narrows, steer this range, course 225° true (SW by W ¾ W mag.), pass 300 yards northwestward of Shabbit Island, and pass in mid-channel through Tabbott Narrows. **Ram Island**, on the southeast side of the narrows, is wooded and the rocks light in color; and **Sheep Island**, on the northwest side of the narrows, is grass-covered, and the rocks are dark in color. When through Tabbott Narrows steer 235° true (WSW ½ mag.) with the northern end of Ram Island astern, pass midway between The Ladle and Cone Island, and pass about ⅜ mile northward of Nash Island lighthouse. Then steer 212° true (SW ½ W

Digitized by Google

mag.) for 8¼ miles to the bell buoy lying 1 mile southward of Petit Manan lighthouse. Then follow the directions in section 3.

THROUGH MOOSABEC REACH FROM WESTWARD.—Passing ⅜ mile northward of Nash Island lighthouse, steer 55° true (ENE ½ E mag.) for the north end of Ram Island, until about ⅜ mile from it. Then steer 45° true (NE by E ¾ E mag.) with Nash Island lighthouse astern, pass in mid-channel through Tabbott Narrows and pass about 300 yards northwestward of Shabbit Island. When about ¼ mile past the latter, steer 71° true (E mag.), pass 100 yards northward of Shabbit Island Ledge black buoy, and pass midway between Fessenden Ledge spindle and the bare rock close to the northwest side of Hardwood Island.

When ¼ mile past Hardwood Island, steer 80° true (E ⅞ S mag.) for Kelley Point (eastern point on northern side of Reach), and pass about 100 yards southward of red buoy No. 12, and about 30 yards northward of Horse Ledge black buoy. Then steer 86° true (ESE ⅝ E mag.), and leave the red buoys marking the northern side of the cut on the port hand, and the light on stone beacon on the starboard hand. When abreast buoy No. 6, steer 73° true (E ¼ S mag.), and leave the red buoys on the port hand, and Gilchrist Rock black buoy on the starboard hand.

3. Petit Manan to Bass Harbor Bar (charts 305 and 306).—These directions lead in deep water, except in Western Way. where the depth is 14 feet, and on Bass Harbor Bar, where the depth is 14 feet, in a dredged channel 250 feet wide.

THROUGH WESTERN WAY (CRANBERRY ISLAND PASSAGE)—24 MILES.—From the bell buoy lying 1 mile southward of Petit Manan lighthouse, steer 255° true (W ⅜ N mag.) for 7¾ miles to Schoodic whistling buoy, lying ⅜ mile southward of Schoodic Island. Then steer 256° true (W ½ N mag.) for 8½ miles, and pass between Lewis Rock buoy and Seal Harbor gas buoy. Pass 200 yards southward of the latter buoy, steer 259° true (W ¾ N mag.) for the southeast end of Greening Island, and pass midway between Bear Island and the western end of Sutton Island.

Then bring Bear Island lighthouse astern on a 204° true (SW ¼ S mag.) course until at the fairway buoy (perpendicularly striped) at the northern end of Western Way. Then steer 176° true (S by W ¼ W mag.) for the red and the black buoys, which will show nearly in line at the south end of the passage. Pass eastward of the black buoy and between it and the red buoy, and pass close to the fairway buoy (perpendicularly striped) which lies 250 yards southwestward of the red buoy. Then steer 205° true (SW ⅛ S mag.) and pass about 100 yards eastward and southward of Long Ledge bell buoy. Then steer 269° true (WNW ⅜ W mag.), and cross Bass Harbor Bar close to the fairway buoy lying about 350 yards southward of Bass Harbor Head lighthouse. Then follow the directions in section 4.

PASSING SOUTHWARD OF BAKER ISLAND—22½ MILES.—From the bell buoy 1 mile southward of Petit Manan lighthouse, steer 242° true (W ⅞ S mag.) for 15⅝ miles to the whistling buoy lying 1⅛ miles south-southeastward of Baker Island lighthouse. Then steer 265° true (WNW ¾ W mag.) for 5 miles, passing 600 yards southward of the spindle on South Bunker Ledge, to a position 100 yards southward of Long Ledge bell buoy. Then steer 269° true (WNW ⅜ W

Digitized by Google

mag.), and cross Bass Harbor Bar close to the fairway buoy lying about 350 yards southward of Bass Harbor Head lighthouse. Then follow the directions in section 4.

4. Bass Harbor Bar through Casco Passage (chart 308), 8 miles.—From Bass Harbor Bar, there are two routes that are used, Casco Passage and the passage northward of Pond Island. Casco Passage is good for a depth of 15 feet at low water. Directions to Eggemoggin Reach by the passage northward of Pond Island are given on page 115.

From the fairway buoy lying about 350 yards southward of Bass Harbor Head lighthouse, steer 254° true (W ¼ N mag.) for 5⅜ miles to a position 300 yards off the south end of Black Island. Pass midway between Black Island and the black buoy northward of Orono Island tripod, and steer 265° true (WNW ¾ W mag.). On this course pass midway between buoys Nos. 2 and 3, pass close southward of buoy No. 2 NR, pass northward of buoys Nos. 5 and 7, the latter at a distance of 50 to 75 yards, and pass 50 to 75 yards southward of Casco Passage Ledge buoy No. 4. Then steer 240° true (W by S mag.), passing 250 yards northward of Egg Rock tripod, to the fairway bell buoy lying ⅜ mile westward of the tripod. From the bell buoy, directions through Merchants Row are given in section 5 following, and through Deer Island Thoroughfare on page 118. Deer Island Thoroughfare has a least depth of 15 feet and is the most direct, but it is very narrow in places, and is not recommended for strangers with a greater draft than 9 feet at low water.

To Eggemoggin Reach.—From a position 100 yards westward of Casco Passage Ledge buoy, steer 301° true (NW ⅜ N mag.) for the head at the north end of Conary Island, and pass 500 yards southwestward of Mahoney Island Ledge red buoy, and midway between Hay Island Ledge horizontally striped buoy and Channel Rock black buoy. When Devils Head is abeam, distant about 350 yards, follow the directions in section 2, page 116.

5. Through Merchants Row to Fox Islands Thoroughfare (charts 308 and 309), 15 miles.—Directions to Merchants Row for vessels entering Jericho Bay from seaward between Marshall and Swan Islands are given on page 112. The following directions lead in a depth of 26 feet or more:

From the fairway bell buoy in Jericho Bay lying ⅜ mile westward of Egg Rock tripod, steer 212° true (SW ⅜ W mag.) for Southern Mark Island in range with the summit of Isle au Haut, and pass about ⅜ mile southeastward of Whaleback Ledge red buoy, and the same distance northwestward of West Halibut Rock horizontally striped buoy.

Pass 300 to 500 yards northwestward of Southern Mark Island, and then bring its summit astern on a 264° true (W by N mag.) course, heading for Ewe Island, passing 400 yards northward of Colby Pup buoy and 250 to 300 yards southward of Gooseberry and McGlathery Islands, to a position 350 yards southward of Barter Island Ledges spindle. Then steer 275° true (WNW mag.), and pass about 100 yards northward of Harbor Island Ledge buoy and the same distance southward of Mid-channel Ledge buoy and to a position midway between Farrel and Sparrow Islands; then steer 312° true (NNW ¾ W mag.), passing about ¼ mile eastward of Scraggy Island, to a position ¼ mile southwestward of Deer Island Thoroughfare lighthouse. Then steer 268° true (WNW ½ W mag.) for 4⅜

Digitized by Google

miles to a position 100 yards southward of Channel Rock bell buoy lying 125 yards southward of Channel Rock tripod. Then follow the direction in section 6.

6. Through Fox Islands Thoroughfare to Owls Head (charts 311a and 310), 11 miles.—These directions lead in a least depth of 16 feet.

Passing 100 yards southward of Channel Rock bell buoy lying 125 yards southward of Channel Rock tripod, steer 292° true (NW ½ W mag.) with Goose Rocks lighthouse a little on the starboard bow, and pass northward of Bradstreet Rock black buoy. Pass about 150 yards southward of the lighthouse, steer 267° true (WNW ¾ W mag.), and pass 100 yards northward of Birch Island black buoy and to a position 100 yards southward of Fish Point Ledge red buoy.

Then steer 223° true (SW by W ⅜ W mag.) for ⅝ mile, pass well eastward of Waterman Ledge red buoy and to a position close eastward of Dobbin Rock red buoy. Then steer 230° true (WSW mag.), pass 75 yards northwestward of Iron Point Ledge spindle, and pass close southeastward of Grindstone Ledge red buoy.

When past Grindstone Ledge buoy, steer 284° true (NW by W ¼ W mag.) for the heavy clump of trees on the northeast one of the Dumpling Islands, and pass southward of Lobster Ledge red buoy and Post Office Ledge horizontally striped buoy. When the western point at the entrance of Youngs Cove is a little abaft the beam, steer 255° true (W ¼ N mag.) to a position 100 yards northward of Youngs Point spindle.

Then steer 225° true (SW by W ½ W mag.), pass 100 yards southeastward of the Sugar Loaves, and to a position ¼ mile southward of the stone beacon on Fiddler Ledge.

Bound to Rockland.—A 273° true (WNW ⅛ W mag.) course for 6 miles will lead to Rockland Breakwater lighthouse.

Bound to Muscle Ridge Channel.—A 263° true (W by N mag.) course for 4¼ miles will lead to a position 300 yards northward of the north point of Monroe Island. Then follow the directions in section 7.

Vessels from Fox Islands Thoroughfare, bound through Muscle Ridge Channel, will find it better and more direct to pass through Fisherman Island Passage, as follows:

From a position ¼ mile southward of the stone beacon on Fiddler Ledge steer 240° true (WSW ⅞ W mag.) for 5⅞ miles, heading for the north end of Ash Island. On this course pass about 250 yards northward of the perpendicularly striped bell buoy lying 1 mile southwestward of Fiddler Ledge beacon; pass 200 yards southward of the red buoy which marks the south end of a reef, partly bare at low water, extending 700 yards southward from Sheep Island; and pass well northward of black buoy No. 1, and Northwest and Emory Ledge buoys (horizontally striped). When about 300 yards northward of Emory Ledge buoy steer 209° true (SW ⅛ W mag.) with the eastern end of Monroe Island astern, and pass about 200 yards eastward of the black bell buoy lying close southeastward of Ash Island tripod and to a position 150 yards westward of Upper Gangway Ledge horizontally striped buoy. Then follow the directions in the third paragraph of section 7.

7. Muscle Ridge Channel, Owls Head to Whitehead (chart 312), 8 miles.—These directions are good for vessels of 15 feet draft at low water.

Digitized by Google

Pass 300 yards westward of the north point of Monroe Island, and steer 208° true (SW mag.), heading just clear of Ash Point, and pass midway between Dodge Point Ledge spindle and Monroe Island and to a position 50 yards westward of Sheep Island Bar red buoy. Then steer 191° true (SSW ½ W mag.) for 1¾ miles to a position 150 yards eastward of the black bell buoy lying close southeastward of the large tripod beacon on the end of the ledge at the eastern end of Ash Island. Then steer 204° true (SW ¼ S mag.) for ½ mile to a position 150 yards westward of Upper Gangway Ledge horizontally striped buoy.

From a position 150 yards westward of Upper Gangway Ledge buoy, steer 216° true (SW ¾ W mag.) for 3 miles, heading for Whitehead lighthouse. The course leads eastward of Ash Island Ledge black buoy at a distance of 150 yards; Otter Island Ledge spindle, 300 yards; Garden Island Ledge spindle, 500 yards; Sunken Ledge black buoy, 200 yards; and the black buoy near Sprucehead Island, 200 yards; and westward of the large red tripod beacon on the north end of Otter Island at a distance of 350 yards; Oak Island Ledge red buoy, 400 yards; Channel Rock, 600 yards; and Hurricane Ledge red buoy, 450 yards.

When nearly up with Lower Gangway Ledge horizontally striped buoy, steer 208° true (SW mag.), pass 150 yards westward of Lower Gangway Ledge buoy, 150 yards eastward of Hay Island Ledge black buoy, 300 yards eastward of Whitehead lighthouse, and to a position 100 yards westward of South Breaker bell buoy. Then to go through Davis Straits and the inside passages farther westward, follow the directions in section 8.

To go outside to Portland.—From a position 100 yards westward of South Breaker bell buoy, steer 217° true (SW ⅞ W mag.) for 4⅝ miles to a position ¼ mile northward of Marshall Point whistling buoy. Then steer 228° true (SW by W ¾ W mag.) for 7 miles, passing ½ mile southward of Old Cilley Ledge bell buoy and ⅝ mile southward of Burnt Island, and to a position ⅜ mile southward of Old Man Ledge gas and whistling buoy. Then steer 239° true (WSW ¾ W mag.) for 16 miles to a position ½ mile southward of Bantam Rock gas and whistling buoy. From here steer 260° true (W ⅝ N mag.) for 18 miles to Halfway Rock whistling buoy, and follow the directions for Portland Harbor.

8. Whitehead to Davis Straits (chart 312), 10 miles.—These directions are good for vessels of 12 feet or less draft.

From a position 200 to 300 yards westward of South Breaker bell buoy, steer 227° true (SW by W ¾ W mag.) for 5 miles to the red bell buoy lying 400 yards southward of Mosquito Island. Then steer 281° true (NW by W ½ W mag.) with Marshall Point lighthouse a little on the port bow, pass 350 yards southward of Mosquito Island, 250 yards northward of The Brothers, and to a position 100 yards northward of Gunning Rocks black buoy. Then steer 259° true (W ½ N mag.), and pass about 100 yards southward of Marshall Ledge red buoy.

Then steer 270° true (WNW ½ W mag.), and pass 50 yards northward and northwestward of Allen Ledge black buoy. Give Hooper Island a berth of 200 yards and steer 231° true (WSW mag.) for the grassy islet on the north side of Davis Straits, passing southward of Hooper Island Rocks buoy and Old Horse Ledge spindle, and

Digitized by Google

northward of The Sisters buoy and Gig Rock bell buoy. When about ¼ mile from Davis Straits, steer 208° true (SW mag.) into the straits, and pass 20 yards eastward of Griffin Ledge red buoy. Then steer 244° true (W ¾ S mag.) with the north end of Davis Island astern, and follow the directions in section 9.

9. Davis Straits to Fisherman Island Passage (chart 313), 14 miles.—These directions are good for vessels of 12 feet or less draft.

From Davis Straits, steer 244° true (W ¾ S mag.) for 3½ miles with the north end of Davis Island astern, and pass about 200 yards northward of Seal Ledges buoy, 400 yards southward of Old Hump Ledge, about 50 yards southward of Egg Rock North Ledge buoy, 200 yards northward of Eastern Egg Rock beacon, and to the perpendicularly striped bell buoy between Eastern Egg Rock and Egg Rock North Ledge. Then steer 247° true (W ½ S mag.) for nearly 8 miles, passing ⅝ mile southward of Pemaquid Point lighthouse, ¼ mile northward of Pemaquid Ledge buoy, and ¼ mile southward of Thrumbcap Island. Then steer 261° true (W ¾ N mag.) for a little over 2 miles, and pass through Fisherman Island Passage northward of the black bell buoy marking The Hypocrites and Ram Island Ledge black buoy, and about 350 yards northward of Ram Island lighthouse. Then follow the directions in section 10.

10. Fisherman Island Passage to Cape Small (chart 314), 13 miles.—These directions lead in a depth of 4 fathoms or more.

Pass about 300 yards northwestward of Ram Island lighthouse and steer 227° true (SW by W ⅝ W mag.) for nearly 3 miles to Cuckolds black bell buoy, lying ⅜ mile south-southwestward of The Cuckolds lighthouse. Then steer 242° true (W by S mag.) for 3⅝ miles to a position ¼ mile northward of The Sisters tripod beacon. Then steer 235° true (WSW ⅜ W mag.) for 1½ miles to a position 150 to 200 yards northwestward of White Ledge black buoy. Then steer 229° true (SW by W ⅞ W mag.) for 4 miles, when Glover's Rock should be ¾ mile distant on the starboard beam. Then—

To cross Casco Bay inside the Islands.—Steer 278° true (NW by W ¾ W mag.), passing ½ mile southwestward of Glover's Rock, and follow the directions in section 11.

To cross Casco Bay outside of Halfway Rock (chart 315).—From a position ¾ mile southeastward of Glover's Rock, steer 253° true (W mag.) for 9½ miles to Halfway Rock whistling buoy. Then follow the directions for Portland harbor.

11. Cape Small to Portland, crossing Casco Bay inside the islands (chart 315), 20 miles.—These directions are good for vessels of 12 feet or less draft.

Passing ½ mile southwestward of Glover's Rock, steer 278° true (NW by W ¾ W mag.) for Little Mark Island monument. The red bell buoy lying ⅜ mile southward of Jaquish Island should be made ahead. Pass about 100 yards southward of the buoy, and steer 289° true (NW ⅞ W mag.) for the south end of Haskell Island. When nearly up with Little Mark Island, steer 268° true (WNW ¾ W mag.), and pass 150 to 200 yards northward of Little Mark Island and about 100 yards southward of the red buoy off the southwest end of Haskell Island. Pass about 50 yards westward of this buoy, steer about 333° true (N by W mag.), and pass

Digitized by Google

close eastward and northward of the black buoy northeastward of Haddock Rock.

Then steer 292° true (NW 5/8 W mag.), with the southwest end of Haskell Island astern, passing midway between Eagle Island and Upper Flag Island. Pass about 50 yards northward of Stave Island Ledge black buoy, steer 250° true (W 1/4 S mag.), and pass 150 yards southward of Little Bangs Island and about 50 yards northward of Sand Island Ledge black buoy. When about 200 yards westward of the latter buoy, steer 234° true (WSW 1/4 W mag.), and pass about 150 yards southward of Deer Point, the southwest end of Great Chebeag Island. Pass midway between Deer Point Rock buoy and Deer Point and steer about 304° true (NW 1/2 N mag.), and pass eastward and northward of the black buoy off the northeast side of Crow Island, rounding it at a distance of about 100 yards. Then steer 250° true (W 1/4 S mag.) to a position about 50 yards northward of a black buoy.

Then pass midway between buoy No. 10 and the wharf on Long Island on a 226° true (SW by W 1/2 W mag.) course, and pass about 50 yards southward of buoy No. 12. Then steer 254° true (W mag.), pass about 250 yards northward of Cow Island, and continue the course until abreast Brimstone Point Ledge red buoy and the water tank on Great Diamond Island bears 153° true (S by E mag.). Pass 250 yards northwestward of the buoy, steer 212° true (SW 1/4 W mag.) for Portland Breakwater lighthouse in range with a church spire in South Portland, and pass close westward of Diamond Island Ledge red buoy and 1/4 mile northwestward of Fort Gorges. When abreast the fort, steer about 232° true (WSW mag.) into Portland Harbor.

Directions from Portland eastward through Casco Bay by the channel between Peaks and Little Diamond Islands are given on page 198.

ST. CROIX RIVER AND APPROACHES.

The waters comprising the approaches to the St. Croix River are Quoddy Roads, Lubec Narrows, Friar Roads, and Passamaquoddy Bay (charts 301 and 300). The principal entrance is around the northern end of Campobello Island through Head Harbor Passage, and is deep and generally clear. The channel through Lubec Narrows is also frequently used, especially at high water. The tidal currents are strong, and sailing vessels can make no headway beating against them.

Quoddy Roads lies between the southwestern end of Campobello Island and West Quoddy Head; it is the usual anchorage for vessels seeking shelter against northerly and westerly winds or waiting for a favorable tide to pass through Lubec Narrows. The entrance between Liberty Point Ledge and West Quoddy Head is about 3/4 mile wide, with a least depth of 28 feet near the middle of the entrance; the best water leads about 1/4 mile eastward of West Quoddy Head. The anchorage affords shelter against all but east and southerly winds in 12 to 25 feet; vessels anchored here for shelter when the wind hauls eastward get under way and pass through Lubec Narrows to the anchorage in Johnson Bay. The northern and western parts of the roads between West Quoddy Head and Lubec are full of shoals, partly bare at low water, on which are numerous fish weirs.

Digitized by Google

West Quoddy Head, on the western side of the entrance of Quoddy Roads, is high and wooded. **West Quoddy Head lighthouse,** a red and white horizontally banded tower at the eastern end, is the most prominent mark. The light is fixed white, 83 feet above the water, and visible 15 miles. The fog signal is a steam whistle sounding a group of three blasts, each of 3 seconds duration, silent intervals 7, 22, and 22 second.

Sail Rock and **Little Sail Rock** are two bare rocks of a group of ledges which lie ¼ mile southeastward of West Quoddy Head lighthouse. Swirls form just southward and eastward of Sail Rock during the strength of the tidal current, and it should be given a good berth. A black whistling buoy is moored ⅜ mile south-southeastward of Sail Rock, in line with it and West Quoddy Head lighthouse.

Round Rock and **Liberty Point Ledge** lie a little over ¼ mile westward of **Liberty Point,** the eastern point at the entrance of Quoddy Roads. These rocks show above water, and vessels should pass at least 300 yards southward of the southermost rock.

Middle Ground, with a least depth of 4 feet, is a shoal in the middle of Quoddy Roads, ⅝ mile northward of West Quoddy Head. It is marked on its southwestern side by a red buoy.

Wormell Ledges, partly bare at low water, lie along the southern shore of Quoddy Roads westward of West Quoddy Head.

Above Middle Ground and Wormell Ledges, Quoddy Roads is full of shoals, largely bare at low water, through which is the buoyed channel to Lubec Narrows.

The channel has been dredged to a width of 500 feet and a depth of 12 feet at mean low water, but low spring tides may fall 4 or 5 feet below this level. It is marked by **Lubec Channel lighthouse** (white tower on black pier), and the turns in the channel are marked by buoys. The average draft of vessels passing through this channel is 12 feet; the deepest draft are regular steamers drawing 16 feet, and they pass only from about 2 hours before to 1 hour after high water. It is necessary for sailing vessels to have a fair wind to pass through the dredged channel and the Narrows, the most favorable time being about 2 hours before high water.

Lubec Narrows is a narrow strait between Mulholland Point (marked by Lubec Narrows lighthouse) and the town of Lubec. The channel has been dredged 250 to 400 feet wide and 12 feet deep, and has strong tidal currents and eddies; for current information, see page 60. The narrowest part of the channel is at the northern end.

There are shoals, bare at low water, on both sides of Lubec Narrows. Making off from the northeastern point of Lubec, opposite Lubec Narrows lighthouse, is a dangerous ledge, on the shore end of which is a breakwater which shows out of water; the northern end of this ledge is marked by a black buoy, which also marks the western side of the northern end of the dredged channel.

Lubec, a town on the western side of Lubec Narrows, has several fish factories. The wharves in the Narrows at the northern end are dry at low water, and those at the southern end have depths of 5 to 8 feet. The steamboat wharf and others on the north side of the town have depths of 15 to 18 feet at their ends. Lubec is connected with Eastport and the adjoining landings by ferry, and is visited by steamers running between Boston Mass., and St. Johns N. B. A standpipe 1 mile westward of the town is prominent.

Digitized by Google

Johnson Bay, on the northwest side of Lubec, is a well-sheltered anchorage for vessels for any draft, and is frequently used. It is approached from southward through Quoddy Roads and Lubec Narrows, and from northward through Friar Roads. The southwestern part of Johnson Bay is shoal for a distance of ½ mile from its head, and a shoal with 17 feet over it lies on the west side, near the middle. The shores of the bay should be given a berth of about 300 yards. The best anchorage for deep-draft vessels is just southward of a line from Lubec Narrows lighthouse to Rodgers Island, in 7 to 9 fathoms.

Popes Folly is a wooded islet ¼ mile northward of the northern entrance to Lubec Narrows. The bar connecting it with the shore southeastward has a least depth of 15 feet in mid-channel, and is crossed by most local vessels bound to Lubec or through Lubec Narrows. A ledge extending northeastward from the island is marked at its end by a black buoy.

Dudley Island, ½ mile northward of the northern entrance to Lubec Narrows, is high and mostly grass-covered.

Treat Island, the larger of the islands between Lubec Narrows and Eastport, is high and grass-covered on the south end, and wooded on the north end. Three hundred yards northwestward of Treat Island is **Burial Islet**, grass-covered and distinguished by a single tree in the center; and 350 yards westward of Treat Island is **Gull Rock**, bare at all times.

Friar Roads (Eastport Harbor).—This harbor is on the western side of Campobello Island, north of Johnson Bay and east of Moose Island (Eastport). It is approached from northward around East Quoddy Head and from southward through Quoddy Roads and Lubec Narrows, and is the principal approach to Passamaquoddy Bay and St. Croix River. Vessels seldom anchor in Friar Roads, as the water is deep, the bottom irregular, and the tidal currents have considerable velocity.

Harbor de Loutre, in the northwestern part of Campobello Island, is sometimes used as an anchorage by small vessels.

Friar Bay, a broad bight in the west shore of Campobello Island, southeastward of Eastport, is sometimes used as an anchorage.

Broad Cove, in the south shore of Moose Island and west of Eastport, is a good anchorage for vessels of any draft; vessels anchored off Eastport get under way and anchor here or in Johnson Bay to ride out a gale. The head of the cove is shoal for a distance of ¼ mile. Rocks bare at low water extend 400 yards southeastward and southward from Shackford Head, on the western side of the entrance, and are marked at their southwest end by a red buoy. A good berth for vessels of moderate size is about 250 yards off the point on the eastern side near the head of the cove, with the lone tree on Burial Islet in line with the high spire in Lubec, in 4 to 6 fathoms. The eastern side of the cove is bold and should be favored when entering.

Eastport, on the southeastern end of Moose Island, is of some commercial importance, its principal business being in lumber, fish, and general merchandise. Vessels loading generally lie at the wharves, some of which are dry at low water; others have from 5 to 15 feet at their ends, and the steamer wharf about 16 feet. The best anchorage off the town for small vessels is abreast the customhouse and quite close to the wharves, where the current has the least veloc-

Digitized by Google

ity. Small craft usually land at the float about 200 yards northward of the steamer wharf.

Eastport is connected with Boston, Portland, St. Johns, New Brunswick, Grand Manan, Calais, and the adjacent towns by steamers. It also has railroad communication with Calais and towns westward. Storm warnings are displayed.

Clark Ledge, covered near high water only, lies about 225 yards from the wharves off the northern part of Eastport, and is marked by a spindle.

Dog Island, small, with grassy top, is about ¼ mile northwestward of Clark Ledge and close to Moose Island. A shelving ledge extends 100 yards off its high-water mark.

North Lubec is a post village on Seward Neck, about 2½ miles westward of Eastport. It has steamer communication with the surrounding towns. The steamer landing is at the southeastern end, 1¾ miles north-northwestward of Lubec.

Cobscook Bay.—This bay, making in westward of Moose Island, is a large irregular bay with several arms. It is approached through the channel leading between Moose Island on the north and Seward Neck on the south. The arms of the bay are full of rocks and have dangerous currents, which require local knowledge to keep the vessel in the channel. Strangers seldom enter Cobscook Bay, and then only with a pilot, generally taken from Eastport. The deepest draft using it is 12 feet. Good anchorage is found in many of the arms and coves, but everywhere in the channel the currents are too strong and the bottom too rocky for anchorage. Ice obstructs navigation during the winter.

Pennamaquan River, making northwestward from Cobscook Bay 2 miles inside the entrance, has ample depth for about 1¾ miles above the entrance, and the principal dangers are marked by buoys. It is bare at low water for ¾ mile below Pembroke, a town on the railroad 3 miles above the entrance of the river, and the channel is usually marked by perches in summer. There is a fish cannery on the western branch at Pembroke; the deepest draft using the river is 12 feet, and the usual draft not over 6 feet.

Dennysville is a village at the head of the northwestern branch of Cobscook Bay, 8½ miles above the entrance of the bay. The river is bare for ½ mile below the town at low water, and the deepest draft that can be taken to the town is about 12 feet at high water and with local knowledge. The channel is unmarked and difficult.

Whiting is a village at the head of the southern branch of Cobscook Bay, 9½ miles above the entrance of the bay. The river is bare for 1 mile below the town at low water, and 12 feet is the deepest draft that can be taken to it at high water and with local knowledge. The channel is unmarked and difficult.

Bar Harbor, the thoroughfare between Moose Island and the mainland northward, has a through depth of about 4 feet at low water, but is fringed with shoals, many of them bare at low water, and is unmarked and difficult without local knowledge. It is crossed by a railroad drawbridge between Carlow Island and Pleasant Point, with a draw 30 feet wide, and by a fixed highway bridge about 1 mile southwestward, which has a headroom of about 5 feet at high water.

Digitized by Google

Pleasant Point is an Indian reservation on the point of that name 3½ miles northward of Eastport. There are no wharves.

Passamaquoddy Bay is a large, open bay indenting the shore of New Brunswick east of the mouth of the St. Croix River. **Western Passage**, the principal entrance to the bay, is between **Deer Island** on the east and Moose Island (Eastport) on the west. This passage has deep water and is comparatively free from dangers; it is 4 miles long from Eastport to Passamaquoddy Bay. Anchorage can be had out of the current in several coves on the sides of the passage, Johnson Cove being the best for vessels.

Frost Ledge, showing bare in places near low water, lies on the western side at the northern end of Western Passage, 300 to 600 yards eastward of Frost Island. It is marked at its eastern end by a black buoy.

St. Andrew is a Canadian town and port near the eastern point at the entrance to the St. Croix River. It is a railroad terminus and has some commerce. The anchorage is between the town and Navy Island, and is available for light-draft vessels only. A channel 13 feet deep has been dredged into the harbor from southeastward and northwestward. The channel from northwestward was said to have shoaled to about 11 feet in 1917. The channel is marked by lights, buoys, and beacons. The railroad and steamboat wharf has a depth of 12 feet at the end.

St. Croix River (chart 300).—This river, emptying into Passamaquoddy Bay from northward, forms the boundary between Maine and New Brunswick. It has a deep and comparatively clear channel for 8 miles above the mouth at Navy Island to Devils Head. Above this point it has a narrow winding natural channel with a least depth of about 12 feet for 3¼ miles to Hills Point, thence a dredged channel 12 feet deep and 150 to 200 feet wide to the steamer landing 1 mile below Calais, and 9 feet deep and 100 feet wide to Calais and St. Stephens.

The channel is marked by buoys and lights, and strangers should have little trouble in taking a draft of 6 feet to Calais at low water with the aid of the chart. With a deeper draft they should take advantage of the tide or employ a pilot. Vessels can anchor and lie afloat below THE LEDGE, a village on the New Brunswick side 2½ miles above Devils Head, but above this point there is no room for anchorage.

ROBBINSTON is a village on the west bank of St. Croix River near the entrance. The steamer landing has a depth of about 10 feet at the end, but a ledge bare at low water extends outside the face of the wharf a little northward of it.

RED BEACH is a village on the west side of St. Croix River 6 miles above the entrance. The steamer wharf, on the point ¾ mile southwestward of St. Croix River lighthouse, has a depth of about 12 feet.

DOCET ISLAND, in mid-channel off Red Beach, is marked by St. Croix River lighthouse, a white dwelling. Scattered shoals, sunken and awash, surround the island and lie in mid-channel for a distance of 1⅛ miles southward of it. The deeper and broader channel leads eastward of these shoals, and is marked by a single black buoy on the edge of the shoals extending eastward from Docet Island. The channel leading westward of the shoals, between them and LITTLE

Digitized by Google

DOCET ISLAND, a wooded islet midway between the southern end of the shoals and the western shore, is marked by several buoys and is generally used by local vessels, but should be used with caution by strangers.

CALAIS, a city on the south bank of the St. Croix River, about 14 miles above its mouth and 23 miles above Eastport, is of considerable commercial importance and has a large lumber trade; it is a terminus of a railroad running through Maine and into Canada. The deepest draft brought up to the city is 21 feet, and the usual draft is about 12 feet. The steamer landing 1 mile below the city has a depth of about 10 feet, and all of the other wharves are bare at low water. Vessels lie aground while loading or discharging. Calais has steamer communication with Eastport and intermediate landings.

ST. STEPHENS, on the north bank on the river, opposite Calais, is connected with the latter by a closed bridge just above the wharves. It has some trade in lumber, and is the terminus of a railroad with connections through Canada. The town wharf has a depth of 9 feet, and the others are bare at low water.

Pilots.—Pilotage is not compulsory for Maine ports. The only pilots available are local fishermen and the masters of the towboats. The former can usually be had near the entrance or at Head Harbor, and the latter by communicating with Calais. Pilots for the St. Croix River or Cobscook Bay can be obtained at Eastport.

A towboat can be obtained fom Calais. Sailing vessels usually sail to Eastport, and often to The Ledge.

Supplies.—Coal in limited quantities and water can be obtained alongside the wharves at Eastport and Calais, and water from a towboat at Calais. Provisions, gasoline, and some ship chandlers' stores can be obtained at Lubec, Eastport, and Calais, and in limited quantities at all of the other towns.

Repairs.—Light repairs to the hulls and machinery of vessels can be made at Eastport, vessels being hauled out on the beach. Repairs to vessels' hulls and minor repairs to machinery can be made at Calais, where there is a dry dock for vessels 130 feet long, 31 feet wide, and 10 feet draft.

Storm warnings displays are made at Eastport.

Ice.—During January, February, and March St. Croix River is usually obstructed by ice and not navigable above Robbinston, but the channel is sometimes kept open by tugs and the regular steamers. Quoddy Roads and Eastport Harbor are never closed by ice.

Freshets.—Spring freshets usually cause the water to rise above the level of the wharves at Calais and are accompanied by strong currents. They are seldom noticeable outside of the river.

Tides.—The mean rise and fall of tides is 18.2 feet at Eastport, 19.2 feet at Robbinston, and 20 feet at Calais; under special conditions the extreme limits may be as much as 5 feet above mean high water or below mean low water.

CURRENTS, ST. CROIX RIVER AND APPROACHES.

In the Grand Manan Channel the flood sets in a general northeast direction and at strength attains a velocity of about 2½ knots. The ebb sets in a southwesterly direction with a velocity at strength of about 2½ knots.

Digitized by Google

Approaching the entrance to Quoddy Roads, if less than 2 miles from the northern shore, the set of the flood is more northward, and about 1 mile southeastward of West Quoddy Head the flood sets directly into the Roads. For a distance of ½ mile southeastward of West Quoddy Head the currents are dangerous on account of swirls and eddies, which are apt to draw a vessel, in a light breeze, onto Sail Rock.

Along the eastern side of Campobello Island the flood sets in a northeasterly direction following the trend of the shore, the ebb setting in a contrary direction.

Along the northwestern side of Campobello Island, 1 mile north of East Quoddy Head, the flood sets strongly westward on the islands lying in the passage westward of Campobello Island. The direction of the flood then changes more southward, following the general direction of the passage until nearly to Eastport, where the set is more westerly, toward the passage between Deer and Moose Islands and toward the entrance to Cobscook Bay. The ebb generally sets in a reverse direction.

Through Lubec Narrows the flood sets northward, following the general direction of the dredged channel; southward of the Narrows it has a velocity of about 4 knots at strength, but in the Narrows it attains a velocity of about 6 knots during spring tides. The ebb sets southward, following the general direction of the channel, and in the Narrows has a velocity of about 8 knots during spring tides. Below the Narrows its velocity is about 4 knots and the set is in the general direction of the channel. The currents at strength form dangerous eddies on both sides of the channel in the Narrows; these are avoided by keeping in mid-channel. It is slack water in the Narrows about 1 hour before high and 1½ hours before low water; the duration of slack is short, from 5 to 15 minutes. With a strong fair wind small sailing vessels can pass through the Narrows with an adverse current at any time after the current has been running 3 hours.

Northward of Lubec Narrows the first of the flood current sets along the west shore of Campobello Island eastward of Popes Folly; it afterwards sets more westward, south of Popes Folly, and across the entrance of Johnson Bay, meeting the flood from Friar Roads westward of Treat Island, and both setting into Cobscook Bay.

Western Passage of St. Croix River.—The flood sets northward into the passage, and off Deer Point, abreast Dog Island, it forms whirlpools and eddies, which are dangerous to open boats. The whirlpools and eddies are strongest 2 to 3 hours before high water and during spring tides; the flood then attains a velocity of 6 to 7 knots. The least disturbance is usually about 300 yards northward of Dog Island, where there is a comparatively narrow direct current known locally as "straight water," which can be readily followed between the whirlpools and eddies on the Deer Island side and the eddies on the Eastport side of the passage. The ebb sets southward, but does not attain the velocity of the flood.

Above Deer Point the flood sets northward with decreasing velocity and follows the general direction of the channel with strong countercurrents and eddies close to the shore where the conformation of the land is favorable; it continues ½ to ¾ hour after the time of high water. The ebb sets southward with reduced velocity and disturbance off Deer Point, and the inshore reverse currents are less marked

Digitized by Google

than on the flood; it continues ¾ to 1 hour after the time of low water.

St. Croix River.—The flood sets northward with countercurrents inshore on both sides where the conformation of the land is favorable for them. The ebb sets southward with less marked countercurrents.

Cobscook Bay and tributaries.—The tidal currents follow the general direction of the channels, but in the coves there are strong reverse eddy currents, and heavy overfalls are formed over the submerged rocks and ledges. The velocity is estimated at 5 to 8 knots, and some of the buoys are towed under when the currents are at strength.

DIRECTIONS, EASTPORT HARBOR AND ST. CROIX RIVER.

Entering through Head Harbor Passage.—From a position ¼ mile northward of Head Harbor lighthouse, follow the northern shore of Campobello Island at a distance of 300 to 400 yards, courses 239° true (W ⅞ S mag.) for 1 mile, then 224° true (SW by W ¾ W mag.) for ¾ mile until Green Islet is abeam, then 216° true (SW by W mag.), passing ¼ mile eastward of the white fog bell structure on the south end of Cherry Island. The course can then be changed for the wharves of the city of Eastport.

To ANCHOR IN BROAD COVE continue the 216° true (SW by W mag.) course to a position 100 to 200 yards southeastward of Buckman Ledge buoy and then steer more westward and pass 150 yards or more southward of Estes Head. Then stand northward into the cove, favoring the eastern side, and anchor as directed in the description of the cove.

To ANCHOR IN JOHNSON BAY when off Eastport stand southward to the white buoy lying 400 yards eastward of Treat Island (large, high, and partly wooded). Then steer about 211° true (SW ⅝ W mag.) and pass about midway between Popes Folly and Dudley Islands. Then stand more westward into Johnson Bay.

Entering through Quoddy Roads and Lubec Narrows.—Local knowledge is necessary to handle a large vessel in the narrow channel with strong tidal currents, and vessels desiring to pass through from Quoddy Roads should do so on the last of the flood. Vessels bound through the narrows from Eastport usually pass through at high water slack, which occurs about 1 hour before high water.

Passing eastward of Sail Rock whistling buoy steer 335° true (N ⅜ W mag.) for West Quoddy Head black bell buoy and pass ¼ mile eastward of Sail Rock and West Quoddy Head lighthouse. Pass eastward of the bell buoy and steer 289° true (NW ½ W mag.), with Middle Ground red buoy a little on the starboard bow. If the wind and tide are not favorable, anchor about 150 yards southward of Middle Ground buoy in 3½ to 4½ fathoms, soft bottom.

THROUGH LUBEC NARROWS.—Pass about 100 yards westward of Middle Ground red buoy and steer 329° true (N ⅞ W mag.) for Lubec Channel lighthouse, and pass eastward of a black buoy and 75 yards eastward of the lighthouse. Swing a little eastward to pass between a red and a black buoy about 100 yards beyond the lighthouse, and then steer 14° true (NE by N mag.) for ½ mile to a position 50 yards westward of a red buoy. Then swing northward to pass 50 yards eastward of a black buoy 150 yards beyond, and then steer 330° true (N ¾ W mag.) for ⅜ mile, heading for the

Digitized by Google

ends of the northerly wharves of Lubec, until abreast the southerly wharves. From this position, a 351° true (N by E mag.) course will lead in mid-channel between Lubec Narrows lighthouse and the end of the breakwater opposite, and eastward of a black buoy a little northward of the breakwater.

The 351° true (N by E mag.) course can be continued, passing in mid-channel eastward of Popes Folly Island, to a position eastward of a black buoy, and then a 0° true (N by E 7/8 E mag.) course will lead to the wharves at Eastport. Or vessels may pass southward and westward of Popes Folly Island.

Eastport to Calais.—Sailing vessels should not attempt to enter Western Passage except with a favorable tide or a strong fair wind, as no headway can be made against the strong tidal currents.

Give the shore at the northern end of Eastport a berth of about 400 yards, and pass 250 to 300 yards northeastward of Clark Ledge spindle and Dog Island. Then make good a 329° true (N by W mag.) course for 3 miles, and pass 350 yards westward of Clam Cove Head. Then steer 335° true (N 3/8 W mag.) for 7 miles to a mid-channel position in the entrance of the river between Liberty Point and Joes Point.

Then steer 341° true (N 1/8 E mag.) for 2¾ miles to a position 3/8 mile eastward of Lower Middle Ground red buoy and the same distance from the eastern shore, taking care to avoid the middle ground extending ¼ mile northeastward from the buoy. From this position, a 334° true (N ½ W mag.) course for 1⅛ miles will lead to a position 3/8 mile eastward of St. Croix River lighthouse and eastward of a black buoy.

Then steer 310° true (NNW 5/8 W mag.) for ½ mile, heading for the summit of Devils Head, until about 400 yards off the point on the east side. Then steer 324° true (N by W 3/8 W mag.), and pass about ¼ mile northeastward of Devils Head. Good anchorage can be had in the river between Devils Head and the red buoy southward of Oak Point, taking care, however, to keep St. Croix River lighthouse well open from the shore at Devils Head to clear the shoal on the southern side of the river.

If bound to Calais, pass about 200 yards southward of the red buoy off Oak Point and haul westward, following the north shore at a distance of 150 to 250 yards for 2 miles, being guided by the buoys, to The Ledge, a village on the north shore. Just above The Ledge, the channel leads midway between a light on the north shore and a row of three piers on the shoal south of it, and then follows the south shore at a distance of 150 yards for 7/8 mile to a light on the south shore. Above this point the channel is dredged 12 feet deep and 150 to 200 feet wide to the steamer landing 1 mile below Calais, and 9 feet deep and 100 feet wide to Calais and St. Stephens. It is marked by buoys, and easily followed by small boats with the aid of the chart.

COAST FROM WEST QUODDY HEAD TO MACHIAS BAY.

From West Quoddy Head to Little River (charts 301 and 303), about 14 miles, the coast is, for the most part, high, rocky, covered with trees, and with precipitous faces seaward. It is generally bold-to, and the only outlying dangers are **Morton Ledge**, with 6 feet

Digitized by Google

of water over it, lying about ⅜ mile offshore, 2¼ miles southwestward of West Quoddy Head lighthouse, and marked by a red buoy. There is a 13-foot spot ¼ mile southwestward of Long Point, about 2 miles eastward of Little River lighthouse.

The shore is broken by the following unimportant coves named from eastward with their distances in miles from West Quoddy Head lighthouse: Carrying Place Cove, 1¼; Wallace Cove, 1¾; Hamilton Cove, 3; Julia Cove, 3¼; Boot Cove, 4; Baileys Mistake, 5½; Haycock Harbor, 6¼; Sandy Cove, 6½; Moose Cove, 7¾; Bog Brook, 9½; Black Point Cove, 11¾; Long Point Cove, 12¼; and Schooner Brook, 13¾. The largest of these are Baileys Mistake and Moose Cove. When passing along outside, both of these will appear to be good, open anchorages, but neither has good holding ground, nor can they be used as a harbor of refuge. Both have ledges, not buoyed, at their entrances, and afford shelter only from northerly winds.

When running close along the coast, the following are the only distinguishing marks between West Quoddy Head and Little River: **Carrying Place Cove** has a Coast Guard station and a few other buildings in the low divide at its head. **Boot Cove** has a few small fishermen's houses on the shore at the head. **Baileys Mistake** is distinguished by the cultivated land and a small settlement (**South Trescott**) at its head; there are landings only for small craft at high water; **Baileys Ledge**, on the west side of the entrance, is bare at low water and unmarked. **Moose Cove** has no distinguishing marks except a wooded islet on the northeast side at the entrance, and **Eastern Head Ledges**, ⅛ mile southward of the islet, which are bare at low water.

Little River (chart 303).—This harbor is 14 miles westward of West Quoddy Head and about 9½ miles eastward of Libby Islands; the entrance is marked by Little River lighthouse on Little River Island. It is a small but excellent harbor of refuge, sheltered from all winds, has 12 to 30 feet of water with good holding ground, and is easy of access. The channel leads northward of the lighthouse and has a depth of about 28 feet. The anchorage is about ½ mile long and ¼ mile wide, just inside of Little River Island. The harbor is never obstructed by ice so as to prevent vessels from entering.

Little River Ledge, bare at low water, lies 100 yards from the north shore just inside the entrance, and is marked by a red buoy. A ledge extends 110 yards from the south shore just eastward of a prominent point ½ mile above Little River Island. With these exceptions there are no dangers in the harbor if the shores be given a berth of 100 yards.

Little River Lighthouse, on the southeast end of Little River Island (wooded, with rocky shores), is a white conical tower. The light is fixed white, with a white flash of 0.6 second duration every 15 seconds, 57 feet above the water, and visible 13 miles. The fog signal is a bell, sounding 1 stroke every 30 seconds.

Cutler is a village on the north side of Little River. It has communication by telephone, and by stage with the railroad at East Machias. It is the headquarters of many small fishing boats. Gasoline and provisions are obtainable. The depth at the principal wharves does not exceed 3 feet at low water.

Digitized by Google

To ENTER LITTLE RIVER, pass northward of Little River Island, giving it a berth of 100 to 200 yards, and pass southward of the red buoy just inside the island. Anchorage can be selected anywhere in mid-channel inside the island. Small local craft anchor off the wharves in 6 to 18 feet. The passage southward of Little River Island has a rocky bar across it with a least found depth of 10 feet in mid-channel, but has not been closely examined, and should not be used by strangers.

Little Machias Bay (chart 303), about 2½ miles westward of Little River, is not used for an anchorage, as it is exposed to southerly and southeasterly winds, and is close to Little River and Machias Bay, both excellent anchorages. The bay is ⅝ mile wide at the entrance and wider inside, and about 2 miles long. **Long Ledge**, in the middle of the bay 1 mile inside the entrance, is covered at high water. Above this ledge the bay is much obstructed by ledges and shoals. There are some houses on the shores of the bay, but no wharves except for small craft at high water.

Old Man, a small but prominent rocky island, sparsely wooded on top, lying 1 mile off the entrance of Little Machias Bay, is a good mark and may be safely approached as close as 400 yards.

Black Ledges are bare islets in the middle of the entrance of Little Machias Bay; there is deep water close-to on both sides.

MACHIAS BAY AND RIVER

(chart 303) is the approach to the towns of Machiasport and Machias. It is easily entered either day or night, and affords well-sheltered anchorage for the largest vessels. It is about 6 miles long, and the main entrance between Cross Island on the east and Stone Island on the west is about 2 miles wide. The principal guide to the entrance is Libby Islands lighthouse, which lies 9 miles westward of Little River lighthouse and 9 miles eastward of Moose Peak lighthouse. Avery Rock lighthouse, in the middle of the bay, 4 miles from the entrance, is the guide for vessels bound up the bay. The best anchorages for vessels are Starboard Cove and the head of the bay above Avery Rock lighthouse.

Cross Island, the large island on the southeast side of the entrance to Machias Bay, is wooded and has no prominent marks except a few shacks on **Quaker Head**, the most prominent marks in approaching Cross Island Narrows from westward. There is a Coast Guard station in a small cove at the eastern end. A skeleton tower near it is the most prominent mark from outside.

Cross Island Narrows is a channel leading into Machias Bay east of Cross Island. This passage is much obstructed by rocks, sunken or awash at various stages of the tide, and should not be used by vessels without local knowledge. Small craft can go through the narrows by the following directions:

Pass on either side of Old Man at a distance of 300 to 500 yards, and then bring it astern on a 276° true (NW by W ¾ W mag.) course, heading for Thornton Point Ledge spindle. Pass 75 yards southward of the spindle and steer 276° true (NW by ¾ W mag.) for a black buoy and pass close northward of it. Give the point on the northeast side a berth of 200 yards and steer 313° true (NNW ½ W mag.) for the middle of Chance Island (wooded on north part),

Digitized by Google

with the summit of Mink Island (thickly wooded) astern, and pass 100 yards northeastward of the black buoy off Quaker Head. Dog Fish Rocks, between Quaker Head and the buoy, are bare at low water only.

North West Harbor, a bight in the north shore of Cross Island near its western end, has from 4 to 9 fathoms of water, but is little used as an anchorage.

Libby Islands, in the middle of the entrance of Machias Bay, consist of two grassy islands, connected by a bare ledge. The lighthouse and buildings on the southwest end are the most prominent marks. Several vessels have been lost on the eastern side of the islands in thick weather.

Libby Islands lighthouse is a white conical granite tower. The light is fixed white, 91 feet above the water, and visible 15 miles. It is obscured when bearing about east-northeast (mag.). The fog signal is a steam whistle (blast 2 seconds, silent 13 seconds).

Scabby Islands are described on page 68.

Foster Channel is a narrow passage, marked by two buoys, between Foster Island and Ram Island, and leads from Englishman Bay to the western entrance of Machias Bay. It has a depth of 19 feet and can be used by vessels up to 15 feet draft when the buoys can be seen. A red buoy at the eastern end of the passage lies 1¼ miles northwestward of Libby Islands lighthouse. To go through the passage from eastward pass 100 yards southward of the red buoy, steer 279° true (NW by W ½ W mag.), and pass 25 yards northward of the black buoy.

Ram and **Foster Islands** are grass-covered and surrounded by ledges. Foster Island has a shanty at each end.

Stone Island is wooded and has a bare rocky face at the south end.

Stone Island Ledge, on the east side, is bare at low water and marked by a spindle.

Starboard Island is grassy at the southwest end and sparsely wooded at the northeast end.

Starboard Cove, on the western side of the bay 2½ miles northward of Libby Islands lighthouse, is formed on the south by Starboard Island and a bar, bare at half tide, connecting it with the shore. It is an excellent anchorage, except in easterly weather, with 15 to 24 feet of water, and is much frequented by coasting vessels making an anchorage for the night if bound through Moosabec Reach. A good berth is in the middle of the cove, with the north end of Starboard Island in line with the south end of Stone Island, in 18 to 21 feet. Small vessels can anchor closer to the bar, taking care, however, not to shut out the north end of Stone Island by the north end of Starboard Island.

Starboard Cove is entered eastward of Starboard Island, passing on either side of Stone Island. Approaching from westward, bring Libby Islands lighthouse astern on a 344° true (N ⅜ E mag.) course, and pass 250 yards westward of Stone Island and the same distance eastward of Starboard Island.

Starboard post office is a small settlement on the western side of Starboard Cove. There is a wharf with a reported depth of 6 feet. Gasoline and some provisions are usually obtainable.

Digitized by Google

Howard Bay, northward of Starboard Cove, is exposed to southeast winds, the holding ground is poor, and it is not a good anchorage. There are no wharves. Broken ground, including a rock bare at low water, extends ⅝ mile southeastward and eastward from Howard Point.

Bucks Harbor is a shallow cove in the west shore of the bay inside of Bar Island and 4 miles north-northeastward of Libby Islands lighthouse; a small village of the same name is located on the shore of this harbor. Small vessels can anchor 200 yards off the southern side of Bar Island in 8 to 15 feet. There is a fish cannery on **Bucks Neck**, with a wharf nearly bare at low water, and another wharf south of it with a depth of about 4 feet.

All of the islands in Machias Bay above the entrance are high and wooded, with rocky shores, and have no distinguishing marks.

Avery Rock, in the middle of Machias Bay, 4 miles above the entrance, is marked by Avery Rock lighthouse, a white tower on dwelling.

Larrabees Cove, largely dry at low water, and **Indian Cove** are small coves in the west shore of the bay, northwest of Avery Rock lighthouse; these coves are of no importance, but good anchorage for vessels of 8 feet draft will be found on the flats between Salt Island and Bare Island, near their entrances. There are small wharves nearly bare at low water in Indian Cove. A rock in the middle, bare at low water, is the principal danger. **Larrabee** is a village and post office at the head of Larrabees Cove.

Holmes Bay, a large bight in the northeastern part of Machias Bay and east of Hog Island, is so shallow that it can not be used as an anchorage, and is seldom entered except by small fishing boats.

Machias River empties into the northwestern part of the bay; it has a narrow, winding channel, leading through flats which are mostly bare at low water. The least depth in the channel up to the town of Machiasport is 19 feet. A little below the town of Machias it shoals to 4 feet at low water. Machias is at the head of navigation, and about 6½ miles above the mouth of the river.

Machiasport is a village on the west bank of Machias River, 2½ miles above the entrance. It has several fish canneries, and wharves with depths of 6 to 7 feet. There is water on the wharves. Storm warnings are displayed.

East Machias River, emptying into Machias River from northeastward 1 mile above Machiasport, is practically bare at low water at East Machias, a village on the railroad 1½ miles above the entrance. Some lumber is shipped from a wharf ½ mile above the entrance. Above this point the channel is difficult, and is little used except by small craft.

A highway drawbridge crosses Machias River 1½ miles above Machiasport and 2½ miles below Machias. It has a center pier draw, the north opening 47 feet wide and the south opening 33 feet wide. The best water is in the north opening.

Machias is a town on the railroad at the head of navigation on Machias River. It ships considerable lumber in small coasting vessels, the deepest draft being 14 feet. There is a depth of about 4 feet at low water to the lumber wharves, and 2 feet to a float landing at the head.

Digitized by Google

A towboat is stationed at Machiasport. Vessels do not usually take a tow unless bound to Machias, and sailing vessels usually sail to Machiasport. The towboat may be ordered by telephone from Starboard Cove.

Supplies.—Gasoline and provisions are obtainable at Machiasport and Machias. There is water on the wharves at Machiasport. Coal is obtainable only in case of emergency.

Repairs.—There are no marine railways for the repair of hulls. There are machine shops at Machias for ordinary repairs to machinery.

Storm-warning displays of the United States Weather Bureau are made at Machiasport.

Ice.—In severe winters Machias River is closed to navigation, and drift ice will sometimes fill the bay above Avery Rock. In ordinary winters the bay and river are open to Machiasport.

The **currents** follow the general direction of the channel and are not strong except in the river.

Tides.—The mean rise and fall of tides is about 13 feet.

DIRECTIONS, MACHIAS BAY.

From eastward.—Many vessels have been wrecked on the eastern side of Libby Islands in thick weather, through failure to hear the fog signal. Steer for Libby Islands lighthouse on any bearing northward of 251° true (W mag.), and when Avery Rock lighthouse is open from the western end of Cross Island, bearing 341° true (N mag.), shape the course to pass about ½ mile eastward of the northern end of Libby Islands. Steer for Avery Rock lighthouse on a 356° true (N by E ⅜ E mag.) course. Pass westward of the lighthouse, giving it a berth of over 200 yards, and steer 352° true (N by E mag.) for the eastern end of Round Island. Anchorage for vessels may be had anywhere between Avery Rock and Round Island, or eastward or northeastward of the latter at a distance not greater than ½ mile, in 5 to 7 fathoms.

From westward.—Steer for Libby Islands lighthouse on any bearing northward of 57° true (ENE ¾ E mag.) and pass ¼ to ½ mile northwestward of the lighthouse. Then steer 29° true (NE ⅜ E mag.) until Avery Rock lighthouse bears 356° true (N by E ⅜ E mag.). Then steer for the latter on that bearing, and follow the directions in the preceding paragraph.

Machias River to Machiasport.—The channel in Machias River is marked by buoys at the turns as far as Machiasport, and is easily followed. The best time is at low water, when the flats are visible.

Pass about 200 yards eastward of Round Island and steer 339° true (N mag.) for ½ mile to a position 100 yards northeastward of a black buoy, then 295° true (NW mag.) for ⅜ mile, keeping the next black buoy well on the port bow until ⅛ mile from it, and then hauling westward to pass 100 yards northward of it. From this position, a 274° true (NW by W ⅞ W mag.) course for ⅞ mile will lead to a position southward of a red buoy, and then a 310° true (NNW ¾ W mag.) course for ¼ mile will lead to a position westward of a second red buoy. After passing the buoy, the wharves at Machiasport should be kept a little on the starboard bow for about ¼ mile; then swing

Digitized by Google

slowly eastward and keep the wharves a little on the port bow until in mid-channel abreast them. Small vessels often anchor in the channel for a distance of ½ mile southward of the wharves at Machiasport.

Above Machiasport.—The channel leads between shoals bare at low water on each side, and is unmarked except by private stakes, which are in position only a part of the time. Local knowledge is necessary to carry the best water, but strangers in small craft should have no trouble in going to Machias on a rising tide with the aid of the chart.

ENGLISHMAN AND CHANDLER BAYS.

(chart 304) form a large bight in the coast between Libby Islands and Head Harbor Island, with Roque Island and numerous smaller islands in the middle. The bays unite northward of Roque Island and form a good anchorage, with depths of 3¼ to 6 fathoms, good holding ground.

Englishman Bay, eastward of Roque Island, has numerous dangers before reaching the anchorage northward of Roque Island, but the channel is marked by buoys, is broad and easily followed in the daytime in clear weather. The principal entrance to the bay from eastward is between Scabby Islands on the east and The Brothers on the west, and affords a straight course to Shoppee Island, above which is the anchorage. The bay may be entered from Machias Bay through Foster Channel. Vessels from westward, bound to the anchorage at the head of Englishman Bay or to Chandler River, usually pass through Chandler Bay.

Foster Channel and the adjacent islands are described on page 65.

Scabby Islands, on the eastern side of the main entrance to Englishman Bay, are grass-covered. A mound on the larger Scabby Island is the most prominent mark in approaching Foster Channel from westward.

Scabby Island Ledge, awash at low water, lies 250 yards southwestward of the southwest end of Scabby Island.

Codhead Ledge, 1½ miles northwestward of Scabby Islands, is awash at low water and marked by a red buoy on its western side.

Shag Ledge, ⅞ mile eastward of Codhead Ledge, has a low islet on its western end. The northeast end of the ledge is covered only at high water, and the south end shelves off to 13 feet.

Pierson Ledge, northward of Shag Ledge, is a rock bare at low water.

Hickey Island, in the entrance of Little Kennebec Bay, has a rock awash at low water 250 yards eastward of it.

Little Kennebec Bay is an anchorage westward of Machias Bay, and makes northward from the eastern part of Englishman Bay; it is of no commercial importance, and is frequented mostly by fishermen and a few lumber schooners. There is good anchorage in 12 to 40 feet of water, soft bottom and well sheltered, inside of Sea Wall Point, but it is seldom used, being so near Machias Bay and Starboard Cove, which are much easier of access and better anchorages. There are no wharves. Chart 303 or 304 is the best guide for entering.

The Brothers, on the western side of the main entrance to Englishman Bay, consist of a string of grassy islands, with rocky shores.

Digitized by Google

Green Island, northward of The Brothers, is grassy. **Green Island Ledge**, partly bare at low water, extends ¼ mile eastward from the island and is marked by a red buoy. A ledge awash at high water extends 200 yards westward from Green Island.

Pulpit Rock, 1 mile westward of The Brothers, is a bare rocky islet. Its southern and eastern sides should be given a berth of 100 yards.

Halifax Island is grass covered on top, with rocky sides, and has a prominent mound at its western end. The islands westward are partly wooded.

A rock bare at low water lies 350 yards southeastward of the southeast end of Halifax Island. The bottom is uneven between Halifax and Green Islands, and this passage should not be used by vessels of over 17 feet draft.

A rock, covered well at high water, lies 350 yards southward of Double Shot Island. **Shag Rock**, lying ¼ mile eastward of Double Shot Island, is high and bare.

Roque Island Harbor is formed on the north and west by Roque Island, and on the south by Great Spruce Island and the islands extending eastward to Halifax Island. It affords shelter from all winds, but is used only by small local vessels. The holding ground is not good except in spots, the entrances to the harbor are generally foul, and it should be avoided by strangers. The best entrance is from eastward, passing north of Halifax Island.

To enter, pass ⅜ mile northward of Halifax Island on a 253° true (W ¼ N mag.) course, heading for the south end of Lakeman Island until Halifax Island is passed, and then keep near the middle of the harbor. Or, coming from northward in Englishman Bay, steer 149° true (S by E mag.), with the western side of Shoppee Island in range with the western side of Pond Cove Island astern, which leads clear between unmarked spots in Englishman Bay to the entrance of the harbor. The best anchorage is in the western or northwestern part of the harbor where the bottom is soft.

The principal dangers in Roque Island Harbor are a spot with 8 feet on it lying ¼ mile off the middle of the north side of Great Spruce Island; and Seal Ledge, bare 3 feet at low water, lying 300 yards westward of the southern point at the eastern end of Roque Island.

The Thoroughfare, connecting the southwest side of Roque Island Harbor with Chandler Bay, has a depth of 9 feet in a narrow crooked channel. To pass through from eastward, enter in midchannel between a rock on each side, bare a few feet at high water. Keep in midchannel throughout the passage, except at a point 300 yards inside the eastern entrance, where the northwest side should be slightly favored to avoid a rock on the southeast side, bare at about half tide; and at the western entrance, where the wooded island on the north side should be favored, to avoid a shoal extending 250 yards northward from the point on the south side.

Shoppee Island is flat, and wooded except at the northwest end.

A reef, on the outer end of which are rocks bare at low water only, extends northeastward from Roque Island to within ⅜ mile of Shoppee Island. It is marked by a black buoy at the end.

Roque Bluff is a post village on and eastward of Shoppee Point, on the northeast side of Englishman Bay. There is a wharf with a depth of about 7 feet on the point southeastward of Pond Cove Island.

Digitized by Google

Shorey Cove is a bight, with 8 to 13 feet of water, in the north shore of Roque Island. It is a good anchorage for small vessels, but is little used. There are no dangers if the southern and western shores of the cove be given a berth of over 300 yards.

Pond Cove, on the northeast side of Englishman Bay above Shoppee Point, has excellent anchorage westward or northwestward of Pond Cove Island, at a distance not greater than ½ mile, in 12 to 18 feet, soft bottom. The entrance is westward of Pond Cove Island, between it and Little Ram Island, and is clear with the exception of a rock, bare at low water, lying 300 yards northeastward of Little Ram Island. The part of the cove northward of Pond Cove Island is shoal.

Chandler River, at the head of Englishman Bay, is very narrow and crooked to Jonesboro, a village at the head of navigation, about 3½ miles above its mouth. The river is bare at low water at Jonesboro. The channel is unmarked, and strangers should not attempt to enter without a pilot. Vessels of 10 feet draft go up to it at high water. Twelve feet is the deepest draft entering the river. Provisions can be obtained at Jonesboro. Ice closes the river to its mouth from December to April.

Masons Bay, making westward at the head of Englishman Bay, has an unmarked channel with a depth of 13 feet into the entrance from southward, but is practically bare at low water and has many rocks inside the entrance. There is a small settlement, and a cannery with a wharf bare at low water, on the south side just inside the entrance. Fish traps are numerous in the vicinity.

Chandler Bay is on the west side of Roque Island, and extends northward from Mark Island to Squire Point, the northwestern point of Roque Island, where it joins Englishman Bay. A good channel leads eastward of Ballast Island and around Squire Point into Englishman Bay and Chandler River. The principal dangers in this channel are buoyed, and it can be readily followed in the daytime in clear weather. This bay is the approach from westward to Chandler River and the anchorage in Englishman Bay, and is the one generally used by strangers. There is no anchorage in the bay until north of Roque Island. Vessels of 21 feet draft can safely pass up the bay, but the anchcorage for vessels of this draft is limited to ½ mile square or less.

Black Ledge, a pinnacle bare at low water and marked by a buoy, lies on the western side of the approach to Chandler Bay from the sea, ¼ mile eastward of Head Harbor Island. It is marked by a black buoy on the east side.

Eastern Ledges are about ¼ mile long east and west and lie 1¼ miles eastward (true) from Mark Island. At its easterly end is a rock bare at low water, and at its westerly end are two sunken rocks nearly awash at low water. A rock, covered near high water and nearly always marked by a breaker, lies ⅝ mile east-northeastward of Eastern Ledges.

Great Spruce Ledges lie close to the south side of Great Spruce Island. The southernmost rock is covered at high water.

Little Spruce Ledge, off the southwest side of Little Spruce Island, is partly bare at low water.

Digitized by Google

Ballast Island, on the western side of the main channel through Chandler Bay, is grassy; a black buoy marks the end of the ledge extending eastward from it.

DIRECTIONS, ENGLISHMAN AND CHANDLER BAYS.

The following directions are for a draft of 17 feet or less to the anchorage northward of Roque Island. Vessels bound from eastward usually go to the anchorage through Englishman Bay, and if bound from westward usually enter through Chandler Bay. The bottom is rocky and uneven and has not been closely examined, and there are many unmarked shoals. For these reasons, caution is necessary.

Through Englishman Bay.—Pass about midway between The Brothers and Scabby Islands and steer 307° true (NW by N mag.) for Shoppee Island (flat, with scattered trees) until nearly up to it, passing well eastward of a black buoy 7/8 mile south-southeastward of Shoppee Island. Pass about 300 yards westward of Shoppee Island and select anchorage above it or in Pond or Shorey Coves.

If entering through Foster Channel (see p. 65), from the black buoy at the western end steer 275° true (NW by W 3/4 W mag.) for 1 7/8 miles to a position 200 yards southward of the red buoy marking Codhead Ledge, then 291° true (NW 3/8 W mag.) for 2 1/2 miles, and pass 300 yards westward of Shoppee Island.

Through Chandler Bay.—If entering from eastward, follow the directions on page 48 for approaching the eastern end of Moosabec Reach until northward of Mark Island; or if bound from westward through Moosabec Reach, follow the directions on page 49 until northward of Mark Island. Then bring the western end of Mark Island astern on a 348° true (N 3/4 E mag.) course, and pass about 250 yards eastward of the black buoy eastward of Ballast Island and the same distance westward of Roque Island Ledge red buoy. From this buoy, steer 38° true (NE by E mag.) for Little Ram Island, and pass about 250 yards southeastward of Great Bar black buoy. Select anchorage anywhere northward of Roque Island or in Pond or Shorey Coves, taking care to avoid the shoal on the western side northward of Great Bar.

CHANDLER BAY TO PLEASANT BAY.

Moosabec Reach.—This thoroughfare (chart 304) is the narrow passage west of Chandler Bay, leading between the mainland on the north, and the group of islands between Chandler Bay and Pleasant Bay on the south. Mark Island, heavily wooded, is the prominent guide to the eastern entrance, and Nash Island lighthouse to the western entrance. This passage is an important thoroughfare and is much used by vessels of 12 feet or less draft in the daytime; a draft of 23 feet can be taken through at high water. Sailing vessels of over 12 feet draft are advised to take a pilot. The eastern entrance has been straightened and dredged to a width of 300 feet and a depth of 14 feet. It is well buoyed and can readily be followed in the daytime in clear weather, but strangers should not attempt to pass through at night.

Pilots can sometimes be had at the eastern entrance by sending to Kelleys Point, and at the western entrance by sending to either Cape

Digitized by Google

Split Harbor or Tabbott Narrows, or from local fishing boats. The channel westward of the dredged channel has a least width of 300 yards in several places before reaching Tabbott Narrows, but it is straight, and the most prominent dangers are marked by buoys or spindles. Vessels headed off by the wind or caught in a fog while passing through the Reach anchor anywhere in the channel where the bottom is soft. Ice obstructs navigation during January and February. The mean rise and fall of tides is 11½ feet.

DIRECTION from eastward and westward are given on page 48. Approaching from southward, steer for the eastern end of Mark Island on a 304° true (NW ¾ N mag.) course, which will lead between Breaking Ledge and the dangers near Eastern Ledges, and pass eastward and northward of Mark Island, giving it a berth of over 200 yards.

JONESPORT is a village on the north shore of Moosabec Reach from 1¼ to 2¾ miles westward of Kelleys Point. There is communication by telephone and stage with Columbia Falls, the nearest point on the railroad. The depth at the ends of the cannery and steamboat wharves is about 15 feet at low water; most of the other wharves run dry. Pilots for the adjacent waters can generally be found by inquiry at Jonesport. Motor boat supplies are obtainable and there is water on the wharves. There are machine shops for minor repairs.

THE TIDAL CURRENTS have considerable velocity in the dredged channel, particularly at the light on the stone jetty which extends northwestward from Nova Rocks.

BEALS ISLAND, on the south side of the Moosabec Reach opposite Jonesport, has a village (Beals post office) at its northern end. The main wharf, on the north side, has a depth of 8 feet at the end; the wharves in a cove on the west side are bare at low water.

INDIAN RIVER and WEST RIVER, making northward at the western end of Moosabec Reach, have crooked unmarked channels fringed by rocks, and are frequented only by local fishermen. There are no landings except for small craft at high water.

The following is a description of the islands adjacent to the usual route bound westward from Moosabec Reach through Tabbott Narrows. **Pomps Island** is grassy and has a single clump of trees. **Hardwood Island** is wooded, and has a house on the north end and a quarry on the south end. **Shabbit Island Ledge** has a small spot bare at high water. **Shabbit Island** is low and wooded in the center. **Sheep Island**, on the northwest side of Tabbot Narrows is grassy, and **Ram Island**, on the southeast side is wooded.

Islands and channels south of Moosabec Reach (chart 304).—Lying between Chandler Bay and Pleasant Bay and extending about 5 miles southward from Moosabec Reach, is a group of islands, which, though of no commercial importance, form several prominent landmarks for vessels passing along the coast. The passages between these islands lead to several small and sheltered anchorages, of which Mistake Harbor is the only one available for strangers on account of numerous unmarked rocks and ledges.

Head Harbor is between Head Harbor Island, the easternmost of the group, and Steel Harbor Island, and is a sheltered anchorage with depths of 15 to 21 feet. The harbor is small and has unmarked rocks bare at low water on both sides of the entrance and anchorage. Strangers should not enter without a pilot. The rocks of **Man Island**,

Digitized by Google

the eastern side of the entrance, are dark, and those on the western side are light in color. There is a small settlement on **Crow Point**, at the western end of Head Harbor, and another farther northward, on the western end of **Head Harbor Island**.

Mistake Harbor.—This harbor, on the northwest side of Steel Harbor Island, is small, but affords a secure anchorage with depths of 4 to 7 fathoms. It is entered from southward through Main Channel Way, a deep but narrow channel leading between STEEL HARBOR ISLAND on the east and MISTAKE and KNIGHT ISLANDS on the west. With care the harbor may also be entered by vessels through Mud Hole Channel; vessels delayed by a head wind in Mistake Harbor sometimes beat out through the Mud Hole Channel. The black buoy in the middle of Mistake Harbor marks a rock bare at low water only.

GREEN ISLAND is the largest of the islands and rocks extending northwestward along the south side of Mistake Harbor. The northernmost rock of the group is bare at low water and lies 350 yards northward of Green Island and 200 yards northwestward of the outer bare rocks northeastward of the island. At the northwestern end of the group are two sunken rocks with 4 feet over them, which lie 300 yards northwestward of the outer bare rock lying 300 yards northwestward of the island.

MOOSE PEAK LIGHTHOUSE, on the southwest side at the entrance to Main Channel Way, is a white tower connected with a white dwelling. The light is flashing white (flash 4 seconds, eclipse 26 seconds), 72 feet above the water, and visible 14 miles.

EASTERN BAY lies between Head Harbor and Great Wass Islands northward of Mistake Harbor; a thorough local knowledge is required for its navigation.

MUD HOLE CHANNEL is ½ mile westward of Moose Peak lighthouse and leads northwestward to the Mud Hole, a narrow cove in Great Wass Island used by boats which enter at high water and lie aground at low water. There is good anchorage for a small vessel at the entrance to Sand Cove and Mud Hole, in 14 to 30 feet, soft bottom.

On the southwest side of Mud Hole Channel and extending nearly 1 mile in a southeasterly direction from Little Cape Point, Great Wass Island, is a group of rocks and ledges called BLACK LEDGES, many of which are bare at half tide. CHANNEL ROCK, the southeasternmost of the Black Ledges, is awash at high water and lies 600 yards northeastward of FREEMAN ROCK, a bare rock about 40 feet high.

The principal dangers on the northeast side of Mud Hole Channel are a rock, bare at low water, lying 150 yards off the southwest side of the island on the northeast side, at the entrance, and a sunken rock lying 350 yards westward of Green Island and 250 yards southward of the bare rock northwestward of the island.

DIRECTIONS, MISTAKE HARBOR.—Give the south end of Steel Harbor Island a berth of about ¼ mile when southeastward of it and enter in mid-channel, about 400 yards eastward of Moose Peak lighthouse, on a 301° true (NW ½ N mag.) course. When through the narrowest part of the channel, select anchorage between the northwest end of Knight Island and the black buoy ½ mile northwestward of it, in 4 to 7 fathoms.

Digitized by Google

To Leave by Mud Hole Channel.—From Mistake Harbor steer 287° true (NW ¾ W mag.) for the southwest side of Minx Island in range with the high bluff on the south side of Sand Cove North, and pass about midway between the outer bare rock northeastward of Green Island and the black buoy northward. Pass 200 to 400 yards southeastward of Minx Island and steer 181° true (S by W ⅞ W mag.), with eastern end of Minx Island in range with the northwestern end of Head Harbor Island astern. When a little over ¼ mile westward of the outer bare rock northwestward of Green Island, steer 123° true (SE ¾ S mag.), pass about ¼ mile southwestward of the rock, and pass about midway between Water Island and Channel Rock to sea.

Western Bay, lying westward of Great Wass Island, has numerous groups of islands which lie generally in a north and south direction. Between the groups are passages that lead to the western end of Moosabec Reach and are used by vessels with local knowledge. There is a small settlement on the western side of Great Wass Island in the vicinity of the Coast Guard station, in a cove locally known as **Black Duck Cove.**

The passage between Great Wass Island and Crumple Island has numerous unmarked sunken rocks and is also obstructed by a line of ledges and rocks extending from Browney Island to Great Wass Island. There is a narrow channel with a depth of about 11 feet through these ledges, marked by Popplestone Ledge red buoy. This passage should not be used by a stranger.

Crumple Island is a high, bare, rocky island with several nubbles; on its summit is a flagstaff and lookout house. Fisherman and Browney Islands lie northwestward of Crumple Island, with rocks and ledges between. **Egg Rock,** a bare, rocky islet, lies 1½ miles westward of Crumple Island, with numerous rocks and ledges between. **Western Egg Rock** is a small, bare, rocky islet about ½ mile northward of Egg Rock. **Sea Horse Rock** is bare at half tide and lies ⅜ mile westward of Egg Rock.

The passage between Sea Horse Rock, Western Egg Rock, and Ram Island on the east, and the Sand and Drisco Islands on the west, has a broad channel in its southern part, although there are unmarked dangers on either side. The northern end of the passage, on either side of Hardwood Island, is foul, and the passage should not be used by strangers.

The passage westward of the Sand and Drisco Islands and Shabbit Island and eastward of Black Rock, Flat Island, and Plummer Island is comparatively clear. There is also a comparatively clear passage westward of Black Rock, Flat Island, and Green Island and eastward of Cone Island. Both passages can be used by vessels in the daytime and clear weather with the assistance of the chart.

Sand and **Outer Sand Islands** are partly wooded. The **Drisco Islands, Stevens,** and **Plummer Islands** are wooded. **Flat** and **Green Islands** are comparatively low and covered with grass. The highest parts of **Stanley Ledge** (¼ mile southward of Outer Sand Island) and **Batson Ledge** (⅜ mile eastward of Sand Island) show above high water. **Black Rock** is a low, bare rock lying 1¼ miles south-southwestward of Flat Island and 2⅛ miles south-southeastward of Nash Island lighthouse.

Digitized by Google

Cape Split Harbor, lying 2 miles northeastward of Nash Island lighthouse, is a secure anchorage for small vessels, and with the aid of the buoys is easily entered in the daytime. The harbor has extensive flats and ledges, between which is a channel 200 yards or more wide. The anchorage with best swinging room is ⅜ to ½ mile inside the entrance, from abreast a red buoy to just above a black buoy, in 3 to 4 fathoms; and vessels of less than 9 feet draft can anchor in the entrance of the cove on the eastern side opposite the black buoy, in 9 to 15 feet. The flats are soft mud in places, and small vessels are sometimes beached on them. A reef, which shows well at low water, extends 400 yards southward and southwestward from the eastern point at the entrance, and is marked on its western side by a red buoy. There is a landing and small settlement on the bay; some motor-boat supplies are obtainable.

The approach to Cape Split Harbor between Sheep Island and The Ladle is clear if these islands be given a berth of over 300 yards. From westward the approach is clear between the spindle southward of Norton Island and the Pot Rocks. Enter the harbor midway between the red and black buoys at the entrance on a 12° true (NNE ¾ E mag.) course.

PLEASANT, NARRAGUAGUS, AND PIGEON HILL BAYS

(chart 305) indent the shore between Nash Island lighthouse on the east and Petit Manan lighthouse on the west, and form the approach to the villages of Addison Point, Harrington, Millbridge, and Cherryfield, all on tributaries of the bays. They are frequented mostly by local fishing boats and a few lumber schooners. The bays are separated by islands and rocks, through which several thoroughfares lead.

Pleasant Bay.—This bay is a secure anchorage and is easily entered in the day time. There are numerous islands and ledges in the bay, but the important dangers are marked by buoys. The entrance is marked by Nash Island lighthouse. A channel in no place less than ½ mile wide, with depths of 6 fathoms or more, leads up the bay to an anchorage in 5 to 6 fathoms westward of Night Cap Island and southward of Barton Ledge. The best and most frequently used anchorage is southeastward and eastward of Birch Islands, in 14 to 18 feet.

Cone and Nash Islands, on the eastern side of the entrance to Pleasant Bay, are grassy. A ledge, the southern end of which shows bare, extends about 500 yards southward from Nash Island.

Nash Island Lighthouse is a white square tower connected with dwelling. The light is fixed red, 51 feet above the water, and visible 9 miles. The fog signal is a bell (1 stroke, silent 20 seconds; 2 strokes, silent 20 seconds).

The Ladle, ¾ mile southwestward of the entrance to Cape Split Harbor, has a bare symmetrical mound at its northern end.

Pot Rock and Big Pot, westward of The Ladle, are bare rocks.

Flint Island, on the west side at the entrance of Pleasant Bay, is sparsely wooded. The southeastern side should be given a berth of at least ¼ mile.

Coles Ledge, ¼ mile eastward of Flint Island, is bare near low water and marked on its eastern side by a black buoy.

Digitized by Google

Flint Island Narrows is a deep passage leading from Pleasant Bay to Narraguagus Bay, between Flint and Dyer Islands. It is used principally by steamers, and is not recommended for sailing vessels on account of ledges which make out from the southern shore of Dyer Island and contract the channel to a width of about 200 yards. A black buoy is placed on the northern edge of the ledges making off from the northeastern side of Flint Island and marks the eastern entrance to the Narrows. The course through the Narrows is 232° true (WSW¼W mag.), passing 50 yards northwestward of the black buoy and about 150 yards off the northwest sides of Flint and Shipstern Islands.

Norton Island is grassy. Norton Island Ledge, ¼ mile westward of Norton Island, is bare in spots at high water. The reef extending ¼ mile southward from the west end of Norton Island is partly bare at high water, and marked by a spindle at the end.

Narrows Island Ledge is bare at half tide.

Pleasant River, emptying into the head of Pleasant Bay from northeastward, can be approached on either side of Birch Islands, the channel eastward of them having a depth of 16 feet, and that westward 17 feet. For a distance of about 2 miles up the river to Wass Point, the channel, with a depth of over 12 feet narrows gradually from 400 to 200 yards, and affords good anchorage in 3 to 6 fathoms. Above Wass Point the channel is narrow and crooked, with a least depth of 5 feet at one place just below Addison Point, and is suitable only for small craft, except with local knowledge. Above this the river is navigable at high water to Columbia Falls, about 10 miles above its mouth.

The channel is partially marked by buoys and easily followed with the aid of the chart to Wass Point. For about 1 mile above to White Point, the channel is bordered by ledges, bare at various stages of the tide, and marked by beacons and sometimes by local bush stakes, but is difficult to follow. From White Point to Addison Point, there are shoals on either side bare at low water; the channel is unmarked, but is most easily followed at low water or on a rising tide. The river above Addison Point is unmarked and difficult. Pilots for the river can usually be obtained from local fishing boats. Ice obstructs navigation from December to April.

Night Cap Island, on the east side at the entrance to Pleasant River, is grassy, with a few bushes on the north side. Night Cap Ledge, extending southward from the island, is bare at the inner end at half tide.

Barton Ledge, ⅜ mile northward of Night Cap Island, is bare at low water and marked by a horizontally striped buoy.

Bunker Ledge, ¼ mile westward of the southern Birch Island, is bare at half tide, and marked on its eastern side by a black buoy.

Birch Islands are wooded. Raspberry and Mink Islands, northward of Birch Islands, are grassy. Fort Island is marked by a shanty.

Addison Point, a village about 5 miles above the mouth of Pleasant River, has a little trade. Vessels of 12 feet draft go up at high water as far as this; there is from 2 to 4 feet of water alongside the wharves. Just above Addison Point the river is crossed by a highway bridge (width of draw 36 feet.) The village of Columbia

Digitized by Google

FALLS is 5 miles above and has railroad communication; the deepest draft of vessels trading there is 9 feet. The wharves run dry at low water.

Harrington Bay is separated from the upper part of Pleasant Bay on the east by RIPLEY NECK, and from Narraguagus Bay on the west by FOSTER ISLAND. The bay extends 2½ miles in a northerly direction from Strout Island to Chamberly Island, where it is met by Harrington River from northeastward and by Flat Bay and Mill River from northwestward. It has a depth in the channel of 4¾ fathoms, and good anchorage in 5 to 7 fathoms, but is seldom used except by local vessels.

FLAT BAY and MILL RIVER are mostly bare at low water, and seldom used except by an occasional wood schooner.

HARRINGTON RIVER has a narrow, crooked unmarked channel, with a depth of 2 feet at low water to the town of HARRINGTON, at the head of navigation on Harrington River about 4 miles above its mouth. The greatest draft taken up to the town is 12 feet; the usual draft is 6 to 10 feet. There is 2 feet alongside the wharves at low water. The town has railroad communication. Ice forms in the river and bay between December and April as far down as Ripley Neck.

STROUT ISLAND, in the middle of the entrance of Harrington Bay, is sparsely wooded. STROUT ISLAND LEDGES, southeastward of Strout Island, are covered at high water; the south end is bare at low water and marked by a red buoy. A rock awash at low water and marked by a red buoy lies ¼ mile eastward of the south end of Strout Island Ledges.

SHAG ISLET is a low bare rock.

Dyer Island Narrows, the passage between Dyer Island and Foster Island, has a depth of 9 feet at low water, and connects Harrington Bay with Narraguagus Bay. This passage is buoyed, but is not suitable for sailing vessels on account of the sharp turns and narrowness of the channel. There are numerous dangers close to the channel, and the buoys must be closely followed.

To go through Dyer Island Narows, pass about 75 yards eastward and 50 yards northeastward of the black buoy lying 300 yards westward of the northern end of Strout Island, steer 304° true (NW ¾ N mag.), and pass 50 yards northward of the next black buoy. Haul sharply southwestward around this buoy, leaving it about 50 yards on the port hand, and steer 209° true (SW ¼ W mag.) to a position 100 yards westward of another black buoy. Then steer 235° true (WSW ½ W mag.), and pass close northward of the black buoy at the western end.

Narraguagus Bay.—This bay lies north-northeastward of Petit Manan and northwestward of Nash Island. The lower part of the bay is a well sheltered anchorage, much used as a harbor of refuge in all seasons by vessels up to 18 feet draft. The principal dangers in the channels are buoyed, and the lighthouses on Nash Island, Petit Manan, and Pond Island (Narraguagus light) are guides for the entrance. It is connected with Pleasant Bay by Flint Island Narrows, and with Harrington Bay by Dyer Island Narrows, both previously described.

JERRY LEDGE, off the southeast end of Bois Bubert Island, is bare at low water.

Digitized by Google

JORDANS DELIGHT LEDGE, in the middle of the entrance to Narraguagus Bay, has a rock at its southwest end, bare at low water and marked by a spindle.

BLACK LEDGE, at the northeast end of Jordans Delight Ledge, is bare at half tide. The ground in this vicinity is very broken and should not be crossed by vessels.

MACKEREL ROCK, an unmarked rock with 10 feet over it, lies 1¼ miles 111° true (SE ½ E mag.) from Narraguagus lighthouse, and ⅝ mile northeastward of Black Ledge, in range with the latter and Petit Manan lighthouse.

JORDANS DELIGHT is a rocky island, sparsely wooded on top.

POND ISLAND shows from southward as a bare conical hill 160 feet high, and is marked on its eastern side by Narraguagus lighthouse.

NARRAGUAGUS LIGHTHOUSE is a white tower connected with dwelling. The light is fixed white, 54 feet above the water, and visible 11 miles. During fog, a bell is struck by hand in answer to signals.

DOUGLAS ISLANDS are wooded.

DOUGLAS ISLAND HARBOR lies north of the Douglas Islands (wooded) and west of Pond Island. It has anchorage in 4 to 6 fathoms, but is seldom used, the anchorage above Trafton Island being better. Considerable sea makes into the harbor in heavy southerly weather. The harbor is clear except at its southwest end, where DOUGLAS ISLAND LEDGES, partly bare at low water, extend 350 yards northwestward from the middle Douglas Island. The dangers in the southern part of the harbor will be avoided by keeping the summit of Pond Island bearing southward of 94° true (ESE mag.).

Entering Douglas Island Harbor northward of Pond Island, pass northward and at least ¼ mile westward of the black buoy on the end of the ledge which extends nearly ⅜ mile northward from Pond Island. The harbor may also be entered from southward between the islands, the best channel being between the wooded island near the southwest end of Pond Island on the east, and the eastern one of the three Douglas Islands and the bare rock 250 yards southward from it on the west. Entering by this passage, avoid two rocks, bare at low water, which lie 125 yards southwestward of the wooded islet lying 250 yards off the middle of the west side of Pond Island.

A narrow channel, said to have a depth of at least 8 feet at low water, but bordered by rocks sunken and awash, on either side, leads from Douglas Island Harbor into the head of Pigeon Hill Bay. It is sometimes marked by bush stakes, but local knowledge is necessary to carry the best water. The best water leads about 75 yards northward of Currant Island (wooded in the center) and then about 283° true (NW by W ⅛ W mag.) with the highest point of Pond Island astern, until into the main channel of Pigeon Hill Bay.

SHIPSTERN ISLAND, on the eastern side, at the entrance of Narraguagus Bay is high, round, and wooded, and has rocky bluffs on its south side.

WESTERN REEF extending ⅜ mile southward from Tommy Island, has a bare rock on its southern end, and is marked by a red buoy.

TOMMY ISLAND is low and sparsely wooded.

TRAFTON ISLAND is wooded. There is a good channel on either side.

TRAFTON ISLAND LEDGE, in the middle of the entrance to the cove on the north side of Trafton Island, is a bare rock.

Digitized by Google

HALF TIDE LEDGE, 5/8 mile northward of Trafton Island, is partly bare at low water and marked by a spindle near its northern end.

WYMAN is a small settlement of fishermen on the western side 1¾ miles northward of Trafton Island. A fish cannery and wharf is located here; gasoline and some provisions are obtainable.

NARRAGUAGUS RIVER, emptying into Narraguagus Bay from northward, has a least depth of about 4 feet to Millbridge, 2 miles above the mouth at Wyman. The channel is narrow, crooked, and leads between flats on each side bare at low water. It is partially marked, but local knowledge is necessary to carry the best water. Strangers should navigate it on a rising tide.

MILLBRIDGE has some ship building business, and ships considerable lumber in small vessels. A draft of 16 feet can be carried to the town at high water, but the usual draft does not exceed 9 feet. There is a depth of about 7 feet at the upper wharf; the lower wharf is in bad repair. A drawbridge with an opening 26 feet wide crosses the river at Millbridge. The draw is close to the south shore, and the channel through it is bare at low water. The opening under the fixed section at the north end is also shoal and not navigable at low water. The current through both openings is very strong.

NARRAGUAGUS RIVER BETWEEN MILLBRIDGE AND CHERRYFIELD, a distance of about 4 miles, is bare at low water throughout most of its length, and the deepest draft using it is about 5 feet at high water and with local knowledge.

CHERRYFIELD has railroad communication. Its principal industry is lumber, which is brought down to Millbridge in scows at high water.

Pigeon Hill Bay.—This bay, having its entrance on the eastern side of Petit Manan Bar and northward of Petit Manan lighthouse, is easy of access by day, and affords good anchorage in 12 to 24 feet, but is seldom used except by local fishermen. The channel is unmarked except at the entrance. There is a small settlement, and a wharf bare at low water on the west side near the Carrying Place. A watch tower on the western side is visible above the trees in all directions.

WHALE LEDGE, on the east side at the entrance to Pigeon Hill Bay, is bare at half tide. A red buoy marks a 13-foot spot 300 yards southward of it.

EGG ROCK shows at low water as a large ledge of dark bowlders, with several high parts which are always out of water. There is a narrow channel between Egg Rock and BOIS BUBERT ISLAND, but a stranger should not attempt it.

GULL ROCKS are a large ledge, bare at half tide, making off ¼ mile from the shore of Bois Bubert Island about 1⅜ miles northward of Egg Rock. These rocks are avoided by keeping in mid-channel.

PIGEON HILL, the high, bare-topped hill on the western shore near the head of the bay, is conspicuous, and a landmark for some distance at sea.

The thoroughfare connecting the head of Pigeon Hill Bay with Douglas Island Harbor is described on page 78.

IN ENTERING PIGEON HILL BAY, having made the red buoy on the east side of the entrance, a 349° true (N ¾ E mag.) course with Pigeon Hill ahead and Petit Manan lighthouse astern, will lead ¼ mile westward of the red buoy, and clear of all dangers until inside

Digitized by Google

the bay. Follow a mid-channel course in the bay, and anchor above Gull Rocks in 3 to 4 fathoms, soft bottom. Small vessels anchor on the west side off the Carrying Place.

Petit Manan Bar connects Petit Manan Island with Petit Manan Point on the mainland; it is composed of ledges and large bowlders, between which is a channel, marked by a perpendicularly striped buoy, which may be used by vessels of 8 feet draft at low water when the sea is smooth. The sea breaks along the whole length of the bar with a swell or in heavy weather, and the tidal currents set over it with considerable velocity, the flood northeastward, the ebb southwestward; sailing vessels are cautioned not to approach the bar in a light breeze.

The buoy marking the channel across Petit Manan Bar is 1¼ miles north-northwestward of Petit Manan lighthouse and 1 mile south-southeastward of the end of Petit Manan Point. The buoy can be left close to on either side.

Another channel across the bar, ⅜ mile southeastward of **Petit Manan Point**, is used by small local boats at all stages of the tide, but it is unmarked and difficult, and should not be attempted by strangers.

Petit Manan Island is low and bare, and marked by the lighthouse and several buildings.

Petit Manan lighthouse is a gray granite tower. The light is fixed white, with a white flash of 6 seconds duration every 2 minutes, 123 feet above the water, and visible 17 miles. The fog signal is an air whistle (blast 3 seconds, silent 27 seconds).

Supplies.—Gasoline and provisions are obtainable at all of the towns and villages on the rivers at the head, but Wyman and Millbridge are the only places convenient to the bays where supplies are obtainable.

Repairs.—There are no facilities for repairs.

Pilots are not necessary to enter the bays. Local fishermen can usually be found to pilot vessels up to the towns on the tributaries.

Ice.—From December to April ice usually forms on Pleasant River and Harrington River to their mouths, and very frequently on Harrington Bay. Ice seldom obstructs navigation in Narraguagus River except in January and February, during which time the river is usually frozen to the mouth.

Anchorages.—The usual anchorage for vessels seeking shelter in Narraguagus Bay is between Trafton Island and Lower Middle Ground buoy, in 21 feet, soft bottom; vessels of 10 feet draft or less sometimes anchor in 14 to 17 feet north of Trafton Island, about midway between it and the spindle on Half Tide Ledge. Vessels bound up to Millbridge anchor in 14 to 16 feet about ½ mile east of Wyman, the wharf bearing about 274° true (WNW mag.). Good anchorage in 24 feet, soft bottom, will be found about ⅜ mile northeastward of the spindle on Half Tide Ledge.

Vessels also anchor in Pleasant Bay in 5 to 6 fathoms, westward of Night Cap Island and southward of Barton Ledge; the best and most frequently used anchorage for small vessels in Pleasant Bay is southeastward and eastward of Birch Islands, in 14 to 18 feet.

Tides.—The mean rise and fall of tides is 11 feet at Nash Island, 11.8 feet at Addison Point and 11.3 feet at Millbridge.

Digitized by Google

DIRECTIONS, PLEASANT AND NARRAGUAGUS BAYS.

This locality is very rocky and broken, and has not been examined by means of a wire drag. Vessels should therefore avoid all rocky and broken areas, as there is no certainty that all of the shoals are charted, or that the least depth on those charted has been found.

Pleasant Bay.—Vessels entering Pleasant Bay from eastward, southward of the islands between Chandler and Pleasant Bays, can pass ¼ mile southward of Seahorse Rock bell buoy, and steer 277° true (NW by W ⅝ W mag.) for 3¼ miles to a position ⅜ mile southwestward of Black Rock, and then 316° true (NNW ¼ mag.) for 2¼ miles to a position ⅜ mile west-southwestward of Nash Island lighthouse.

Then steer 338° true (N ¼ W mag.) for nearly 2 miles, passing ⅜ mile eastward of Coles Ledge buoy and to a position ⅜ mile westward of Norton Island Ledge. Then steer 12° true (NNE ¾ E mag.) for the eastern end of Birch Islands in range with Tumble-down Dick Head, and pass 250 yards westward of Night Cap Island. Anchor anywhere eastward or southeastward of the south end of Birch Islands, in 14 to 18 feet, soft bottom.

ENTERING FROM TABBOTT NARROWS, steer 267° true (WNW ⅝ W mag.) with the south end of Ram Island astern, and pass nearly ¼ mile northward of The Ladle and the same distance southward of the spindle on the end of the ledge extending southward from Norton Island. Pass southward and westward of Norton Island Ledge at a distance of about ¼ mile, steer 12° true (NNE ¾ E mag.), and proceed as directed in the preceding paragraph.

ENTERING FROM WESTWARD, from the perpendicularly striped bell buoy 1 mile southward of Petit Manan lighthouse, steer 32° true (NE ½ E mag.) for 8 miles to a position ½ mile northwestward of Nash Island lighthouse. Then steer 338° true (N ¼ W mag.) and proceed as directed in entering from eastward. The 32° true (NE ½ E mag.) course leads ⅜ mile southeastward of JO LEIGHTON GROUND, a rocky area with a least found depth of 15 feet. Vessels should exercise care not to be set upon it.

Harrington Bay.—Follow the directions for entering Pleasant Bay, until 1 mile north-northwestward of Nash Island lighthouse, and then steer 319° true (NNW mag.) with the lighthouse astern, and pass midway between Otter Island and Strout Island. Follow the western side of Strout Island at a distance of about 200 yards and pass about 75 yards eastward of buoy No. 1. Then steer about 1° true (N by E ¾ E mag.), pass 125 yards westward of Shag Islet, and then follow the eastern shore at a distance of about 300 yards. Anchor anywhere in the channel on the eastern side of the bay.

Narraguagus Bay.—In entering from eastward, southward of the islands between Chandler Bay and Pleasant Bay, pass ¼ mile southward of Seahorse Rock bell buoy, and steer 277° true (NW by W ⅝ W mag.) for 3¼ miles to a position ⅜ mile southwestward of Black Rock, then steer 300° true (NW ⅜ N mag.) for the southwest end of Trafton Island until ⅜ mile west-southwestward of Shipstern Island. Then haul westward and pass southward and westward of Trafton Island at a distance of about 300 yards, and steer 356°

Digitized by Google

true (N by E 3/8 E mag.). The depth will shoal gradually from 5 fathoms abreast Trafton Island to 15 feet about 1¾ miles above its southwest end, and anchorage can be selected in any depth desired.

Or, to pass eastward of Trafton Island, steer for its southwest end on a 300° true (NW 3/8 N mag.) course until ¼ mile southwestward of Western Reef buoy. Then steer 353° true (N by E mag.) and pass about 400 yards westward of the buoy, and midway between Trafton and Tommy Islands. Pass 200 to 300 yards eastward of Trafton Island and steer 336° true (N 3/8 W mag.). The depth will shoal gradually from 6 fathoms abreast Trafton Island to 15 feet 1¼ miles northward of it, and anchorage can be selected in any depth desired.

In entering from Moosabec Reach vessels can pass ¼ mile northward of Cone Island, at least ¼ mile southward of Flint Island and Shipstern Island, and proceed as directed in the preceding paragraphs.

From westward.—From the perpendicularly striped bell buoy 1 mile southward of Petit Manan lighthouse, steer 13° true (NNE 7/8 E mag.), pass about 5/8 mile southeastward of Bois Bubert Island, about 400 yards westward of Jordans Delight, the same distance eastward of Narraguagus lighthouse and about 200 yards eastward of the black buoy northeastward of the lighthouse. Then steer 336° true (N ½ W mag.) to a position 300 yards westward of Trafton Island, and then steer 356° true (N by E ¼ E mag.) to the anchorage. Or, to pass eastward of Trafton Island, from a position 200 yards eastward of the black buoy 400 yards northeastward of Narraguagus lighthouse, steer 8° true (NNE 3/8 E mag.) and pass midway between Trafton and Tommy Islands. Pass 200 to 300 yards eastward of Trafton Island and steer 336° true (N ½ W mag.).

COAST FROM PETIT MANAN TO FRENCHMAN BAY.

The bight inclosed between Petit Manan Bar and Schoodic Peninsula is the approach to Dyer and Gouldsboro Bays and Prospect Harbor. Prospect Harbor is the most important village, although Gouldsboro and Steuben can be reached by small craft at high water. These waters are frequented only by local fishermen and a few lumber schooners. There are many rocks in the approach and tributaries, not closely examined, and vessels should use caution when crossing broken areas where the charted depth does not considerably exceed the draft.

Moulton Ledge, off the entrance to Dyer and Gouldsboro Bays, 3 miles west-northwestward of Petit Manan lighthouse, is bare at low water. There are several other unmarked ledges and broken ground in this vicinity, and it should be avoided by vessels.

Dyer Bay (chart 305), the entrance to which lies 3 miles northwestward of Petit Manan lighthouse, has excellent anchorage in 4 to 7 fathoms, but it is unmarked and seldom used except by small local vessels. Petit Manan Point, on the eastern side of the bay, has a large watch tower which forms a prominent mark. A group of islands and rocks, with narrow, deep passages between them, extends from westward across the entrance of Gouldsborough Bay and part way across Dyer Bay entrance, leaving a good passage nearly ½ mile wide between the easternmost bare ledge, The Castle, and Petit

Digitized by Google

Manan Point. One mile above The Castle the channel is contracted to a width of 250 yards by rocks and ledges, which extend out from both shores and have a depth of 9 to 11 feet over them. Above this the channel widens to ½ mile, and contracts gradually to ¼ mile westward of Sheep Island. The least depth in the channel is 3¼ fathoms, but a stranger should not attempt to enter at low water with a vessel of more than 9 feet draft. There are no commercial wharves.

PINKHAM BAY, at the head of Dyer Bay, is full of rocks and ledges; a narrow, crooked channel with a depth of 8 feet at low water leads for some distance toward its head, which runs dry at low water.

DYER HARBOR, north of Sheep Island and west of Good Point, is shallow; the upper part is dry at low water.

CARRYING PLACE COVE makes southeastward, north of Sheep Island; the head of this cove is nearly all dry at low water and is 300 yards from Pigeon Hill Bay.

THE TIDAL CURRENTS are strong in the entrance of Dyer Bay, but follow the general direction of the channel except near Dyer Point, where they set in and out of Gouldsborough Bay.

THE CASTLE, BONNY CHESS LEDGE, and LITTLE LEDGE are bare ledges, without distinguishing marks.

YELLOW BIRCH HEAD, on the east side ⅞ mile northeastward of The Castle, is a high, bare bluff. The channel at this point and for ⅜ mile above is contracted to a width of about 300 yards by unmarked ledges on either side, having least found depths of about 9 feet. The best water is about in mid-channel.

DIRECTIONS, DYER BAY. ENTERING FROM EASTWARD.—From the perdendicularly striped bell buoy 1 mile southward of Petit Manan lighthouse, steer 315° true (NNW ⅜ W mag.) for 3¼ miles until the south end of Petit Manan Point is ⅝ mile distant and in range with Egg Rock, bearing 60° true (E by N mag.). Then steer 351° true (N ⅞ E mag.) and pass 250 yards eastward of The Castle. Then bring it astern on a 359° true (N by E ⅝ E mag.) course, heading to pass in mid-channel westward of Sheep Island. Select anchorage near the middle of the bay when over 1¼ miles above The Castle, in 4 to 7 fathoms, but do not go over ¼ mile above Sheep Island.

ENTERING FROM WESTWARD.—From the whistling buoy off Schoodic Island, steer 46° true (NE by E ¾ E mag.) for 7 miles, passing ⅜ mile southeastward of Little Black Ledge, ⅝ mile northwestward of Stone Horse Ledge, and to a position ⅜ mile southward of The Castle. Pass about 250 yards eastward of The Castle and proceed as directed in the preceding paragraph.

Gouldsboro Bay.—This bay (chart 305) lies 4 miles northwestward of Petit Manan lighthouse and 6 miles northeastward of Schoodic Island. It forms an excellent anchorage in 2 to 9 fathoms. It is the approach to the villages of Gouldsboro and Steuben, 6½ and 7 miles, respectively, above the entrance, but the approaches to these villages are unmarked and can be navigated only by small craft at high water, and are little used. Ice obstructs navigation in the bay from December to March. In severe winters the bay is closed to the entrance.

SALLY ISLANDS, a chain of small islands and ledges, extend across the entrance; through the chain are two navigable channels known as

Digitized by Google

Eastern Way and Western Passage. When approaching from westward, care must be taken not to mistake the passages, the islands being difficult to recognize. Inside the islands, the bay is free from outlying dangers and the water shoals gradually toward its head.

Eastern Way, or Ship Channel, leads into the bay between Eastern Island (wooded on top) and Bald Rock (a bare rock); it is about 350 yards wide between the 18-foot curves, and has a spot with 24 feet over it about 200 yards west of Eastern Island. This channel has the strongest tidal currents, and when the current is running ebb sailing vessels can enter only with a strong favorable breeze. The currents set diagonally across the channel.

Western Passage leads into the bay between Sally Island (rocky with grass on top) and Sheep Island (thickly wooded in center). It is about 200 yards wide between the 12-foot curves and leads close along the eastern side of Sheep Island westward of ledges bare at half tide; the least depth in the channel is 18½ feet. The tidal currents run true with the channel and have a velocity of 2 to 3 knots at strength.

There is a passage from Dyer Bay to Gouldsborough Bay north of Sally Islands. It is obstructed by rocks, partly bare at low water only, which extend 300 yards southward and southwestward from the southern end of Dyer Neck, and by a shelving ledge which extends 250 yards northeastward from Eastern Island. The channel where narrowest, abreast Eastern Island, is 250 yards wide, and the range of the northwest sides of Bald Rock and Sheep Island, bearing 240° true (W by S mag.), leads through the middle of it.

Point Francis, on the western shore, 3½ miles above the entrance, is high and wooded, and is prominent from the lower end of the bay.

Joy Bay, a shallow body of water 1½ miles long, with a narrow, crooked channel to the village of Steuben, makes northward from Gouldsborough Bay at Rogers Point; it separates into two coves at its head; the eastern one is Steuben Harbor and the western Joy Cove. Steuben can be reached at high water by vessels of 7 to 8 feet draft; the channel is nearly bare at low water, and is unmarked and seldom used.

Gouldsborough Harbor is a large shallow arm with numerous ledges at its entrance, making into the northwestern part of Gouldsborough Bay and extending about 2½ miles to the village of Gouldsborough, which is of no commercial importance. The harbor has a narrow, crooked, unmarked channel, nearly dry at low water, and is seldom used.

Directions, Gouldsboro Bay.—A depth of 4 fathoms can be carried into the bay through the Eastern Way, and 18 feet through the Western Passage. The tidal currents have a velocity of 2 to 3 knots at strength through these passages, and in Eastern Way they set diagonally.

From eastward, entering through Eastern Way.—From the perpendicularly striped bell buoy southward of Petit Manan lighthouse steer 312° true (NNW ⅝ W mag.) a little over 4 miles; the tidal currents set across this course with considerable velocity, the flood northeastward and ebb southwestward. Continue nearly this course and pass midway between Eastern Island and Bald Rock. When inside the islands steer a little more northward and stand up the middle of the bay; the water shoals gradually toward the head, and

Digitized by Google

anchorage can be had anywhere between the entrance and Point Francis by giving the shores a berth of 500 yards.

FROM EASTWARD, THROUGH WESTERN PASSAGE.—From the perpendicularly striped bell buoy southward of Petit Manan lighthouse steer 305° true (NW ¾ N mag.) for the northeastern side of Sheep Island. Pass about 100 yards off the eastern side of the island, steer 343° true (N ⅛ E mag.) and stand up the middle of the bay.

FROM WESTWARD, ENTERING THROUGH EASTERN WAY.—From the whistling buoy off Schoodic Island steer 46° true (NE by E ¾ E mag.) for 4¼ miles, passing ⅜ mile southeastward of Little Black Ledge and for ½ mile beyond, until Cranberry Point is in line with Prospect Harbor lighthouse. Then steer 29° true (NE ¼ E mag.) for the eastern end of Eastern Island until about ¼ mile from the island. Then steer about 342° true (N mag.) and pass about midway between Eastern Island and Bald Rock. Then steer more northwestward to avoid the rocks, bare at low water only, lying 300 yards off the southwest side of the south end of Dyer Neck, and then stand up the middle of the bay.

FROM WESTWARD, THROUGH WESTERN PASSAGE.—From the whistling buoy off Schoodic Island steer 46° true (NE by E ¾ E mag.), and continue the course for 1 mile after Cranberry Point is in range with Prospect Harbor lighthouse. Then steer 343° true (N ⅛ E mag.), keep the eastern side of Sheep Island aboard, distant about 100 yards, to clear the ledges which extend 450 yards westward of Sally Island, and stand up the middle of the bay.

Indian Harbor is a small cove between Gouldsboro Bay and Prospect Harbor, inside a group of grassy islands. It has depths of 10 feet in the entrance and 3 to 5 feet at the head. The best water leads westward of Western Island, and then favors the northeast side of Indian Harbor to the head. Small craft enter from Gouldsboro Bay, inside of all the islands, but strangers should not attempt this passage.

Corea is a post village of fishermen at the head of Indian Harbor. The wharf is bare at low water. A church and a group of houses are prominent for a considerable distance offshore. There is a store here, where supplies in limited quantities can be obtained.

Prospect Harbor.—This harbor (chart 305), 3 miles northeastward of Schoodic Island and 6 miles northwestward of Petit Manan lighthouse, is the approach to the village of Prospect Harbor. The outer harbor has ample depth and affords anchorage for the largest vessels, exposed to southerly winds. It is easily entered, but seldom used.

The ledges off the entrance to Prospect Harbor divide the approach into two channels; both are clear and deep if the ledges between them be avoided.

LITTLE BLACK LEDGE and BIG BLACK LEDGE show at high water, and OLD MAN and OLD WOMAN are partly bare at low water. The latter is marked by a red buoy at its southwest end.

SAND COVE, the eastern branch at the head of Prospect Harbor, has ample depth until near the head, but is seldom used.

INNER HARBOR, the western branch at the head, is marked on the eastern side by Prospect Harbor lighthouse, and on the western side by Clark Ledges spindle. It has a depth of 2 to 5 fathoms just inside, sheltered from all but southeast winds, and is extensively used by small local vessels. The anchorage is on the southwest side in soft

Digitized by Google

bottom, about 200 yards northward of a line joining Clark Ledges spindle and the fish factory on Clark Point.

PROSPECT HARBOR is a village of fishermen on Inner Harbor. The depth is 18 feet at the cannery wharf on Clark Point, and about 5 feet at the wharves just inside Clark Point. The wharf at the head is bare before low water. Gasoline and provisions are obtainable.

BIRCH HARBOR, on the western side of Prospect Harbor, 1½ miles above the entrance, has a depth of 6 feet for ½ mile, and shoals rapidly above. There is a small settlement of fishermen near the head; the landings are bare at low water. The channel is unmarked and difficult. The best water in entering favors the southwest side to avoid ROARING BULL, a rock bare at extreme low water.

BUNKER HARBOR, on the west side of Prospect Harbor just inside the entrance, has a small settlement of fishermen at the head. The landings are bare at low water. The entrance is obstructed by ledges. The outer one is BUNKER LEDGE, partly bare at low water only and marked at its eastern end by a black buoy. Inside of this are ledges awash at high water. The channels are unmarked and the one southward of the ledges in the entrance is said to be the best.

Directions, Prospect Harbor.—ENTERING FROM EASTWARD, from a position midway between the perpendicularly striped bell buoy southward of Petit Manan lighthouse and the red buoy ⅝ mile northward, a 285° true (NW by W mag.) course for 5½ miles will lead about midway between Moulton Ledge buoy and Stone Horse Ledge, and to the red bell buoy off the eastern point at the entrance to Prospect Harbor. Continue the course until ¼ mile northwestward of the buoy, and then steer for Prospect Harbor lighthouse on a 322° true (N by W ¾ W mag.) course until off the entrance to Inner Harbor. Then pass close to the perpendicularly striped buoy and steer 286° true (NW ⅞ W mag.) into the inner harbor, passing at least 100 yards northward of the spindle. Anchorage can be selected eastward or northeastward of the fish factory.

ENTERING FROM WESTWARD, vessels can pass ⅜ mile eastward of Schoodic Island and then steer 10° true (NNE ½ E mag.) for 3 miles, passing midway between Bunker Ledge and Old Woman buoys, and continue the course for 1 mile beyond to a position a little over ¼ mile off the western shore; then a 349° true (N ⅝ E mag.) course, heading for Prospect Harbor lighthouse, will lead eastward of a black buoy and to the perpendicularly striped buoy off the Inner Harbor. The course into the inner harbor is then 286° (NW ⅞ W mag.) as described in the preceding paragraph.

Schoodic Harbor, between Prospect Harbor and Frenchman Bay, has ample depth but is exposed to the sea and never used as an anchorage. There are no wharves. There are several islands and ledges in the entrance.

Schoodic Island is low and partly wooded on the south end. The north end is grassy. It is bordered by extensive ledges.

Schoodic Ledge, northward of Schoodic Island, is covered near high water and breakers are always visible. The channel between Schoodic Island and Schoodic Ledge is marked by a buoy on either side. It has ample depth and is generally used by small local vessels and motor boats, bound along the coast.

Middle Ledge is bare at about half tide.

Digitized by Google

The island in Schoodic Harbor northward of Schoodic Ledge has a few trees in the center.

Arey Cove, 1 mile westward of Schoodic Island, is exposed to a heavy sea and never used. There are no distinguishing marks.

FRENCHMAN BAY

(chart 306) lies westward of Schoodic Peninsula and eastward of Mount Desert Island. It is the approach to the towns and important summer resorts of Bar Harbor, Winter Harbor, South West Harbor, North East Harbor, and many smaller villages. The bay is frequented by many passenger steamers, yachts, small pleasure craft, and fishing vessels, and a few cargo vessels. The bay proper is about 10 miles long, and has an average width of about 4 miles. Halfway toward its head is a group of islands extending across the bay, between which are two good channels leading to the upper part. Vessels of the largest size and deepest draft can find an anchorage, and the navigation is not difficult for strangers.

The principal entrance is from southward, between Schoodic Peninsula and Baker Island, but small vessels can enter from southwestward through Western Way. Small vessels may also enter the head of Frenchman Bay at high water through Mount Desert Narrows.

Prominent objects.—The principal guides to the entrance of Frenchman Bay from the sea are Mount Desert (Rock) lighthouse, Great Duck Island lighthouse, Baker Island lighthouse, Winter Harbor lighthouse, and Egg Rock lighthouse. Mount Desert Island is mountainous, the highest on the coast of Maine. GREEN MOUNTAIN, the highest point, is 1,532 feet above the sea, and is visible in clear weather between 35 and 45 miles. There are several others nearly as high. SCHOODIC MOUNTAIN, near the eastern entrance to the bay, is 437 feet high and the most prominent mark on the eastern side.

Mount Desert Rock, 17½ miles southward of Mount Desert Island and 11½ miles outside the nearest island, is a rocky islet about 20 feet high, with a lighthouse on the top.

Mount Desert lighthouse is a gray conical tower. The light is flashing white (flash 2 seconds, eclipse 13 seconds), 75 feet above the water, and visible 14 miles. The fog signal is a reed horn, sounding a group of three blasts every 60 seconds (each blast 5 seconds, silent 25 seconds).

Anchorage.—Winter Harbor is a good anchorage, and is frequently used by vessels entering for shelter; it is usually open throughout the winter. Bar Harbor is partially protected, except against heavy southeasterly winds, but has poor holding ground except near the head of the harbor. Large vessels sometimes anchor northward or northwestward of Bar Island. Stave Island Harbor is a good anchorage, but is seldom used except by local boats. South West Harbor is a well-sheltered and frequently used anchorage.

Pilots.—No licensed pilots are available and none are needed to enter. Local fishermen can usually be obtained as pilots for the tributaries.

Supplies.—Gasoline and provisions are obtainable at all of the towns and villages. Water from the wharves and coal in limited quantities can usually be obtained at Bar Harbor and Winter Harbor.

Digitized by Google

Repairs.—There are no facilities for repairs to hulls. There are machine shops for minor repairs to machinery at Bar Harbor.

Ice.—During the winter, navigation is practically closed by ice above Porcupine Islands. Steamers usually run all winter but have considerable trouble with ice. Winter Harbor is said to be always open, and is the only harbor or refuge available in winter.

Tides.—The mean rise and fall of tides varies from 10.3 feet at the entrance to 10.6 feet at the head.

Communication.—Mount Desert Ferry is the terminus of a railroad, and has frequent steamer communication with Bar Harbor. There is steamer communication between Bar Harbor and all of the towns on the bay and with practically all towns westward along the coast as far as Portland.

DIRECTIONS, FRENCHMAN BAY.

The bay is rocky, but the water is deep and generally free from dangers except near the shores. The main part of the bay, from a little southward of Egg Rock lighthouse to the entrances of Skillings River, Sullivan River, and Eastern Bay, including the channels between Jordans and Long Porcupine Islands, and between Burnt Porcupine and Sheep Porcupine Islands, has been examined by means of a wire drag.

The tributaries, with the exception of the main part of Winter Harbor and the channels northward and southward of Suttons Island, have not been examined by means of a wire drag, and vessels navigating them should proceed with caution when crossing areas where the charted depth does not considerably exceed the draft.

The following directions are good for vessels of the deepest draft, and lead to Eastern Bay at the head of Frenchman Bay. General directions for entering the harbors and arms of Frenchman Bay are given in the description of the tributaries following.

From eastward.—From the whistling buoy off Schoodic Island, steer 296° true (NW mag.) for Egg Rock lighthouse for 3¼ miles until ¼ mile southwestward of a red bell buoy and Winter Harbor lighthouse is in line with the southern end of Turtle Island. Then steer 313° true (NNW ½ W mag.) for 4 miles, with the east side of Sheep Porcupine Island ahead, passing ½ mile northeastward of Egg Rock lighthouse, to a position 300 to 500 yards eastward of Round Porcupine Island.

Or, from the whistling buoy off Schoodic Island, steer 284° true (NW by W ⅛ W mag.) for 4¾ miles to Egg Rock whistling buoy. Continue the course about ⅜ mile past the buoy, and then steer 342° true (N mag.) to a position 300 yards eastward of Round Porcupine Island.

From a position 300 yards eastward of Round Porcupine Island, steer 329° true (N by W ⅛ W mag.), pass midway between Burnt Porcupine and Sheep Porcupine Islands, and when 1½ miles northward of them pass ¼ mile eastward of Bald Rock buoy. Then steer 300° true (NW ⅜ N mag.) for 2 miles, and pass ¼ mile northeastward of Sunken Ledge buoy. When about ¼ mile past this buoy and Sands Point bears 252° true (W mag.), steer 266° true (WNW ⅝ W mag.), pass about ¼ mile northward of Sands Point, and pass

Digitized by Google

southward of the buoys marking Googin Ledge, giving them a berth of over 100 yards.

From westward.—From the whistling buoy 1⅛ miles south-southeastward of Baker Island lighthouse, steer 13° true (NNE ⅞ E mag.) for 6¼ miles, heading for Egg Rock lighthouse. When Egg Rock whistling buoy is ½ mile distant ahead and Great Head bears 266° true (WNW ¾ W mag.), steer 341° true (N mag.) for 3¾ miles, with the west side of Burnt Porcupine Island ahead, to a position 300 yards eastward of Round Porcupine Island. Then follow the directions preceding.

Or, having come from westward through the passage northward of Sutton Island, as described under the directions for South West Harbor on page —, pass about 200 yards southward of Seal Harbor gas buoy and steer 58° true (ENE ⅞ E mag.) for 2½ miles, following the shore of Mount Desert Island at a distance of ¼ mile. When 200 yards southward of Otter Cliff Ledge bell buoy, steer 21° true (NE ½ N mag.) for 1¾ miles, passing about 400 yards southeastward of Great Head, to a position 200 yards eastward of Schooner Ledge black buoy. Then steer 353° true (N by E mag.) for 3¼ miles to a position 300 to 500 yards eastward of Round Porcupine Island. Then follow the directions preceding.

WINTER HARBOR

(chart 317), on the eastern side of Frenchman Bay, just inside the entrance, is a frequently used harbor of refuge, with good anchorage in 5 to 9 fathoms, good holding ground. It is comparatively free from dangers, and although open southward, a heavy sea never enters. Ice seldom interferes with navigation. The principal entrance from southward is deep and free from dangers. Winter Harbor lighthouse is the principal guide. It can also be entered from northward, close along the western side of Grindstone Neck. The dangers along this channel are marked, but it is used only by local vessels of 12 feet or less draft; the aids are colored for vessels bound north.

Turtle Island, on the western side of the entrance, is wooded. **Turtle Island Ledge,** bare at half tide, extends ¼ mile off the southwest side of the island.

Mark Island is grassy and marked by **Winter Harbor lighthouse,** a white tower connected with dwelling.

Of the islands northward of Turtle and Mark Islands, **Neds** and **Heron Islands** are partly wooded, **Spectacle Island** has a house and a few trees, and the others are grassy or bare rocks. All are surrounded by extensive ledges, bare at various stages of the tide.

Grindstone Neck, forming the west side of Winter Harbor, is wooded, but has many cottages and hotels visible. A standpipe on the highest point is prominent. A wharf on the west side 1 mile above the south end has a depth of 12 or 14 feet, and is the landing for the steamer from Bar Harbor.

Grindstone Ledge, extending 400 yards southward from Grindstone Neck, is bare at half tide and marked by a spindle. There is a red buoy a little southward of the end of the ledge.

Sand Cove, on the northwest side, at the head of Winter Harbor, is the usual and best anchorage. The coal and steamer wharf on the western side has a depth of 14 feet at the end.

Digitized by Google

Winter Harbor is a town on the two coves at the head of Winter Harbor. **Winter Harbor Cove**, the westerly of the two coves, is the most frequently used anchorage for local fishing boats, and is generally fully occupied. The wharves are bare at low water. A spindle and red buoy marks a ledge on the north side at the entrance; the midchannel is clear inside. Gasoline and provisions are obtainable.

Directions, Winter Harbor.—The entrance to Winter Harbor from southward is deep and clear. Vessels can steer for Winter Harbor lighthouse on any course between 339° true (N ¼ W mag.) and 21° true (NE ½ N mag.). They should pass at least 300 yards eastward of the lighthouse and steer north-northeastward for ¾ mile until inside the harbor, and then more northward, following the western shore into the middle of Sand Cove. Anchorage can be selected in the cove according to draft. If bound to the village, the north-northeasterly course from 300 yards off Winter Harbor lighthouse can be continued until between the red and the black buoys at the entrance to the coves at the head. Then haul westward, pass southward of the red buoy on the north side at the entrance to the inner harbor, and enter in midchannel.

To ENTER WINTER HARBOR FROM NORTHWARD, westward of Grindstone Neck, pass midway between the black buoy off Crow Island and the wharf northeastward, and follow the western shore of Grindstone Neck southward at a distance of 150 yards for ¾ mile to a black buoy, and at a distance of 75 yards while passing eastward of the black buoy and a spindle just southward of it. After passing the spindle follow the shore at a distance of 100 yards for 200 yards, then steer 121° true (SE ⅜ S mag.) and pass close southward of a red buoy. When well past the buoy vessels can haul northward into Winter Harbor and follow the directions preceding.

FRENCHMAN BAY, EAST SIDE, WINTER HARBOR TO SULLIVAN HARBOR.

Egg Rock, in the middle of Frenchman Bay, is low and grassy and marked by **Egg Rock lighthouse**, a white square tower on a dwelling. Ledges, bare at various stages of the tide, extend ¼ mile northeastward and ⅜ mile southwestward of the lighthouse.

Iron Bound Island, the largest of the islands in Frenchman Bay, is thickly wooded and has no prominent marks

Cod Ledges, eastward of Iron Bound Island, have a least found depth of 19 feet, but have not been closely examined and probably have less. Vessels should pass eastward of the black buoy marking them.

Halibut Hole, the passage between the north end of Iron Bound Island and Jordans Island, is deep and clear with the exception of a rock on the northeast side, 200 yards off the shore of Jordans Island, with a least found depth of 17 feet, not closely examined. The channel is southward of the rock. The western entrance to Halibut Hole is marked on the south side by a black buoy.

Stave Island Harbor.—This is an excellent harbor of refuge on the eastern shore of Frenchman Bay, formed by the mainland on the east, STAVE ISLAND on the north, and JORDANS ISLAND on the south; the anchorage has a depth of 3½ to 6 fathoms, soft bottom, and is sheltered from all winds. It is considerably used as an anchorage by local fishing craft.

Digitized by Google

South Gouldsboro is a village on the northeastern shore of Stave Island Harbor. There is a long cannery wharf with a depth of about 11 feet at the end. The other wharves are nearly bare at low water. Gasoline and some provisions are obtainable.

Summer Harbor is the local name given to a small settlement in the southeast end. The wharf has a depth of 10 feet.

The harbor is clear with the exception of a rock with 7 feet over it lying 200 to 400 yards from shore in its southeast part. The north end of the harbor eastward of Stave Island is shoal. There is a narrow channel into the harbor from southward over Jordans Island Bar, which is used only by small local craft; the channel has a depth of 5 feet and lies 100 yards off Jordans Island.

The main entrance to Stave Island Harbor is between Stave and Jordans Islands. There is a rock with 4¼ fathoms on it nearly midway between Jordans and Stave Islands, the deeper channel lying southward of it. **Yellow Island**, lying 200 yards westward from the north end of Jordans Island, is named from the color of its rocks and is wooded. To enter, pass 200 to 300 yards northward of Yellow Island on a 72° true (E mag.) course. Approaching Stave Island Harbor from southward there is a broad, clear channel between Ironbound and Long Porcupine Islands, and the approach northward of the Porcupine Islands is also clear. There is no navigation from Stave Island Harbor to Flanders Bay inside of Stave Island, except for small craft at high water.

Flanders Bay.—This bay is on the northeast side of Frenchman Bay, inside Stave and Calf Islands. It is an excellent anchorage, but is little used except by small craft. It forms the approach to the villages of West Gouldsboro and East Sullivan. The bay can be entered across Stave Island Bar between Calf and Stave Islands, or around the north end of Calf Island. The latter has the best water, but the former is more direct, and is generally used.

Calf Island is wooded except on the south end, which is low and bare. A house and barn on the southeast side is visible from southward.

Little Calf Island and Thrumbcap are partly wooded islands on the extensive shoal extending southward from Calf Island.

Calf Island Bar, connecting Calf and Stave Islands, has a depth of 9 to 11 feet in a buoyed channel, and can be used by vessels of 8 feet draft at low water.

An extensive chain of bare and sunken ledges extends through the middle of Flanders Bay from the north end to near the south end. The southerly ledge is bare at half tide and marked by a black buoy off its south end. The opening between the south end of Long Ledge (partly bare at high water) and the ledge with 5 feet over it southward, has a least found depth of 19 feet and was marked in 1917 by private barrel buoys on each side.

West Gouldsboro is a village at the head of the southeasterly tributary of Flanders Bay. There is a depth of 4 feet to within ¼ mile of the village, above which the channel is bare at low water to the landing. The channel is unmarked and difficult, and seldom used even by local boats.

East Sullivan is a village at the northern end of Flanders Bay. The wharf is bare at low water and boats seldom go to it.

Digitized by Google

To enter across Calf Island Bar, give the western shore of Stave Island a berth of ¼ mile and steer 19° true (NE ¾ N mag.) for the bar buoys, passing ⅜ mile southeastward of the Thrumbcap. Pass the black buoy and the red buoy on the bar close-to, and from the latter steer 61° true (E ⅞ N mag.) for Half Tide Ledge black buoy. Pass about 100 yards southward and eastward of it and steer 344° true (N ¼ E mag.) for the prominent house on Hall Point until about ⅜ mile from it. Then steer 308° true (NW by N mag.), pass midway between Hall Point and a black buoy, and follow the shore of Ash Neck at a distance of 300 yards. Anchor ¼ mile to ⅜ mile northwestward of Ash Point, in 3 to 4 fathoms.

The entrance to Flanders Bay between Preble and Calf Islands is clear and deep. Enter in mid-channel, and follow the shore of Calf Island, giving it a berth of 200 yards. When northeastward of the island, steer 111° true (SE ½ E mag.) and pass 100 yards southward of Half Tide Ledge black buoy. Round the buoy at this distance and proceed as directed in the preceding paragraph.

Eastern Point Harbor is a sheltered anchorage for small craft on the north side of the eastern end of Preble Island. The head of the harbor is shallow, and is separated from Sorrento Harbor by a partly dry reef.

Sorrento Harbor is a small anchorage, used by small pleasure craft in summer, on the north side of Frenchman Bay north of Preble and Dram Islands. The entrance from southward favors Dram Island slightly, and is narrowed by reefs bare at low water, which extend 100 yards from Preble Island and 50 yards from Dram Island. The entrance from westward is narrowed by a reef, partly showing at high water, which extends 175 yards from the north side. The best water is found 100 yards north of Dram Island on a 91° true (ESE ¼ E mag.) course.

Sorrento is a summer resort on the north side of Sorrento Harbor. It has steamer communication with the other landings on Frenchman Bay. The steamer wharf has a depth of about 11 feet.

SULLIVAN HARBOR

(chart 306) is an arm of Frenchman Bay making northward from the north end. It forms the approach to Hancock Point, Mount Desert Ferry, Sullivan, and Franklin. It is used by the regular steamers as far as Sullivan, and by vessels up to 13 feet carrying stone from the quarries above Sullivan. The least depth to the falls just above Sullivan is about 20 feet.

Beans Ledge, eastward of Beans Island, shows at high water.

Beans Island, in the middle of the entrance to Sullivan Harbor, is grassy and has a few trees on its east end. The generally used channel leads westward of it.

Crabtree Ledge, on the west side at the entrance to Sullivan Harbor, is marked by a lighthouse (white tower on black pier).

Hancock Point is a steamer landing on the western side of Sullivan Harbor westward of Crabtree Ledge lighthouse.

Mount Desert Ferry, on the west side of Sullivan Harbor, 1½ miles above the entrance, is the terminus of a railroad, and has steamer communication with Bar Harbor and the other towns on Frenchman Bay. The wharf has a depth of about 11 feet.

Digitized by Google

Sullivan is a small village on the north side of Sullivan River, 3½ above the entrance. There is a depth of about 15 feet at the steamer wharf, but there is a ledge with a depth of 10 feet 100 yards southward of it.

Sullivan Falls, the contracted section of the river, ½ mile above Sullivan, is said to have a depth of about 7 feet at low water, but is obstructed by ledges and the tidal currents are dangerous. Vessels using it go in and out at high water slack.

West Sullivan, on the north side just above the falls, has several quarries at which vessels load to 13 feet. A small ferry crosses the river from West Sullivan to Hancock, a small settlement opposite.

Taunton Bay is the name given to the expanded section of Sullivan River, 6 miles above the entrance. An unmarked channel with a depth of about 8 feet leads through it to near the head, but the bay outside this channel is bare, or nearly so, at low water.

Franklin, a town on the railroad at the head of Taunton Bay, has several quarries at which vessels load to a draft of 12 feet at high water.

Ice obstructs navigation in Sullivan River during January, February, and March.

Tides.—The mean rise and fall of tides is about 10½ feet below the falls and about 6½ feet above. The tidal currents through the falls are dangerous at strength. High water slack is 1⅓ hours and low water slack 1¾ hours later in the falls than below them.

Directions, Sullivan Harbor and Taunton Bay.—The main entrance to Sullivan Harbor is between Beans Island and Crabtree Ledge lighthouse. Vessels can also enter by the buoyed channel eastward of Beans Island, but this channel is seldom used. The channel from the entrance to Sullivan has ledges bare and submerged on either side but has ample depth and is well marked.

Approaching Sullivan Harbor from southward, when in mid-channel between Burnt Porcupine and Sheep Porcupine Islands, steer 343° true (N ⅛ E mag.) for 4½ miles and pass between Crabtree Ledge lighthouse and Beans Island; the former should be given a berth of 100 yards, and the western end of Beans Island a berth of over 200 yards. Then steer 15° true (NE by N mag.) with Crabtree Ledge lighthouse astern, and pass westward of a red nun buoy, and to a mid-channel position between the two spindles above Mount Desert Ferry. Then steer 21° true (NE ½ N mag.) to a position 125 yards eastward from Moon Ledge black buoy. Then steer more northward and anchor, favoring the northern shore, in 3½ to 7 fathoms off the town of Sullivan. The water shoals abruptly on both sides of the channel throughout the harbor.

Navigation through the falls just above Sullivan is safe at slack water only. Vessels sometimes go in on the flood tide but always come out at high water slack. The channel is unmarked above Sullivan, has dangerous ledges on either side, and is unsafe except with local knowledge.

Pilots can usually be obtained near the entrance.

FRENCHMAN BAY, SULLIVAN HARBOR TO MOUNT DESERT NARROWS.

Skillings River (chart 306) is an arm of the northern part of Frenchman Bay westward of Sullivan Harbor. The entrance is 1⅝

Digitized by Google

miles wide between Crabtree Point on the east and Meadow Point on the west, but it contracts rapidly to a width of 400 yards 1¾ miles above Crabtree Point. Above this the river leads about 4 miles in a northwesterly direction to the post village of North Hancock.

The channel is narrow and crooked and has numerous rocks and ledges, making its navigation difficult. Strangers wishing to enter the river with vessels should get a pilot at Bar Harbor, or anchor 1½ miles above Crabtree Point in 5 to 7 fathoms, and get a pilot from South Hancock. The river is unmarked, and is seldom used except by local fishing craft. The wharves are generally small and bare at low water. Strangers in small craft can enter with the aid of the chart.

South Hancock, Hancock, and **North Hancock** are villages along the main road, some distance from the bay, and have little business by water.

Eastern Bay forms, with Mount Desert Narrows, a thoroughfare from the head of Frenchman Bay to Blue Hill Bay, north of Mount Desert Island. It is generally deep and clear in mid-channel to the entrance of Mount Desert Narrows, except for **Googin Ledge,** nearly ½ mile long, bare in the center at low water and marked on the south side by two red buoys. The channel leads southward of it.

There is a **naval coaling station** on the north side of Eastern Bay, northwestward of Googin Ledge. The coal hoists and other marks are prominent. **Lamoine Beach** is the name of the settlement in this vicinity.

There is good anchorage for deep-draft vessels between Googin Ledge and a position northwestward of the coaling station in 6 to 9 fathoms. There is also good anchorage about ¼ mile from shore off the entrance of **Salisbury** and **Emery Coves,** in 7 to 8 fathoms. At **Hadleys Point,** Eastern Bay merges into Mount Desert Narrows, and **Berrys Cove** makes into the northern shore. There is good anchorage in 3 to 4 fathoms off the entrance to this cove, which is shallow at its head.

Jordan River, making northward just west of Berrys Cove, has a narrow, crooked channel with 5 feet at low water up to Lamoine. Strangers should take a pilot at Berrys Cove (**East Lamoine**); the channel is not marked so as to be followed, except by persons well acquainted with the locality. **Lamoine** is a town on the east bank of the river just above the entrance; a draft of 15 feet can be taken up to it; the wharves are dry at low water and there is little business.

Mount Desert Narrows (chart 307) connects the head of Frenchman Bay with the head of Blue Hill Bay northward of Mount Desert Island. It is crossed by a highway drawbridge having two openings 36 feet wide; the north opening is generally used.

The channel is bare at low water and is used at high water by boats up to 9 feet draft. It is narrow and difficult and is fringed with reefs. The most difficult part was marked in 1917 by small private buoys.

Strangers should not attempt to use it with a greater draft than 4 or 5 feet, and should go through on a rising tide. The mean rise and fall of tides is 10½ feet, and high water occurs at about the same time as at Eastport and Bar Harbor. The flood current sets westward and ebbs eastward.

Digitized by Google

The following remarks may be of use to strangers in going through the Narrows: Having passed through Eastern Bay, pass at least 200 yards northward of Hadleys Point and steer westward for 1⅛ miles with the steel tower at the north end of the bridge ahead, until 250 yards northward of the north end of Thomas Island (wooded). Then swing a little northward and head for Trap Rock (low bare islet) showing a little to the right of the northerly steel tower for ⅜ mile until 400 yards from Trap Rock and past a reef on the south side (marked by a fish trap in 1917). Then haul southwestward to round the reef extending 250 yards southwestward from Trap Rock, and then steer westward for the draw, with the north end of Thomas Island astern, being guided by the private buoys or other marks. After passing through the draw give the shore on the south side a berth of 150 yards to avoid ledges making off it, until ¼ mile from the bridge, and then haul south-southwestward into Western Bay, giving Haynes Point on the western side a berth of 300 yards to avoid ledges off it.

BAR HARBOR

is a town and anchorage on the eastern side of Mount Desert Island, 3½ miles above Egg Rock lighthouse. This harbor is formed by an indentation in the shore of Mount Desert Island and two islands northward; a breakwater extending southwesterly from Round Porcupine Island to within ⅛ mile of the shore affords some shelter against southerly winds. The bottom is generally rocky and poor holding ground except near the head of the harbor, and the water deepens quickly from 4 to 13 fathoms. A swell heaves in during southeast winds, and vessels should not attempt to ride out a gale here from that direction.

All of the islands surrounding Bar Harbor are high and wooded, and have no prominent marks. When approaching from southward, **Round Porcupine Island** is distinguishable on account of its bare rocky slopes.

Rodericks Cove, westward of the end of the breakwater, has several float landings, but is seldom used as an anchorage.

Bar Harbor is an important summer resort. It is connected by steamer with the railroad at Mount Desert Ferry, and with the principal towns on Frenchman Bay, and westward along the coast. Coal in limited quantities can be had at the wharf or from lighters. Water can be had from the wharves or from water boats. The steamboat wharves at the eastern end of the water front have depths of 10 to 13 feet. The coal and other wharves westward have depths of 1 to 4 feet.

The usual anchorage is southward and southeastward of the eastern end of Bar Island, in 1 to 13 fathoms, the depths shoaling rapidly toward the bar southward of Bar Island. The southern limit of the anchorage is marked by white barrel buoys placed by the harbor master to leave a clear channel to the wharves.

The principal entrance is from eastward between **Round Porcupine** and **Sheep Porcupine Islands**, and is clear. Passing about 300 yards northeastward of Round Porcupine Island, a 289° true (NW ⅝ W mag.) course will lead to the anchorage. Local vessels sometimes enter from northward between Sheep Porcupine Island and the islet eastward of Bar Island, where the depth is 8 feet. There is a deep

Digitized by Google

channel 150 yards wide into the harbor from southward between the end of the breakwater extending southwestward from Round Porcupine Island and the western shore; it is generally used by local vessels entering from southward. To enter by this channel, pass 50 yards westward of the end of the breakwater, and give the shore northward of the breakwater a berth of 300 yards or more.

Large vessels frequently anchor northward or northwestward of **Bar Island**, in 7 to 10 fathoms, soft bottom. A 7½-fathom rocky patch lying 650 yards northward of Bar Island should be avoided. The bar inside of Bar Island will be avoided by keeping the north side of Sheep Porcupine Island open from the north side of Bar Island. The western shore is fairly bold, with the exception of a rock, bare at low water, lying ⅝ mile westward of Bar Island and 250 yards from the shore at the entrance of **Duck Brook**. **Bald Rock Ledge**, the highest part of which shows at low water, lies ⅞ mile northward of Bar Island, and is marked at its southwest end by a red buoy. Vessels should keep over ¼ mile southward of a line joining the buoy and Bald Rock (a bare rocky islet).

FRENCHMAN BAY, BAR HARBOR TO SOUTH WEST HARBOR.

The southeast side of Mount Desert Island between Bar Harbor and Seal Harbor is rocky and precipitous. The small coves indenting the shore are of no importance to navigation. Several dangers lie off the shore, but the most dangerous either show above water or are marked by buoys.

The Thrumbcap, 1½ miles southward of Round Porcupine Island, is a round rocky island, with a clump of trees in the center.

Newport Ledge, 400 yards from shore, midway between the Thrumbcap and Schooner Head, is bare at extreme low water and marked on its eastern side by a black buoy. The bottom inside of it is broken, and should not be crossed by vessels.

Egg Rock is described on page 90.

Schooner Head and **Great Head** are prominent rocky headlands, and Great Head is distinguished by an observation tower on the top.

Schooner Ledge, 350 yards from shore, midway between Schooner Head and Great Head, is bare 4 feet at low water and marked by a black buoy 300 yards eastward of it.

Newport Cove, a small cove westward of Great Head, is exposed southward, has poor holding ground and is never used as an anchorage. There is a bare rock off the entrance.

Otter Cliff Ledge, 400 yards eastward of Otter Creek Point, is bare at half tide and marked by a black bell buoy.

Otter Cove, a long cove making northward of the west side of **Otter Creek Point**, has deep water in the entrance and is bare for ⅜ mile from the head. It is exposed southward and not used as an anchorage. Two radio towers are visible.

The other coves and islands are described under "South West Harbor and approaches."

SOUTH WEST HARBOR AND APPROACHES.

South West Harbor, Somes Sound, North East Harbor, and several other coves lie in the southeast side of Mount Desert Island, inside a large group of islands and shoals. These waters are the ap-

Digitized by Google

proaches to several important villages and summer resorts, and are frequented by passenger steamers, fishing boats, and many pleasure craft. South West Harbor is also extensively used as a harbor of refuge. They can be approached through the channels on either side of Sutton Island or through Western Way.

Baker Island, the most southeasterly of the islands in this vicinity, is wooded and marked in the center by Baker Island lighthouse. It is surrounded by ledges, bare and submerged, and should be given a berth of at least ⅜ mile. **The Thumper** is a ledge, bare at low water, lying 300 yards southward of the island. Another ledge, partly bare at low water, lies ¼ to ⅜ mile off the southwest side.

Baker Island lighthouse is a white tower connected with dwelling. The light is fixed white, with a white flash of 5 seconds' duration every 90 seconds, 105 feet above the water, and visible 16 miles.

Little Cranberry Island is low and wooded, and has no prominent marks visible from southward or eastward. **Islesford** is a post village on the northwest end. There is a large wharf and several fish houses.

The passage between Little Cranberry and Cranberry Islands is used at any stage of the tide by small local craft, but it has many unmarked ledges and should not be used by strangers.

Cranberry Harbor is southward of Sutton Island between Little Cranberry and Cranberry Islands. It is frequented by small local vessels, and coasting vessels sometimes anchor here, but South West Harbor is a much better anchorage. The usual anchorage is in 14 to 20 feet in the middle of the harbor with the wharves at Isleford bearing about 50° true (ENE mag.), taking care to keep well clear of the black buoy on the end of the ledge which extends 350 yards westward from the east side at the entrance.

Cranberry Island is wooded and has no prominent marks visible from southward. **Cranberry Isles** is a post village on the island. There are two wharves in **Spurling Cove** on the north side, a fish wharf on **Long Point** at the northeast end, and a wharf, bare at low water, in **The Pool**, a shoal cove in the eastern side, obstructed by many reefs.

South Bunker Ledge, in the southern approach to Western Way, is bare 4 feet at low water and marked by a spindle.

The Nubble is a dangerous reef, mostly bare at low water and having a few rocks bare at high water, extending ½ mile southeastward from Mount Desert Island. It is marked off its end by a black bell buoy.

Western Way, between the western side of Cranberry Island and Mount Desert Island, is a frequently used passage for vessels bound to South West Harbor and vicinity, and is generally used by all small vessels bound between points westward and any point in Frenchman Bay. The channel is buoyed and the least depth is 14 feet on a bar at the northern end, but there are unmarked spots of 10 to 12 feet close to the sailing lines, and the passage should not be used by strangers with a greater draft than 10 feet.

South West Harbor (chart 306) is the most important harbor on the south side of Mount Desert Island. It is an excellent, well-sheltered anchorage in 2 to 8 fathoms, and can be entered from eastward, northward of Sutton Island, by vessels of the deepest draft. The

Digitized by Google

approach from southward across Cranberry Island Bar has a depth of 14 feet.

Deep-draft vessels can anchor midway between Greening Island and the southern shore, in 7 to 9 fathoms. Smaller vessels can anchor farther in, the depths shoaling gradually to 12 feet 150 yards eastward of the islet which lies 400 yards from the head of the harbor. In the daytime, with clear weather, a pilot is not required to enter from eastward. Strangers coming from westward and crossing Bass Harbor and Cranberry Island Bars can take a pilot at Bass Harbor, if desired. Pilots for the waters eastward and westward can generally be found at South West Harbor by making inquiries on shore. Anthracite coal, water, and ship chandler's stores in limited quantities can be had alongside the wharves. There is steamer communication with Bar Harbor and points westward along the coast.

South West Harbor is the name of the village and resort on the north side of the harbor. The steamer landing on **Clark Point** is the principal wharf and has a depth of about 14 feet.

Manset, on the south side of South West Harbor, has several fish cannery wharves, varying in depth from 8 to 15 feet.

Greening Island, on the north side at the entrance of South West Harbor, is low and wooded, but has several houses visible. A large house at the eastern end is prominent. It has several float landings. Shoals border it on all sides.

The passage between Greening Island and the point westward has a least found depth of 15 feet and is extensively used. It is buoyed, and a ledge in the middle is marked by a light on a spindle. The best water from southward leads 100 to 150 yards westward of the red buoy at the south end, 100 yards eastward of the light, and eastward of the black buoy a little northward of the light.

Somes Sound (chart 306 or 307) is a narrow body of water, about 4½ miles long and ¼ to ¾ mile wide, making into the south shore of Mount Desert Island. It lies between steep, rocky shores, and has a narrow entrance with few dangers. With the aid of the chart, good anchorage can be selected in the sound, in 9 to 12 fathoms, but it is out of the way and little used. Sailing vessels should enter under easy canvas on account of the heavy squalls of wind which occasionally strike down from the mountains. Greening Island lies in the middle of the approach, with a channel on either side of it.

Hall Quarry is an unused quarry and small settlement on the west side of Somes Sound 3½ miles above the entrance.

Somes Harbor is a small cove at the head of Somes Sound. The entrance is narrow and marked by buoys.

Somesville (Mount Desert post office) is a village on Somes Harbor. The principal wharf has a depth of 8 feet.

North East Harbor has its entrance northwestward of Bear Island. The head of the harbor is shoal, but there is anchorage 200 yards wide for very small vessels for a distance of ⅜ mile inside its entrance, favoring the western side, in 3 to 4 fathoms. Vessels generally anchor just outside the entrance, between it and buoys Nos. 2 and 4, in 4 to 6 fathoms. There are several large summer hotels on the shores of the harbor. There are several landings for small craft. The harbor is little used except by small boats. The steamer land-

Digitized by Google

ing for North East Harbor is ¾ mile westward of the entrance and just westward of Gilpatrick Cove.

A rock, bare at low water, lies in the middle of the entrance to North East Harbor, and is marked by a buoy on either side. The best passage into North East Harbor lies westward of the rock.

Bear Island, on the eastern side of the entrance to North East Harbor, is high and marked on its western end by a lighthouse. The passage north of the island is blocked by reefs.

Sutton Island, about 1 mile long and wooded, lies in the middle of the passage between the south shore of Mount Desert Island and Cranberry Islands. **Sutton,** a post office and summer resort, is on its western part. There is a small wharf and several float landings. The channel north of Sutton Island has a depth of about 8 fathoms and is generally used—the ledges are marked by buoys. The channel south of it has a depth of about 17 feet and is contracted by rocks; the principal dangers are marked by buoys, and its navigation is not difficult in the daytime with the aid of the chart.

Bracy Cove, ⅝ mile eastward of Bear Island, is exposed to southeast winds, has a rocky and uneven bottom, and is unfit for anchorage.

Seal Harbor makes into the south shore of Mount Desert Island about 1⅜ miles east of Bear Island; it is an anchorage for small vessels, but is exposed to southeasterly winds. There is a steamboat landing (depth, 11 feet) and the village of Seal Harbor, a summer resort, on the eastern shore. A black buoy marks the end of the ledge which extends from the western shore halfway across the entrance of the harbor. The anchorage is about 400 yards in diameter, in the middle of the cove, in 16 to 18 feet; the head of the cove must be given a berth of over 300 yards. The approach is between Seal Harbor gas buoy on the east and Bowden Ledge buoy on the west.

East Bunker Ledge, 1 mile eastward of Sutton Island, is ¼ mile long and has two sections bare at high water. There is a stone beacon near its southwestern end and a black buoy marking a 6-foot rock 200 yards northward of its northern end.

DIRECTIONS, SOUTHWEST HARBOR.

The channel northward of Sutton Island is deep and well marked and has been examined by means of a wire drag; it is used by all vessels entering from northward and by most of those entering from eastward and southeastward. The channel southward of Sutton Island has unmarked rocks with a least found depth of 16 and 17 feet. It has been examined by means of a wire drag. Its navigation is easy in the daytime with the aid of the chart. Vessels of 14 feet or less draft, approaching from southward or westward, usually enter through Western Way, but this passage is not recommended for strangers with a greater draft than 10 feet.

From eastward, northward of Sutton Island.—Pass 200 yards southward of Seal Harbor gas buoy and steer 259° true (W ⅝ N mag.) for the southeast end of Greening Island, until midway between Bear Island and the western end of Sutton Island. Then steer 249° true (W ¼ S mag.) and pass 100 to 200 yards southward of the buoy lying nearly 200 yards southward of the southeast end of Greening Island.

Digitized by Google

Then steer 269° true (WNW ½ W mag.) and select anchorage according to draft.

From westward through Western Way.—Crossing Bass Harbor Bar close to the fairway buoy lying about 350 yards southward of Bass Harbor Head lighthouse, steer 89° true (ESE ½ E mag.) and pass about 100 yards southward of Long Ledge bell buoy. Round the buoy at this distance and steer 25° true (NE ⅛ N mag.) for a little over 1 mile to the fairway buoy.

From the fairway buoy steer northeastward about 300 yards and pass between Cranberry Island Ledge red buoy and Flynn Ledge black buoy. From the latter buoy steer 356° true (N by E ¼ E mag.) for the fairway buoy at the northern end of Western Way. Then steer 323° true (N by W ⅝ W mag.) and follow the western shore at a distance of about 400 yards into Southwest Harbor.

Approaching southward of Long Island, pass about 1 mile southward and eastward of Long Island Head and steer 6° true (NNE ¼ E mag.) for nearly 8 miles, passing ⅜ mile eastward of The Drums buoy, ¼ mile westward of South Bunker Ledge spindle, and to the fairway buoy nearly ¾ mile northward of the spindle. Then proceed as directed in the preceding paragraph.

ISLANDS OFF BLUE HILL BAY (CHART 308).

Under this heading are described all of the islands southward of Bass Harbor Bar and Casco Passage from the Duck Islands westward to Swan Island.

This area includes numerous islands, generally wooded and having few prominent marks. The only ones having settlements are Swan Island, Long Island, and Great Gott Island. The area is very broken and rocky and has numerous bare and submerged ledges, many of them unmarked. The through route by way of Casco Passage and Bass Harbor Bar is used by many vessels, but the passages through the islands southward are seldom used except by local fishermen. With the exception of the broad channel leading between Black and Placentia Islands on the east and Long and Swan Islands on the west, which has been examined by means of a wire drag, the area has not been closely examined and strangers should use it with extreme caution and should avoid crossing broken areas.

Great Duck Island, the most southeasterly of the islands off Blue Hill Bay, is partly wooded and appears as two islands from eastward or westward. The lighthouse at the south end and the buildings around it are prominent.

Great Duck Island lighthouse is a white cylindrical tower. The light is flashing red (flash 1 second, eclipse 9 seconds), 67 feet above the water, and visible 14 miles. The fog signal is a steam whistle (blast 5 seconds, silent 20 seconds, blast 5 seconds, silent 30 seconds).

Little Duck Island, ¾ mile north-northeastward of Duck Island, is partly wooded and has no distinguishing marks.

The Drums is a dangerous ledge 2 miles northeastward of Long Island. It is bare at low water and marked by a black buoy at the south end. The range of the western ends of Green and Placentia Islands leads well westward of it.

Horse Shoe Ledge is bare at low water and marked by a spindle.

Digitized by Google

Drum Island is a bare rock 400 yards eastward of the easterly Green Island.

Green Islands are two rocky islets with grass on top lying ¾ mile southward of Black Island.

Black Island is wooded. There are a few houses and a small wharf on the north side. Three ledges lie off its east side; **Inner Dawes Ledge** is bare at high water, **Outer Dawes Ledge** is awash at high water, and **Grindstone Ledge** is bare at about half tide and marked by a spindle.

Placentia Island is wooded except on its eastern end, which is grassy.

Little Gott Island and **Great Gott Island** are generally wooded. There is a small settlement of fishermen and a post office (**Gotts Island**) on the west side of Great Gott Island, the approach to which is by the passage between the islands. This passage can be entered from southward at low water, but a bar, bare at low water, crosses it at the northwest end. There are no wharves. The houses of the settlement are the most prominent marks in this vicinity.

Bass Harbor Bar and Bass Harbor are described on page 103.

Staple Ledge, between Placentia Island and the north end of Swan Island, is bare at low water only, and marked by a horizontally striped buoy.

Long Island, the most southerly of the large islands off Blue Hill Bay, is wooded and has no prominent marks visible from seaward.

Long Island (Lunts) Harbor is a cove on the north side of the island. **Frenchboro** is a village of fishermen in the cove. There is a large fish-packing wharf with a depth of 1 to 2 feet at low water; the other wharves are bare before low water. Gasoline and provisions are obtainable. The cove has good holding ground and is used as an anchorage by local boats, but it is somewhat exposed in northeasterly weather. Ice seldom interferes with navigation. Mail comes by small boat from Swan Island, to which there is steamer communication.

The passage between Long and Swan Islands has deep water, but there are many unmarked ledges. The best channel leads between Johns Island and Beach Ledge bell buoy, thence between the westerly **Sister Island** and **Ram Island**. Any of the passages can be used by small craft with the aid of the chart. The islands are all wooded and have no prominent marks, except Ram Island, which is marked by a single tree. **Sunken Money Ledge** is bare at low water. **Dry Money Ledge** is a white rock islet about 10 feet high. **Otter Island Ledge** is awash at low water.

Johns Island is wooded and has many dead trees. **Johns Island Dry Ledge** is ¼ mile in diameter and has rocks showing at high water. **Johns Island Sunken Ledge** has 6 feet over it and is marked on its south side by a red buoy.

Swan Island is the largest of the islands off Blue Hill Bay. There are three post villages on the island, Atlantic, Swans Island, and Minturn. The people are mostly fishermen. The island has several sheltered coves, but all except Mackerel Cove and Burnt Coat Harbor are generally foul and little used.

Mackerel Cove and Atlantic are described with Blue Hill Bay on page 105.

Digitized by Google

Burnt Coat Harbor.—This is a small well-sheltered anchorage on the southwestern side of Swan Island; it is much used by local fishermen, but seldom by other vessels. The anchorage eastward of the lighthouse is about 500 yards wide, with depths of 3½ to 6 fathoms, soft bottom. There is also good anchorage for small craft in the channel northward of the lighthouse in 13 to 24 feet.

BURNT COAT HARBOR LIGHTHOUSE on the west side at the entrance is a white tower connected with dwelling. The light is fixed white, 75 feet above the water, and visible 12 miles. The fog signal is a bell, sounding 1 stroke every 15 seconds.

SWANS ISLAND is a village on the west side of Burnt Coat Harbor. It is connected with Rockland by steamer. The steamer wharf has a depth of 10 feet and the fish wharves less. Gasoline and provisions are obtainable.

MINTURN is a quarry and small settlement on the east side of Burnt Coat Harbor. The wharf is said to have a depth of 6 feet, and vessels load here to 14 feet.

DIRECTIONS, BURNT COAT HARBOR.—The main entrance to the harbor is from southwestward, between Harbor Island and the point northward, and is marked on the north side by a lighthouse (white tower connected with dwelling) and on the south side by a spindle marking a rock bare at low water.

Vessels entering from southward may make the perpendicularly striped whistling buoy 3 miles westward of Long Island, then steer 342° true (N mag.) for 2¾ miles, passing 350 yards westward of Green Island, to the perpendicularly striped bell buoy off the entrance. From southeastward, they may pass ¼ mile southward of Southwest Point of Long Island, steer 267° true (WNW ⅝ W mag.) for 1¾ miles to a position ¼ mile south-southwestward of a red buoy, then 304° true (NW ⅝ N mag.) for 2¼ miles to a position 350 yards westward of Green Island, and then 342° true (N mag.) to the bell buoy. From Jerico Bay, vessels may pass midway between the two buoys marking the passage between Hat Island and Marshall Island, and steer 108° true (SE ¾ E mag.) to the bell buoy.

From the perpendicularly striped bell buoy off the entrance, a 42° true (NE by E ⅜ E mag.) course will lead through the entrance, passing midway between the lighthouse and the spindle opposite. Anchorage may be had eastward or northeastward from the lighthouse, or in the channel northward.

TO ENTER INSIDE BAKER AND HARBOR ISLANDS.—This passage is available for small craft entering from eastward. It is extensively used by local boats but narrow and difficult, and strangers are advised to use it only on a rising tide. In entering, pass between the northerly Baker Island and the south shore of Swan Island, favoring Baker Island slightly to avoid two reefs bare at low water on the north side. Then steer 292° true (NW ½ W mag.) for ½ mile, passing northward of a reef awash at low water on the south side and drawing in to 100 yards off the north shore abreast Stanley Point. Then haul northward through the passage eastward of Harbor Island, passing 50 yards southwestward of the southerly of two thickly wooded islets, and the same distance northeastward of a ledge, bare at half tide, opposite the islets. Then haul northwestward into the main channel.

Digitized by Google

Islands southwestward of Swan Island.—**Harbor Island** is wooded except on the northwest side. **Baker, Scrag, Heron, Ringtown, Hat,** and **Marshall Islands** are wooded. **Green, Gooseberry,** and **Brimstone Islands** are bare and grassy. **Gooseberry Island Ledge,** southeastward of Gooseberry Island, is bare at low water only and is marked by a black buoy at the southeast end. **Yellow Ledge,** southeastward of Ringtown Island, has a rock bare at high water and a considerable area bare at low water. There are many other bare and submerged rocks, most of them unmarked. This area has not been closely examined and should be navigated with extreme caution.

BLUE HILL BAY

(charts 307 and 308) lies west of Mount Desert Island; it is about 14 miles long and contains several large and some small islands, between which are good channels with deep water. The dangers are comparatively few, and the most prominent are marked by buoys. There are numerous coves on both sides of the bay, and its head is divided into several large arms, the most important of which is Union River Bay.

Blue Hill Bay forms the approach to the villages of McKinley, South Blue Hill, Blue Hill, and Surry, and the city of Ellsworth. It is frequented by regular passenger steamers to South Blue Hill and Blue Hill, a few coasting vessels to Ellsworth, and many fishing vessels.

Supplies.—Gasoline and provisions are best obtainable at McKinley or Ellsworth, although they are kept at all of the villages. Coal can be obtained at Ellsworth and there is water on the wharves.

Repairs.—There are marine railways at Ellsworth, the largest for hauling out vessels of 100 tons, 6 feet draft forward, 9 feet aft, and 130 feet long. Ordinary repairs to machinery can be made.

Pilots.—Local fishermen are the only pilots available around the entrance. Vessels seldom take pilots. Pilots for Union River can be obtained at the mill near the entrance or by telephoning to Ellsworth.

Tides.—The mean rise and fall of tides varies from 10.2 to 10.5 feet.

Communication.—South Blue Hill and Blue Hill are connected by steamer with Rockland. Ellsworth has railroad communication. The other settlements are reached by small boat, or by road from Ellsworth or Bar Harbor.

Directions for Blue Hill Bay are given on page 110.

BLUE HILL BAY, EAST SIDE.

Placentia, Little Gott, and Great Gott Islands are described on page 101.

Bass Harbor Bar, connecting Great Gott Island with Mount Desert Island at Bass Harbor Head, has been improved by dredging a channel 14 feet deep and 250 feet wide across it. The channel lies 350 yards southward of **Bass Harbor Head lighthouse** (white tower connected with dwelling) and is marked by a perpendicularly striped buoy, which may be left close to on either side. The channel is on the through route used by most vessels of 12 feet or less draft, and it is sometimes used by vessel of 18 feet draft at high water and with a

Digitized by Google

smooth sea. In heavy weather, breakers sometimes form entirely across it.

Bass Harbor, in the south end of Mount Desert Island, just westward of Bass Harbor Bar, is an important fishing port, and is sometimes used as an anchorage by vessels bound through the inside passage, but the outer harbor is exposed southward. The outer harbor is clear with the exception of **Weaver Ledge**, in the middle, bare about 2 feet at low water and marked by a black buoy on the southeast side and a red buoy on the northwest side. Vessels can enter on either side and anchor between Weaver Ledge and the entrance to the inner harbor, in 5 to 7½ fathoms, bottom soft in places.

The inner harbor is a crooked channel, 100 yards wide, with depths of 2 to 4 fathoms, and forms a secure anchorage for small craft. The entrance is marked by two buoys on the western side. The channel inside is unmarked and there are shoals close to it on either side.

McKinley is a village at the head of Bass Harbor. It has fish factories and is the headquarters of many fishing vessels. The principal wharves are on the east side at the head of the outer harbor, and have depths up to 16 feet. There are landings for small craft, bare at low water, on the inner harbor. Gasoline and provisions are obtainable. A stack and water tank are prominent from southward.

Mitchell Cove and **Duck Cove**, northward of Bass Harbor, are shoal and foul and have no landings.

Goose Cove, on the eastern side of Blue Hill Bay, 2 miles northward of Bass Harbor, is frequented by fishing boats. The principal wharf, on the west side, has a depth of about 7 feet and was in bad repair in 1917. A black buoy off the wharf marks the end of a shoal making off from the shore just northward of the wharf, and a red buoy southeastward marks a shoal in mid-harbor. **West Tremont** is a village at the head of the cove.

Goose Cove Rock and **Rumells Hub** are rocky islets with grass on top.

Seal Cove, 4 miles northward of Lopau Point, is a sheltered anchorage for small vessels except with westerly winds. A rock awash at high water lies 300 yards off the north side just inside the entrance, and a ledge partly showing at high water lies off the shoal bight on the south side. Entering midway between the rock and ledge, anchor near the middle of the cove, in 3 to 6 fathoms. There are no wharves.

Moose Island, north of the entrance to Seal Cove, is covered with grass and bushes. The point eastward of the island has a few small huts. The bar connecting the island and the point is bare at low water.

Hardwood Island is wooded at the north end and grassy, with scattered trees, southward. There is a small wharf on the east side.

Sawyer Cove, on the eastern shore of Blue Hill Bay eastward from the north end of Hardwood Island, is an anchorage for small craft. On the northeast side at the entrance is a ledge awash at high water.

Pretty Marsh Harbor makes into the eastern shore of the bay northeastward from Hardwood Island. There is good anchorage for vessels 300 to 500 yards from the eastern shore eastward of Folly Island in 5 to 6 fathoms. The northern and western sides of the cove inside West Point are shoal, and a shoal extends 350 yards southeastward from the point. **Folly Island** is grassy, with a few trees. A shoal extends 150 yards southeastward from Folly Island, and a ledge with

Digitized by Google

3 feet over it lies 200 to 300 yards eastward from the island; otherwise there are no dangers away from the shores.

John Island is a grassy islet, and there is a lower grassy islet 400 yards northward.

Bartlett Narrows leads between Mount Desert Island and Bartlett Island. The channel is narrow, but has deep water, with few dangers, and is not difficult. The mid-channel westward of Folly and John Islands is clear. If passing eastward of Folly Island give it a berth of about ¼ mile, and give the south end of John Island a berth of over 100 yards. The eastern shore of the Narrows from West Point to its northern end is bold and should be favored. In the narrowest part keep the eastern shore aboard distant 100 yards to avoid a ledge which extends 200 yards southward from a group of bare rocks.

A ledge with 2 to 3 feet over it lies 400 to 600 yards from the eastern shore ⅜ mile northward of Bartlett Narrows. It will be avoided by keeping westward of a line from the north end of the Narrows to the north end of Black Island.

Bartlett Island is generally wooded and has a few houses. There is a wharf on the east side, just northward of Birch Island Cove. There is a bare rocky islet close to the northeast end of the island.

Western Bay is northeastward of Bartlett Island, and is a part of the waters which separate Mount Desert Island from the mainland. Mount Desert Narrows, described on page 94, is at the head of Western Bay. Vessels of any size can select anchorage in the bay below Alley Island, in 10 to 12 fathoms, but the broken ground with 5½ to 6 fathoms extending ⅜ mile off the southeast side of Oak Point should be avoided. With the aid of the chart, good anchorage can also be selected in 3½ to 6 fathoms southeastward and eastward of Alley Island. The range of the summit of Bartlett Island over the middle of **Black Island** (thickly wooded) clears the shoal which extends ¼ mile southeastward from Alley Island.

Foul ground extends about ¼ mile from the south shore between Green Island and Indian Point. **Clark Cove**, eastward of Indian Point, has an anchorage in 12 to 18 feet, but a ledge with little water over it extends ¼ mile from its southeast shore ¼ mile eastward from Indian Point.

Goose Cove is a large shallow bight on the north side of Western Bay above Alley Island, and at its head is the village of **West Trenton**. The head of the cove is dry at low water for a distance of ½ mile, and thence it deepens gradually to 7 feet ½ mile farther down. There are no wharves.

BLUE HILL BAY, WEST SIDE.

Mackerel Cove is a good anchorage on the north side of Swan Island, at the eastern entrance of Casco Passage. There are islets and numerous ledges in the cove, but the entrance from northward is easy of access in the daytime. There is a narrow channel into Mackerel Cove from York Narrows which follows closely the shore of Swan Island, passing southward of Orono and Round Islands. On account of numerous unmarked dangers, it should not be used by vessels except with local knowledge.

Digitized by Google

Atlantic is a post village on the south side of Mackerel Cove. The wharf is said to have a depth of 5 feet and there are dangers in the approach. A church spire is prominent from eastward.

The Triangles is a bare ledge from which a reef covered at half tide extends ¼ mile northward. A red buoy marks the eastern side of a rock bare at low water, lying 400 yards southeastward of **Crow Island** (has two trees). A black buoy marks a rock with 6 feet on it, lying 300 yards northwestward of North Point of Swan Island. Enter Mackerel Cove between the black buoy and the red buoy and steer about 181° true (S by W ¾ W mag.) so as to pass westward of a black buoy which marks a 11-foot spot. Anchorage can be selected between the red buoy and inner black buoy in 4 to 5 fathoms, taking care to give the eastern shore a berth of 300 yards; there is also a good berth about midway between the inner black buoy and the bare ledge, lying ¼ mile northwestward of the wharf, in 4 fathoms. A rock with 4 feet over it lies ¼ mile northwestward of the bare ledge.

Casco Passage and York Narrows.—Northward of Swan Island, between it and Black Island, there is a narrow passage which separates into two branches in its western part. The eastern end and northern branch is known as Casco Passage, the southern branch as York Narrows. They form a part of the different inland passages from Mount Desert to Whitehead. Casco Passage and York Narrows are well marked by buoys, and at the eastern entrance, on the north end of Orono Island, there is a large black tripod. The islands are generally low and wooded, and have no prominent marks.

Casco Passage is the straighter and better channel, and has a depth of 15 feet and a width of 150 yards; there are rocks with little depth on each side. Vessels of 16 feet draft have been taken through. Directions for the passage are given on page 50. The current through Casco Passage and York Narrows sets eastward on the flood and westward on the ebb. The velocity is influenced greatly by strong winds. There is a rock, bare at low water, 125 yards off the south side of Black Island.

York Narrows has a width of but little over 100 yards, and has dangerous ledges on both sides. It is not recommended for vessels of a greater draft than 9 feet at low water, except with local knowledge. The following directions will lead through the Narrows:

Pass about 50 yards northwestward of the black buoy northward of Orono Island tripod, and steer 222° true (SW by W ¼ W mag.) for the western edge of the trees on Buckle Island, with the eastern edge of the trees on Black Island astern. On this course pass 15 to 25 yards southeastward of two red buoys and about 50 yards northward of a black buoy. Then steer 243° true (W ¾ S mag.) with the northern end of the trees on Orono Island astern, pass about 25 yards southward of a horizontally striped buoy and give the edge of the bare ledge on the north side of Buckle Island a berth of 150 yards.

Passage north of Pond Island.—This passage is used by vessels entering Blue Hill Bay from westward and sometimes by vessels following the inside passage eastward or westward. It has a least depth of about 19 feet in the buoyed channel, but there are dangers close to the sailing lines. The buoys are colored for vessels bound westward. Directions are given on page 115.

Digitized by Google

Pond Island is wooded on its eastern side. The western side is bare and is marked by a house and barn. Lamp Islet is a grassy islet ¼ mile northward of Pond Island.

Channel Rock is about 5 feet above high water. A submerged ledge extends ⅜ mile east-southeastward of it.

Green Island is grassy and marked by **Blue Hill Bay lighthouse** (white tower connected with dwelling). The shoal of which it is a part is bare at low water from the island to the shore 1⅛ miles northward and for a distance of ¼ mile southward of the island. It is marked by a black buoy off the south end. **Sand Islet,** ¼ mile northeastward of the lighthouse, is nearly covered at high water.

Flye Island Ledge, having rocks with depths of 7 to 13 feet, not closely examined, extends to a point 1 mile south-southwestward of Blue Hill Bay lighthouse.

Herrick Bay is a shallow and unimportant bight on the western side of Blue Hill Bay northwestward of Blue Hill Bay lighthouse. It is dry at low water for a distance of nearly 1 mile from its head. There is good anchorage in the approach to the bay ¼ to ¾ mile from the western shore northward of Naskeag Point, in 4 to 7 fathoms. The range of the western ends of Flye and Long Islands leads westward of Flye Point Ledge.

Ship and Barges Ledge, ⅝ mile south-southeastward of Ship Island, is 350 yards long and bare at half tide. It is marked by a tripod beacon on the south end, a spindle on the north end, and a black bell buoy 250 yards eastward.

West Barge is a flat grass-topped rock 600 yards westward of Ship Island. **East Barge** is a round grassy islet on the end of the shoal extending 200 yards southward from Ship Island.

Ship, Trumpet, Bar, and **Tinker Islands** are a chain 4 miles long in the middle of Blue Hill Bay. The islands are joined by shoals bare at low water, except for a channel between Trumpet and Bar Islands, which has a depth of 17 feet and is marked by a perpendicularly striped buoy. Ship and Bar Islands are high and grassy, and Bar Island is marked by a house and barn. Trumpet Island is low and grassy. Tinker Island is partly wooded and has an old house at its southeast end.

Cow and Calf Ledge, extending ¼ mile westward and northward from the north end of Tinker Island, has several rocks with little water, and one rock bare at half tide. It is marked by two red buoys.

Allen Cove, on the west side of Herriman Point, 3½ miles northward of Blue Hill Bay lighthouse, is rarely used as an achorage. The shores are foul. The anchorage is in the middle in 2 to 5 fathoms and is open northward.

Long Island is generally wooded, with many clear sections, and has some inhabitants. **Seaville** is a post office on the island.

South Blue Hill, a village on the western side of Blue Hill Bay just south of Sand Point, has a fish cannery and is a point of call for the steamers between Blue Hill and Rockland. The wharf has ample depth.

Salt Pond, just south of the entrance to Blue Hill Harbor, has falls at the entrance, is crossed by a fixed bridge, and can not be entered.

Darling Island lies just eastward of the entrance to Blue Hill Bay. **Darling Ledge,** the top of which shows at low water, extends ¼ mile

Digitized by Google

southward of Darling Island. There is foul ground between the ledge and the shore.

Morgans Bay, lying northward of Long Island and on the west side of Newbury Neck, is about 3 miles long, but is little used. The entrance is obstructed by Jed Islands and the surrounding ledges, leaving a deep narrow channel close to the western shore on either side of Conarys Nub.

To enter, pass in mid-channel westward of Conarys Nub on a 38° true (NE by E mag.) course, and keep the western shore aboard distant 200 yards until abreast Seal Ledge. Or pass 125 yards eastward of Conarys Nub on a 2° true (N by E ¾ E mag.) course, and pass midway between Seal Ledge and the western shore. Good anchorage can be selected in the bay, in 2 to 6 fathoms, for which the chart is the guide.

Conarys Nub is a rock with a clump of scrub. **Seal Ledge** is awash at high water. **Black Rock** is on a shoal with 7 to 10 feet which extends ⅜ mile northeastward of Seal Ledge. **Bird Rock**, westward of Jed Islands, is about 3 feet high. **South Ledge**, ¼ mile southwestward of Jed Islands, is covered at half flood. A rock with 4 feet over it lies ¼ mile southwestward of South Ledge. Danger will be avoided by keeping westward of a line from Conarys Nub to the southwest end of Newbury Neck.

BLUE HILL HARBOR

(chart 307) is in the northwestern part of Blue Hill Bay, northwestward of Long Island. It consists of a large bight, called the outer harbor, and a small arm extending northwestward to the village of **Blue Hill**, called the inner harbor. Ledges extend 200 to 400 yards from the western shore of the outer harbor, and at a point 1 mile southward of the entrance of the inner harbor they extend ½ mile from shore. Anchorage, sheltered from northerly and westerly winds, will be found in the outer harbor in 4 to 8 fathoms.

The channel in the inner harbor is narrow and crooked. The entrance has a depth of about 18 feet, but it is so narrow that a stranger should not depend on carrying a greater depth than 8 feet at low water. There is secure anchorage for small vessels just inside the entrance, in 3 to 4 fathoms. The steamer landing for Blue Hill is on the north side ⅝ mile above the entrance and has a depth of about 12 feet at its end. Ice closes the harbor from December to April.

Many of the rocks show except at high water, and the principal dangers are buoyed. **The Triangles** are three rocks, bare at low water only. The entrance is 50 yards wide between **Sculpin Ledge** (bare at one-quarter ebb and marked by a red buoy) and a ledge southward of it which has 8 feet on its northern end and extends to the shore southwestward. Eastward of the entrance is a detached shoal 350 yards long, with 4 feet over it, the eastern end of which is marked by a black buoy. Vessels can enter on either side of the shoal.

To enter northward of it, pass 50 yards eastward and 100 yards northward of the black buoy and steer 279° true (NW by W ⅝ W mag.) for Sculpin Ledge red buoy. Leave it about 20 yards on the starboard hand and steer 320° true (NNW mag.) Select anchorage near mid-channel 200 to 500 yards above Sculpin Ledge, in 3 to 4

Digitized by Google

fathoms, bottom soft in places. If going to the wharf, be guided by the chart and buoys.

To enter westward of the shoal, steer 323° true (N by W 5/8 W mag.) with a rock awash at high water, lying in the entrance of the eastern cove on the north side of the inner harbor, in range with the arch in the culvert at the head of the cove. Keep the range until about 250 yards from Sculpin Ledge, and then keep a little eastward of it to allow room for making the turn westward. Pass about 20 yards southward of Sculpin Ledge red buoy, steer 320° true (NNW mag.), and anchor as directed in the preceding paragraph.

UNION RIVER BAY

is a large bay extending about 5½ miles in a northerly direction between Oak Point on the east and Newbury Neck on the west. It is free from dangers, except near its northern end. The head of the bay is separated into two arms, Union River, the eastern, leading to the city of Ellsworth, and Patten Bay, the western, leading to the town of Surry.

Patten Bay is a long, narrow arm making northwestward from Union River Bay. The town of **Surry** is at its head. The deepest draft entering is 10 feet, but the depth in the channel up to the town is only 2 feet at low water, and the wharf runs dry. There is good anchorage at the entrance near mid-channel as far as 1½ miles above the entrance in 4 to 5 fathoms. A ledge, partly bare at half tide, extends 400 yards from the northern shore ¾ mile westward of Weymouth Point, and is marked by a red buoy. Between the buoy and a point 1 mile above, the northern shore is fairly bold, while the opposite side should be given a berth of 300 yards. Ice closes the upper end of the bay during January, February, and March.

Union River.—This river empties into the head of Union River Bay from northward and forms the approach to the city of Ellsworth, 4 miles above the entrance. There are several rocks off the entrance and the most prominent are buoyed. It is about 1 mile wide at the entrance but contracts to 250 yards 1 mile above. Union River has been improved by dredging a channel through the flats at the entrance, and for a distance of 1 mile below Ellsworth and had a depth of about 4 feet at low water to Ellsworth in 1917. It has considerable trade, mostly in sailing vessels, which always take a towboat. The river has many sawdust shoals. Freshets occasionally occur in the spring. Ice closes the river from December to April.

Whitmore Cove, on the eastern side of Union River at the entrance, is small and shoal. There is a sawmill and wharf on the cove. Pilots may be obtained here, or a towboat by telephone from Ellsworth.

Ellsworth is a city on the railroad at the head of Union River. It has some trade, the deepest draft being 12 feet. The wharves have depths of 4 to 5 feet. There is a towboat here. Coal in limited quantities and other supplies are obtainable, and there is water on the wharves. The river water is fresh at low water. There are marine railways, the largest capable of hauling out vessels of 100 tons, 7 feet draft forward, 9 feet aft, and 130 feet long. Ordinary repairs to machinery can be made.

Digitized by Google

Directions, Union River.—Directions through Blue Hill Bay to the entrance of Union River are given on page 111. The channel in Union River is narrow and difficult, and strangers in vessels should not enter without a pilot. The dredged channel was marked by small private buoys and stakes in 1917. With the aid of the chart and the following directions, small craft should be able to go to Ellsworth, but should do so on a rising tide.

Pass between Lord Rock red buoy and Tupper Ledge black buoy and steer northeastward to the red buoy at the entrance of the dredged channel. The dredged channel across the flats at the entrance favors the eastern side and was marked in 1917 by red buoys on the eastern side at the turns. Stakes are sometimes used in place of the red buoys, and may be on either side. From the red buoy at the entrance the course is 31° true (NE ⅜ E mag.) for 350 yards, then 9° true (NNE ½ E mag.) for ⅜ mile, keeping about 150 yards off the eastern short, and then 341° true (N mag.) for ⅝ mile to a position close westward of a spindle at the entrance to the narrow part of the river. From this point to the entrance of the dredged channel 1 mile below Ellsworth, there are no marks and a general mid-channel course is the best, although in the bend just before reaching the dredged channel the best water slightly favors the east side. The dredged channel in the upper end does not follow a mid-channel course. It was marked in 1917 by small private black buoys on the western side, and these are the guides.

DIRECTIONS, BLUE HILL BAY.

Blue Hill Bay is approached from eastward across Bass Harbor Bar, from southward between Black Island and Swan Island, and from westward through Jericho Bay, which is entered through Merchants Row, Deer Island Thoroughfare, or Eggemoggin Reach. The channels between Blue Hill and Jericho Bays are Casco Passage, York Narrows, and the passage northward of Pond Island. These approaches are more or less obstructed by islands and ledges, but are sufficiently marked to be safely navigated in clear weather. At high water small vessels can also enter the head of Blue Hill Bay from Frenchman Bay through Mount Desert Narrows (described on p. 94).

The generally used inside route, used by most vessels of 12 feet or less draft, across Bass Harbor Bar and through Casco Passage, leads across the south end of Blue Hill Bay. Directions for it are given on page 50.

The vessels bound to points in Blue Hill Bay do not often exceed 12 feet draft, and these vessels usually follow the inside passage, generally entering from eastward across Bass Harbor Bar and from westward by the passage between Pond Island and Blue Hill Bay lighthouse. Vessels of too deep draft, or when there is too much easterly or southeasterly swell on Bass Harbor Bar, can enter the bay southward of Little Gott and Placentia Islands and northward of Black Island; but this passage has not been closely examined and is not recommended for a greater draft than 15 feet. Vessels of the deepest draft can enter by the main channel between Black and Placentia Islands on the east and Long and Swan Islands on the west. This

Digitized by Google

passage has been covered sufficiently by means of a wire drag to insure a clear channel as indicated on the chart.

Above the entrance, Blue Hill Bay is deep and generally free from dangers, and several channels are available.

From Bass Harbor Bar.—Directions to Bass Harbor Bar from eastward and from Bass Harbor Bar westward through Casco Passage are given on page 49. Vessels bound from Bass Harbor Bar to Union River usually use the channel between Tinker and Hardwood Islands, and between Long and Bartlett Islands. This channel is deep and unobstructed and the chart and buoys are the guides. Small craft sometimes use the more protected passage between Moose and Hardwood Islands and through Bartlett Narrows (described on p. 105). Bound to Blue Hill Bay from Bass Harbor Bar, the most direct route leads eastward of the chain of islands and reefs extending from Ship and Barges Ledge to Tinker Island, and southward and westward of Long Island. It is deep and clear and the chart is the guide.

Entering between Black and Placentia Islands.—This passage has a rock with a least found depth of 18 feet, not closely examined, 250 yards off the southwest end of Little Gott Island. Vessels of 15 feet or less draft may use it by favoring the north shore of Black Island, 250 yards off, after passing Inner Dawes Ledge (a rock islet), and round the north end of Black Island at a distance of 200 yards. Then steer west-southwestward and round the southwestern end of Placentia Island at a distance of 400 to 500 yards. The course can then be shaped northward into Blue Hill Bay, or if bound to Casco Passage, northeastward to pass northeastward of Staple Ledge buoy and North Point of Swan Island. Directions through Casco Passage are given on page 50.

Entering from southward.—Pass ¾ mile eastward of Long Island Head, and steer 334° true (N ¾ W mag.) for the western end of Green Islands. Or, passing ⅜ mile or more southward of Great Duck Island lighthouse, bring it astern on a 282° true (NW by W ⅜ W mag.) course, heading for the western end of Green Islands, and pass about ⅜ mile northeastward of The Drums buoy. Pass 400 to 500 yards westward of Green Islands and steer 315° true (NNW ⅜ W mag.) for 2¼ miles to a position ¼ mile westward of Placentia Island. The course can then be shaped as desired.

Entering from westward.—Vessels entering Blue Hill Bay from westward generally come through Eggemoggin Reach or Deer Island Thoroughfare, and enter Blue Hill Bay by the passage between Pond Island and Blue Hill Bay lighthouse. The regular steamer, drawing about 10 feet and entering from Eggemoggin Reach, passes between Hay Island Ledge horizontally striped buoy and the red buoy northward, then between Smutty Nose and Mahoney Islands, then close eastward of the black buoy ⅜ mile southward of Blue Hill Bay lighthouse, and then between Blue Hill Bay lighthouse and Sand Islet. This route should not be used by strangers except in small craft. The deeper channel (about 19 feet) leads through the buoyed channel ½ mile northward of Pond Island.

Vessels entering Blue Hill Bay from Eggemoggin Reach can reverse the directions on page 115. **Entering from Deer Island Thoroughfare,** they can reverse the directions on page 118 to the perpendicularly striped bell buoy in Jerico Bay, then steer 19° true (NE ¾ N mag.)

Digitized by Google

for 3¼ miles, passing ⅜ mile east-southeastward of Mahoney Island, to a position 50 yards westward of buoy No. 3, and then 69° true (E ¼ N mag.) passing 50 yards southward of a red buoy and 100 yards northward of a black buoy, into Blue Hill Bay. The course can then be shaped as desired.

JERICO BAY.

(chart 308) is the body of water between Swan and Marshall Islands on the east and Isle au Haut and Deer Isle and adjoining islands on the west. The inside routes leading from Casco Passage and York Narrows to Deer Island Thoroughfare and Merchants Row and from the passage north of Pond Island to Eggemoggin Reach lead across its head, and this section is used by many vessels. The part of the bay southward of these thoroughfares has deep water but there are many ledges, rocks, and small islands, and this part is little used except by local fishermen.

The islands on the eastern side are described under "Islands off Blue Hill Bay" on page 100. Casco Passage and York Narrows, the passage north of Pond Island, and Herrick Bay are described under "Blue Hill Bay." Some of the dangers on the western side are described with Merchants Row and Deer Island Thoroughfare following.

Spirit Ledge, ¾ to 1¼ miles southwestward of Marshall Island, is in two sections; the northeastern is bare at high water and the southwestern is bare at about half tide.

Boxam Ledge, off the southwest side of Marshall Island, is bare at low water.

Drunkards Ledge, 2 miles southwestward of Marshall Island, is bare at low water.

Marshall Ledge, off the west side of Marshall Island, is bare at low water.

Directions, Jerico Bay. FROM SOUTHWARD.—The channel leading into Jerico Bay between Spirit Ledge and Three Bush Island on the east, and Drunkard Ledge, Blue Hill Rock, and North Popplestone Ledge on the west, the main part of the bay northward, and also the channel leading into the bay between Marshall and Swan Islands, have been partially examined by means of a wire drag. Approaching from southward, it is advisable to pass between Marshall and Swan Islands, where the dangers are well marked. The entrance between Marshall Island and Isle au Haut is obstructed by a number of unmarked submerged ledges, and is little used.

Vessels may pass ¼ mile southward of Southwest Point of Long Island, steer 267° true (WNW ⅝ W mag.) for 1¾ miles to a position ¼ mile south-southwestward of a red buoy, then steer 301° true (NW ⅜ N mag.) for 5⅜ miles, passing midway between Green and Brimstone Islands, 350 yards northeastward of Ringtown Island, 200 yards northeastward of the black buoy northward of Marshall Island, and to a position 200 yards southwestward of the red buoy westward of Hat Island; or from the whistling buoy 1¾ miles southeastward of Heron Island, a 337° true (N ½ W mag.) course for 2 miles will lead to a position midway between Green and Brimstone Islands, and the 301° true (NW ⅜ N mag.) course can then be fol-

Digitized by Google

lowed to a position 200 yards southwestward of the red buoy westward of Hat Island.

BOUND TO MERCHANTS ROW.—From this position, vessels may haul westward, pass northward of a black bell buoy and ¼ mile northward of West Halibut Rock horizontally striped buoy, and follow the directions on page 50.

BOUND TO DEER ISLAND THOROUGHFARE.—From a position 200 yards southwestward of the red buoy westward of Hat Island, vessels can steer 310° true (NNW ⅞ W mag.) for 2½ miles, passing ¼ mile northeastward of Whaleback Ledge red buoy, and to a position 200 yards southwestward of Shabby Island (marked by a few trees). Then bring Shabby Island astern on a 293° true (NW ⅜ W mag.) course, with Sheep Island a little on the port bow, and pass 250 yards northeastward of buoy No. 1 and 100 yards northeastward of buoy No. 3; then haul westward and follow the directions for Deer Island Thoroughfare on page 118.

BOUND TO EGGEMOGGIN REACH.—Pass 200 yards westward of the red buoy westward of Hat Island and steer 0° true (N by E ⅝ E mag.) for 2⅝ miles to the perpendicularly striped bell buoy westward of Egg Rock. Then steer 330° true (N by W mag.), heading for Devils Head, until midway between Hay Island Ledge buoy and Channel Rock buoy, and then haul northwestward and follow the directions given on page 116.

EGGEMOGGIN REACH

(chart 309) lies between the Deer Isles and the mainland and connects Blue Hill Bay and the head of Jerico Bay with Penobscot Bay near its head. It is 11 miles long and has a least width of ⅜ mile at Byard Point. The reach has several villages along its shores. Regular steamers between Rockland and Blue Hill make landings at all of the villages. The eastern entrance is well marked by **Devils Head**, a prominent, high rocky bluff on the south end of Hog Island, and the western entrance by **Pumpkin Island lighthouse** (white tower connected with dwelling) and **Cape Rosier** (high and thickly wooded).

Mahoney Island, just eastward of the entrance to Eggemoggin Reach, has scattered trees. **Smutty Nose Island**, ½ mile northwestward of Mahoney Island, is grass covered. **Mahoney Ledge**, westward of Mahoney Island, is partly bare at low water.

Greenlaws Cove, on the southwest side of the eastern entrance to Eggemoggin Reach, has a narrow unmarked channel with shoals on both sides, and is suitable only for small craft with local knowledge. **Mountainville** is a post village near the head. The landing is said to be nearly bare at low water. There is little business by water.

Devils Head Ledge, extending ¼ mile southeastward from **Devils Head**, is partly bare at high water and marked off its end by a red buoy. **Channel Rock** is bare at extreme low water and marked by a black buoy. **The Bowlders**, 400 yards northwestward of Channel Rock, are bare at low water.

Naskeag Harbor, north of **Harbor** and **Hog Islands**, has a fish cannery and the post village of **Naskeag** on the north side. The harbor can be entered from eastward or westward, but there are many unmarked

Digitized by Google

dangers and strangers should not attempt to enter except in small craft.

Centre Harbor, a small cove on the eastern side of the Reach northeastward of **Torry Islands**, is an anchorage for small craft only. The town of **Brooklin** is at the head of the harbor. A rock marked by a black spindle with cage lies in the middle of the entrance northward of **Chatto Island**; the channel is close southward of the rock. Between the spindle and the fish factory on the north side the cove has depths of 8 to 10 feet, and above this is mostly dry at low water. The steamer landing is on the north side at the entrance and has a depth of about 12 feet. There is good anchorage off the entrance in 4 fathoms, bottom soft in places. The main approach to Centre Harbor is from westward, but local vessels enter by the channel eastward of Torry Islands, passing in mid-channel on either side of the bare rock 350 yards eastward of the easterly Torry Island. This passage should be used by strangers only in small craft.

Benjamin River, the approach to the town of Sedgwick, makes into the eastern shore 2 miles northward of Center Harbor. The channel at the entrance, northward of Cape Carter, has a least depth of 19 feet, but is much obstructed by ledges on both sides, leaving a passage only 100 yards wide at its narrowest part. The town of **Sedgwick** can only be reached at high water, as the river runs dry some distance below. Steamers passing through the Reach in summer land at the wharf on the west side at the entrance, which has a depth of about 11 feet.

North Deer Isle is a post village at the north end of **Deer Isle**. The steamer wharf, 3/8 mile westward of **Tinker Ledges**, has a depth of about 12 feet.

Billings Cove, on the northern shore of the Reach, lies east of Byard Point. It affords anchorage in the middle just inside the entrance in about 5 fathoms. **Sargentville**, a post village on the eastern shore of the cove, is one of the landings for steamers passing through the Reach in summer.

Eggemoggin is a summer resort at the north end of Little Deer Isle southeastward of Pumpkin Island lighthouse. The steamer wharf has a depth of about 11 feet.

Buck Harbor is on the north side of the Reach, north-northeastward of Pumpkin Island lighthouse; it affords excellent anchorage, and is often used by small vessels. **Harbor Island**, in the middle of the harbor, has a good channel around it, which forms the anchorage. Shoals extend 250 yards off the northeast side of Harbor Island, and the channel is narrow between them and the shore northeastward. **Harbor Rock**, at the north end of the shoals, is marked by a horizontally striped buoy. The channel between the rock and the north end of Harbor Island has a depth of 12 feet. Small craft can anchor in the bight on the northeast side of Harbor Island. The best anchorage for vessels is westward and northwestward of Harbor Island, in 5 to 6 fathoms. The post village and landing of **South Brooksville** is at the head of the harbor. The steamer wharf has a depth of 12 feet. There are several float landings.

Orcutt Harbor lies just westward of Buck Harbor and northward of Pumpkin Island lighthouse. It is about 1¼ miles long and ¼ mile wide. It has good anchorage in 3½ to 8½ fathoms in the

Digitized by Google

middle of the harbor just above a small wooded islet. A reef, bare at low water, extends 300 yards southward from **Condon Point**, on the east side at the entrance. When inside this reef, favor, if anything, the eastern side of the entrance to avoid a sunken rock lying nearly 200 yards from the western shore and the same distance southward of the wooded islet. In the slight expansion ½ mile above the islet care must be taken to avoid two sunken rocks, one lying 200 yards from the western shore and the other 150 yards from the southeast side of the expansion.

Horseshoe Cove is a long, narrow cove, the entrance to which lies northwestward of Pumpkin Island lighthouse; it is navigable only for small craft with local knowledge. There are no wharves.

Thrumbcap Island, 1 mile northward of Pumpkin Island lighthouse, is low and grassy. **Thrumbcap Ledge**, southwestward of Thrumbcap Island, is partly bare at high water. **Merriman Ledge** is bare at low water only and marked by a black buoy on its north side.

Of the islands near the western entrance to Eggemoggin Reach, **Spectacle Islands** are grassy, **Two Bush Islet** is bare, **Hog Island** has scattered trees and a house and barn in the center, and **Pond Island** is grassy, with a small clump of trees on the northeast side and a shanty at the south end. **Western Island** is grassy on its eastern end and has a thick clump of trees on its western end. **Green Ledge** is grassy.

Anchorage.—Vessels can anchor anywhere in the Reach where the depth is suitable and the bottom soft, making a lee of either shore, according to the wind. Small craft anchor in the coves.

Tides.—The mean rise and fall of tides is about 10 feet.

Supplies.—Gasoline and provisions can usually be obtained near most of the steamer landings. No other supplies are obtainable.

DIRECTIONS, EGGEMOGGIN REACH.

The main channel through Eggemoggin Reach has been examined by means of a wire drag. The depth is sufficient for deep-draft vessels, but the channel is narrow and the bottom irregular in places and the passage is not recommended for a greater draft than 18 feet, except with local knowledge. The principal dangers for this draft are buoyed, and can be easily avoided in the day time and clear weather.

Directions to Eggemoggin Reach from southward through Jerico Bay are given on page 112 and from Casco Passage on page 50. The following directions lead in a depth of 19 feet through the channel northward of Pond Island and 16 feet if using the route northward of Mahoney Island; by using the route southward of Mahoney Island they are good for a draft of 18 feet throughout. The aids are colored for vessels bound northwestward.

1. **Bass Harbor Bar to Devils Head by the passage northward of Pond Island.**—From the fairway buoy lying about 350 yards southward of Bass Harbor Head lighthouse, steer 271° true (WNW ⅜ W mag.) for 4 miles, heading for the summit near the southern end of Pond Island, to a position ¼ mile southwestward of the tripod on Ship and Barges Ledge. Then steer 301° true (NW ⅜ N mag.) for Blue Hill Bay lighthouse for 2 miles, passing 400 yards southwestward of West Barge. Pass about 200 yards eastward and 100 yards

Digitized by Google

northward of buoy No. 1; steer 248° true (W ⅜ S mag.) for the summit of Harbor Island, and pass 50 yards southward of buoy No. 2 and the same distance northward of buoy No. 3.

Then steer 228° true (WSW mag.) for the western end of Crow Island (flat and wooded) and keep Smutty Nose Island best aboard, distant about 250 yards, when passing between it and Mahoney Island. When Smutty Nose is abeam, steer 258° true (W ½ N mag.) and pass 200 yards northward of Hay Island Ledge horizontally striped buoy and 50 yards southward of Devils Head Ledge red buoy. Pass about 300 yards southwestward of Devils Head and proceed as directed in section 2.

To pass southward of Mahoney Island.—Pass 50 yards northward of buoy No. 3, steer 204° true (SW ⅜ S mag.), pass ¼ mile southeastward of Mahoney Island, and continue the course ⅜ mile past the island. Then steer 280° true (NW by W. ½ W mag.) for the summit of White Island, and pass 50 yards southward of Mahoney Island Ledge red buoy and 400 yards southward of Hay Island Ledge horizontally striped buoy. When the latter buoy is abeam, steer 311° true (NNW ¾ W mag.) for Torry Castle beacon, pass about 300 yards southwestward of Devils Head, and proceed as directed in section 2.

2. **Eggemoggin Reach, Devils Head to Penobscot Bay.**—Pass 300 yards southwestward of Devils Head and steer 311° true (NNW ¾ W mag.) for Torry Castle tripod beacon, passing ¼ mile northeastward of Conary Island. Pass 300 yards northeastward of Conary Ledge black buoy and steer 298° true (NW ⅛ N mag.) to a position 100 yards southwestward of the red buoy southward of Torry Castle. Then steer 315° true (NNW ⅜ W mag.) for 3¼ miles, heading for the wharf at Sargentville, and pass about 300 yards eastward of the outer black buoy off North Deer Isle. From a position ¼ mile northward of this buoy, steer 291° true (NW ½ W mag.) for 1½ miles and pass midway between Byard Point and Little Sally.

Give the shore of Byard Point a berth of 300 yards and steer 307° true (NW ⅞ N mag.) for 2¼ miles, passing 300 yards northeastward of Howard Ledges buoy and to a position 400 yards northeastward of the easterly black buoy on The Triangles. Then steer 258° true (W ½ N mag.) for ¾ mile, with Blake Point, the south end of Cape Rosier ahead, to a position 350 yards north-northeastward of Pumpkin Island Ledge black buoy, and then 229° true (WSW mag.) for 1¼ miles, passing midway between a horizontally striped buoy on the south side and a red buoy on the north side, to the perpendicularly striped bell buoy southward of Spectacle Island. Vessels bound to points northward in Penobscot Bay can then steer west-northwestward and round Cape Rosier at a distance of ¼ mile or more.

Bound to Rockland.—Local vessels bound from Eggemoggin Reach to Rockland generally pass westward of Western and Resolution Islands and through the channel between Mouse, Goose, and Saddle Islands on the southeast and Lime, Lasell, and Mark Islands on the northwest, passing southward of the red bell buoy southward of Mark Island. This passage is well marked and easily followed in the day time with as much draft as can be taken through Eggemoggin Reach. A deeper channel, leading clear of all dangers, leads westward of Resolution Island, southward of McIntosh Ledge horizon-

Digitized by Google

tally striped buoy and then for the entrance of Rockland Harbor. Directions from Two Bush Channel to Eggemoggin Reach are given on page 148.

DEER ISLAND THOROUGHFARE

(chart 309) is a narrow passage leading along the south side of Deer Isle, between it and the numerous islands southward. It joins Jerico Bay on the east and Penobscot Bay on the west and forms one of the chain of inland passages. It is used by the passenger vessels between Rockland and points eastward, and by many other vessels and small craft bound through the inland passages. It has a least width of 150 yards in several places and a least depth of 15 feet in a dredged channel 300 feet wide through the bar between Moose and Crotch Islands. It is used by vessels up to 16 feet draft, but there are unmarked rocks with 9 to 14 feet close to the channel, and local knowledge is necessary to carry through a greater draft than 9 feet at low water. The dangers for vessels of this draft are marked, and the channel easily followed in the daytime and with clear weather.

Southeast Harbor lies northwestward of the eastern end of the thoroughfare, between **Stinson Neck** on the east and **Whitmore Neck** on the west. It is an excellent anchorage for vessels using the thoroughfare. The entrance is easily distinguished and the principal dangers are marked by buoys.

Oceanville is a post village on the south side of Southeast Harbor. There is a cannery here and a wharf with little depth. **South Deer Isle** is a village at the head; it has a wharf with a reported depth of about 6 feet at high water.

To enter Southeast Harbor, enter Deer Island Thoroughfare southward of Long Ledge tripod, between a red and a black buoy, steer 264° true (W by N mag.) and pass 100 yards southward of Lazygut Ledge red buoy. When 400 yards westward of this buoy, steer 298° true (NW mag.), and pass about 350 yards northeastward of Boat Rock horizontally striped buoy and buoy No. 1; select anchorage northeastward of Whales Back, taking care to avoid the rock with 11 feet over it. From westward in Deer Island Thoroughfare, pass between Haycock Rock spindle and Sheldrake Rock, and from a position 250 yards eastward of the latter a 328° true (N by W ¼ W mag.) course leads into the harbor.

Webb Cove, on the north side of Deer Island Thoroughfare, has rocks in the entrance, but there is good anchorage inside in 8 to 12 feet. The best water favors the west side of the entrance. There is a quarry on the cove and a wharf with a reported depth of about 8 feet.

Stonington is a town on the north shore of Deer Island Thoroughfare. It has steamer communication with Rockland and Bar Harbor and intermediate points, and is the headquarters for the large granite quarries on the adjacent islands. The steamboat wharf has a depth of 12 feet, but there is a ledge off the wharf, marked by private buoys. The other wharves have less depths. Gasoline, provisions, and some ship chandlery are obtainable.

Prominent objects.—At the eastern entrance the most prominent object is Long Ledge tripod beacon. SHABBY ISLAND is marked by a

Digitized by Google

few trees. At the western entrance MARK ISLAND (wooded on top) with DEER ISLAND THOROUGHFARE LIGHTHOUSE (white tower attached to dwelling) are the most prominent marks. There is an unused quarry on the north side of Crotch Island.

Anchorage.—The best anchorage for vessels bound through the thoroughfare and overtaken by night or bad weather is Southeast Harbor. When overtaken by fog, they may anchor anywhere near the channel where the bottom is soft and depth suitable. Many small vessels anchor on the north side of the channel abreast Stonington, the generally used anchorage being between the steamer wharf and the red buoy 3/8 mile eastward.

Ice closes the thoroughfare and Southeast Harbor for about one month each winter.

Tides.—The mean rise and fall of tides at Stonington is 9.7 feet.

Currents.—The tidal currents follow the general direction of the channel and are not strong. The direction of the currents is influenced by the wind; with strong easterly winds both the flood and ebb set westward, and with westerly winds they set eastward. When not influenced by the wind the flood sets eastward and the ebb westward, and continues to run about 3/4 hour after high and low waters.

DIRECTIONS, DEER ISLAND THOROUGHFARE.

Deer Island Thoroughfare has a least depth of 15 feet, and is used by vessels up to 16 feet draft, but there are unmarked rocks with depths of 9 to 14 feet close to the channel, and local knowledge is necessary to carry through a greater draft than 9 feet. The dangers for vessels of this draft are marked, and the channel easily followed in the daytime and in clear weather.

From the fairway bell buoy in Jericho Bay, lying 3/8 mile westward of Egg Rock tripod, steer 252° true (W mag.), which leads 200 yards southward of an unmarked ledge with 8 feet over it lying 5/8 mile eastward of Long Ledge tripod beacon. Continue the course to a position 50 to 75 yards southward of the red buoy 250 yards southward of Long Ledge tripod.

Then steer 263° true (W by N mag.), pass northward of Potato Ledge black buoy, southward of Lazygut Ledge red buoy, and to a position 100 yards northward of a black buoy which marks a rock with 7 feet over it lying 400 yards northward of Eastern Mark Island.

Then steer about 230° true (WSW mag.) and pass between Haycock Rock spindle and **Sheldrake Rock**, the bare rock 400 yards northward of the spindle. Then steer 251° true (W 1/8 S mag.) for the south end of Grog Island and pass southward of red buoys Nos. 6 and 8 and northward of black buoys Nos. 5 and 7. When northward of buoy No. 7 and about 1/8 mile from Grog Island, steer 237° true (WSW 5/8 W mag.) for the summit of Russ Island and pass 100 to 150 yards southward of Grog Island.

When **Humpkins Islet**, the bare rock 1/2 mile westward of Grog Island, bears 0° true (N by E 1/2 E mag.), steer 260° true (W 3/4 N mag.) with the north side of Bold Island astern, and pass 50 yards northward of the black buoy off the north side of Russ Island and about 100 yards southward of red buoys Nos. 12 and 14, the latter buoy lying southeastward of the wharf at Stonington. Give the

Digitized by Google

north side of **Two Bush Islands** (largest has a clump of scrub) a berth of over 150 yards, and keep the north shore aboard distant about 100 yards when entering the narrow passage northward of Crotch Island.

Pass 20 to 30 yards northward of Thurlow Knob Ledge black buoy, steer 242° true (W by S mag.) and pass 90 yards northward of a stone beacon marking a ledge bare at low water, and 50 yards northward of the black buoy abreast the beacon. The channel from this point to 300 yards westward has been dredged 300 feet wide. From a position 90 yards northward of the beacon steer 228° true (SW by W 7/8 W mag.) for 300 yards with the summit of Green Head astern and Deer Island Thoroughfare lighthouse a little on the starboard bow, then steer 243° true (W 3/4 S mag.), pass 150 to 200 yards southward of Yellow Rock (which shows at high water), 100 yards northward of buoy No. 15, 250 to 300 yards southward of Western Deer Island Ledge (a large bare rock), and 200 to 300 yards northward of Mark Island. Then bring Deer Island Thoroughfare lighthouse astern on a 265° true (WNW7/8 W mag.) course, passing about 400 yards southward of Western Mark Island Ledge red buoy, which lies 5/8 mile northwestward of the lighthouse. This course made good for 4½ miles from the lighthouse will lead to a position 100 yards southward of Channel Rock bell buoy, lying 125 yards southward of Channel Rock tripod. Directions through Fox Islands Thoroughfare are given on page 51.

A buoyed channel with a depth of 14 feet leads into Deer Island Thoroughfare from southward, eastward of Crotch Island. Directions for entering are given on page 131.

MERCHANTS ROW.

This passage (chart 309), leading from Jericho Bay to East Penobscot Bay and passing between the islands and ledges lying between Deer Island and Isle au Haut, is used by vessels in the winter, when Deer Island Thoroughfare is closed by ice, and by deep-draft vessels at all times. It is not quite so direct as Deer Island Thoroughfare, but the channel is wider, and is good for a depth of 26 feet. There are numerous ledges and rocks on both sides of this passage, but the principal ones are marked by buoys or spindles, and the channel can be readily followed in clear weather and daylight.

Directions for Merchants Row from eastward are given on page 50. Deep-draft vessels can enter through the passage between Marshall and Swan Islands and Jericho Bay, as directed on page 112. Directions for entering Merchants Row from southwestward in Isle au Haut Bay are given on page 131.

Halibut Rocks, in Jericho Bay eastward of the entrance, are two rocks, the northerly one marked by a red slatted beacon. There is a black bell buoy northward of the rocks.

West Halibut Rock, 1 mile westward of Halibut Rocks, has 2 feet over it and is marked by a horizontally striped buoy. A rock with 9 feet over it lies 400 yards northeastward of the buoy. A local magnetic attraction is reported on the broken ground ½ mile east-northeastward of Southern Mark Island.

Southern Mark Island is about 30 feet high and grassy. **Southern Mark Island Ledge**, 3/4 mile northward, has a rock bare at high water.

Digitized by Google

Colby Ledge is bare at half tide and marked by a spindle. A ledge with 15 feet over it lies 300 yards southward of the spindle.

Barter Island Ledges are partly bare at high water and marked by a spindle.

Eve Island is a prominent, round, thickly wooded islet, 3/8 mile northwestward of Merchant Island.

Farrel and **Scraggy Islands** are wooded; there are several bare rocks off the south side of Scraggy Island. **Sparrow Island** is grass covered. The islands and rocks southward and westward are described on page 128.

Deer Island Thoroughfare lighthouse, a white tower connected with dwelling on the north side at the entrance, is the most prominent mark entering from westward.

FOX ISLANDS THOROUGHFARE.

This thoroughfare (chart 311a), leading from East Penobscot Bay to West Penobscot Bay, between North Haven and Vinal Haven Islands, is one of the chain of inshore passages commencing at Bass Harbor and ending at Whitehead. It is about 7 miles long, and the channel, with a depth of 18 feet or more, has a least width of about 150 yards in several places; the principal dangers are marked by buoys and spindles, which can be easily followed in the daytime with clear weather. The least depth in the channel is 19 feet, but the thoroughfare is seldom used by vessels of over 14 feet draft at low water. The main channel has been examined by means of a wire drag.

Carvers Cove, in the south shore of the thoroughfare, near its eastern end, is a secure anchorage, easy of access, and convenient for vessels windbound in East Penobscot Bay or passing through the thoroughfares. The anchorage is about 1/2 mile from the head of the cove and 197° true (SW by S mag.) from the hospital on Widows Island, in 16 to 20 feet, good holding ground. The entrance on either side of Widows Island is clear, if the shores be given a berth of about 200 yards; but the point on the south side, at the eastern entrance of the cove, must be given a berth of over 300 yards.

Kents Cove, in the north shore of the thoroughfare, north of Widows Island, is a secure anchorage, with 15 to 24 feet, good holding ground. Goose Rocks lighthouse is the prominent guide for entering either in the daytime or at night, the entrance being westward of the lighthouse. **Kent Ledge**, the only outlying danger, has 5 feet over it and lies 1/4 mile northeastward of Fish Point Ledge red buoy, and the same distance from the northwest shore of the cove.

Waterman Cove makes into the north shore west of Kents Cove; it is a good anchorage for small vessels, the water shoaling gradually from 18 feet at the entrance to 5 feet near its head, where a narrow channel leads into a shallow cove called the **Cubby Hole**. **Waterman Ledge**, with 4 feet over it and marked by a red buoy, lies in the mouth of the cove 1/4 mile from the western shore. The better entrance is between the buoy and the bare rock 1/4 mile northeastward of it. **Fish Point Ledge**, partly bare at half tide and marked at its southeast end by a red buoy, lies 400 to 600 yards southeastward of Fish Point, with foul ground between.

Digitized by Google

Seal Cove is a large arm extending 1½ miles southward from Fox Islands Thoroughfare southeastward of the village of North Haven. Large areas in the cove have depths of 8 to 12 feet, bottom soft in places. Good anchorage can be selected in the channel of the thoroughfare between the entrance of Seal Cove and the western end of the village of North Haven, in 4 to 6 fathoms, soft bottom.

Perry Cove is a long, narrow arm making westward on the west shore of Seal Cove; it is of no importance as an anchorage and should be avoided by strangers.

Southern Harbor makes northeastward between the Dumpling Islands and Amesbury Point, near the western end of the thoroughfare. It has good anchorage in 19 to 22 feet, soft bottom, in the middle of the harbor; the water shoals gradually toward its head.

In the western entrance of Fox Islands Thoroughfare there is good anchorage for vessels of any draft westward or northward of Sugar Loaves, and between Crabtree Point Ledge and Amesbury Point, in 5 to 7 fathoms, soft bottom.

North Haven is a village on the north shore of Deer Island Thoroughfare. It has steamer communication with Rockland, Bar Harbor, and other villages. The steamer wharf has a depth of about 12 feet and the other wharves less. Gasoline and provisions are obtainable. Small craft anchor on the north side of the channel, taking care to leave a clear channel to the steamer wharf. Two ledges off the town, both marked by buoys, must be avoided.

Prominent objects.—**Channel Rock tripod**, at the eastern entrance, is a prominent mark. **Widows Island** is marked by a large brick hospital and is easily distinguished. **Goose Rocks lighthouse** (white conical tower on black base) is on the north side of the channel, north of Widows Island; it is the guide for the eastern entrance of the thoroughfare and for the anchorage in Kent Cove. **Browns Head lighthouse** (white cylindrical tower connected with dwelling) marks the entrance to the thoroughfare from westward. **Sugar Loaves** are a ledge of prominent high rocks lying 600 yards northwestward of Browns Head lighthouse. **Fiddler Ledge beacon** (gray stone), lying 1⅜ miles westward of Browns Head lighthouse, is a prominent mark when approaching from westward. Drunkard Ledge spindle is ½ mile westward of the beacon. Broken ground, which should be avoided by vessels, extends ¼ mile southward of the line joining the beacon and spindle.

Tidal currents.—The currents are not strong; they meet at Iron Point, in the middle of the thoroughfare, the flood setting in from both ends and the ebb setting out. The mean rise and fall of tides is 9.5 feet.

Directions through Fox Islands Thoroughfare from eastward are given on page 51. Vessels from westward can reverse those directions, but the following may assist: Passing 100 yards southeastward of the Sugar Loaves, steer 45° true (NE by E⅝E mag.) for the summit of the sharp hill lying ⅜ mile northeastward of Amos Point until 100 yards northwestward of Young Point spindle. Then steer 75° true (E ¼ S mag.) until the western point at the entrance of Young Cove is abeam. Then steer 104° true (SE by E⅛E mag.) with the heavy clump of trees on the northeast one of the Dumpling Islands astern, and pass southward of the buoys southward and

Digitized by Google

southeastward of North Haven. The last course insures clearing the unmarked ledge with 7 feet over it lying on the north side of the channel off the entrance of the shoal cove westward of North Haven.

PENOBSCOT BAY.

This is the largest and most important of the many indentations on the coast of Maine. It is about 20 miles wide from Isle au Haut on the east to Whitehead on the west, and is 28 miles long from its entrance to the mouth of the Penobscot River. A chain of large and small islands divides it into two parts known as East and West Penobscot Bays; the southern part of East Penobscot Bay is known as Isle au Haut Bay. Numerous harbors indent its shores, those of the most importance being Rockland, Rockport, Camden, and Belfast on the western shore, and Castine on the eastern. The bay is the approach to Penobscot River, which has several towns, and the city of Bangor at the head.

The sea approaches to the bay are well marked by the lighthouses on Monhegan Island and Matinicus Rock, and the entrances by Saddleback Ledge lighthouse on the east and Whitehead and Two Bush Island lighthouses on the west sides of the bay. The harbors are well lighted and the more important dangers are indicated by buoys or beacons. A large number of coasting and some foreign vessels enter the bay, especially in summer. In winter many of the harbors are obstructed by ice, and the Penobscot River is sometimes entirely closed by it. The thoroughfares are only occasionally obstructed by ice and are much used by vessels bound along the coast.

Penobscot Bay is a region of rocks and ledges, and extreme caution is necessary in navigating. It can be entered from eastward through Eggemoggin Reach, Deer Island Thoroughfare, or Merchants Row, and from westward through Muscle Ridge channel or Two Bush Channel. The main channel through these thoroughfares and the main part of both East and West Penobscot Bay, from a line joining Isle au Haut and Matinicus Islands northward to the entrances of Penobscot River and Belfast Harbor have been examined by means of a wire drag.

Pilots.—Pilotage is not compulsory for vessels entering Penobscot Bay, and vessels seldom take pilots. There are no regular licensed pilots, but local fishermen are competent pilots for the tributaries or the inside passages, and can usually be obtained from boats at work near the entrances or from the towns in the vicinity. Pilots for the inside passages between Bass Harbor Bar and Rockland can usually be obtained from Southwest Harbor, Bass Harbor, or Rockland.

Towboats.—There are towboats at Rockland and Bangor.

Supplies.—Gasoline and provisions are obtainable at all of the towns and villages; and coal, water, and ship chandlery at Rockland and Bangor, and usually in limited quantities at Camden, Belfast, Bucksport, and Winterport. Matinicus and Criehaven are the only places on the islands off the entrance to Penobscot Bay where gasoline and provisions can be obtained.

Repairs.—The only marine railways available in Penobscot Bay in 1917 were at Rockland and Camden (see their descriptions). Much of the repairing to small vessels and motor boats is done on the

Digitized by Google

beaches at low water. Ordinary repairs to machinery can be made at Rockland and Bangor, and minor repairs at Camden and Belfast.

Communication.—Rockland and Bangor and intermediate landings have steamer communication with Boston. There is also steamer communication from Rockland to points westward along the coast as far as Portland, and to all of the towns and villages on the islands and thoroughfares eastward as far as Blue Hill and Bar Harbor. The main steamer lines generally run throughout the year, but are more frequent in summer. Rockland, Belfast, and the points on the Penobscot River have railroad communication.

Tides.—The mean rise and fall of tides varies from 9.1 feet near the entrance to about 10 feet in Eggemoggin Reach and near the head of Penobscot Bay, and 13.1 feet at Bangor.

ISLANDS AND ROCKS OFF PENOBSCOT BAY.

The area including these islands and rocks (charts 225 and 104) has an extreme length of 21½ miles from Three Fathom Ledge, eastward of Seal Island, to Roaring Bull, westward of Metinic Island. There is no secure harbor for vessels at any of the islands, but the small craft of local fishermen moor in Matinicus Harbor, the cove on the eastern side of Matinicus Island northward of Wheaton Island. The waters of this area are well surveyed, and there are deep passages between the Islands, as shown on the chart. On account of the broken nature of the bottom, however, vessels, particularly deep-draft ones, should avoid all broken ground, especially with depths less than 10 or 12 fathoms.

These waters are frequented mostly by local fishermen. The only settlements are on Matinicus and Ragged Islands, to which there is steamer communication from Rockland.

Seal Island, the easternmost, is bare, rocky, about 60 feet high, and 1 mile long. There are several small houses near its eastern end. **Eastern Ledge**, on which the sea generally breaks, extends 350 yards off the east end of the island. **Three Fathom Ledge** lies 1½ miles eastward of Seal Island.

Malcolm Ledge, lying midway between Seal Island and Wooden Ball Island, is ⅜ mile long. The north end of the ledge is awash at high water; the south end is bare at half tide.

Wooden Ball Island is bare, rocky, about 60 feet high, and 1 mile long. The eastern point of the island is a prominent knob about 80 feet high, and there are a few small houses at the low place in the western part of the island.

Matinicus Rock, the southernmost islet, is about 40 feet high, and is marked near its south end by Matinicus Rock lighthouses.

Matinicus Rock lighthouses are two cylindrical granite towers, 60 yards apart. The lights, shown from each tower, are fixed white, the northern one 85 feet above the water and the southern 90 feet, and both visible 15 miles. The fog signal is a steam whistle (blast 5 seconds, silent 25 seconds). A bell will be struck by hand if whistle is disabled.

No Mans Land, Matinicus Island, Ten Pound Island, and **Ragged Island** are partly wooded, and are the principal ones of a group of islands and rocks about 5 miles long. There are numerous, high,

Digitized by Google

bare rocks, including **Green** and **Brig Ledges**, on the east and south sides of Ragged Island, and broken ground extends ¾ mile southward from it to **Inner Breaker**, which has a depth of 3 feet over it. **South Breaker** is on a small rock, awash at lowest tides and marked by a horizontally striped buoy, 1¾ miles southward of Ragged Island and 1⅝ miles northwestward of Matinicus Rock lighthouse.

Criehaven is a village of fishermen in the cove on the western side of Ragged Island. The steamer wharf has a depth of about 6 feet and the other wharves are shoal. Gasoline and provisions are obtainable. There are shoals on the south side just outside the entrance to the harbor, and the best water favors the north side until inside. The harbor is a poor shelter in westerly weather. At such times the steamer lands at a wharf in **Marsh Cove**, on the southeast side of Ragged Island, and anchorage can also be had here. The wharf here is nearly bare at low water.

Shag Ledge, close to the northeast end of Ragged Island, is high, bare, and rocky. **The Hogshead** is a small bare rock ¼ mile northeastward. Ten Pound Island is grassy with a few trees.

Western and **Eastern Black Ledges** are bare rocks eastward of Matinicus Island. **Tuckanuck Ledge**, 200 yards eastward of **Eastern Black Ledge**, is covered at high water. A rock with 10 feet over it lies ¼ mile south-southwestward of Western Black Ledge. **Mackerel Ledge**, bare at half tide, lies 700 yards north-northeastward of Eastern Black Ledge.

Matinicus Harbor (chart 225) is a cove on the east side of Matinicus Island inside Wheaton Island and a breakwater making out from the north shore to **Indian Ledge**. Small vessels can anchor in the middle, south-southwestward of Indian Ledge, in 4 fathoms, exposed to northeasterly winds. Small craft can anchor inside the breakwater, where there is an area 200 yards square with depths of 1 to 7 feet, protected from all winds; this anchorage is usually full of local fishing boats in bad weather. The entrance to the inner harbor is on either side of **Dexter Ledge**, awash at high water and marked on the southwest side in 1917 by a small private spindle. The usual entrance is 125 feet southwestward of the highest part of the ledge, and 50 feet southwestward of the spindle.

Matinicus is a town on Matinicus Harbor. It has steamer communication with Rockland. The principal wharf, on the northwest side, has a depth of about 2 feet at low water, and the other wharves are bare. Gasoline, provisions and some motor boat supplies are obtainable.

The thoroughfare between **Wheaton Island** and the point westward is bare at low water. There are small wharves, and small craft sometimes anchor here. **Old Cove**, westward of the south end of Wheaton Island, is seldom used as an anchorage.

Harbor Ledge is a rock with 4 feet on it, lying 300 yards northeastward of the entrance of Matinicus Harbor, and is marked on its south side by a horizontally striped buoy. **The Barrel**, lying 300 yards northeastward of Harbor Ledge, is a rock bare at half tide at the south end of a sunken ledge 300 yards long.

No Mans Land, the largest of the rocks and islets northeastward of Matinicus Island, is sparsely wooded and has a shanty on its west side.

Digitized by Google

Two Bush Islet is grassy on top and is joined to the northeast end of Matinicus Island by a sunken ledge. **Two Bush Ledge**, high and bare, lies southeastward of the islet; sunken rocks extend 350 yards eastward and northeastward from the ledge. **Beach Ledges** are two rocks, bare at a little below high water, between Two Bush Ledge and Matinicus Island. **Whaleback** is a rock, bare at low water, lying ¼ mile westward of No Mans Land, and is marked on its northwest side by a black buoy. **Zephyr Ledges** are two rocks, bare at low water, lying ¼ mile northeastward of No Mans Land. **Zephyr Rock**, the northeast end of the group, is a rock with a 5 feet over it, lying ⅝ mile northeastward of No Mans Land, and is marked on its northerly side by a black buoy.

Local boats bound to Matinicus Harbor from northward carry a draft of 6 feet at low water through the channel between Matinicus Island on the west and Two Bush Island and Beach Ledges on the east. Strangers should use this passage only in small boats and with a smooth sea.

Black Rocks are three bare rocks ¼ mile westward of Matinicus Island.

Bantam Ledge is a rock bare at half tide, with deep water around it, lying 2⅜ miles 283° true (NW by W ¼ mag.) from the south end of Ragged Island. It is marked by a horizontally striped buoy, placed 100 yards south of the ledge.

Foster Ledges are two rocks with 6 and 13 feet over them; the southwestern and shoaler rock is marked on its south side by a horizontally striped buoy. The ledges lie 1¾ miles westward of the north end of Matinicus Island.

Pigeon Ground is broken ground about 2 miles long in an east-northeasterly direction, lying 2 miles southward of Large Green Island. There are depths of 3½ and 2½ fathoms on its eastern and western parts, respectively.

Green Island Seal Ledges lie ⅝ to ⅞ mile south-southeastward of Large Green Island, with broken ground between. The southern part of the ledge is awash at high water; its north end is covered at half tide. A black whistling buoy is moored about ⅜ mile southeastward of the ledge.

Large Green Island is low and grassy, and has some houses on its northern part. **Herring Ledge**, partly bare at low water, extends ⅜ mile southward from the island.

Little Green Island is low and grassy, and has one house near its eastern end. **Collins Rock**, with 5 feet over it, lies 1⅛ miles eastward of the island.

Northern Triangles is a reef about 1 mile long in an east-southeasterly direction lying 1 mile northward of Little Green Island. In the western half of the reef are some ledges bare at low water. Northern Triangles black buoy is placed about ½ mile northward of the eastern end of the reef. A ledge with 15 feet over it lies 2 miles northward of Little Green Island and 2 miles southeastward of Two Bush Island lighthouse, and is marked by a horizontally striped buoy.

Alden Rock, with 4 feet over it and marked by a horizontally striped buoy, lies 1⅜ miles northwestward of Little Green Island. An unmarked rock with 14 feet over it lies ¾ mile west-northwestward of

Digitized by Google

Alden Rock. The 14-foot rock is at the eastern end of broken ground nearly 1 mile long, with least depths of 25 to 28 feet.

Southern Triangles are three rocks awash at low water lying midway between Little Green and Metinic Islands. The southwestern rock lies 5/8 mile from the other two. A black buoy lies 5/8 mile southeastward of the easternmost rock.

Metinic Island is nearly 2 miles long, 70 feet high near its northern end, and partly wooded; it has no wharves. **Metinic Green Island,** low and grassy, lies 3/8 mile southwestward of Metinic Island, with foul ground between. A rock awash at low water lies 300 yards southwestward of Metinic Green Island. **Wheeler Rock,** with 5 feet over it, lies 3/8 mile north-northeastward, and **Wheeler Big Rock,** awash at high water, lies 300 yards northward of the northeast point of Metinic Island. **Green Point Shoal,** with 19 feet over it, lies 7/8 mile eastward of the middle of Metinic Island.

Broken ground extends 2 to 3 miles westward and southwestward from Metinic Island. The following are the shoaler places determined by the survey:

Black Rock, covered at high water, lies 5/8 mile westward of the middle of Metinic Island. A rock with 14 feet over it, lies 3/8 mile southwestward of Black Rock.

Metinic Island Ledge, with 8 feet over it and marked at its southwest end by a horizontally striped buoy, lies 1 3/4 miles westward of Metinic Island, on the range of the north end of the latter and the middle of Large Green Island. A rock with 26 feet over it lies 5/8 mile northeastward of it. **Hooper Shoal,** with 17 feet over it, lies 5/8 mile southwestward from Metinic Island Ledge.

Roaring Bull, awash at low water and generally marked by breakers, lies 2 3/4 miles westward of Metinic Green Island. It is marked on its northwest side by a black buoy. A ledge, with a least depth of 4 1/2 fathoms, lies 5/8 mile north-northwestward of Roaring Bull.

Southeast Breaker is on a ledge about 1/2 mile long in a northeast direction, the higher part of which is bare at half tide. It lies 2 miles southwestward of Metinic Green Island, on the range of the south end of the latter and the north end of Large Green Island.

Haddock Ledge, with 13 feet over it, lies 1 1/4 miles southward of Southeast Breaker and 2 1/2 miles southwestward of Metinic Green Island.

EAST PENOBSCOT BAY

is the part of Penobscot Bay lying eastward of Vinal Haven, North Haven, and North and South Islesboro; its southern end, between Isle au Haut and Vinal Haven Island, is called **Isle au Haut Bay.** The islands in East Penobscot Bay have numerous coves and small harbors, but few of these are available anchorages, some on account of their depth and others on account of the numerous dangers which obstruct their entrances. East Penobscot Bay is entered from eastward through Eggemoggin Reach, Deer Island Thoroughfare, and Merchants Row, and from southward between Isle au Haut and Vinal Haven Island. Saddleback Ledge lighthouse is the guide to this entrance. Numerous unmarked ledges lie westward of Isle au Haut and off the western entrance to Merchants Row and Deer Island Thoroughfare. Northeastward of North Haven Island there are numerous islands and ledges.

Digitized by Google

The channel to the head of Penobscot Bay leads eastward of **Eagle Island**, marked by a lighthouse, and passes between the islands in a north-northwesterly direction to Cape Rosier. A depth of over 5 fathoms can be taken up the bay by closely following the directions.

Saddleback Ledge lighthouse, on a rocky islet in the middle of the southerly entrance to East Penobscot Bay, is a gray conical tower with white dwelling attached. The light is fixed white, 54 feet above the water, and visible 13 miles. The fog signal is a bell, sounding one stroke every 10 seconds. There is broken ground between the lighthouse and Vinal Haven, and deep-draft vessels should enter eastward of the lighthouse.

Head Harbor is a small bight in the south shore of Isle au Haut, just west of **Eastern Head**; it is exposed to southerly winds and used only by fishermen. The bottom is rocky, except in the northwestern part, where the depth is from 4¾ to 9 fathoms. There are a few houses in the northeastern part, but no wharves.

Roaring Bull Ledge, 1 mile south-southwestward of Head Harbor, is bare at half tide and marked by a spindle. There is a gas and whistling buoy ⅝ mile southward of the ledge.

Western Ear is a wooded island at the southwest end of Isle au Haut. **Western Ear Ledge**, ¼ mile southward of Western Ear, is bare at half tide.

The western side of Isle au Haut is fringed with many rocks and shoals, bare and submerged. The westernmost visible at high water are **The Brandies**, three bare rocks 1 mile westward of the southern part of Isle au Haut, and **Kimball Rock**, awash at high water, ⅝ mile westward of the western end of **Kimball Island**. Several rocky spots with depths of 18 to 30 feet lie outside the line joining these rocks.

Moore Harbor is a cove on the western side of Isle au Haut, about 2½ miles above Western Ear. This harbor has many outlying ledges off the entrance and in the harbor, and is an unsafe anchorage.

Isle au Haut Thoroughfare is on the western side of Isle au Haut, between it and Kimball Island; though called a thoroughfare it has a bar near its eastern entrance, dry at low water, extending from Isle au Haut to Kimball Island. It has a greatest width of ¼ mile at its western end, and is a secure anchorage for small craft or very small vessels in 5 fathoms. A buoy and spindle mark the two principal dangers.

Enter Isle au Haut Thoroughfare between Isle au Haut lighthouse (on Robinson Point) and **Sawyers Ledge** black buoy, and pass southward of **Inner Ledge** spindle, giving it a berth of over 50 yards. Then keep in mid-channel except in the choke at the entrance of the anchorage, where the northern side should be favored slightly. Avoid a rock, bare at low water only, which lies 90 yards from the northwest side of the enchorage.

Isle au Haut is a village on the south side of Isle au Haut Thoroughfare. There are several wharves. Gasoline and provisions are obtainable.

Lookout is a village and summer resort at the eastern end of Isle au Haut Thoroughfare. It has steamer communication with Rockland to a wharf on Point Lookout. There is a buoyed channel to the wharf from Merchants Row, leading between Merchants and Hardwood Islands.

Merchants Row is described on page 119.

Digitized by Google

Hardwood Island is round and heavily wooded. **Ram Island**, ¼ mile southwestward of Hardwood Island, has a clump of trees on its north side. **Channel Rock**, nearly ½ mile westward of Ram Island, is covered at high water and is marked by a large white tripod beacon, upper half slatted. **Ram Island Ledge**, bare at low water, lies 400 yards southeastward of Channel Rock tripod.

Scraggy Ledge is a bare ledge ⅜ mile westward of Channel Rock tripod. There is foul ground between it and **West Halibut Ledges**; the latter are bare. **Outer Scrag Ledge**, 1 mile northwestward of Scraggy Ledge, is partly bare at high water. **Brown Cow**, 1 mile north-northwestward of Outer Scrag Ledge, as awash at high water. It is the westernmost danger at the western end of Merchants Row.

Winter Harbor, Seal Bay, and **Smith Cove** make into the northeastern part of Vinal Haven Island, south of the eastern entrance to Fox Islands Thoroughfare; they are of no commercial importance, and not safe for a stranger to enter.

Fox Islands Thoroughfare is described on page 120. Carver Cove and Kent Cove are two excellent anchorages, easily entered by strangers, in Fox Islands Thoroughfare near its eastern entrance.

Little Thoroughfare is a passage into Fox Islands Thoroughfare north of the main entrance. It is not buoyed, and strangers should not attempt to use it.

Passage north of North Haven Island.—There is a passage northward of North Haven Island, which is used in winter when Fox Islands Thoroughfare is closed by ice. To go through this passage, pass about 300 yards southward of Eagle Island and steer 275° true (WNW mag.) for **Spoon Ledge** (high, with grass on top). On this course pass 400 yards northward of **Grass Ledge** (high and grass-covered) and the same distance northward of **Oak Island**, the grassy island southeastward of Spoon Ledge. Pass midway between Oak Island and Spoon Ledge and steer 242° true (W by S mag.) for 12¼ miles to Rockland Breakwater lighthouse.

Deer Island Thoroughfare, south of Deer Isle, is described on page 117.

Burnt Cove and **Crockett Cove** are two small coves lying between Fifield Point and Barred Island, on the southwestern side of Deer Isle. They are of no importance as anchorages, and are foul, especially Burnt Cove. **West Deer Isle** is a village on Burnt Cove. **Southwest Harbor** is on the western side of Deer Isle, about 4 miles north of Deer Island Thoroughfare lighthouse. It is about ½ mile wide at the entrance and 1 mile long, with anchorage in 3 to 5 fathoms, but is not much used, as it is open southward. The village of **Sunset** is on the eastern shore of the harbor; there are no wharves.

Northwest Harbor, on the northwestern side of Deer Isle, is about ⅜ mile wide and 1¼ miles long. A large part of its upper half is bare at low water, but in mid-harbor below the small wharf on the northeast side good anchorage will be found for small vessels in 13 to 17 feet, soft bottom. The harbor is sheltered from all but northwesterly winds. There is also good anchorage off the entrance of the harbor between Gull Ledge and Heart Island, in 3½ to 5 fathoms. The village of **Deer Isle** is near the head of the harbor; the steamboat landing is at North Deer Isle on Eggemoggin Reach. During January and February the harbor is closed by ice.

Digitized by Google

Approaching Northwest Harbor from southward, pass 300 to 400 yards westward of the bare ledge off the north side of **Dunham Point**, steer 33° (NE ½ E mag.) for the eastern end of Little Deer Isle, and pass 300 to 400 yards northwestward of a red buoy which marks the southwest end of a ledge bare at half tide. When well past the buoy, steer 67° true (E ½ N mag.) for **Heart Island** (high, grassy, partly wooded knoll near Deer Isle), and pass 300 to 400 yards northward of **Gull Ledge** (partly bare at high water). When past Gull Ledge, steer 124° true (SE ½ S mag.) for the middle of the entrance of Northwest Harbor.

Approaching Northwest Harbor from northwestward, pass 150 to not over 250 yards southwestward of the southwest point of **Pickering Island** (high and wooded), and from this position a 124° true (SE ⅝ S mag.) course for 2¾ miles will head to the middle of the entrance.

Eagle Island is wooded, and has a lighthouse (white tower attached to dwelling) at the eastern end. There is a post office (**Eagle**) and small settlement on the island, and a wharf at which vessels sometimes land at high water.

The other islands in this vicinity are wooded and have no prominent marks. **Great Spruce Head Island** is the highest (220 feet on the north end). **Butter Island** is inhabited, and has a post office (**Dirigo Island**) in summer.

Eggemoggin Reach and the islands off its western entrance are described beginning on page 113.

Egg Rock, the most westerly of the dangers north of North Haven Island, is a small, high, dark rock. **Egg Rock Ledge**, ¼ mile southwestward of Egg Rock, has a least depth of 2 feet, and is marked on the east side by a horizontally striped buoy.

Resolution Island, the northwesterly island of the group between North Haven Island and Cape Rosier, is 60 feet high, partly wooded, and has an inconspicuous house on the north end and a flagstaff in the center.

Long Island, Islesboro, and the adjacent islands and coves separating East and West Penobscot Bay at their heads, are described under a separate heading on page 136. Bagaduce River and Castine Harbor are described on page 131 and Penobscot River on page 149.

DIRECTIONS, EAST PENOBSCOT BAY.

This region is an area of rocks and ledges, many of them unmarked, and extreme care is necessary in navigating it. The main part of East Penobscot Bay, from a little southward of Saddleback Ledge lighthouse to the entrance of Penobscot Bay by the channel between Eagle and Hardhead Islands, has been examined by means of a wire drag. The principal thoroughfares east and west have also been dragged. Areas near the shores were not covered.

The principal traffic through East Penobscot Bay is in an east and west direction, through the inside passages, but there is a clear channel, good for the deepest draft vessels and with the principal dangers marked, through the bay from sea to the head. The following directions lead in a depth of over 5 fathoms to the entrance of Penobscot River. For directions through the thoroughfares, see their descriptions.

Digitized by Google

1. **Approaching from eastward or southward.**—Approaching from eastward or southeastward, shape the course for Roaring Bull Ledge gas and whistling buoy, lying 1¾ miles southward of Isle au Haut, and from the buoy steer 295° true (NW ⅛ W mag.) for Saddleback Ledge lighthouse.

Or, steer for Saddleback Ledge lighthouse on any bearing between 295° true (NW ¼ W mag.) and 343° true (N mag.); the latter bearing leads 1 mile eastward of Three Fathom Ledge.

When northward of Seal, Wooden Ball, and Matinicus Islands, steer for Saddleback Ledge lighthouse on any bearing northward of 59° true (ENE ⅞ E mag.). This bearing leads ½ mile southeastward of Bay Ledge bell buoy.

Pass ¼ to ½ mile eastward of Saddleback Ledge lighthouse and proceed as directed in section 2 or 2 A.

1 A. **Approaching from southwestward.**—The passages between the islands eastward and westward of Matinicus Island may be used with the assistance of the chart. (See the description of the islands on page 123.) One of the best is as follows:

Steer for Matinicus Rock lighthouses, passing southward of South Breaker buoy, pass ½ mile northwestward of the lighthouses, and steer 17° true (NE ⅞ N mag.) for 4½ miles to a position ½ mile off the northwest side of Wooden Ball Island. Then steer 26° true (NE ⅛ N mag.) for Saddleback Ledge lighthouse, the distance to which is 10½ miles. The last course leads about ¼ mile westward of **Snippershan**, which has a least depth of 6 fathoms, as determined by means of a wire drag, and lies 4¼ miles southwestward of Saddleback Ledge lighthouse.

Or, pass 1½ to 2 miles southward of Monhegan Island, and steer 64° true (E ¾ N mag.) for 17½ miles, heading for the north end of Matinicus Island. When about 1½ miles from the island, and its southwest end is closed on the northeast end of Ragged Island, the position should be ½ mile southward of Foster Ledges horizontally striped buoy. Then steer 45° true (NE by E ⅝ E mag.) for 13 miles, and pass ½ mile northward of Matinicus Island and ¼ to ½ mile southward and eastward of Saddleback Ledge lighthouse. Then follow the directions in section 2 or 2 A.

Or, pass 1½ to 2 miles southward of Monhegan Island and steer 55° true (ENE ½ E mag.) for 16 miles to the black whistling buoy between Pigeon Ground and Green Island Seal Ledges. From this buoy the course continued for 13½ miles will lead 1 mile southeastward of Bay Ledge bell buoy and to Saddleback Ledge lighthouse. The lighthouse will be made in line with the summit of Isle au Haut ahead.

2. **Saddleback Ledge to Fort Point.**—Pass ⅜ mile eastward of Saddleback Ledge lighthouse and steer 351° true (N ¾ E mag.) for 12¼ miles, passing ⅝ mile westward of The Brown Cow and ⅛ mile eastward of a horizontally striped buoy ⅞ mile southward of Eagle Island lighthouse to a position ¼ mile eastward of Eagle Island lighthouse. Then steer 322° true (N by W ¾ W mag.) for 5¼ miles to a position ½ mile westward of **Green Ledge**, the grassy islet westward of Western Island. Then steer about 2° true (N by E ¾ E mag.) for 9 miles, passing about ⅜ mile westward of Cape Rosier, and then following the eastern shore at a distance of about ½ mile.

Digitized by Google

When Fort Point lighthouse bears 19° true (NE ¾ N mag.), steer for it. Pass over 200 yards westward of Fort Point Ledge beacon and midway between the beacon and the lighthouse. Pass ¼ mile eastward of Fort Point and follow the directions for Penobscot River on page 151.

2 A. Saddleback Ledge to Merchants Row or Stonington.—The directions of this section are good for a depth of 28 feet to Merchants Row, and are good for vessels of 12 feet or less draft through the passage eastward of Crotch Island to Deer Island Thoroughfare, but lead close to unmarked dangers with less depth. Strangers are advised not to use them with a greater draft than 10 feet.

Bring Saddleback Ledge lighthouse astern on a 15° true (NNE ⅞ E mag.) course, heading for the prominent standpipe at Stonington. **Farrel Island** (wooded) will be made ahead, and Scraggy Ledge (bare) a little on the starboard bow. When ½ mile or more southward of Scraggy Ledge, stand eastward until the standpipe is in line with the eastern end of Farrel Island, and then steer this range, course 11° true (NNE ⅝ E mag.), which will lead nearly 200 yards eastward of the rock with 11 feet over it lying 400 yards southward of Scraggy Ledge, and pass midway between Scraggy Ledge and Channel Rock tripod.

From a position 300 yards northwestward of Channel Rock tripod, steer 31° true (NE ¼ E mag.) for the summit of Green Island and pass 300 to 400 yards southeastward of **John Island**, the low, grassy island with some scrubby trees lying ⅜ mile southward of Crotch Island. Pass 150 to 200 yards eastward of **Sand Island**, the rocky, wooded island close to the southeast end of Crotch Island, and steer 348° true (N ½ E mag.), following the shore of Crotch Island at a distance of 250 to 300 yards and passing westward of two red buoys. When a little past the second buoy steer 45° true (NE by E ⅝ E mag.), with the entrance of Mill Cove astern, and pass about 100 yards eastward of a black buoy into Deer Island Thoroughfare. Select anchorage in the channel off Stonington.

Bound eastward through Merchants Row.—Steer the 31° true (NE ⅜ E mag.) course of the preceding paragraph until **Harbor Island**, the grassy island with a few trees lying on the northeast side of Merchants Island, opens northward of Ewe Island. Then stand eastward, pass about 400 yards northward of Ewe Island and 100 yards southward of Mid-Channel Ledge horizontally striped buoy. Then steer 95° true (ESE mag.) and reverse the directions for Merchants Row on page 50.

BAGADUCE RIVER AND CASTINE HARBOR.

Bagaduce River empties into the eastern side of East Penobscot Bay near its head. It is the approach to the town of Castine, on the north side, just inside the entrance, and to several smaller settlements farther up. The entrance, known as Castine Harbor, has ample depth and is easily entered; there is considerable business by water in this portion. **Dice Head lighthouse** (white tower connected with dwelling) is on the north side at the entrance.

The channel for 6 miles above Castine is buoyed and is used by small craft and local vessels of 6 to 8 feet draft, carrying wood products, but is narrow and so contracted by rocks in places that

Digitized by Google

navigation is possible at slack water only, on account of the current. It is not safe for strangers.

Castine has steamer communication with Rockland and other points on Penobscot Bay and River. There are several wharves with depths of about 15 feet. Vessels of 16 feet are the deepest draft coming here. Pilots are obtainable here for the river above. Gasoline and provisions are obtainable, and there is water on the wharves.

West Brooksville is a village on the south side 1½ miles above Castine, and **North Castine** is a village on the north side 2¼ miles above Castine.

North Brooksville is a village on the southern branch of Bagaduce River, about 7 miles above Castine. At high water small vessels sometimes go to the bridge crossing the river at the village, but the channel is unmarked and unsafe for strangers. Small craft with local knowledge can go about 3 miles above North Brookville.

Penobscot is a village at the head of navigation on the north branch of Bagaduce River, 7½ miles above Castine. The approach to the village is by a channel dredged 4 feet deep, in which some shoaling has occurred.

Anchorage.—The best anchorage for vessels is in Smith Cove, southward of Castine, in 4 to 11 fathoms, soft bottom, sheltered from all winds. The holding ground abreast the town is not good and the general depth is about 12 fathoms.

Ice.—The river is usually free from ice at Castine and for some distance above, but in very severe winters the river is entirely closed.

Tides.—The mean rise and fall of tides is about 10 feet from Castine to the head.

Directions, Castine Harbor.—The eastern shore northward and southward of the entrance is bold, and can be followed at a distance of ¼ mile. There is a perpendicularly striped bell buoy in the entrance. Pass close to this on either side, and steer 57° true (ENE ⅝ E mag.) into the harbor to abreast the wharves at Castine, passing about 100 yards southward of Otter Rock Shoal black buoy. If going to an anchorage, from the wharves steer 101° true (SE by E ⅜ E mag.) for Henry Point and anchor in 5 to 11 fathoms, 200 to 500 yards southward of the point.

VINAL HAVEN AND NORTH HAVEN ISLANDS.

These islands and numerous smaller ones adjoining (charts 309 and 310) lie in the entrance of Penobscot Bay and separate East and West Penobscot Bays. The principal settlements are the villages of Vinal Haven, North Haven, and Pulpit Harbor. The eastern side of the islands is described with East Penobscot Bay on page 128 and Fox Islands Thoroughfare, leading between the islands, is described on page 120.

Aside from the vessels passing through Fox Islands Thoroughfare, the coves among the islands are frequented mostly by local fishermen and vessels carrying granite from the quarries. The coves are generally foul and not sufficiently well marked for the use of strangers except in small craft.

The south and west coasts of Vinal Haven Island are fringed by numerous islands and rocks to a distance of about 2 miles. Between them are channels which are used principally by small local vessels

Digitized by Google

and vessels loading granite at some of the quarries. Carvers Harbor is the best anchorage, and the only one of any importance. The channels are well marked by buoys, and are generally not difficult in the daytime and clear weather for vessels of 12 feet or less draft.

Brimstone and **Otter Islands** are the largest and most prominent of the eastern islands, and Saddleback Ledge lighthouse, in the entrance of East Penobscot Bay, is a guide for approaching from eastward. **Diamond Rock**, 3/8 mile northeastward of Brimstone Island, is a round rock about 20 feet high, and is a good mark. The large standpipe at Vinal Haven is prominent for many miles. **Green Island**, the large wooded island westward of Vinal Haven, is marked at its south end by **Heron Neck lighthouse** (white tower connected to dwelling). **Hurricane Island** is the most prominent westward of Vinal Haven. Its southeast end is marked by a village and the large buildings of a quarry (not in operation in 1917).

Arey Cove and **Robert Harbor**, on the southeast side of Vinal Haven Island, are much obstructed by rocks and ledges, and are unsafe for strangers. There are two quarry wharves.

Carvers Harbor is a secure anchorage for small vessels on the southwest side of Vinal Haven Island. The anchorage is about 500 yards long and 250 yards wide, and has been dredged to a depth of 16 feet, and an additional area on the south side to a depth of 10 feet. The village of **Vinal Haven**, at the head of the harbor, is of some importance for its shipment of granite and fish. There is communication by telephone and steamer with Rockland. The deepest draft of vessels entering is 12 feet; the depth at the wharves is 6 to 15 feet. Water, provisions, and gasoline can be obtained. There are marine railways with a capacity of about 10 tons. Ice closes the harbor during January and February, but a channel is kept open to the steamboat wharf. Storm warnings are displayed at the village. A standpipe is prominent.

Indian Creek, just eastward of Carvers Harbor, has an entrance from sea and also from Carvers Harbor through a thoroughfare crossed by a drawbridge. It has a quarry at the head from which granite is lightered to vessels in Carvers Harbor at high water. The channel is not safe for strangers.

Sand Cove, making northward from Carvers Harbor, is foul. There is a wharf at the head at which vessels lie aground at low water while loading.

The Reach is a narrow, much-obstructed channel leading northwestward from the entrance of Carvers Harbor, inside Green Island. It is buoyed and used by vessels between Carvers Harbor and Rockland, but it is the most difficult part of the route, and care is required.

Old Harbor is a small cove at the northern end of The Reach and northeastward of the northern end of Green Island. It affords good anchorage for small craft in 9 to 17 feet, soft bottom, and small vessels can anchor in or off the entrance in 3 to 6 fathoms.

Hurricane Sound lies between Vinal Haven and Green Islands on the east, and Hurricane Island and White Islands on the west. It has deep water, but is little used except by local vessels and vessels loading granite. Several passages lead into the sound, but there are no good anchorages.

Digitized by Google

The Basin is a large irregular bight in the west side of Vinal Haven Island, about 2½ miles north of Heron Neck lighthouse. **Barton Island** lies in the middle of the entrance, leaving a narrow, crooked, and shallow channel north and south of it. The depth of water in the basin varies from 1½ to 18 fathoms.

Laireys Narrows leads between Leadbetter Island on the north and Laireys Island on the south. This passage is a part of the route between Carvers Harbor and Rockland, and the principal dangers are buoyed.

Leadbetter Narrows is a narrow passage between the Vinal Haven shore on the north and Leadbetter Island on the south; passing south of the eastern side of Leadbetter Island, it leads into the northern end of Hurricane Sound. This passage should not be attempted without a pilot. There is a quarry and wharf on the shore of Vinal Haven eastward of the narrows, from which loaded vessels leave at high water.

Crockett Cove is just eastward of Crockett Point, the southeastern point at the western entrance to Fox Islands Thoroughfare. The cove is 1 mile long and 200 yards wide at the entrance, is obstructed by ledges, and is suitable only for small craft with local knowledge.

Bartlett Harbor is a small cove with deep water and good anchorage sheltered from all but westerly and northerly winds. It is about 2 miles above Stand-in Point on the western shore of North Haven island. There is a rock with 9 feet over it in the middle of the entrance; it has deep water close-to around it.

Pulpit Harbor is on the northwest side of North Haven Island, 4 miles northeastward of Stand-in Point and 2⅜ miles southwestward of **Webster Head**, the high, partly wooded head at the north end of the island. The entrance has a clear width of 150 yards, and the harbor is a secure anchorage for small vessels of about 13 feet or less draft. **Pulpit Rock**, high and pointed, is near the end of the reef, which extends 250 yards northeastward from the western point at the entrance, and is a good mark. To enter, give the north side of Pulpit Rock and the eastern shore just northward of the entrance a berth of over 100 yards, and enter in mid-channel eastward of Pulpit Rock on a 191° true (SSW ½ W mag.) course. Keep in mid-harbor and anchor in its broad part in 4 to 5½ fathoms. The post village of Pulpit Harbor is on the northeast side of the harbor.

Pilots for these waters can usually be obtained at Rockland or Carvers Harbor, or from local fishing boats.

DIRECTIONS, CARVERS HARBOR.

These directions are good for vessels of 12 feet or less draft in the daytime and with clear weather, but lead close to unmarked dangers, and should be used with extreme caution by strangers. The channels have not been dragged.

From Merchants Row.—Pass between Channel Rock tripod and Scraggy Ledge, and southward of the 11-foot rock 400 yards southward of Scraggy Ledge. Then steer 226° true (SW by W ⅝ W mag.), passing well southeastward of the black buoys marking the **Triangle Ledges** (bare at low water) and 150 yards southeastward of the black buoy marking **Halibut Ledge** (bare at low water). Make good this course for 5¾ miles to a position 250 yards southeastward

Digitized by Google

of Crosby Ledge red buoy. Then steer 241° true (W by S mag.), pass 250 yards southward of Sheep Island and 50 to 100 yards southward of red buoys Nos. 2B and 4. A ledge with a least depth of 10 feet lies 250 yards southward of buoy No. 2B.

Passing southward of buoy No. 4, steer 279° true (NW by W ⅝ W mag.) with either Saddleback Ledge lighthouse or Diamond Rock in range with the south extreme of Carver Island astern, until 300 yards southwestward of Point Ledge spindle. Then steer 298° true (NW ⅛ N mag.) and pass between **Folly Ledge** (bare at high water) and **Green Ledge** (grassy top), slightly favoring the latter. Pass about midway between Green Ledge and **Green Island Knob** (awash at high water) and steer about 33° true (NE ½ E mag.) for the entrance of Carvers Harbor, passing between a red and a black buoy (the latter marks the eastern end of a reef bare at low water only). Pass about 75 yards westward of Potato Island, and enter the harbor in midchannel. Anchor about 150 yards from the western shore, abreast or a little above the steamboat wharf, in 16 feet.

From eastward.—Give Saddleback Ledge lighthouse a berth of about ¼ mile and then bring it astern on a 285° true (NW by W mag.) course, heading for the flagstaff on the knoll on the west side at the entrance of Indian Creek. On this course pass 300 yards northward of Diamond Rock, about ¼ mile southward of the black buoy marking the north end of **Diamond Rock Ledge** (bare at low water) and pass between Carver Island and the red buoy marking the south end of **Sheep Island Ledge** (partly bare at low water). From a position 250 yards northward of Carver Island, steer 256° true (W ⅜ N mag.) and pass 100 yards southward of red buoy No. 4. Then follow the directions in the preceding paragraph.

From southward.—Steer for the standpipe at Vinalhaven on a 4° true (NNE mag.) course, passing westward of the red buoy marking the southwest end of Colt Ledge, and between the black buoy marking the eastern end of **Breaker Ledge** (bare at low water) and the red buoy marking the southwest end of Arey Ledges (higher parts are bare rocks). Continue the course for the standpipe until about ¾ mile past these buoys and about ¼ mile eastward of Folly Ledge. Then steer about 320° true (NNW mag.) and pass about 200 yards southwestward of **Green Ledge** (grassy top). Pass about midway between Green Ledge and Green Island Knob, steer about 33° true (NE ½ E mag.) for the entrance of Carvers Harbor, and enter as directed in a preceding paragraph.

Or, from Heron Neck whistling buoy, steer 41° true (NE by E ¼ E mag.) for Heron Neck lighthouse until about ⅜ mile from the lighthouse. Then steer 70° true (E ⅛ N mag.) and pass midway between Heron Neck and **Heron Neck Ledge** (a bare rock). Continue the course and pass about 300 yards southward of the southeast point of Green Island. Then haul northward between Green Island and Folly Ledge and follow a mid-channel course westward and northward of the ledge. Then steer 24° true (NE ¼ N mag.) for the standpipe at Vinal Haven and pass about 200 yards westward of Green Ledge. Then steer 33° true (NE ½ E mag.) for the entrance of Carvers Harbor, and enter as directed in a preceding paragraph.

From Rockland through Lairey Narrows and The Reach.—Passing 200 yards southward of Rockland Breakwater lighthouse, steer 99°

Digitized by Google

true (SE by E 5/8 E mag.) for 5¼ miles to Fox Islands Thoroughfare bell buoy (perpendicularly striped). Then steer 125° true (SE ¾ S mag.) for the perpendicularly striped bell buoy westward of Green Islet, and pass northward of two black buoys. From the bell buoy, steer 107° true (SE 7/8 E mag.) for the north end of Lairey Island, to a position 25 to 50 yards southward of a red buoy. Then steer about 101° true (SE by E 3/8 E mag.), pass midway between the north end of Lairey Island and the south end of the bare rocks northward, and pass about 100 yards northward and eastward of a horizontally striped buoy. Then stand southward to a mid-channel position between the eastern side of **Cedar Island** (wooded) and the grassy islet opposite.

Then steer 135° true (SSE 3/8 E mag.) for 1⅛ miles to a position 50 yards southwestward of Dog Point Ledge red buoy. Then steer 118° true (SE mag.), pass midway between the northeast point of Green Island and the rock awash at high water lying southward of the island in the entrance of Old Harbor, and pass in mid-channel eastward of the island close to the northeast end of Green Island. Pass close westward and about 50 yards southward of buoy No. 4 and steer 113° true (SE 3/8 E mag.) to a position about 50 yards northeastward of black buoy No. 1A. Then steer 152 true (S 7/8 E mag.), and pass 100 feet eastward of the black spindle on the end of the ledge extending eastward from a grassy island. A rock with 3 feet over it lies 200 feet northeastward of the spindle, and the channel has a width of but little over 100 feet between the rock and the edge of the ledge just northward of the spindle. Great care is required in passing this point.

Pass about 100 yards southwestward of red buoy No. 2 at the south end of The Reach, and steer 92° true (ESE ¼ E mag.), heading a little northward of red buoy No. 4. When nearly up with the latter buoy, steer about 33° true (NE ½ E mag.), pass eastward of a black buoy and about 75 yards westward of Potato Island, and enter Carvers Harbor in mid-channel. Anchor about 150 yards from the western shore, abreast or a little above the steamboat wharf, in 16 feet.

LONG ISLAND (ISLESBORO).

Long Island (Islesboro) and the adjacent islands and shoals (charts 310 and 311), 15 miles long, separate East and West Penobscot Bays near their heads. The main island is nearly divided in the middle. A chain of islands and rocks, through which several channels lead, extends for 5 miles southward from the larger island. The island is an important summer resort, and is frequented by many pleasure boats in summer. Dark Harbor, Islesboro, and North Islesboro, are villages on the island.

McIntosh Ledge, the most southerly of the dangers, lying about ¾ mile southeastward of Robinson Rock, is awash at low water and marked by a horizontally striped buoy on its southwest side.

Robinson Rock, the most southerly visible danger, is a grassy rock with several smaller bare rocks around it. Unmarked ledges extend for a greatest distance of 5/8 mile north-northeast and south-southwest of the rock.

Digitized by Google

Mark Island, the most southerly wooded island, is high, rounded, and prominent. A spindle and red bell buoy mark the reef extending southward from it.

Goose Rock, ½ mile north-northeastward of Mark Island, is about 15 feet high and grassy. **Saddle Island** is thickly wooded and **Lasell Island** is high and wooded except at its north end. **Goose** and **Mouse Islands,** eastward of Saddle and Lasell Islands, are rocky islets with grass on top, and there are several bare and submerged rocks between them. A spindle marks a ledge northeastward of Mouse Island.

Lime Island, ¼ mile northeastward of Lasell Island, is low and generally wooded, and there is a bare rock ¼ mile northeastward of it. **Job Island** is thickly wooded. The southerly **Ensign Island** is thickly wooded, and the northerly is wooded in the center and has a house on the west side.

The channel between Mark, Lasell, and Lime Islands on the west, and Saddle, Goose, and Mouse Islands on the east is used by most local vessels bound from Rockland or westward to Eggemoggin Reach or points in the northern part of East Penobscot Bay. The least depth found by an examination with a wire drag was 29 feet. the principal dangers are marked.

To go through this channel from southwestward, shape the course to make the red bell buoy southward of Mark Island and pass 200 yards southeastward of it. A 38° true (NE by E mag.) course for 2¾ miles will then lead through the thoroughfare, passing 250 yards northwestward of Saddle Island, 250 yards southeastward of Lasell Island, 400 yards northwestward of Mouse Island, and to a position 250 yards northwestward of the spindle northeastward of Mouse Island. The course can then be shaped as desired.

Dark Harbor is a summer resort occupying the southern part of South Islesboro. It has steamer communication with the adjoining towns, the steamer landing being on the eastern side, just south of the cove called Dark Harbor. A large hotel and water tank on the hill back of the wharf, and a white house on the wharf, are prominent. The cove called Dark Harbor is crossed by a dam just inside the entrance and is seldom used by boats. Small craft frequenting the resort land at numerous float landings on Gilkey Harbor.

Gilkey Harbor, on the western side of South Islesboro, between it and **Seven Hundred Acre, Warren,** and **Spruce Islands,** is a secure anchorage and is frequently by many yachts in summer. There are numerous wharves for small craft in the southern part, but no commercial wharves. Gasoline and provisions are obtainable at Dark Harbor, on the eastern side. The harbor is frequently closed by ice during the winter.

The main entrance to Gilkey Harbor is from southwestward, between Job Island and Ensign Islands, and has a least depth of about 27 feet in mid-channel, with unmarked rocks of less depth near the sides. It is partially buoyed and easily entered. The entrance from northward has **Grindel Point lighthouse** (white tower with covered way to dwelling) on the north side; it is narrow and not recommended for a greater draft than 12 feet. The channel inside the entrance was marked by a buoy and private spindles in 1917.

Small craft can enter Gilkey Harbor by a narrow crooked channel westward of the south end of South Islesboro and eastward of Job

Digitized by Google

and Minots Islands. The channel is said to be good for a depth of about 6 feet at low water with local knowledge. It was marked by private spindles in 1917, red on the west side and black on the east side. The best water favors the east side of the thoroughfare.

The following courses lead through Gilkey Harbor, entering by the main channel from southward and leaving through the northern channel:

Pass about ½ mile westward of Mark Island and steer 28° true (NE ⅛ E mag.) for the eastern end of Seven Hundred Acre Island for 4⅝ miles, passing nearly ½ mile westward of Job Island, ¼ mile eastward of Ensign Islands, and to a position 100 yards northwestward of Minot Ledge black buoy. Then steer 39° true (NE by E ⅛ E mag.) to a position 300 yards southeastward of the eastern end of Seven Hundred Acre Island. Then steer 8° true (NNE ⅜ E mag.), and pass 100 yards westward of Thrumbcap Ledge black buoy and 300 yards eastward of Spruce Island. When the north end of Warren Island opens northward of Spruce Island, steer 306° true (NW ¾ N mag.) for Grindel Point lighthouse and pass the northeast point of Spruce Island at a distance of 250 yards. When a little past this point steer 287° true (NW ⅞ W mag.) and pass about 25 yards northward of a red buoy, 250 yards southward of Grindel Point lighthouse, and nearly 300 yards northward of the north end of Warren Island.

Islesboro Harbor is an open bight in the northeastern side of South Isleboro, west-northwestward of the south side of Cape Rosier. It affords good shelter in westerly winds, and has a depth of 7 fathoms. Off the southern point at the entrance is a ledge partly bare at half tide and marked by two buoys. Vessels can pass on either side of the ledge, being guided by the buoys. Foul ground extends nearly ¼ mile from the western shore, and will be avoided by keeping the knoll northward of the harbor open from the north point of the harbor. There is a wharf and a village (**Islesboro**) on the south side.

Sabbath Day Harbor is a small cove in the southeastern side of North Islesboro, and a little over 2 miles northward of **Hewes Point**, the high point on the south side at the entarnce to Islesboro Harbor. It is open southward and affords anchorage for small vessels in 6 to 18 feet. There are several summer houses on its shores, and a wharf and village (**North Islesboro**) on the west side.

Parker Cove, on the east side of North Islesboro, is a shallow cove, used only as an anchorage by small local craft. **Long Island Ledge**, eastward of the entrance, is distinguished by a wreck visible at all stages of the tide.

Seal Harbor, at the southwestern end of North Islesboro and about 3 miles north of Grindel Point lighthouse, is a good anchorage, sheltered from all but southwest winds. This harbor is used by vessels bound up or down the bay as an anchorage for the night, and is easy of access. Vessels of any size can anchor with ample swinging room about ½ mile eastward of Flat Island, in 9 to 11 fathoms. Anchorage can be had nearer the head of the harbor, keeping the southern shore aboard distant about ¼ mile, in 8 to 10 fathoms. The northern side of the harbor is foul. The entrance from northward is 400 yards wide, with depths of 18 to 28 feet, between Seal Island and a shelving ledge which extends ¼ mile northward from **Flat Island**. The latter is grassy, and **Seal Island** is wooded and has a large summer

Digitized by Google

residence. **Crow Cove** is an anchorage for small craft only. There is a wharf on the south side with a depth of about 7 feet at the end.

Approaching Seal Harbor from southward, give the eastern shore a berth of ½ mile for a distance of 1 mile northward of Grindel Point lighthouse, and then steer about 50° true (ENE mag.) and pass about midway between Flat Island and the southern shore. Approaching from northward, pass 300 yards southwestward of Seal Island, heading about 129° true (SE by S mag.).

Hog Island, ¼ mile north-northeastward of Seal Island, is wooded. The ledge extending ¼ mile north-northeastward from it has three rocks bare at half tide. **Sprague Ledge,** ⅝ mile north-northeastward of Hog Island, has a least depth of 2 feet, and **Barley Ledge,** a little farther northward, is bare at low water and marked by a spindle.

Turtle Head Cove is a broad bight in the north end of North Islesboro. It is sheltered from southerly and easterly winds, and has good anchorage in 18 to 40 feet, soft bottom. The anchorage has a clear width of about ⅜ mile and is in the eastern part of the cove. The eastern shore must be given a berth of 250 yards, and the south end of the cove 500 yards. In the western half of the cove a shoal, bare in one spot at low water and with 9 feet near its north edge, extends ⅜ mile from shore. The north end of Turtle Head bearing anything eastward of 62° true (E ⅞ N mag.) clears the shoal. **Turtle Head,** the north end of North Islesboro, is a prominent wooded head joined to North Islesboro by a low narrow neck.

TWO BUSH AND MUSCLE RIDGE CHANNELS

are entrances to West Penobscot Bay from westward, the former leading southward and the latter northward of an extensive group of islands and shoals.

Two Bush Channel is broad and deep and has been examined by means of a wire drag. The principal dangers are buoyed and it is used in preference to Muscle Ridge Channel by large vessels and tows, and is generally used at night by all except small local vessels.

Two Bush Island lighthouse, a white square tower on a small island on the north side, is the principal guide to the channel. The light is flashing white (flash 0.5 second, eclipse 4.5 seconds), with a flashing red sector bearing between 196° true (SW by S mag.) and 247° true (W ⅝ S mag.) and obscured when bearing between 61° true (E by N mag.) and 196° true (SW by S mag.). It is 65 feet above the water and visible 14 miles. The fog signal is a bell, sounding a group of two strokes every 20 seconds.

Halibut Rock, 1⅝ miles northeastward of Two Bush Island lighthouse; and **Northeast Pond Ledge,** ⅝ mile northeastward of Andrew Island, are bare at half tide.

The larger islands between Two Bush Channel and Muscle Ridge Channel are generally wooded and of little importance except for their granite quarries. The smaller islands are bare and grassy and there are many bare and submerged rocks. **Dix Island** is distinguished by large buildings and **High Island** by a quarry and iron stack. **Fisherman** and **Marblehead Islands** are grassy.

Muscle Ridge Channel is much used by vessels in daylight and clear weather on account of its being sheltered and affording anchorage in case of bad weather. The channel has been examined by

Digitized by Google

means of a wire drag, and is good for a depth of 4 fathoms, but it is narrow in places, especially at the southwest end of Owlshead Bay, and is not recommended for a greater draft than 15 feet at low water, except with local knowledge. From its entrance at Whitehead it extends in a northeasterly direction about 6 miles to Sheep Island, and the channel passes between numerous rocks and ledges. These dangers are well marked and in daylight and clear weather with a fair wind no difficulty will be experienced by sailing vessels.

Whitehead lighthouse, a gray tower attached to a red house on the southeast end of **Whitehead Island,** is the principal guide to the entrance of Muscle Ridge Channel. The light is fixed white, 75 feet above the water, and visible 14 miles. The fog signal is a steam whistle (blast 5 seconds, silent 25 seconds). There is a storm warning display station near the lighthouse and a Coast Guard station on the southwest side of the island.

Seal Harbor is an anchorage much used by coasters, on the western side of Muscle Ridge Channel, between Whitehead and Sprucehead Islands; it has 18 to 23 feet of water, with soft bottom. The post village of **Sprucehead** and a large granite quarry are on the north side of Seal Harbor. The principal dangers are buoyed, and the harbor is easy of access in the daytime. **Long Ledge** shows in two places at high water.

Enter Seal Harbor between the two black buoys which lie about 250 yards southward of Burnt Island and nearly ¼ mile northwestward of Lower Gangway Ledge horizontally striped buoy, and steer 304° true (NW ½ N mag.). Pass between a red buoy and Long Ledge black buoy, and anchor in 3 to 4 fathoms 300 to 400 yards westward of the red buoy.

Dix Island Harbor is an anchorage on the south side of Muscle Ridge Channel between Andrew, Birch, and Dix Islands; it is reached from southwestward through a narrow and crooked channel leading between the ledges north of Hewell Island; it is unsafe for strangers to enter.

Weskeag River empties into the western side of Muscle Ridge Channel at the head of the bight westward of Ash Island. This river has a narrow and crooked unmarked channel, unsafe for strangers. The village of **South Thomaston** is at the head of navigation, 2 miles above its mouth; the greatest draft taken to the village is 10 feet at high water; 4 feet can be taken into the entrance at low water. Vessels seldom enter.

Fisherman Island Passage leads from Muscle Ridge Channel to Penobscot Bay, between Fisherman Island and Sheep Island. Several dangers lie in this passage, but the principal ones are marked by buoys and can be easily avoided in the daytime in clear weather. Directions through the passage are given on page 51.

Owlshead Bay lies between Sheep and Monroe Islands on the east and the mainland on the west, and is a continuation of Muscle Ridge Channel northward of Fisherman Island Passage. The channel through Owlshead Bay is very narrow on the western side of Sheep Island, where it is marked by two buoys. Vessels can anchor in the middle of the bay abreast Monroe Island, in 8 to 10 fathoms, and small vessels can anchor in the entrance of the cove between Dodge Point and the bare ledge southwestward, in 2 to 4 fathoms.

Owlshead is a prominent hill marked by a lighthouse on the top.

Digitized by Google

The following information concerning the dangers close to the sailing line through Muscle Ridge Channel and Owlshead Bay is given to identify the dangers:

South Breaker, 3/8 mile southward of Whitehead lighthouse, is awash at low water and marked at the southwest end by a red buoy. **Yellow Ledge** is awash at high water and marked by a spindle. **Burnt Island Ledge** is bare at low water and marked on its southwest side by a black buoy. **Hurricane Ledge** is bare at lowest tides and marked on its northwest side by a red buoy. **Garden Island** is bare, with a little grass on top, and **Garden Island Ledge** is bare at half tide and marked by a spindle. **High Clam Ledge** is bare and grassy at its south end and bare at low water at its north end. **Channel Rock** is awash at high water and unmarked. **Otter Island Ledge** is bare at half tide and marked by a spindle. The rock 350 yards eastward of **Emery Island** is bare at low water and marked by a spindle. **Dodge Point Ledge**, eastward of Dodge Point, is bare at half tide and marked by a spindle. **Owlshead Ledge**, southeastward of Owlshead, is bare at low water and marked by a black buoy.

ROCKLAND HARBOR.

This harbor (chart 310 or harbor chart 320), one of the most important in Penobscot Bay, is on the west shore of West Penobscot Bay between Owlshead on the south and Jameson Point on the north It affords anchorage for the largest vessels, but is somewhat exposed to easterly winds. Northeasterly winds raise a heavy sea in the southwestern part, but shelter may be found behind the breakwater, which extends 3/4 mile in a southerly direction from Jameson Point, and is about 4 feet above high water. Rockland Breakwater lighthouse marks the end of the breakwater. The principal dangers are marked, and the harbor is easy of access both day and night.

There are several rocks and ledges in the harbor. The chart is the guide for avoiding them. Those visible are **Shag Rock**, a cluster of bare rocks marked by a black tripod beacon; **Lowell Ledge**, a cluster of rocks bare at low water and having a black buoy 300 yards northeastward, marking a rock with 3 feet over it; and **Seal Ledge**, bare at half tide and marked by a spindle.

Rockland, the city on the western shore of the harbor, has a large trade in lime, and some shipbuilding. Several lines of steamers touch here, and a number of small steamers ply to the islands in the bay. The usual draft of vessels entering Rockland for cargoes is about 12 feet. Some of the wharves are dry, or nearly so, at low water, but there is from 6 to 15 feet alongside the principal ones, according to location. The bottom is soft mud, and some vessels lie aground at low water while loading and unloading. Rockland is the terminus of a branch of the Maine Central Railroad, which connects with the main line at Bath. There are float landings on the northern side of Tillsons Wharf.

Prominent objects.—Owlshead, marked by Owlshead lighthouse, is on the southeastern side of the entrance to the harbor. A little over 1/4 mile northwestward of Owlshead lighthouse there is a large black tripod called **Shag Rock beacon**. **Jameson Point**, on the northern side of the entrance. is low and grassy, with a large hotel a short distance back from its end; the breakwater and lighthouse on its end, making

Digitized by Google

off from the point, are conspicuous. **Tillsons Wharf** is a large stone pier with buildings lying 272° true (WNW ¼ W mag.) from Rockland Breakwater lighthouse.

Anchorages.—Vessels anchor anywhere in the harbor where the depth and bottom are suitable, taking care to keep 300 yards from the end of Tillsons Wharf, and leaving a clear channel for the steamboats landing at this wharf. Deep-draft vessels entering for the night usually anchor just inside the breakwater and ½ mile from the south shore of the harbor. Standing westward in the harbor the water shoals gradually toward the wharves. There are depths of 12 to 14 feet in the harbor eastward of Tillsons Wharf and northward of South Ledge, and less water in the bight in the northern part of the harbor between Tillsons Wharf and Jameson Point; only small vessels or small craft anchor in this part of the harbor.

Pilots are not necessary to enter or leave the harbor and are seldom taken; if desired they can sometimes be found on fishing vessels off the mouth of the bay. There are no regularly licensed pilots for the port.

Towboats can be had at Rockland.

Supplies.—Coal can be obtained alongside the wharves and water at the principal wharves and from the towboats. Provisions, gasoline, and some ship-chandler's stores can be had in the city.

Repairs.—There are several marine railways, the largest capable of hauling out vessels of 600 tons, 126 feet long, and a draft of 8 feet forward and 9½ feet aft; there are excellent facilities for repairs to wooden sailing vessels and hulls of steamers. Ordinary repairs to machinery can be made here, but Bath is the nearest place affording facilities for extensive repairs.

Approaching Rockland Harbor, Rockland Breakwater lighthouse may be steered for on any course between 287° true (NW ⅞W mag.), through west to 205° true (SW ⅛ S mag.). The first course leads ¼ mile northward of Owlshead lighthouse and the second leads about ⅜ mile eastward of The Graves spindle. Enter the harbor southward of the lighthouse, giving it a berth of 100 yards or more.

WEST PENOBSCOT BAY, ROCKLAND TO BELFAST.

Under this heading are described the harbors and towns on the western shore. Long (Islesboro) Island and adjacent islands are described on page 136.

Clam Cove, on the west side of West Penobscot Bay, about 2 miles northward of Rockland Harbor, is shoal at the head and not a good anchorage. There are no wharves. **Brewster Point Ledge**, extending ⅜ mile southeastward from Brewster Point, on the south side at the entrance is covered at its highest point at high water and marked by a black buoy. **Ram Islet** is a grass-covered rock ¼ mile northeastward of Brewster Point; a black buoy marks the end of the shoal extending northeastward from it.

Rockport Harbor.—This harbor (chart 310 or 321), on the western side of West Penobscot Bay, about 4 miles northward of Rockland Harbor, is a good anchorage for vessels of any size, sheltered from all but southerly winds, and is easy of access. Vessels can anchor anywhere between the entrance and a point 1 mile southward of the head, in 7 to 10 fathoms, soft bottom. Small vessels and motor boats can

Digitized by Google

find anchorage nearer the head. The head of the harbor to the entrances of the two coves near the head has been dredged to a depth of 12 feet, and this depth can be taken to the principal wharves at ROCKPORT, a town at the head. Rockport ships considerable lime.

PORTERFIELD LEDGE, in the middle of the entrance, is bare several feet at low water and marked by a stone beacon and spindle.

On the eastern side at the entrance the prominent marks are a hotel on BEAUCHAMP POINT, INDIAN ISLAND LIGHTHOUSE on INDIAN ISLAND (grassy), LOWELL ROCK (bare) southward of the lighthouse, and a spindle a little southward of Lowell Rock.

Vessels can enter Rockport Harbor anywhere between the black buoys off Brewster Point and Lowell Rock spindle, giving the spindle and Porterhouse Ledge stone beacon a berth of at least 150 yards, and then stand northward in mid-harbor until ¼ mile from the head, then slightly favor the eastern side to the wharves.

The Graves, ⅞ mile offshore about midway between the entrances to Rockport and Camden Harbors, is a ledge showing bare rocky heads at high water and a large area bare at low water. It is marked by a spindle.

Camden Harbor.—This harbor (chart 310 or 321), on the west side of West Penobscot Bay, is the approach to the town of Camden. It is frequented by many yachts and small craft and has some trade in vessels. The outer harbor is easy of access and affords good anchorage in 14 to 30 feet, soft bottom. The anchorage is eastward of a line from the steamboat wharf on Eaton Point to the black buoy northward of Negro Island. The depths in the outer harbor shoal gradually northward to 12 feet about ¼ mile from the head of SHERMAN COVE, above which the cove is shoal.

The greater part of the inner harbor has been dredged to depths of 7 to 10 feet, and is occupied as an anchorage by small pleasure craft in summer; the entrance is through a dredged channel 80 yards wide and 10 feet deep. A shoal extends 80 yards from the north shore between the steamboat wharf and the shipyard at the entrance of the inner harbor, and was marked in 1917 by a pile.

ICE sometimes forms in the harbor from January to March, but is not dangerous for vessels in the outer harbor. Westerly winds clear the harbor of ice.

CAMDEN, the town on the inner harbor, has several marine railways, the largest for vessels 160 feet long, 9 feet draft forward and 15 feet aft, with a capacity of 700 tons. The greatest draft of vessels loading here is 15 feet. It has steamer communication. The steamboat wharf has a depth of 14 feet at its end, the other wharves from 2 to 9 feet. There are float landings for small craft on the south side of the inner harbor. Coal in limited quantities and water are obtainable at the wharves, and all kinds of supplies for motor boats in the town.

The most prominent marks in approaching Camden Harbor are the mountains north of the town and NEGRO ISLAND LIGHTHOUSE, a white house on the eastern end of Negro Island. NEGRO ISLAND is wooded and lies on the southwest side of the main entrance. The passage westward of the island is shoal and used only by small local craft.

NORTHEAST LEDGES (inner and outer) lie southward of NORTHEAST POINT, and contract the main entrance to Camden Harbor to about

Digitized by Google

400 yards. The higher parts of both ledges are bare at half tide. A red buoy is placed about 300 yards south-southeastward of the south end of OUTER LEDGE, and the southwest end of INNER LEDGE is marked by another red buoy.

NORTHEAST PASSAGE is a narrow channel with depths of 12 to 18 feet, leading into Camden Harbor between Northeast Point and Inner Ledge. It is marked by two spindles, a red one on the end of the ledge extending 50 yards southward from Northeast Point and a black one on Inner Ledge; the deeper water favors the red spindle. At the eastern end of Northeast Passage a black buoy is placed to mark the north end of Outer Ledges and a black bell buoy is placed nearly ⅜ mile northeastward of the spar buoy. This channel is not recommended for strangers with a greater draft than 6 feet.

DIRECTIONS, CAMDEN HARBOR.—Entering by the main channel, vessels can steer for Negro Island lighthouse on any course between 354° true (N by E mag.) and 264° true (W by N mag.), taking care to avoid The Graves. Pass 200 to 300 yards eastward of Negro Island and steer 320° true (NNW mag.) and select anchorage in the outer harbor, eastward of a line joining the steamboat wharf and the black buoy northward of Negro Island. If going to the inner harbor, pass 100 yards northeastward of the black buoy and steer 285° true (NW by W mag.) for the entrance of the inner harbor, pass southward of the pile marking the shoal on the north side at the entrance to the inner harbor, and haul northward in mid-harbor.

To enter by Northeast Channel, from the bell buoy steer 230° true (WSW mag.) for the north end of Negro Island until up with the black buoy at the northerly end of Outer Ledges. Pass northward of this buoy and steer westward midway between the two spindles, favoring if anything the one on the north side of the passage.

Duck Trap Harbor is a broad, open bight in the west shore of the bay, 5 miles northeastward of Camden Harbor. Good anchorage, sheltered from all northerly and westerly winds, will be found about ¼ mile from the north shore of the harbor, in 6 to 8 fathoms, bottom soft in places. **Haddock Ledge**, the only outlying danger, is a rock with 4 feet over it lying a litle over ½ mile from the western shore and the same distance southwestward of Spruce Head, the northeast point of the harbor; the rock is marked on its southwest side by a red buoy. With this exception, danger will be avoided by giving the shore of the harbor a berth of about ¼ mile.

Lincolnville, a village at the southwest end of Duck Trap Harbor, has a wharf in bad repair and bare at low water.

Saturday Cove is a small cove on the west side of West Penobscot Bay, 9 miles northeastward of Camden Harbor. The village of **Northport** is on the south side. There are float landings at the entrance and a wharf at the head bare at low water.

Temple Heights is a small summer settlement ½ mile northward of Saturday Cove. The wharf has a depth of about 9 feet at the end.

Northport Camp Ground (Bayside post office) is a summer settlement on the west side of West Penobscot Bay, 2½ miles northward of Temple Heights. It has steamer communication. The steamer wharf has a depth of about 15 feet. A water tank on the hill back of the village is prominent.

Digitized by Google

BELFAST BAY AND RIVER

(chart 311 or 319) empty into the head of Penobscot Bay from northwestward and form the approach to the town of Belfast and the village of Citypoint, about 2 miles above Belfast. The bay affords good anchorage, exposed to southeasterly winds, and is easy of access. The depth in the river is about 12 feet to Belfast and there is considerable trade to this point, the deepest draft being 18 feet. The channel from Belfast to Citypoint is narrow, crooked, and unmarked, is bare at low water and can be used by a draft of about 6 feet at high water, but is little used except by small craft. Ice obstructs navigation throughout the river and bay in severe winters. The bay has been frozen over to Islesboro.

Steel Ledge, on the north side of Belfast Bay, is an extensive ledge with a least depth of 3 feet. It is marked near its south end by a light on a stone base, and by a red bell buoy a little farther south. A red spar buoy marks the north end and there is a channel between the buoy and the shore, but it is narrow and little used.

Belfast, on the southwest side of Belfast River, at the mouth, has several factories and considerable trade by water. Steamers between Boston and Bangor call here. The steamer wharf is the most southerly large wharf and has a depth of about 13 feet. The other principal wharves have depths of 10 to 12 feet. Vessels go to the upper wharf, above the bridge, drawing up to 18 feet. Coal in limited quantities and water are obtainable on the wharves, and other supplies in the town. Minor repairs to machinery can be made. Belfast and Citypoint are on a branch of the Maine Central Railroad.

Bridges.—Two highway drawbridges cross Belfast River. The lower one, at the upper end of Belfast, has a single opening 41 feet wide, and a headroom of 6.5 feet at high water. The second, ¾ mile above, has a single opening 28 feet wide, and a headroom of 7 feet at high water.

Anchorage.—Good anchorage can be had in the entrance westward of Steel Ledge, in 3 to 5 fathoms; also in the river below the steamboat wharf, in midchannel, or favoring the western shore, in 12 to 16 feet, soft bottom. Above the steamboat wharf shoals extend halfway across the harbor from the northeast side, and for a short distance below the bridge extend two-thirds of the distance across. Small vessels can anchor about 75 yards off the upper wharves of the city in 10 to 20 feet.

Directions, Belfast Bay and River.—Vessels entering Belfast Bay can shape the course to pass anywhere between the red bell buoy southward of Steel Ledge and the western shore, then head north-northwestward in midchannel, or slightly favoring the western side, until off the steamer wharf. To go above the steamboat wharf, pass 100 yards off it and steer northwestward, following the wharves at a distance of 75 yards.

SEARSPORT AND STOCKTON HARBORS

(chart 311) are at the head of Penobscot Bay westward of the entrance to Penobscot River.

Searsport Harbor is about 4 miles east of Belfast. It is a broad bight, open southward, but it affords good anchorage in 18 to 30 feet,

Digitized by Google

soft bottom, sheltered from northerly winds, and is used by all classes of vessels. **Searsport** is a town at the head of the harbor. It has steamer communication. There is a depth of 10 feet at the steamboat wharf. Water can be obtained alongside the wharf and some other supplies in the town.

Long Cove is eastward of Searsport Harbor, between the northwestern shore of Sears Island and Mack Point. The greater part of the cove is shoal, but good anchorage can be selected just inside the entrance in 2 to 4 fathoms, sheltered from all but southwesterly winds. On the south side of **Mack Point** is one of the termini of the **Bangor & Aroostook Railroad**. There are three wharves; the eastern one is the railroad coal-receiving wharf, which has a depth of 22 feet at its end, and the two westerly are fertilizer wharves. The approach is between Sears Island and the black buoy off the southeast end of Long Cove Ledge. From the western shore of the south half of Sears Island, ledges make off ¼ mile, one of which, **Sears Island Ledge**, is bare at low water. The south end of the ledges is marked by a black bell buoy, which lies ½ mile southwestward of Sears Island.

Long Cove Ledge, awash at lowest tides near its south end, lies 400 to 800 yards southward of the western end of Mack Point, and is marked off its southwest side by a red buoy and off its southeast end by a black buoy.

Stockton Harbor is between Cape Jellison and Sears Island, westward of the entrance to Penobscot River. It is a secure harbor for vessels of about 22 feet or less draft, and is easy of access. The depths shoal gradually from about 4 fathoms at its southern end to 12 feet about ¼ mile above the wharves on the east side, above which the harbor is shoal. The lead is a good guide.

Stockton Springs is a village at the head of the harbor, and this name is also applied to the terminus of the Bangor & Aroostook Railroad on the harbor. There is a yard at the head for building wooden ships. The wharf at the village is bare at low water.

On Cape Jellison, on the eastern side of Stockton Harbor, is a large wharf, with good facilities for handling cargo, from which some farm produce, lumber, and other commodities are shipped. There is a depth of 24 feet at the prinicpal wharf, and an unmarked dredged channel 300 feet wide and 25 feet deep from the southern end of the harbor to the wharf.

On Kidder Point, on the western side of the harbor, is a large steamboat wharf with a depth of 15 feet at its end, and shoaling thence to 12 feet 450 feet up the wharf. It was not used in 1917.

Sears Island, on the western side of Stockton Harbor, at the entrance, is high and thickly wooded, and has a small clearing on the south end. A ledge, the outer part bare at half tide, extends ⅜ mile south-southeastward from **Squaw Point** on the eastern side of Stockton Harbor at the entrance. It has a grassy islet in the middle.

A lighted range marks the channel through the entrance of Stockton Harbor; the structures are not prominent by day. To enter, pass 300 yards eastward of the black can buoy off the southeast side of Sears Island and steer 353° true (N by E mag.) on the range, passing in midchannel through the entrance and westward of two red buoys. When inside the harbor the course can be shaped for either wharf.

Digitized by Google

Muscle Ridge Channel, Two Bush Channel and the main part of West Penobscot Bay from the vicinity of Matinicus Island to the entrance of Penobscot River have been examined by means of a wire drag, and the dangers are shown on the charts.

Directions through Fox Islands Thoroughfare are given on page 51 and thorough Eggemoggin Reach on page 116.

Large vessels and the larger tows, approaching Penobscot Bay from southward, either from Boston or Cape Cod Canal, or passing eastward of Cape Cod, usually make the whistling buoy off Cape Ann, and then shape the course for Manana Island gas, whistling, and submarine bell buoy, and then enter through Two Bush or Muscle Ridge Channels. Approaching from westward along the coast, they usually make Bantam Rock gas and whistling buoy. Two Bush Channel is used by most large vessels and tows, and by all except small local vessels at night.

Entering from the eastward, vessels of the deepest draft should pass southward of Bay Ledge as directed in section 1.

Muscle Ridge Channel is good for a depth of 4 fathoms, but it is narrow in places and is not recommended for a greater draft than 15 feet at low water, except with local knowledge. Directions through the channel from northeastward are given on page 51.

The directions of sections 2 and 2 A for standing up the bay are good for vessels of the deepest draft.

1. Entering from eastward.—From Roaring Bull Ledge gas and whistling buoy, 1¾ miles southward of Isle au Haut, steer 260° true (W ¾ N mag.) for 10 miles to a position 1 mile southward of Bay Ledge bell buoy. Pass 1 mile southwestward of the bell buoy and steer 307° true (NW ⅞ N mag.) for 5½ miles, passing 1⅛ miles northeastward of Junken Ledge horizontally striped buoy and to a position ½ mile westward of a red buoy; this course leads ½ mile southwestward of rocky shoals with depths of 32 feet. From a position ½ mile westward of the red buoy, steer 339° true (N ¼ W mag.) for 4¾ miles to a position ¼ mile eastward of the black bell buoy off the eastern side of Monroe Island. Then follow the directions in section 2 or 2 A.

1 A. Entering from eastward, passing northward of Bay Ledge.—The directions of this section are good for vessels of 18 feet or less draft.

From Roaring Bull Ledge gas and whistling buoy, lying 1¾ miles southward of Isle au Haut, steer 274° true (WNW mag.) for 10¼ miles, passing 1¾ miles southward of Saddleback Ledge lighthouse and 1 mile southward of the islands and rocks westward. When Heron Neck lighthouse is on the starboard beam bearing 4° true (NNE mag.) distant 2 miles, steer 298° true (NW ⅛ N mag.) for 1¼ miles to Heron Neck whistling buoy. Continue the course, which leads ⅜ mile northeastward of Perry Ledge and ⅝ mile southwestward of White Islands Ground; the southern end of Sheep Island (high and heavily wooded) should be made ahead. Having stood 5 miles on the course from the whistling buoy, and Owlshead lighthouse is in range with the eastern side of Monroe Island, steer 335° true (N ⅝ W mag.) for 2¾ miles to a position ¼ mile eastward of the black bell buoy lying ¼ mile eastward of Monroe Island. Then follow the directions in section 2 or 2 A.

Digitized by Google

1 B. Entering from westward through Two Bush Channel.—From a position ½ mile southward of Bantam Rock gas and whistling buoy, steer 59° true (ENE ¾ E mag.) for 16 miles to a position about ⅜ mile southward of Old Man Ledge gas and whistling buoy. Then steer 48° true (NE by E ¾ E mag.) for 7 miles to a position ¼ mile northward of Marshall Point black whistling buoy. This course leads ⅝ mile southward of Burnt Island, ½ mile southward of Old Cilley Ledge bell buoy and ½ mile northward of an obstruction with 28 feet over it, probably the mast of a vessel.

Or, from Manana Island gas, whistling, and submarine bell buoy steer 40° true (NE by E ⅛ E mag.) for 12 miles to a position ¼ mile northward of Marshall Point whistling buoy, passing ⅜ mile northwestward of Duck Rocks bell buoy.

From a position ¼ mile northward of Marshall Point black whistling buoy steer 63° true (E ⅞ N mag.) for 5½ miles to a position 300 yards southward of the red buoy southwestward of Two Bush Island lighthouse and 400 yards northeastward of a horizontally striped buoy; then 49° true (NE by E ⅞ E mag.) for 2¾ miles, passing nearly ½ mile southeastward of Two Bush Island lighthouse, to a position ½ mile northwestward of a red buoy marking a 32-foot spot; then 16° true (NE by N mag.) for 3 miles, passing ⅞ mile eastward of Andrews Island (wooded), and to a position ¼ mile east-southeastward of the black buoy ¾ mile east-northeastward of Crescent Island (bare rock). Then steer 356° true (N by E ¼ E mag.) for 3¼ miles to a position ¼ mile eastward of the black bell buoy off the eastern side of Monroe Island. Then follow the directions in section 2 or 2A.

2. Monroe Island to Fort Point.—From a position ¼ mile eastward of the black bell buoy lying ¼ mile eastward of Monroe Island steer 10° true (NNE ½ E mag.) for 11 miles, passing ⅝ mile westward of Mark Island, and to a position ½ mile westward of the knoll near the middle of the northwest side of Seven Hundred Acre Island. Then steer 18° true (NE ¾ N mag.) for 7¼ miles, passing the western shore at Great Spruce Head at a distance of about ¼ mile. When Turtle Head bears 61° true (E by N mag.), steer 42° true (NE by E ⅜ E mag.) for 7 miles, pass ⅝ mile northwestward of Turtle Head, ⅛ mile southeastward of the black spar buoy southward of Sears Island, and midway between Fort Point lighthouse and Fort Point Ledge beacon. Pass about ¼ mile eastward of Fort Point and follow the directions for Penobscot River on page 151.

2 A. Monroe Island to Cape Rosier.—From a position ¼ mile eastward of the black bell buoy lying ¼ mile eastward of Monroe Island, steer 35° true (NE ¾ E mag.) for 5⅜ miles to a position ½ mile southeastward of McIntosh Ledge horizontally striped buoy. Then steer 27° true (NE mag.) for 10¾ miles, passing ½ mile westward of Resolution Island to a position ⅜ mile westward of Cape Rosier. Then, if bound up Penobscot River, steer 2° true (N by E ¾ E mag.) and follow a part of the directions in section 2, page 130.

Bound to Eggemoggin Reach.—Follow the preceding directions to a position ½ mile northwestward of Resolution Island. Then steer 39° true (NE by E mag.) for 2½ miles to a position ½ mile northwestward of Green Ledge, the grassy islet westward of Western Island. Then steer 78° true (E ½ S mag.) for Pumpkin Island lighthouse and reverse the directions in section 2, page 116.

Digitized by Google

(chart 311), emptying into the head of Penobscot Bay, forms the approach to the towns of Bucksport, Winterport, Hampden, and Brewer, and the city of Bangor, the two latter at the head of navigation, about 24 miles above Fort Point lighthouse at the entrance. It has considerable trade in regular steamers drawing about 10 feet, and many vessels, the deepest draft ordinarily trading to Bangor being about 18 feet.

Channel.—The main channel in Penobscot River has a least depth of 22 feet to Crosby Narrows, 3½ miles below Bangor, and 14 feet to Bangor. Dredging has been done in places between Bucksport and Bangor to obtain these depths. Unmarked shoals with less depth lie close to the channel in places.

Fort Point, on the west side at the entrance to Penobscot River, is partly wooded, and marked on the end by Fort Point lighthouse, a white tower connected with dwelling. There are several houses farther back and a wharf on the north side of the point.

Fort Point Ledge, ⅜ to ⅝ mile southward of Fort Point lighthouse, is bare at half tide and marked near the north end by a spindle on a stone beacon.

Fort Point Cove, on the west side of the river northward of Fort Point, is frequently used as an anchorage. The depths are 6 to 24 feet, shoaling gradually westward.

About 2½ miles above Fort Point the river is divided by **Whitmore Island** into two channels, the principal one leading on the west side of the island and the **Eastern Channel** on the east side; they unite north of Whitmore Island, near the town of Bucksport. Flowing into Eastern Channel from a northeasterly direction is a shallow stream navigable for small coasting vessels and fishermen at high water to the village of **Orland,** about 2¼ miles above its mouth; the channel is crooked and unmarked, and bare at low water a little below Orland.

Sandypoint is a village on the west bank of the river 2½ miles above Fort Point. There is little water at the wharves.

Odom Ledge, in the middle of the main channel 3 miles above Fort Point, is marked by a spindle on a stone beacon.

Verona Park is a small summer settlement and wharf on the west side of Whitmore Island about 1 mile below Bucksport.

Bucksport, a town on the east bank of the river, 6½ miles above Fort Point, is the terminus of a branch of the Maine Central Railroad; the Boston to Bangor line of steamers touch here. There is 14 to 18 feet at low tide alongside the principal wharves. Bucksport is connected with Whitmore Island by a drawbridge, which crosses Eastern Channel eastward of the principal wharves; the width of draw is 38 feet. Anchorage is found off the western end of the town in 5 to 10 fathoms.

Marsh River is a shallow stream flowing into Penobscot River from a southwesterly direction, about 3 miles above Buckcport. **Frankfort** is a village of little commercial importance on the west bank. The channel is bare at low water a little below the village. Boats seldom enter.

Winterport is a town on the west bank of the river, 12 miles above Fort Point; it is at the head of winter navigation, as ice closes the

Digitized by Google

river 10 to 12 miles below Bangor. There is 16 feet at low water at the steamboat wharf.

Hampden, a small town on the west bank of the river, is 19 miles above Fort Point. There is 14 feet at the principal wharf at low water, but it is in bad repair. The village of **Orrington** is on the east bank opposite Hampden. It has no wharves.

Bangor, on the west bank of Penobscot River at the head of navigation, is connected with Boston and points on Penobscot Bay by steamer, and has considerable trade in coasting vessels. Most of the river in front of the city has been dredged where necessary to obtain a depth of 14 feet. The bottom is rocky and there are a few rocks with a little less than 14 feet. The depths are about 18 feet at the High Head coal wharf and 10 to 14 feet at the others. Storm warning displays are made.

Brewer is a town on the east side of Penobscot River opposite Bangor. It is connected with Bangor by a highway bridge and by ferry.

Kenduskeag River empties into Penobscot River from westward at the north end of Bangor. Some dredging has been done in the entrance to a depth of 5 feet. A drawbridge crosses the river at the entrance. Small vessels sometimes go a little above the bridge.

Anchorage.—The usual anchorage for vessels waiting at the entrance of the river for a towboat or favorable wind and tide is northward of Fort Point on the west side of the channel. Vessels bound up the river anchor anywhere in the channel where soft bottom is found. Vessels towing to Bangor, if the tide does not serve, anchor in Crosby Narrows, about 5 miles below, and wait for a favorable tide.

Pilots for Penobscot Bay and River can sometimes be had from fishermen or coasters off the entrance, or in the bay. There are no regular pilots for the river except the masters of the towboats.

Towboats are always taken by large vessels bound up the river. There is one at Bangor, which can be telephoned for from Fort Point or any part of Penobscot Bay. Vessels towing up the river do not require a pilot.

Supplies.—Coal and water can be had alongside the wharves at Bangor. Water is also taken from the river at Bangor; below the city it is taken from wells in casks. Provisions and gasoline can be obtained at any of the towns, and ship chandler's stores at Bangor.

Repairs.—There were no marine railways in operation on the river in 1917. Much of the repairing is done on the beaches at low water. Bangor is the only place on the river at which repairs to the machinery of steamers can be made.

Steamers from Boston run to Bucksport, Winterport, and Bangor daily in summer; when the river is closed by ice, they run to Bucksport or Winterport. Small steamers ply between Bangor and the landings on the river and in Penobscot Bay.

Freshets occur in the river during March and April; they are at times dangerous to vessels.

Tides.—The mean rise and fall of tides varies from 10.3 feet at the entrance to 13.1 feet at Bangor.

Ice obstructs navigation above Winterport for nearly five months each year, beginning about December. During extreme winters the

Digitized by Google

river is closed to the mouth. The most difficult place below Winterport is abreast Fort Point, where ice jams occur. If vessels can pass this point they can usually go to Winterport.

DIRECTIONS, PENOBSCOT RIVER.

Directions to the entrance of Penobscot River through East Penobscot Bay are given on page 130, and through West Penobscot Bay on page 148.

The depths in the channel are 22 feet to Crosby Narrows, 3½ miles below Bangor, and 14 feet to Bangor, and some of the dangers are marked, but there are numerous unmarked shoals with less depths close to the sailing lines; the channel is crooked and narrow in places, and strangers should not attempt to carry a greater draft than 10 feet to Bangor, and with this draft care is necessary and the use of the lead advisable in places. With a deeper draft a pilot or towboat should be employed. The safest time is on a rising tide. The river is not safe for strangers to run at night.

Fort Point to Bucksport.—From a position ¼ mile eastward of Fort Point, steer 6° true (NNE⅛E mag.) for 2⅞ miles, passing about 100 yards eastward of the black buoy at the end of the ledge which extends 600 yards southeastward from Sandy Point, and to a position about 400 yards eastward of Odom Ledge stone beacon; then steer 332° true (N by W mag.) for ½ mile to mid-river and then follow a mid-river course until westward of Bucksport.

Bucksport to Winterport.—Give the western side of the point (marked by brick buildings) northwestward of Bucksport a berth of over 200 yards in rounding it, steer 357° true (N by E ⅜ E mag.) for ¾ mile for the northern point of Luce Cove, and pass about 200 yards westward of Indian Point (wooded); this course leads through a dredged channel, has unmarked shoals on either side, and care is necessary. Pass 150 yards westward of the north point of Luce Cove and steer 331° true (N by W mag.) for nearly 1 mile, heading for Drachm Point. Then steer 281° true (NW by W⅜W mag.) for the summit of Treats Hill, and pass about 50 yards southward of a red buoy. When the upper wharves of Winterport are open just clear of Drachm Point, steer 337° true (N⅜W mag.) and pass 50 yards westward of a second red buoy. From this buoy steer 355° true (N by E ⅛ E mag.) with the summit of Mount Heagan astern for ⅝ mile, until about 250 yards from the western shore. Then steer about 28° true (NE mag.) in mid-channel past Winterport.

Winterport to Crosby Narrows.—Follow a mid-river course for 2 miles above Winterport to Oak Point, and pass southward and eastward of the latter, rounding it at a distance of 250 yards; the cove westward of Oak Point is shoal. A shelving reef extends a greatest distance of 150 yards off the southeast side of Oak Point, and the bight in the eastern shore opposite is shoal. Keep in mid-river, and when about ¾ mile above Oak Point, pass westward of a ledge, covered at high water and marked by a spindle, lying 125 yards from the eastern bank. Round the point on the western bank above the spindle at a distance of about 150 yards, and follow the southern bank at this distance until southward of a red buoy southward of Bald Hill.

Digitized by Google

Then haul northward, pass 50 to 100 yards westward of the buoy and round the shore of Bald Hill at a distance of 150 to 200 yards. Then steer 0° true (N by E⅝E mag.) for ¼ mile to a position 150 yards eastward of the next point on the western shore. Then steer 341° true (N mag.) for ½ mile, following the western bank and giving it a berth of 100 yards. Then keep in mid-river for 2¾ miles and at the south end of Crosby Narrows avoid at high water the ruins of the wharf making out from the mouth of the stream on the west side.

Crosby Narrows to Bangor.—Pass in mid-channel through Crosby Narrows until the narrowest point is reached, then follow the northwest bank at a distance of 75 yards in the bight west of Seven Pines Point (marked by the ruins of some cribs off the point), passing westward of a shoal in mid-channel. Follow the west bank at this distance until abreast the ruins of a crib wharf on the west side, and then keep in mid-channel to abreast the large sawmill on the northwest side ¼ mile above. The best water then favors the south side, 75 to 100 yards off, for ½ mile to the point where the river bends northward, then crosses over and follows the west side, 75 to 100 yards off, for ⅜ mile, to abreast a crib landing in ruins. The channel then follows the southeast bank at a distance of 75 to 100 yards for ⅜ mile, and then is in mid-river or slightly favoring the northwestern side to the bridge at Bangor.

COAST FROM MUSCLE RIDGE CHANNEL TO PORT CLYDE (CHART 312).

Muscle Ridge Channel and Seal Harbor are described with Penobscot Bay on page 139.

Norton Island Ledges lie ½ to 1¼ miles westward of Whitehead Island. There is a bare rock near the middle of the south side of the ledge, and rocks bare at low water lie 600 yards east-southeastward and west-southwestward of the bare rock.

Seavey Ledges, westward of Norton Island Ledges, has two rocks awash at high water; there is a depth of 5 feet at the southern end of the ledges, lying 300 yards southwestward of the southern one of the two bare rocks.

Wheelers Bay and **Clarks Cove,** north-northeastward of Tenants Harbor lighthouse, are foul and little used. **Clarks Island** is a post village on the west side of Clarks Cove.

Tenants Harbor.—This is an excellent anchorage, frequently used as a harbor of refuge by small vessels, and is easy of access. It lies 3 miles westward of Whitehead lighthouse, and its entrance is marked by Tenants Harbor lighthouse, on the eastern end of Southern Island. It is open eastward and an easterly gale raises a choppy sea in the harbor, but vessels with good ground tackle can ride in safety. Ice seldom obstructs the harbor; during extremely cold weather it is sometimes frozen over for a few days.

Tenants Harbor is a village on the northern shore near the head of the harbor; there is a depth of about 9 feet at the steamboat wharf. Steamers make calls here.

Long Cove, making northward from the entrance of Tenants Harbor, has several stone quarries where vessels load granite; 10 feet is their usual loaded draft. The entrance is 150 to 200 yards westward of Northern Island, between reefs partly bare at low water. There

Digitized by Google

is a bare rock on the eastern part of the reef on the western side of the entrance.

The anchorage with most swinging room in Tenants Harbor is halfway from the western ends of Northern and Southern Islands to the short stone pier on the north side. Small craft anchor more toward the head of the harbor. The bottom is mostly soft mud and good holding ground, and shoals gradually westward. The north side of the harbor eastward of the stone pier is clear, while westward of it are spots with 4 to 9 feet over them. The south side of the harbor abreast the western point of Long Cove should be given a berth of 250 yards.

TENANTS HARBOR LIGHTHOUSE is a white tower connected with dwelling. The light is fixed red, with a red flash of 3 seconds duration every 60 seconds, 64 feet above the water, and visible 9 miles. The fog signal is a bell (1 stroke, silent 30 seconds, 2 strokes, silent 30 seconds).

Vessels entering Tenants Harbor can pass midway between Southern and Northern Islands, and steer 268° true (WNW 5/8 W mag.) into the harbor, slightly favoring the northern side.

Hart Ledge extends nearly 1/4 mile from shore 3/4 mile southwestward of Tenants Harbor lighthouse. There is a rock covered at high water near its northeast end, and one bare at low water near its southwest end. The ledge is marked off its southeast side by a black buoy.

Mosquito Harbor, 1 3/4 miles eastward of Marshall Point lighthouse, is shoal and little used. **Martinsville** is a settlement at the head. **Mosquito Head,** on the eastern side at the entrance, is high and wooded and looks like an island from a distance.

Mosquito Island, off the entrance to Mosquito Harbor, is partly wooded. The islets westward of Mosquito Island, including **Hay Ledge, The Brothers,** and **Gunning Rocks,** are rocky, with grass on top, and **Black Rock** is a bare rock. **Hart Bar,** extending 1/2 mile northward of **Hart Island,** is partly bare at low water. There are many unmarked submerged ledges in this vicinity.

The passage south of Mosquito Island and north of these islands and rocks is part of the inside route used by many vessels of 12 feet or less draft. The principal dangers are buoyed, but there are unmarked rocks with 15 and 16 feet. Directions through the passage are given on page 52.

Old Cilley Ledge, 1 1/2 miles east-northeastward of Burnt Island, is about 3/8 mile long; its eastern end is awash at low water, and its western end is awash at high water. There is a red bell buoy 1/4 mile east-southeastward of the eastern end.

Port Clyde (Herring Gut).—This is an excellent, though small, harbor and anchorage, lying between Marshall Point and Hooper Island, and about 9 1/2 miles north-northeastward of Monhegan Island; it is used as a harbor of refuge by fishermen and coasters. A bar with a depth of about 8 feet obstructs the northern entrance; vessels of 15 feet draft have been taken over this bar at high water by local pilots, but strangers should not attempt to cross it. Ice does not usually interfere with navigation. In very severe winters the harbor may be frozen over for a short time. The anchorage is anywhere in the channel inside of Marshall Point, in 4 to 6 fathoms, good holding ground, and has a clear width of 200 to 250 yards.

Digitized by Google

MARSHALL POINT LIGHTHOUSE, on the eastern side of the entrance to Port Clyde, is a white tower with a covered way to shore. The light is fixed white, 30 feet above the water, and visible 9 miles. The fog signal is a bell, sounding 1 stroke every 20 seconds. Storm warnings are displayed near the lighthouse.

PORT CLYDE is a village on the eastern side of the harbor. It is the headquarters of many fishing boats, and has a fish cannery and cold-storage plant. The principal wharves have depths of about 15 feet. Gasoline, provisions, and some ship-chandlers stores are obtainable. Coal is sometimes delivered from Thomaston by lighters.

Directions, Port Clyde.—Vessels can approach the entrance from eastward, between Mosquito Island and The Brothers; or from westward, through Davis Straits. Directions through these passages are given on page 52.

ENTERING FROM SOUTHWARD, vessels should pass close eastward of Old Cilley Ledge red bell buoy, and steer for Marshall Point lighthouse on a 335° true (N 5/8 W mag.) course, passing a little over 1/4 mile eastward of Black Rock and 150 to 200 yards westward of Gunning Rocks. Pass 200 to 300 yards westward of Marshall Point lighthouse and enter the harbor in mid-channel, passing westward of a red buoy and eastward of a black buoy. Anchorage may be had 125 yards off the wharves at Port Clyde, in 3½ to 5 fathoms, soft bottom.

ENTERING FROM NORTHWARD.—There are entrances from northward on either side of Raspberry Island, both having a depth of about 8 feet, but they are narrow and difficult, and should not be used by strangers except in small craft. The easterly channel is the best for strangers in small craft. The best water follows the eastern shore at a distance of about 70 yards and passes eastward of a reef which makes eastward from a small islet, which was marked at the end in 1917 by a private spar buoy. Care should be taken to avoid the submerged ruins of a marine railway on the east side just north of the wharves.

MONHEGAN ISLAND,

lying 9 miles off the mainland, is one of the important landmarks for vessels bound along the coast. It is 1⅜ miles long, 160 feet high, and presents a rocky shore, with high bluffs in places.

Monhegan Island lighthouse, in the middle of Monhegan Island, is a gray conical tower, with a covered way to a white dwelling. The light is fixed white, with a white flash of 5.6 seconds duration every 60 seconds. 178 feet above the water, and visible 20 miles.

Manana Island, a smaller island close westward of Monhegan Island, is 110 feet high and rocky, and has a fog signal on its summit. The signal is an air siren, sounding a group of three blasts, each of 3 seconds duration, every 60 seconds, silent interval 35 seconds. A bell will be struck by hand if the siren is disabled.

Monhegan Harbor is an anchorage for small craft, exposed southward, lying between Monhegan and Manana Islands; it is used principally by local fishermen, and has 3 to 5½ fathoms, good holding ground, but there is scant room at the anchorage for a small vessel to swing. The deeper water in the harbor favors Manana Island. A depth of 12 feet can be taken through the northern

Digitized by Google

entrance, between Monhegan Island and the grass-covered rock on the end of the ledge making out from Manana Island; the best water leads close to the end of the wharf in entering.

Monhegan is a village of fishermen on the east side of Monhegan Harbor. The principal wharf has a depth of about 12 feet at the end. The village has telephone communication with the mainland, and communication by steamer with Boothbay Harbor and Thomaston. Gasoline and provisions are obtainable.

Eastern Duck Rock is a large bare rock, with some grass on top, lying 400 yards off the north end of Monhegan Island; the narrow channel between them is near the rock.

Duck Rocks, lying ⅝ mile off the northwest side of Monhegan Island, are two large bare rocks, the western one marked by a large black tripod beacon. **Sunken Duck Rock,** with 6 feet over it, lies 350 yards north-northeastward of the tripod, and is marked on its north side by a black buoy. A black bell buoy is moored 650 yards north-northwestward of the tripod.

Allen Shoal lies 1⅞ miles eastward of Monhegan Island lighthouse and 1 mile from the nearest point of the island. The least depth found by the survey is 5½ fathoms, but a depth of about 3 fathoms is reported.

A breaker is reported to lie 2¼ miles 96° true (ESE mag.) from Monhegan Island lighthouse.

Gull Rock Ledge, with 3¾ fathoms over it, lies 1 mile south-southeastward of Monhegan Island lighthouse.

ST. GEORGE RIVER AND THOMASTON.

The entrance of this river (chart 312) lies about 9 miles southwestward of Whitehead and north-northeastward of Monhegan; Marshall Point lighthouse marks the eastern and Franklin Island lighthouse the western approach. A group of islands, known as the Georges Islands, extends 6½ miles south-southwestward from the middle of the entrance, which is also obstructed by numerous ledges and rocks, the most prominent of which are marked by buoys or spindles. Several channels with deep water lead into the river between these islands and ledges. St. George River extends 10 miles in a northeasterly direction to the town of Thomaston, where the Warren River, a shallow stream of no commercial importance, empties into it from northwestward.

Georges Islands.—These are a group of islands and rocks extending about 6½ miles south-southwestward from the middle of the entrance to St. George River. The larger islands are generally wooded, and the smaller ones grassy or rocky, and there are few prominent marks. Several channels lead between the islands; the most important are Davis Straits, the channel between McGee and Seavey Islands, and the channel northwestward of Caldwell Island.

Old Man Ledge, the most southerly of the dangers, is marked by a spindle; there is a gas and whistling buoy ¼ mile south-southwestward of it. **Old Woman Ledge,** ⅝ mile northward of Old Man Ledge, is bare at half tide.

Burnt Island, the eastern large island at the south end of the group, is 150 feet high, wooded, and marked on its summit by a prominent tower. There is a Coast Guard station on the north side.

Digitized by Google

Georges Harbor is between **Allen, Benner,** and **Davis Islands.** There is a small settlement of fishermen on the thoroughfare between Allen and Benner Islands, and small craft sometimes anchor here. The best water is in mid-channel in entering the thoroughfare from northeastward. Entering from southwestward the south side should be favored.

Davis Straits is the passage between Davis Island on the south and Thompson Island and other small islands on the north. It is part of the through route, used by many vessels of 12 feet or less draft. It has ample depth, but **Griffins Ledge,** in mid-channel, has a depth of 10 feet over it. There is a red buoy on the south side of the ledge; the channel is south of the red buoy, and is only 75 yards wide.

Davis Island is grassy and has two knolls with a saddle between. The two southernmost islets on the north side of Davis Straits are grassy and the others are wooded.

Between **Thompson** and **Hooper Islands** the bottom is very broken and there are numerous dangers, most of them marked or visible at some stage of the tide. **The Sisters** are two small ledges awash at low water and marked on the northwest side by a black buoy. **Old Horse Ledge** is bare at low water and marked by a spindle. **Outer Shag Ledge** is bare at half tide and **Inner Shag Ledge** is awash at high water. **Kelp Ledge** has a small part bare at low water.

The channel between **Bar** and **Seavey Islands** on the east and **McGee Island** on the west has ample depth, and some of the dangers are buoyed, but there are unmarked dangers close to the channel. It is used by the regular steamers of 10 feet draft. Bar Island is low and grassy, with a few trees, and Seavey Island is grassy and has a house in the center. **Jenks Ledge,** the most westerly danger, is bare at low water and marked by a horizontally striped buoy.

Port Clyde is on the eastern side of the entrance to the river (see page 153). There is good anchorage in the middle of the northern entrance of Port Clyde, northward of Hooper Island, in 4 fathoms. The entrance is clear northward of Blubber Island.

Deep Cove, on the eastern shore, just north of the northern entrance to Port Clyde, has good anchorage in 4 to 7 fathoms, soft bottom.

Gay Cove is a shallow and unimportant cove in the eastern shore of **Gay Island,** the western point at the entrance of the river.

Pleasant Point Gut separates Gay Island from the mainland. Its western part is bare at low water.

Turkey Cove, on the eastern shore, about 1½ miles above **Caldwell Island,** has good anchorage in 3 to 4 fathoms, soft bottom, about midway between the points at the entrance.

Maple Juice Cove is a long, shallow cove on the west shore about 2¼ miles above Caldwell Island; good anchorage is found in the entrance in 2 to 4 fathoms. There is a small wharf on the western shore 1 mile northward of Maple Juice Cove.

Otis Cove is a broad cove, shallow at its head, on the eastern shore, about 1 mile above Maple Juice Cove. The village of **St. George** is at its head. There is good anchorage off the entrance in 3 to 5 fathoms, but no wharves. A bare rock lies 150 yards off the south side of the entrance, and a ledge covered at three-quarters flood, extends 350 yards off the shore ¼ mile northeastward of the entrance.

Broad Cove is a shallow cove on the western shore about 4½ miles above Caldwell Island; the village of **Cushing** is situated near its

Digitized by Google

western shore. There are no wharves. **Bailey Ledge** is bare at low water and marked on the southeast side by a black buoy.

Watts Cove and **Cutlers Cove**, at its head, are shallow coves on the eastern shore opposite Broad Cove.

Thomaston is a town on the railroad at the head of St. George River. The average draft of vessels entering here is 10 to 12 feet, and the deepest 16 feet. There are shipyards where wooden vessels are built. A steamer runs to Port Clyde and Monhegan.

Warren River empties into St. George River west of Thomaston; it is navigable at high water to the village of **Warren**, about 4 miles above Thomaston. There are three drawbridges above Thomaston, with draws estimated to be 40 feet wide. The river is little used.

Channel.—There is a channel in St. George River up to Broad Cove, which has 10 fathoms or more water; above this the depth gradually decreases and it narrows to a small stream through extensive flats which show bare at low water. There is a depth of 19 feet in the channel to 1 mile below Thomaston. From this point a narrow channel, which is liable to shoal, has been dredged 16 feet deep and 90 to 220 feet wide to Thomaston. In 1917 there was a depth of 16 feet, but the channel was very narrow, especially at the bend eastward of a stone beacon.

Anchorages.—Good anchorage for the deepest draft vessels is found eastward of Caldwell Island in 6 to 8 fathoms, soft bottom; above this vessels anchor anywhere in the channel where the depth is not great or in Turkey Cove, Maple Juice Cove, or Otis Cove.

Pilots are usually taken by vessels. The only ones available are local fishermen, which may be obtained from Port Clyde, or from fishing boats at work in the vicinity of the entrance.

Towboats can be obtained from Bath or Rockland.

Supplies.—Gasoline and provisions are obtainable at Port Clyde or Thomaston. Coal in limited quantities, and water are obtainable at Thomaston.

Ice closes the river to navigation from December to March in severe winters. In ordinary winters, it is not usually entirely closed more than one month, although ice sufficient to interfere with navigation may be encountered at any time for a period of three months.

Tides.—The mean rise and fall of tides is 9.3 feet.

DIRECTIONS, ST. GEORGE RIVER.

The approach to the entrance of St. George River has very broken and irregular bottom, with numerous ledges, bare and submerged, and has not been examined by means of a wire drag. Strangers should therefore proceed with caution and avoid crossing broken areas where the charted depth does not greatly exceed the draft.

From eastward.—Follow the directions in section 8, page 52, to a position 50 yards northwestward of Allen Ledge black buoy. Then steer 242° true (W by S mag.), pass 150 yards southward of Hooper Island Rocks red buoy, and round the buoy at this distance. Then steer 326° true (N by W ½ W mag.) for the western end of Teal Island, and when ¼ mile eastward of the northern end of Bar Island, steer 37° true (NE ¾ E mag.) for about 1 mile, heading for Hoopers Point. Pass midway between Hoopers Point and Channel Rock buoy, and steer 340° true (N ¼ W mag.) for the black buoy off Pleas-

Digitized by Google

ant Point Gut, passing ¼ mile westward of Howard Point, and 200 yards westward of a red buoy off the point.

Pass 150 yards eastward of the black buoy and steer 36° true (NE ¾ E mag.) for 2½ miles, passing through the middle of the Narrows. Above the Narrows there is excellent anchorage near the middle of the river off Otis Cove, in 4 to 5 fathoms. Above this point be guided by chart 312 and the buoys; the safest time is at low water, when the flats are bare or on a rising tide.

From westward.—When Franklin Island lighthouse is distant 4 miles or more, steer for it on any bearing between 28° true (NE mag.) and 51° true (ENE mag.). Pass about 300 yards westward of Franklin Island and steer 51° true (ENE mag.), heading just clear of the northern end of Caldwell Island. On this course pass about ¼ mile northwestward of Gangway Ledge (bare rock), 250 yards northwestward of Jenks Ledge buoy, and midway between Goose Rock (high and rugged) and Goose Rock Ledge buoy (both buoys horizontally striped). Keep the northwest side of Caldwell Island aboard, distant 200 to 250 yards, steer 36° true (NE¾E mag.), and pass about 150 yards eastward of two black buoys. Continue the course and follow the directions in the paragraph preceding.

MUSCONGUS BAY

(chart 313), lies between the Georges Islands on the east and Pemaquid Neck on the west, and forms the approach to Meduncook and Medomak Rivers and Muscongus Sound, the villages of Friendship, Round Pond, and Medomak, and the town of Waldoboro. It is obstructed by numerous islands and ledges, and is seldom entered by vessels seeking shelter in heavy weather. Tenants Harbor and Port Clyde, eastward; and Boothbay Harbor, westward, are easier of access and more convenient. Many of the dangers are marked by buoys. The bay is frequented by passenger steamers of about 10 feet draft, and many local fishing boats and small craft.

Meduncook River is an unimportant estuary making in a general northeast direction, just westward of St. George River; the entrance forms an approach to Friendship Harbor, and is a good anchorage with 4 to 5 fathoms. The approaches to the entrance are the same as for St. George River, and the anchorage is marked by buoys. The river above the anchorage has a narrow, crooked channel, and is obstructed by numerous unmarked rocks and ledges, so that local knowledge is necessary for its navigation.

Directions to the anchorage from eastward are given on page 163. Approaching from westward, follow the directions for approaching St. George River from westward until up with Jenks Ledge buoy, and then steer 357° true (N by E¼E mag.) for the summit of Morse Island until up with the red buoy at the entrance. Pass about 50 yards northwestward of the red buoy, steer 40° true (NE by E⅛E mag.), and pass about 100 yards eastward of Northeast Point Reef black buoy. The anchorage is northward of the black buoy, and is about ⅜ mile in diameter.

Friendship Harbor.—This harbor lies west of Meduncook River, and is separated from it by **Friendship** and **Garrison Islands**, between which a channel leads from the anchorage in Meduncook River into the harbor. The harbor is about 1 mile long and has good anchorage in

Digitized by Google

4 to 6 fathoms, but is little used. Ice closes the harbor proper from December to March.

A ledge extends 300 yards southwestward from Jameson Point. A rock bare at low water at the south end of the ledge is marked by a black spindle. Above the wharf the northern and eastern sides of the harbor should be given a berth of over 200 yards. The southeast side of the harbor should be given a berth of over 200 yards. **Murphy Ledge** is a rock bare at half tide and marked by a red spindle, lying 200 yards from the southeast side of the harbor abreast Jameson Point. In the eastern part of the harbor a shoal extends 350 yards northeastward from the northeast end of Friendship Island, and is marked at its end by a black buoy.

Friendship is a town on the north shore of the harbor; the usual draft of vessels loading here is 10 feet. The town has steamer communication. There is a depth of about 12 feet at the steamer wharf, but a ledge with little depth lies northeastward of it. Gasoline and provisions are obtainable, and there is water on the wharf.

Directions for the passage from Port Clyde through Meduncook River, Friendship Harbor, and to the head of Muscongus Sound are given on page 162. Directions from southward in Muscongus Bay are given on page 161.

Hatchet Cove is a shallow cove making northward at the western end of Friendship Harbor. A narrow channel, with a least depth of 15 feet, leads northeastward into the cove near the western point at its entrance. It is of no importance as an anchorage.

Gull Rock, in the western entrance to Friendship Harbor, has two rocks bare at high water.

Medomak River.—This river enters the head of Muscongus Bay westward of Martin Point, the western point at the entrance to Friendship Harbor. Strangers wishing to enter the river in vessels should take a pilot, on account of the many unmarked dangers, narrow and crooked channels, and strong tidal currents, which require local knowledge.

The lower part of the river is about 2 miles wide, but is separated by several islands into two approaches, which have three narrow and crooked channels by which the river proper is entered. The approaches to these channels are through Muscongus Bay or Muscongus Sound. The eastern approach is 5/8 mile wide and comparatively clear of dangers; at its upper end are two passages leading into the river, one through Back River Cove, and the other Flying Passage. Both have good water, but are very narrow in places, with strong tidal currents. Hockomock Channel, the western entrance, has a least depth of 4½ fathoms, but is narrow in places and has strong tidal currents.

The channel in Medomak River has ample depth for 5 miles above the entrance, and some of the dangers are marked, but there are unmarked dangers close to the channel. For the next 2½ miles to within 1¾ miles of Waldoboro, the channel leads between flats bare or nearly so at low water, and shoals gradually to 5 feet. From that point to Waldoboro the channel has been dredged 75 feet wide and 5 feet deep between flats bare at low water. The channel for 3 miles below Waldoboro is marked by bush stakes. It can best be followed at low water when the flats are visible, or on a rising tide. Ice closes the river from December to April.

Digitized by Google

MEDOMAK is a post village on the western side of Hockomock Channel. There is a wharf at the village and a cannery wharf ½ mile southwestward.

There is a float landing and small settlement on the eastern side of Hockomock Channel inside CLAM ISLAND.

BROAD COVE, on the west side of Medomak River, is used by a few motor boats and small schooners carrying fertilizer and wood products. The channels are unmarked.

WALDOBORO is a town on the railroad at the head of navigation on Medomak River. The deepest draft going to the town is about 10 feet. The principal wharf has a depth of about 4 feet.

Pemaquid Neck, on the west side of Muscongus Bay, is wooded. Pemaquid Point, the south end, is marked by **Pemaquid Point lighthouse**, a white tower connected with dwelling. The light is fixed white, 79 feet above the water, and visible 12 miles. The fog signal is a bell (1 stroke every 10 seconds).

Pumpkin Cove Ledge, 1 mile east-northeastward of Pemaquid Point lighthouse, is unmarked and has a least found depth of 18 feet; the sea breaks on it in heavy weather.

New Harbor Dry Ledges lie 2 miles northeastward of Pemaquid Point lighthouse and ¼ mile from the western shore. The ledges are ¼ mile long, with a bare rock at each end, and there is no safe passage between them and the shore. **Little Island**, with a clump of trees, lies 200 yards from the shore ¼ mile southward of New Harbor. It is the highest part of a ledge about ¼ mile long.

New Harbor is a cove on the western shore of Muscongus Bay, about 2⅜ miles northeastward of Pemaquid Point lighthouse; it is used as an anchorage by small craft only, and though open eastward, is well sheltered from the sea. The channel is narrow between a shelving ledge extending northeastward from the south point at the entrance, and a ledge just inside it which extends half way across from the north side and is marked at its end by a red buoy. The channel, with a width of about 150 feet, then leads close northward of a black spindle. Inside the spindle a part of the harbor has been dredged to a width of 200 to 250 feet, the lower half of the dredged area to a depth of 12 feet and the upper half 6 feet. Regular steamers drawing up to 12 feet make landings at a wharf on the north side.

Muscongus Sound.—This sound is on the western side of Muscongus Bay, between MUSCONGUS and HOG ISLANDS on the east and the mainland on the west. It is about ⅝ mile wide and 5 miles long, and has several rocks and ledges near its southern entrance, the most prominent of which are marked by buoys. Above Poland Ledges to abreast Muscongus Harbor the depths in the sound shoal gradually from 8 to 4 fathoms, and anchorage can be selected with the aid of the chart.

Islands and ledges extend 1¾ miles southward from Muscongus Island. HADDOCK ISLAND is wooded and Ross ISLAND is grassy. WEBBER DRY LEDGE is awash at high water. BAR ISLAND LEDGE is ¼ mile long and bare in one place at low water; it is marked on the south end by a red buoy. BAR ISLAND is grassy, with a cottage in the center.

MARSH HARBOR, on the southeast side of Muscongus Island, between it and MARSH ISLAND, is not used as an anchorage.

Digitized by Google

POLAND SOUTH LEDGE has a depth of 9 feet and POLAND NORTH LEDGE is bare at low water. Both are marked on the east side by black buoys. The better channel leads eastward of them.

ROUND POND is a small landlocked harbor with 12 to 18 feet in its middle on the west shore of Muscongus Sound, about 2 miles above the southern end of Muscongus Island; it affords good anchorage for small vessels, but is little used. There is a granite quarry on the north side of the entrance, and Round Pond, a village and landing, is at the head of the harbor. The northeast and southwest ends of the harbor should be given a berth of 350 yards and the west side 200 yards. Regular steamers make landings at a wharf which has a depth of about 12 feet. The best water in entering favors the north side, northward of a black buoy marking the end of a reef making northward from the point on the south side of the entrance.

MUSCONGUS HARBOR is a small cove and village on the west shore of the sound about 1½ miles above Round Pond. There is a landing for small craft.

GREENLAND COVE is the extreme northern end of the sound; it is shallow and of no importance.

LOWER NARROWS, leading into the head of Muscongus Sound north of Hog Island, has a depth of about 13 feet, and is used by the regular steamers drawing 10 feet and sometimes by vessels bound into Medomak River. The principal dangers are marked, but local knowledge is necessary to carry the best water. Directions through the narrows are given following.

Supplies.—Gasoline and provisions are obtainable at Friendship, New Harbor, Round Pond, and Waldoboro. There is water on the wharf at Friendship.

Pilots for these waters are local fishermen, and can be obtained at any of the towns or from boats at work near the entrance.

Tides.—The mean rise and fall of tides varies from 8.9 to 9.5 feet.

DIRECTIONS, MUSCONGUS BAY.

This region is an area of rocks and ledges and very broken bottom and has not been examined by means of a wire drag. Vessels should therefore proceed with extreme caution and should avoid broken bottom where abrupt changes in depth are indicated by the chart to depths less than 10 fathoms.

Directions through the bay from Davis Straits to Pemaquid Point are given on page 53. The following directions lead into the bay from seaward.

From eastward.—Passing southward of Old Man Ledge gas and whistling buoy, steer about 276° true (WNW mag.) for 3¾ miles, passing ¼ mile or more southward of Shark Island, and to a position 1¼ miles southwestward of Eastern Egg Rock and with Franklin Island lighthouse bearing 20° true (NE ¾ N mag.). Then steer 6° true (NNE mag.) for Jones Garden Island, passing ⅝ mile westward of Eastern Egg Rock tripod, ½ mile eastward of Western Egg Rock Breakers buoy, ¾ mile westward of Franklin Island lighthouse, and to a position 150 yards westward of Harbor Island Rock horizontally striped buoy. Then steer 34° true (NE½E mag.) for the summit of Black Island, and keep the northwest side of Harbor Island aboard, distant 300 to 400 yards.

Digitized by Google

Pass 300 to 400 yards westward of Black Island, steer 23° true (NE⅜N mag.), and pass about 300 yards northwestward of the southwest end of Friendship Island. When Gull Rock bears 262° true (W⅞N mag.), steer 57° true (ENE⅝E mag.), and select anchorage near the middle of Friendship Harbor below the black buoy, in 4 to 6 fathoms.

Bound to Medomak River, follow the directions preceding to a position 300 to 400 yards westward of Black Island. Then steer 3° true (N by E ¾ E mag.) and pass about ¼ mile westward of Gull Rock. Anchor near mid-channel, about 1¾ miles above Gull Rock, and ⅜ mile below Hungry Island. Above Gull Rock, danger will be avoided by giving the shores a berth of 400 yards. If desiring to enter the river, or if bound to Waldoboro, take a pilot, or if in small craft, be guided by the chart.

From westward.—When Franklin Island lighthouse is distant 4 miles or more, bring it on any bearing between 28° true (NE mag.) and 51° true (ENE mag.) and steer for it. When Jones Garden Island bears 6° true (NNE mag.) steer for it and proceed as directed above.

Or, from a position ¼ mile northward of Pemaquid Ledge buoy steer 61° true (E by N mag.) for 3¾ miles, passing ½ mile southward of Pemaquid Point lighthouse, and to a position ⅜ mile southward of New Harbor Sunken Ledges red buoy. Then steer 51° true (ENE mag.) for 2¾ miles, heading for Franklin Island lighthouse, and pass ¼ mile southeastward of the black buoy eastward of Western Egg Rock. When Jones Garden Island bears 6° true (NNE mag.) steer for it and proceed as directed above.

Directions, Muscongus Sound, from Eastward.—Having come from Davis Straits as directed on page 53, pass 200 yards northward of Eastern Egg Rock beacon and steer 284° true (NW by W ¼ W mag.), passing ⅜ mile southward of Western Egg Rock and to a position 400 yards southwestward of Haddock Island Kelp Ledge horizontally striped buoy. Then steer 329° true (N by W ¼ W mag.) and pass about 300 yards southwestward of Webber Sunken Ledge red buoy.

When about 400 yards from the western shore, steer 17° true (NE by N mag.), pass midway between Brown Head Ledge buoy and the western shore, about 300 yards off Brown Head, and to a position 100 to 200 yards eastward of Poland South Ledge black buoy. Then steer 355° true (N by E mag.) and pass about 250 yards eastward of Poland North Ledge black buoy. When Round Pond is opened, pass close northward of the black buoy on a 253° true (W mag.) course, and keep the north point at the entrance aboard distance about 75 yards. Anchor in the middle of Round Pond in 14 to 18 feet.

From Southward or Westward.—Follow the eastern shore of Pemaquid Neck at a distance of about ¾ mile on a 17° true (NE by N mag.) course until abreast Long Cove. Continue the course, pass midway between Brown Head Ledge buoy and the western shore, and proceed as directed in the preceding paragraph.

Directions, Port Clyde entrance through Friendship Harbor to Muscongus Sound.—These directions are good for vessels of 10 feet or less draft. The tidal currents have little velocity, and generally the navigation is not difficult in daylight and clear weather with the aid of the chart and the buoys, but there are three places requiring extra cau-

Digitized by Google

tion. These are at the north end of McGee Island, between Garrison Island and the northeast point of Friendship Island, and in Lower Narrows. This route is used by the regular steamers and many small craft.

Follow the directions in section 8, page 52, to a position 50 yards northwestward of Allen Ledge black buoy. Then steer 242° true (W by S mag.) and pass 150 yards southward of Hooper Island Rocks red buoy. Then steer 282° true (NW by W ⅜ W mag.) for the summit of McGee Island until Bar Island is abeam, distant 300 to 400 yards. Then steer about 308° true (NW by N mag.), and keep the northern end of McGee Island aboard, distant 100 to 125 yards, when passing between it and the end of the ledge, partly bare at low water, which extends 250 yards westward from the south end of Seavey Island; a shelving ledge also extends 250 yards southward from **Seavey Island.** Continue the course and pass about 50 yards northeastward of a black buoy and 150 yards southwestward of a red buoy.

Then steer 346° true (N ¼ E mag.) for the summit of Morse Island with the summit of McGee Island astern, until up with the red buoy between Morse and Gay Islands. Pass about 50 yards northwestward of this buoy, steer 40° true (NE by E mag.), and pass eastward and northward of Northeast Point Reef black buoy, rounding it at a distance of about 100 yards. Then steer 283° true (NW by W ¼ W mag.) and pass about 50 yards southward of Crotch Island Ledges red buoy.

When about 300 yards westward of this buoy, steer 327° true (N by W ⅜ W mag.) for the northeast point of Friendship Island, with the northeast end of Morse Island astern until up with the red buoy lying 140 yards southwestward of Garrison Island. Pass 50 yards westward of this buoy, steer 6° true (NNE mag.), and pass between Garrison Island and the northeast point of Friendship Island, slightly favoring if anything Garrison Island. Pass eastward and northward of a black buoy, rounding it at a distance of about 75 yards, and steer 237° true (WSW ½ W mag.) through Friendship Harbor, passing midway between the red spindle on the southern side of the harbor and the black spindle near the end of the ledge extending southward from **Jameson Point.**

Pass about 350 yards southward of **Ram Island** (wooded) and steer 270° true (WNW ½ W mag.) to a position 100 yards southwestward of the black buoy southward of Martin Point. Then steer 299° true (NW mag.) for the red buoy at the end of the ledge extending southward from Bremen Long Island. Pass close southward of this buoy, steer 270° true (WNW ½ W mag.) for the south part of **Middle Ledges,** which shows as two wooded clumps; on this course pass 150 yards southward of the south end of Bremen Long Island and close northward of a black buoy, and pass close southward and about 100 yards westward of a red bell buoy. Then steer 329° true (N by W ¼W mag.) and pass about 150 yards eastward of the north end of the brush-covered islet on the northern part of Middle Ledges.

Pass about 150 yards eastward and 50 yards northward of the red buoy at the north end of Middle Ledges, steer about 270° true (WNW ½W mag.), and pass about 150 yards northward of the point at the northeast end of Hog Island. When about 125 yards from the eastern side of Hockomock Point, steer about 237° true (WSW⅝W

Digitized by Google

mag.), and pass between the point and the small bare rock on the ledge extending northeastward from Hog Island, slightly favoring, if anything, the rock. The channel is narrow and great care is required at this point. When past the rock, keep the shore of Hog Island aboard, distant about 75 yards for ¼ mile, and pass southward of two black buoys at the western end of Lower Narrows. Then follow the shore of Hog Island at a distance of about 200 yards for nearly ½ mile until past the black buoy marking the south end of Half Tide Ledge.

JOHNS BAY

(chart 313) lies westward of Pemaquid Neck, between it and Rutherford Island. It is about 1¼ miles wide at its entrance and 2 miles long to Johns Island, above which the Pemaquid River empties into its northeastern end and Johns River into its northwestern. The depths in the bay are very irregular, and there are several ledges and rocks.

The bay is of no commercial importance; a number of summer resorts are located on its shores, and it is used as an anchorage only by fishermen and yachts well acquainted with the locality. The holding ground is poor, except in a few places near the head of the bay and in the coves. Port Clyde, eastward, and Boothbay Harbor, westward, are preferable at all times.

Pemaquid Harbor is at the entrance to Pemaquid River, northeastward of Johns Island; the bottom is rocky and irregular, but there is a fair anchorage for small vessels in the eastern part of the harbor between Fish Point and the entrance of Pemaquid River, in 6 fathoms. **Pemaquid Beach** and **Pemaquid Harbor** are post villages at the entrance of Pemaquid River, the former on the south side and the latter on the north side. **Pemaquid River** extends northeastward about 2 miles to the village of **Pemaquid Falls.** The river is dry at low water near its head and has a narrow, crooked, and unmarked channel. It is seldom entered.

Thurston Ledges are mostly bare rocks which extend 300 yards southward from the north side at the entrance of Pemaquid Harbor, their south edge lying 300 yards northward of Beaver Island.

Pemaquid Harbor can be entered from westward by passing 125 to 150 yards northward of **Beaver Island,** the high, round islet with some trees lying 300 yards northward of Johns Island. Or, when ½ mile or more southward of Johns Island, steer 355° true (N by E mag.) so as to pass 150 yards eastward of Johns Island and 125 yards westward of the western bare rocks of **Knowles Rocks.** A ledge, partly bare at half tide, extends 225 yards northeastward from the north end of **Johns Island.**

McFarling Cove is in the northwestern side of the bay northward and northwestward of Davis Island; a steep hill about 150 feet high is on the western shore of the cove. There is good anchorage for a small vessel about 300 yards northward, or in mid-channel northwestward, from the north end of Davis Island, in 4 to 6 fathoms.

McFarling Ledges lie 450 to 800 yards northward of Davis Island and 300 to 500 yards from the western shore. At the north end is a rock covered at half tide, and at the west end is a rock bare at low water. A red buoy marks the south end.

Digitized by Google

The Gut (described with Damariscotta River) is a thoroughfare connecting McFarling Cove with Damariscotta River. It has a depth of 2 feet at low water.

To enter McFarling Cove steer 273° true (WNW¼W mag.) with the south end of Beaver Island astern, which leads midway between Corvette Ledge buoy and McFarling Ledges buoy and 250 yards northward of Davis Island.

Johns River extends northward about 2 miles above McFarling Cove, and separates into two branches, the eastern, **Foster Cove**, the western, **Western Branch**. **Robinson Cove** makes into the western shore of Johns River above High Island. There is good anchorage in the river southeastward and eastward of Clarke Point, in 3 to 4 fathoms. The river is little used.

Thread of Life is a narrow, deep channel lying between Thread of Life Ledges and Crow Island on the east and the southern part of Rutherford Island and Turnip Island on the west. It is used by small local vessels entering Johns Bay from westward or from Damariscotta River. **Thrumbcap Island** is partly wooded in its northern part, **Thread of Life Ledges** are bare or grassy islets, **Turnip Island** has several houses, and **Crow Island** has a few trees. A shelving ledge, awash at low water at its south end, extends 300 yards southward from **Hay Island**; the latter has some trees on its south end, and there is a wharf and large hotel westward of it.

To pass through Thread of Life from westward, steer 61° true (E by N mag.) for the north end of Thrumbcap Island with Ram Island lighthouse astern and pass 400 yards southward of **The Bulldog** (covered at half tide) and 500 yards southward of the rock covered at high water lying ¼ mile eastward of the south end of Inner Heron Island. When about 400 yards from Thrumbcap Island, steer 15° true (NNE ⅞ E mag.) and pass 200 yards westward of Thread of Life Ledges and 100 yards eastward of Turnip Island. Then keep in mid-channel and pass into Johns Bay about 100 yards westward and northward of a red buoy lying about 200 yards northward of Crow Island, between it and a black buoy northward of it.

Directions, Johns Bay.—Stand up the middle of the bay on a 349° true (N ½ E mag.) course, heading for the eastern end of High Island, and pass 300 yards westward of Johns Island and the same distance off the eastern shore northward of Pemaquid Harbor. Then keep in mid-channel until abreast High Island, and then pass about 50 yards westward of a red spar buoy. Anchor near mid-river, about ¼ mile northeastward of the buoy, in 3 to 4 fathoms.

DAMARISCOTTA RIVER.

The entrance to this river (chart 313) is about 3 miles westward of Pemaquid Point lighthouse and 1 mile northeastward of Ram Island lighthouse. From its mouth the river trends in a general north-northeast direction for 14 miles to the towns of Damariscotta and Newcastle, at the head of navigation. It is navigable to these towns for vessels of 18 feet draft at high water, but the tidal currents are strong, and, although some of the dangers are marked by buoys, strangers should not pass above The Narrows without a pilot.

The channel of the river is crooked, and in many places, owing to islands and ledges, very narrow; for a distance of 11 miles above the

Digitized by Google

mouth of the river a least depth of 5 fathoms may be carried in the channel; above this the water shoals gradually to 9 feet at low water just below the town of Damariscotta, and this depth can be carried to the town.

The islands and shoals southwestward of the entrance are described with Boothbay Harbor and Linekin Bay.

Little River, on the west side of the entrance, has some cottages and float landings; the channel is narrow and unmarked and suitable only for small craft.

Inner Heron Island, on the eastern side of the entrance to Damariscotta River, is thickly wooded, and has a prominent hotel on the top of the hill at the north end. There is a post village (**Heron Island**) on the island and a steamer landing on the northeast side with a depth of about 12 feet at the end. Boats going to the wharf must avoid the reef, bare at half tide, extending northward from the island to a red buoy.

Inner Heron Island Ledge, ¼ mile southwestward of the south end of Inner Heron Island, is bare at low water and marked on the southwest side by a red buoy. **The Bulldog**, 300 yards southward of the island, is bare at half tide. The rock 350 yards southeastward of the island is bare a little after high water. There are other unmarked dangers between Inner Heron Island and the eastern shore, and this passage should not be used by strangers.

Christmas Cove is an anchorage for small craft or a very small vessel on the eastern side of the entrance, ¾ mile north-northeastward of Inner Heron Island. The narrow entrance to the cove proper is midway between two bare rocks, the one on the southeast side being marked by a tripod beacon. A black spindle marks the north side of the channel just inside the entrance and a red spindle marks the point of a ledge near the south side westward of the steamboat landing. The anchorage with best swinging room is in the middle of the cove off the landing in 4 fathoms.

Christmas is a post village and summer resort on the eastern side of the cove. The steamer landing is said to have a depth of about 15 feet at the end. A large hotel is prominent. There is also a wharf with a depth of about 10 feet on Johns Bay, on the eastern side of the village. To enter Christmas Cove enter in mid-harbor, pass midway between the tripod beacon and the outer spindle and northward of the inner spindle.

South Bristol is a village and summer resort on the east side of Damariscotta River 2½ miles above the entrance. The steamer landing has a depth of about 9 feet at the end, but the depth in the approach is only about 6 feet, and the best water leads midway between a bare rock and the south shore.

The Gut is a thoroughfare connecting Damariscotta River at South Bristol with McFarling Cove and Johns Bay. The channel has been improved by dredging to a width of 25 feet and depth of 2 feet at low water in the vicinity of the drawbridge, where the channel has its least depth. The bridge has a single draw opening about 28 feet wide. Boats after passing through the bridge from eastward must haul southward to avoid a ledge on the north side just westward of the bridge.

Digitized by Google

East Boothbay is a village on the west bank of the river, about 3 miles above its mouth; vessels bound up the river and waiting for a favorable wind or tide usually anchor here, and strangers take a pilot if one has not been taken off the entrance. The steamer wharf has a depth of about 8 feet, and some dredging to this depth has been done off the wharves. There are shipyards for building wooden vessels. **Kelp Ledge,** just south of the approach to the wharves and 150 yards from the eastern shore, is bare at low water and unmarked.

At **The Narrows,** 1⅜ miles above East Boothbay, the channel is contracted to a width of 100 to 150 yards, and the tidal currents are strong with swirls. **Eastern Ledge,** extending 100 yards from the eastern shore, is a rock with 3 feet over it, and is marked at its southwest end by a red buoy. On the west side of The Narrows is a ledge, mostly sunken, extending 250 yards southwestward and 75 yards eastward from **Fort Point.** There are other submerged ledges in this vicinity.

Seal Cove and **Long Cove,** on the east side, just above The Narrows, have many unmarked dangers and are seldom entered.

Clark Cove, on the east side, 2½ miles above The Narrows, is a broad bight, shoal near the shores. There is a steamer landing on the end of the point ⅜ mile southeastward of **McGuire Point.** The long ice-house wharf, northward of the steamer wharf, is in ruins.

Pleasant Cove is on the western shore of the river, opposite Clark Cove, and makes in nearly 1½ miles southwestward. There is good anchorage in the mouth of this cove just northwestward of Carlisle Point, in 2½ to 5 fathoms, soft bottom. **Pleasant Cove Ledges,** northward of the cove, are covered at high water. There are no wharves in the cove.

Pooles Landing is a steamer wharf on the west side of the river ⅝ mile northward of Pleasant Cove Ledges. There is a grassy islet 400 yards northeastward of the wharf.

Damariscotta, on the east bank, and **Newcastle,** on the west bank of the river, 14 miles above its mouth, are connected by a fixed bridge. They are on a branch of the Maine Central Railroad. Vessels of 18 feet draft can go to the wharves at either place at high water. The usual draft of vessels loading here is 10 feet. There is 8 to 10 feet alongside the wharves.

Anchorages.—Vessels bound into the river usually go as far as Meadow Cove, just above East Boothbay, where there is good anchorage in 5 to 8 fathoms, keeping 150 yards from the shore. This is as far as a stranger should attempt to go in a vessel without a pilot. Above The Narrows vessels can anchor anywhere in the channel where the bottom and depth are suitable.

Communication.—There is steamer communication from Boothbay Harbor to all landings in the river. Damariscotta and Newcastle have railroad communication.

Pilots can be found at Boothbay and at East Boothbay. The vessels ordinarily loading here sail up the river with a favorable wind and tide.

Supplies.—Gasoline and provisions can be found at any of the villages. Water can be had on the wharf at Damariscotta.

Ice closes the river for a distance of 8 miles below Damariscotta during January, February, and March.

Digitized by Google

Currents.—The tidal currents have considerable velocity. The ebb lasts about two hours after low water, in the upper part of the river, and is usually stronger than the flood. The currents follow the general direction of the channel.

Tides.—The mean rise and fall of tides is about 9 feet.

DIRECTIONS, DAMARISCOTTA RIVER.

This region has many rocks and ledges, and very broken bottom, and has not been examined by means of a wire drag. Extreme caution is necessary.

Directions for approaching from eastward are given in section 9, page 53.

Approaching from southward, pass eastward of Pumpkin Island and the islands off the entrance, giving them a berth of 1¼ miles. Pass ⅜ mile southwestward of Thrumbcap Island, steer 299° true (NW mag.) and pass about 400 yards southward and westward of Inner Heron Island Ledge red buoy. Or, coming from Fisherman Island Passage, steer 51° true (ENE mag.) for the south end of Inner Heron Island, with Ram Island lighthouse astern, and pass about 400 yards southward and eastward of the black buoy off Little River.

Enter the river about midway between the black buoy and Inner Heron Island Ledge red buoy, and steer 6° true (NNE mag.) in mid-river for 1½ miles above Inner Heron Island. Pass westward of the red buoy off the entrance to South Bristol, give Farnum Point on the west side, a berth of 300 yards, and when it is abeam change the course to 327° true (N by W⅜W mag.), keeping about the middle of the river. Pass eastward of Montgomery Point black buoy and haul in for the western side of the channel off Meadow Cove; anchor in 5 to 8 fathoms. Small craft should have no trouble in going to the head with the aid of chart 313. The best time is on a rising tide.

BOOTHBAY HARBOR AND LINEKIN BAY

(chart 314) are included between Linekin Neck on the east and Southport Island on the west. They form the approach to the town of Boothbay Harbor and numerous smaller summer resorts. They are frequented by many vessels, and by a large number of fishing boats and pleasure craft in summer.

Boothbay Harbor is one of the best anchorages on the coast of Maine, and is much used as a harbor of refugee by all classes of vessels. It lies 14 miles northwestward of Monhegan Island and 9 miles northeastward of Seguin Island, and is marked at its eastern and western entrances by **Ram Island lighthouse** and **The Cuckolds lighthouse**, respectively. Lying south of the entrance are several islands and a number of rocks and ledges. The entrance between Linekin Neck on the east and Cape Newagen on the west is 2⅝ miles wide.

Channels.—There are three channels by which to approach the harbor. Fisherman Island Passage has a depth sufficient for the largest vessels, but there are some unmarked spots with a least depth of 13 feet, lying northwestward and westward of Ram Island, and the bottom is very broken; the passage is not recommended for a greater

Digitized by Google

draft than about 18 feet at low water. The channel westward of Squirrel Island has a depth sufficient for the largest vessels, but there are unmarked spots with from 19 to 25 feet nearly in the middle of the channel between Squirrel and Burnt Islands. The channel from southward, leading east of Squirrel Island, leads in the deepest water, and 8 fathoms can be taken up to the anchorage.

Islands and rocks off Boothbay Harbor.—Islands and rocks extend 4 miles south-southeastward and 7 miles southwestward from the southwest end of Linekin Neck. The ground is very broken, rocks rising abruptly from deep water, and has not been examined by the means of a wire drag. Vessels should therefore avoid crossing this area. A gas and bell buoy is placed at the southwest end of the broken ground, and deep-draft vessels passing along the coast should pass outside of it.

Bantam Rock, the most southerly visible danger, is 1⅜ miles southwestward of the south end of Damiscove Island. It is bare at low water, and marked on the southwest side by a red bouy.

Damiscove Island is 1¾ miles long, bare except at the north end, which is wooded, and nearly divided in the middle. Damiscove Harbor, at the south end, is used as a small-boat harbor by local fishermen. There is a Coast Guard station on the west side of the harbor. The Motions, extending ¼ mile south-southwestward of the southwest end of Damiscove Island, is nearly awash at low water, and marked off the end by a black buoy.

Fisherman Island, northeastward of Damiscove Island, is bare except for a few trees on the south end, and two inconspicuous houses on the west side.

Ram Island, on the south side of Fisherman Island Passage, is a grassy island, marked on the northwest side by Ram Island Lighthouse. The lighthouse is a tower with a gray base and white top. The light is fixed red, with two white sectors, bearing between 27° true (NE mag.) and 49° true (ENE mag.), and between 256° true (W ¼ N mag.) and 263° true (W by N mag.), 36 feet above the water, and visible 11 miles. The fog signal is a bell (1 stroke every 20 seconds).

The Hypocrites are two low bare rocks southeastward of Fisherman Island. White Islands, ¾ mile farther southeastward, are two high round islands with a patch of woods in the center of each.

The Cuckolds are two grassy islets off Cape Newagen, on the west side of the entrance of Boothbay Harbor. The easterly islet is marked by **The Cuckolds lighthouse**, a white tower on a dwelling. The light is group flashing white (flash 0.3 second, eclipse 1.7 seconds, flash 0.3 second, eclipse 3.7 seconds), 59 feet above the water, and visible 13 miles. The fog signal is a reed horn (blast 3 seconds, silent 17 seconds).

Cape Harbor is a harbor for small craft between **Cape Island** (wooded in the center) and **Cape Newagen**. It is used mostly by local fishermen. **Newagen** is a post village on the harbor. There are landings for small craft. There are two entrances to the harbor; the easterly, leading between **The Ark** and Cape Newagen, is said to have a depth of only about 2 feet at low water. The main entrance is from westward, and has a depth of about 10 feet. The depths inside are 6 to 10 feet.

Digitized by Google

Squirrel Island, in the middle of the entrance of Boothbay Harbor, is an important summer resort. It is wooded and has many cottages visible. There is a steamer landing (depth 15 feet or more) and landings for small craft in the northerly of two coves on the west side. **Squirrel Cove**, the southerly, is sometimes used as an anchorage by small craft. A beacon marks the ledge at the south side of the entrance.

Linekin Bay.—This bay lies northeastward of Squirrel Island, between LINEKIN NECK and Spruce Point. The principal dangers are buoyed, and good anchorage can be selected, the depths being 10 to 12 fathoms in the lower part of the bay and 5 to 6 in the upper. There are several summer resorts and landings. SPRUCE POINT LEDGES, bare at low water, lie on the northern side of the entrance, and are marked by two buoys, a black at the south end and a red at the north end. The better entrance is between the black buoy and Negro Island. In the narrow entrance between the red buoy and Spruce Point, give the point a berth of over 150 yards. A 26° true (NE ¼ N mag.) course with the southeast point of Squirrel Island astern will lead to the head of Linekin Bay.

OCEAN POINT is a summer resort on the south side of the entrance to Linekin Bay. The steamer wharf is about ⅜ mile eastward of NEGRO ISLAND, and has a depth of 10 feet. There is a float landing alongside. This is the principal wharf in Linekin Bay, but there are several other small summer resorts and float landings. The most important are LINEKIN on the east side, WALL POINT on the west side of Linekin Bay and the north side of Lewis Cove, and BAYVILLE and MURRAY HILL at the head. All have communication by boat with Boothbay Harbor in summer.

The visible dangers of Linekin Bay inside Spruce Point Ledges are as follows: INDEPENDENCE ISLAND, wooded and with a house in the center; HOLBROOK LEDGE, bare at low water and marked on its west side by a red buoy; SEAL ROCKS, bare at half tide and marked on its east side by a black buoy; a ledge on the east side surrounding an islet with several trees, and marked at the southwest end by a red buoy; and FISH HAWK ISLET, having several trees and a ledge bare at half tide, extending southward. The narrow channel westward of Seal Rocks should be used with caution. There are numerous unmarked rocks at the head, in the vicinity of Bayville and Murray Hill landings.

Spruce Point is wooded, and has a wharf at the southwest end with a depth of 13 feet.

Cove Island (locally known as **Capitol Island**) is a summer resort and post office (**Capitol**). Many cottages are visible. There is a steamer wharf at the north end with a depth of about 10 feet.

Burnt Island is partly wooded and marked on the southeast side by a lighthouse (white tower with covered way to a dwelling).

Mouse Island, northward of Burnt Island, has a wharf on the north side with a depth of about 12 feet. The cove westward of it and just southward of the entrance to Townsend Gut has a wharf with ample depth.

Tumbler Island, on the east side of the entrance to Boothbay Harbor, is low and covered with scattered trees. The passage between it and the shore eastward should not be used by strangers.

Digitized by Google

Boothbay Harbor is a town on the inner harbor. The wharves have depths of 4 to 13 feet; the deepest draft going to the town is 18 feet. All kinds of supplies are obtainable. There is a public float landing on the northwest side, westward of the larger steamer wharf. The anchorage for small craft is on the northwest side, inside of McFarland Island, and has been dredged to a depth of about 11 feet. **McFarland Island** has a wharf and several buildings. A footbridge with a small draw crosses the head of the harbor.

Communication.—Boothbay Harbor and all of the other resorts in this vicinity have steamer communication with Bath and other points on the Kennebec River as far as Augusta. The steamers run through the inside passage and stop at all landings en route. There is also communication from Boothbay Harbor to the landings on the Damariscotta and Sheepscot Rivers and to the principal towns along the coast between Portland and Rockland.

Anchorages.—The usual and best anchorage is northward of Tumbler Island and to the head of the harbor; there are 4 to 7 fathoms, good holding ground, anywhere in the channel above the island, the depth shoaling gradually toward the head of the harbor. The anchorage in the inner harbor off the town has a depth of 4 to 5 fathoms, but is limited in area and usually occupied by small craft and fishermen. The motor-boat anchorage on the northwest side of the inner harbor has a depth of 11 feet.

Towboats are seldom used by vessels entering or leaving the bay; they can be obtained from Bath.

Supplies.—Coal in limited quantity can be had at the wharves at Boothbay Harbor where the depths are about 13 feet at low water. Water can be taken alongside the wharves. Gasoline, provisions, and some ship chandlers stores can be obtained in the town. Gasoline and provisions are obtainable at most of the summer resorts.

Repairs.—There was no marine railway available for repairs in 1917. Ordinary repairs to machinery can be made.

Storm warnings are displayed from a staff on the eastern side of the harbor on Mount Pisgah.

Ice occasionally, in severe winters, obstructs navigation above Tumbler Island during February and March.

The tidal currents have little velocity in the harbor. The mean rise and fall of tides is 8.8 feet.

DIRECTIONS BOOTHBAY HARBOR.

This region is an area of very broken ground, shoals rising abruptly in places from deep water, and has not been examined by means of a wire drag. Vessels should therefore proceed with caution and should avoid crossing broken ground where the charted depth does not greatly exceed the draft.

From eastward, through Fisherman Island Passage.—Directions from Davis Strait to Fisherman Island Passage are given on page 53. Coming from any other point eastward the course can be shaped to a position ½ mile southward of Thrumbcap Island, taking care to avoid Moser Ledge and Pemaquid Ledge.

Passing ½ mile southward of Thrumbcap Island, steer 268° true (WNW ¾ W mag.), pass northward of the black bell buoy marking the Hypocrites and the black buoy northeastward of Ram Island

Digitized by Google

lighthouse, and about 350 yards northward of Ram Island lighthouse, and pass southward of the red buoys marking Gangway and Dictator Ledges.

Pass about 200 yards southward and westward of Dictator Ledge Buoy No. 2A, and steer 321° true (NNW mag.) for 1⅝ miles to a position 200 yards westward of the red buoy ½ mile eastward of Burnt Island lighthouse. Then steer 332° true (N by W mag.), and pass about 300 yards westward of Tumbler Island. Then steer about 17° true (NE by N mag.), and anchor in the middle of the harbor in 5 to 7 fathoms.

From westward.—The directions of section 10, page 53, reversed will lead northward of Seguin Island and to Cuckolds black bell buoy. Pass eastward of the buoy and about ¼ mile eastward of the Cuckholds lighthouse and steer 2° true (N by E¾E mag.) for Burnt Island lighthouse, passing about ¼ mile westward of Squirrel Island. When about ½ mile from the lighthouse and 300 yards westward of Squirrel Island Ledge red buoy, steer 23° true (NE½N mag.), passing 250 yards southeastward of a black buoy and to a position 400 yards east-southeastward of Burnt Island lighthouse. Then steer 351° true (N¾E mag.) for the eastern end of McKown Point to a position 300 yards westward of Tumbler Island. Then steer about 17° true (NE by N mag.) and anchor in the middle of the harbor in from 5 to 7 fathoms. These courses lead close to depths of 20 and 21 feet between Burnt and Squirrel Islands.

From southward.—Pass about ½ mile westward of Bantam Rock gas and whistling buoy and steer 2° true (N by E¾E mag.) for Burnt Island lighthouse and follow the directions in the preceding paragraph. This course passes 1 mile westward of Bantam Rock and ⅝ mile westward of an unmarked 11-foot rock.

From westward, eastward of Squirrel Island.—Pass eastward of Cuckolds black bell buoy and about ¼ mile southeastward of the lighthouse and steer 33° true (NE ⅜ E mag.). Follow the eastern side of Squirrel Island, giving it a berth of about ¼ mile, steer 332° true (N by W mag.), and pass about 200 yards westward of Tumbler Island Ledge red buoy, and about 300 yards westward of Tumbler Island. Then steer 17° true (NE by N mag.) and anchor in the middle of the harbor in 5 to 7 fathoms.

To enter the inner harbor off the town.—Pass about 200 yards northwestward of Tumbler Island and steer 29° true (NE mag.) for McFarland Island until a large bare ledge near the eastern shore is abeam distant about 250 yards. Then steer about 62° true (E by N mag.) into the inner harbor, passing southward of the black buoy southward of McFarland Island and another black buoy eastward of the island. The course can then be shaped to the wharves, or small craft may select anchorage on the northwest side northward of the inner black buoy in 10 to 13 feet.

INSIDE PASSAGE FROM BOOTHBAY HARBOR TO BATH.

This passage (chart 315a) is about 11 miles long and leads between the islands lying between Boothbay Harbor and the Kennebec River, forming an inland passage from Boothbay Harbor to Bath. The only vessels using this passage are the small steamers of 10 feet or less draft running from Boothbay Harbor to points on the Kennebec

Digitized by Google

River and small vessels owned in the vicinity. It is used considerably by small craft.

The channel is very narrow in places, has strong tidal currents, is much obstructed by rocks and shoals, and, although many of the dangers are marked, strangers should not attempt to pass through in vessels without a pilot. The passage leads through Townsend Gut, across Sheepscot River, and through Goose Rock Passage into Sassanoa River; about midway through Sassanoa River the channel crosses the southeastern part of Hockomock Bay and then continues through the Sassanoa River, coming out in the Kennebec River opposite the city of Bath. The least depth in the channel is about 10 feet, but local knowledge is necessary to carry the best water.

There are several summer resorts and other landings along the thoroughfare, at which the steamers running between Boothbay Harbor and Kennebec River points make landings.

Bridges.—Two bridges cross the thoroughfare. The one crossing Townsend Gut is a center pier draw with openings 45.5 feet wide. The one crossing Sassanoa River near its outlet into Kennebec River has a single opening 39 feet wide.

Ice.—The thoroughfare is usually closed by ice for about two months, but in mild winters has been known to be open all winter.

Townsend Gut is a narrow, crooked thoroughfare connecting Boothbay Harbor with Sheepscot River. There are unmarked rocks with little depth close to the channel.

Southport is a village and summer resort on the west side of Townsend Gut. There are two wharves at which steamers land, one just southward and the other ½ mile northward of the bridge.

Isle of Springs is a summer resort on Sweet Island, at the north end of Townsend Gut. The steamer landing, on the northeast side, has a depth of about 10 feet.

Sawyer Island is a steamer landing and summer resort on the west side of the island of that name. The wharf has a depth of about 10 feet, but there is a shoal 75 yards off its face with a depth of about 8 feet, usually marked at each end by a bush stake.

Goose Rock Passage leads from Sheepscot River into Sassanoa River northward of McMahan Island, and forms a part of the inside route. It has ample depth but is narrow in places; the principal dangers are marked.

Little Sheepscot River is a narrow passage leading from Sheepscot River into Sassanoa River westward of McMahan Island. There is a rock with a depth of about 1 foot at low water 100 yards westward of a red buoy marking the end of a ledge. The channel leads between the buoy and the rock. A steamer wharf on the east side of the channel has a depth of about 10 feet.

Sassanoa River is an estuary leading from Sheepscot River to Kennebec River, north of Georgetown and Arrowsic Islands. It has numerous coves and bays making off northward and southward, but none of them are of commercial importance. Near its western end the river is crossed by a drawbridge. The principal coves and bays making southward are **Robin Hood Cove, Riggs Cove, Hall Bay,** and **Back River,** the latter separating **Georgetown** and **Arrowsic Islands.** Northward is **Heal Cove** and **Hockomock Bay;** from the latter **Montseag** and **Brooking Bays** lead northward; the former separates Westport Island from the mainland, and joins the Sheepscot River at Wiscas-

Digitized by Google

set, through Back River. **Knubble Bay** is the broadest part of the river, after passing Robin Hood Cove and The Knubble, before entering Hockomock Bay when coming from eastward. **Great Hell Gate** is the crooked passage from Knubble Bay into Hockomock Bay. **Upper Hell Gate** is about 2 miles from the western entrance to the river; this is the narrowest part, and is only about 60 yards wide.

Riggsville (Robin Hood Landing) is a steamer landing and small settlement on the point on the south side of Riggs Cove. There is another steamer landing **(Westport)** on the east side of Sassanoa River and the west side of **Westport Island.**

Directions, Inside Passage, Boothbay Harbor to Bath.—This passage is narrow and crooked, has strong tidal currents, and local knowledge is necessary to carry the best water. Strangers in small vessels or yachts should take a pilot at Boothbay Harbor or Bath. With the aid of chart 315a and the following directions, strangers in small craft of 4 feet or less draft should be able to go through. The best time is on a rising tide.

The entrance to Townsend Gut can be approached either northward of Mouse Island or westward of Burnt and Mouse Islands. Pass midway between the red buoy at the southern entrance of Townsend Gut and the western shore and follow the western shore at a distance of about 100 feet for ⅜ mile until the channel expands, then head for the draw in the bridge, passing close to the end of the wharf just south of it. After passing through the bridge, follow a general mid-channel course and pass close to the end of the wharf on the west side ½ mile above. Keep in mid-channel for ⅜ mile above this wharf to avoid reefs on the south side, and pass between a spindle and a red buoy at the north end of Townsend Gut.

The generally used channel across Sheepscot River leads from the north end of Townsend Gut north-northwestward for 1¼ miles, passing between Indiantown and Spectacles Islands, past the wharf at Isle of Springs, and between Sweet and Sawyer Islands. It then turns sharply westward, leads 125 yards off the north end of Sweet Island, and between a tripod beacon and a small island northward of it. The course is then 236° true (WSW ½ W mag.) for ¾ mile, passing well northward of a red buoy and southward of a horizontally striped buoy, to a position 100 yards north-northwestward of a black bell buoy; then 215° true (SW ⅝ W mag.) for ⅜ mile, passing westward of Clous Ledge spindle and eastward of Whittum Island, to a position 75 yards northward of a spindle off North East Point, and then 245° true (W ¾ S mag.) for ½ mile, through the middle of Goose Rock Passage, to a position 75 yards northward of a black buoy.

The channel then leads westward, south of a red buoy well toward the south side of the channel, and then northwestward for ¼ mile and northward for 1⅝ miles to Great Hell Gate, following a general mid-channel course to avoid the dangers near the shores. Follow a mid-channel course through Great Hell Gate, except in the middle, where the channel leads 50 yards southward of a spindle, and at the north end, where it leads northward of a black buoy. Then steer 306° true (NW ⅝ N mag.) for ⅜ mile, to a position 125 yards northward of Castle Rock, and then haul northward for ⅝ mile and northwestward for ⅜ mile, being guided by the buoys, to the entrance of the narrow part of Sassanoa River.

Digitized by Google

The best water then favors the southwest side for ½ mile, passing westward of a red buoy, eastward of a spindle, and westward of a small islet 150 yards beyond the spindle. The channel leads between an islet on the west side and a red buoy on the east side ¼ mile beyond the spindle, and favors the east side through Upper Hell Gate, passing eastward of two black buoys. From this point to the bridge the channel leads between flats bare or nearly so at low water and is marked by buoys and spindles. After passing through the bridge the mid-channel is clear to the outlet into Kennebec River.

SHEEPSCOT RIVER

(shown on chart 314 and a portion on chart 315a), having its entrance about 5 miles northeastward of Seguin Island, between the Cuckolds and Griffith Head, is the approach to several small villages in the lower end and to the town of Wiscasset, 14 miles above the entrance. The channel has a depth of about 30 feet to Wiscasset and is navigable for small vessels at high water for about 4 miles above Wiscasset to the village of Sheepscot. The river is used by small passenger steamers, many small craft, and an occasional coasting vessel to Wiscasset or above. The deepest draft going to Wiscasset is about 20 feet.

The Cuckolds lighthouse and Cape Harbor, on the east side at the entrance, are described on page 169. There are rocks, bare and sunken, extending ½ mile westward of the point in this vicinity.

The Sisters, 1⅜ miles from the northwestern shore, at the entrance to Sheepscot River, are three small bare rocks with shoals surrounding them. The westerly rock is marked by a tripod beacon.

The Black Rocks, 1 mile from the northwestern shore of Sheepscot Bay at the entrance, are a group of three bare and several sunken rocks about ⅝ mile long. The southwesterly rock has 13 feet over it and there is a rock awash at high water 250 yards northeastward of it. The middle rock is 15 feet above high water and the northeasterly rock 10 feet above hight water. The channel between the Black Rocks and the black buoy, ⅜ mile northward has not been closely examined and should be used with caution. The area between the black buoy and the northern shore is very broken and should not be crossed.

Griffith Head, on the west side, at the entrance of Sheepscot River, is a white, rocky head, with a bare, rocky island 200 yards eastward. There is a horizontally striped buoy ⅜ mile off the island, marking **Griffith Head Ledge.**

Lower Mark Island, on the eastern side, just inside the entrance, is wooded and a good mark. A ledge, bare at low water, lies 150 to 350 yards eastward of the island.

Cat Ledges are a group of rocks, the higher ones bare, lying ½ to 1 mile northward of Lower Mark Island, the outer ones ⅜ mile from the eastern shore. The coves eastward of the ledges are foul and of no importance. There is a red buoy marking a reef with a depth of 23 feet ⅜ mile southwestward of Cat Ledges.

Herman Harbor is a long, narrow cove making northward on the western side of the river about 1½ miles above Griffith Head. It has good anchorage in 4 to 7 fathoms, but has a very narrow entrance between a bare ledge near the west shore and a dangerous reef, bare at low water, which extends 275 yards westward from the wooded

Digitized by Google

island on the eastern side of the entrance. There is a hotel and wharf on the west side near the middle of the harbor, and a small settlement and landings for small craft at the head. The best water in entering leads 100 yards eastward of the middle of the bare ledge on the west side at the entrance.

Five Islands Harbor (chart 315a) is a narrow passage between Five Islands and the western shore, forming a secure harbor for small craft, with 3 to 5 fathoms at low water. The main entrance is northward of the largest wooded island, between it and a bare rock. A rock with a depth of 10 feet in the middle of the entrance is marked by a horizontally striped buoy. The buoy can be passed close to on either side in entering. Boats can also enter the harbor from the northeastward, following the western shore, inside of all island and shoals. **Five Islands** is a small summer resort and post village on the western side of the harbor. It has steamer communication with Boothbay Harbor and Bath. The steamer wharf has a depth of about 12 feet.

Hendricks Harbor (chart 315a) is a cove on the eastern side of Sheepscot River, the entrance lying ⅜ mile southward of **Hendricks Head lighthouse** (white tower with a covered way to a dwelling). It is used only by small craft. The entrance has a depth of about 9 feet between ledges on either side, and the depths inside are 4 to 9 feet. To enter, pass close northward of a red spindle and close southward of a black spindle. **West Southport** is a post village on the east side of the harbor. There are landings for small craft.

Ebenecook Harbor is an excellent anchorage for vessels up to 20 feet draft. Its entrance lies about 1 mile above Hendricks Head lighthouse, on the eastern bank of the river, and leads between Dog Fish Head on the south and the Green Islands on the north. It is the first anchorage available for large vessels entering the river; but the entrance is narrow, and large sailing vessels require a fair wind when leaving the anchorage. The village of **West Southport** is near the southern end of the harbor. This end of the harbor should be avoided by strangers in vessels unless they employ a pilot. There are landings for small craft.

To enter Ebenecook Harbor, give the eastern shore of Sheepscot River a berth of over 300 yards for 1 mile above Hendricks Head lighthouse until up with **Dog Fish Head,** which is rocky and grass covered, with a low neck behind it. Pass about 125 yards northward of Dog Fish Head, and steer about 96° true (ESE mag.) between it and Green Islands, favoring, if anything, the southern side, until past the south point of Green Islands. Follow the southeast side of Green Islands at a distance of about 200 yards, and steer 74° true (E mag.) with the south point of the islands astern; anchor on this course near mid-harbor, or favoring the eastern shore, in 4 to 6 fathoms, soft bottom.

Extending northward from Ebenecook Harbor to Sawyer Island is a channel, affording good anchorage in places, which is used by small pleasure craft in summer, and is a part of the inside passage used by local vessels between Boothbay Harbor and Bath. Its northern part, and also the passages between the islands and ledges on its western side, require some local knowledge to insure safety. The principal islands and rocks are:

Digitized by Google

Green Islands are partly wooded; a rock, bare at low water, lies 200 yards northeastward of them, and is marked on its southeast side by a black buoy. A bare ledge lies between Green Islands and Boston Island, and a rock with 4 feet over it lies 250 yards westward of the ledge. **Boston Island** is high and grassy, and has several houses on top. **Spectacle Islands** are grassy, with some trees, and a bare rock lies 150 yards westward of their southwest end.

Townsend Gut, Sweet Island, and Sawyer Island, on the eastern side of Sheepscot River, and Little Sheepscot River and Goose Rock Passage, on the western side, are described under the heading "Inside Route, Boothbay Harbor to Bath," on page 173.

Bull Ledge, 1 mile northward of Hendricks Head lighthouse, is bare in one place at low water, and marked at the south end by a red buoy.

Middle Mark Island, a small, round, bare islet, is in the middle of a ledge ¼ mile long, and lies ¼ mile from the western shore and 1½ miles above Hendricks Head lighthouse. **Mark Island Ledge,** with 7 feet on it, lies 250 yards southwestward of the island. The main channel leads eastward of the island.

Powderhorn Island, low and grassy, is on the eastern side of the river 2 miles above Hendricks Head lighthouse. **Powderhorn South Ledge,** awash in places at low water, extends ¼ mile southward from the island, and is marked at its south end by a red buoy. There is a narrow channel between the buoy and the north end of **Harding Ledge.** The latter is sunken and is marked at its south end by a red buoy.

Powderhorn Ledge, with 4 feet on it, lies 200 to 350 yards northward of Powderhorn Island, and is marked on its northwest side by a red buoy.

Middle Ledge, lying 600 yards eastward of the southern side of the entrance to Goose Rock Passage, has a least-found depth of 10 feet, although less has been reported; it is marked on its southern side by a horizontally striped buoy.

Clous Ledge, lying ¼ mile eastward from **Whittum Island** (wooded) at the entrance to Goose Rock Passage, is awash at half tide and marked by a black spindle on the middle of the ledge and a black bell buoy off its northern end.

Four-foot Rock, on the west side of the channel about ¼ mile northward of Clous Ledge spindle, is marked on its southern side by a horizontally striped buoy.

Upper Mark Island is a low grassy ledge, from which a shoal extends 600 yards northward toward Hodgdon Ledge.

Ram Island Ledge, awash in spots at half tide, is on the east side of the channel and extends ⅜ mile in a north-northeasterly direction from Ram Island to the entrance to Back River. It is marked on its eastern side by a black spindle and a buoy, which are guides to the narrow channel leading northward from Ebenecook Harbor.

Back River is a shallow, narrow, and unmarked stream between Barter Island and the mainland. Its southern entrance is on the eastern side, 3¼ miles northward of Hendricks Head; its northern entrance is from Cross River. Local knowledge is necessary for its navigation. It is used only by small craft and an occasional lumber schooner. There is a wharf on the south end of Barter Island, just inside the entrance. A drawbridge with an opening 41 feet wide and

Digitized by Google

a headroom of 6.3 feet at high water crosses the river from Hodgdon Island to the south end of Barter Island.

Jewett, Long, and **Tarbox Coves** are unimportant coves on the west side of Sheepscot River westward of the entrance to Back River. **Tarbox Landing** is a steamer landing and small settlement just north of Tarbox Cove. **Hodgdon Ledge,** just southward of the wharf, is bare at half tide and marked on the southeast side by a black buoy.

Cross River empties into the east side of Sheepscot River 6¼ miles above Hendricks Head. It has a deep channel for 1¼ miles, but is seldom used.

Greenleaf Ledge, on the west side of Sheepscot River, just south of the entrance to Cross River, is bare at low water and marked by a black buoy. Shoals fill the bight from the buoy to the western shore.

Merrill Ledge, 2½ miles above the entrance to Cross River, is bare at low water in the middle; it is marked at the south end by a spindle and at the north end by a buoy. The channel leads westward of it.

Montseag Bay and **Back River** form a thoroughfare from Sassanoa River and Hockomoch Bay to Sheepscot River near Wiscasset. The channel is narrow and unmarked, and seldom used except by small local craft.

Wiscasset is a town on the west side of Sheepscot River 14 miles above the entrance. The principal wharf has a depth of 18 feet, and the deepest draft going to it is 20 feet. The town has railroad communication, and communication with Boothbay Harbor by steamer.

Sheepscot River above Wiscasset.—There is said to be a depth of about 10 feet at low water for 4 miles above Wiscasset to rapids in the river; the deepest draft going to the rapids are lumber scows up to 9 feet draft. Boats of about 4 feet draft can go through the rapids at high water slack and for about 3 miles above. **Sheepscot** is a village just above the rapids. The channel is unmarked above Wiscasset, and local knowledge is necessary for its navigation. Drawbridges cross the river at Wiscasset, at a point 1 mile above Wiscasset, and at Sheepscot. The bridge at Wiscasset has a draw opening 47 feet wide, the second bridge a draw opening 40 feet wide, and the third a draw opening 28 feet wide.

Supplies.—Gasoline and provisions are obtainable at Wiscasset, and usually at Five Islands and Isle of Springs. Boothbay Harbor and Bath are the nearest places where coal and water can be obtained.

Anchorages.—Ebenecook Harbor is the first anchorage available for large vessels entering the river. Above Stover Ledge, anchorage can be had in the channel, the depths being generally 12 fathoms or less. Colby Cove, in the west bank about 2¼ miles above Cross River, affords anchorage in 8 to 10 fathoms; Merrill Ledge spindle is northeastward of the anchorage. The anchorage at Wiscasset is below the bridge and near the wharves of the town. Above Wiscasset, vessels bound to Sheepscot Falls anchor anywhere in the channel where the bottom and depth are suitable.

Pilots can usually be had from the settlements near the entrance or from fishing boats. Vessels bound to Sheepscot Falls generally take a pilot at Wiscasset.

Towboats are sometimes used by vessels bound up the river; they can be had from Bath. Vessels bound above Wiscasset generally tow.

Ice does not usually interfere with navigation below Wiscasset. The river above Wiscasset is usually closed in winter.

Digitized by Google

Tides.—The mean rise and fall of tides varies from 8.5 feet at the entrance to 9.4 feet at Wiscasset.

Currents.—The currents in the river generally set in the direction of the channel and have considerable velocity in the narrow parts. At the entrance of Cross River the flood sets onto Quarry Point. The ebb sets onto Clough Point.

DIRECTIONS, SHEEPSCOT RIVER.

The channel in Sheepscot River is deep, and the principal dangers are buoyed. It is a region of rocks and ledges, many of them rising abruptly from deep water and has not been examined by means of a wire drag. There are several unmarked rocky shoals with depths of 3¼ to 5 fathoms in the middle of the river from Bull Ledge southward. Other ledges with less depth than charted have been reported, and undoubtedly exist. The river should therefore be navigated by vessels with extreme caution.

From eastward.—Having come from Boothbay Harbor or Fisherman Island Passage, pass close to Cuckolds black bell buoy and steer 265° true (W by N mag.) for 1 mile until Lower Mark Island is abeam, distant 1¼ miles. Then steer 331° true (N by W mag.) for 1¾ miles and pass ½ mile westward of Lower Mark Island and about 250 yards westward of Cat Ledges buoy. When about ¼ mile northwestward of this buoy, steer 2° true (N by E ⅝ E mag.) for nearly 1½ miles and pass 350 yards westward of Hendricks Head lighthouse.

Or, coming from southward, pass ½ mile westward of Bantam Rock gas and whistling buoy and steer 339° true (N ⅜ W mag.) for 6 miles, passing 1⅝ miles westward of The Cuckolds lighthouse and to a position ⅞ miles westward of Lower Mark Island. Then steer 2° true (N by E ⅝ E mag.) for about 2 miles, passing ¼ mile westward of Cat Ledges buoy and 350 yards westward of Hendricks Head lighthouse. Then follow the directions in section 2.

From westward.—Pass 1½ miles southward of Seguin lighthouse and steer 37° true (NE ¾ E mag.) for The Cuckolds lighthouse to a position ⅝ mile southeastward of Tom Rock buoy. Then steer 6° true (NNE mag.) for 3¼ miles, heading for Hendricks Head lighthouse until The Cuckolds lighthouse is abeam, distant 2 miles. Then steer 2° true (N by E ⅝ E mag.) for nearly 2½ miles, and pass ⅞ mile westward of Lower Mark Island, ¼ mile westward of Cat Ledges buoy, and 350 yards westward of Hendricks Head lighthouse.

Or, the directions reversed of section 10, page 53, will lead northward of Seguin Island and The Sisters. Pass ¼ mile northward of The Sisters tripod beacon, and bring it astern on a 20° true (NE ¾ N mag.) course. Keep this course for nearly 3 miles, passing ⅜ mile eastward of Black Rocks and Griffith Head Ledge buoy, and to a position ⅞ mile westward of Lower Mark Island. Then steer 2° true (N by E ⅝ E mag.) for about 2 miles, passing ¼ mile westward of Cat Ledges buoy and 350 yards westward of Hendricks Head lighthouse. Then follow the directions in section 2.

Hendricks Head to Wiscasset.—Passing 350 yards westward of Hendricks Head lighthouse, steer 2° true (N by E ⅝ E mag.) for 4½ miles, passing eastward of Bull Ledge buoy, Middle Mark Island at a distance of 250 yards, Middle Ledge buoy, Clous Ledge spindle and bell buoy, Four-foot Rock buoy, Upper Mark Island at a dis-

Digitized by Google

tance of 350 yards, and Hodgdon Ledge buoy; and passing westward of Harding Ledge buoy, Powderhorn Island, Powderhorn Ledge buoy at a distance of 175 yards, Ram Island, Barter Island buoy, and Stover Ledge buoy at a distance of 200 yards.

From a mid-river position ¾ mile above Stover Ledge buoy, steer 20° true (NE ¾ N mag.) for 2 miles to the entrance of the narrow part of the river between Quarry Point and Fowle Point. Then steer more northward and follow a mid-river course for 2 miles. Pass westward of the spindle and red buoy marking the southerly and northerly ends of Merrill Ledge, and when about ¾ mile above the buoy, favor slightly the eastern bank to avoid the shoal on the western side above Hilton Point. Then keep in mid-river until up with Clough Point, where the river makes a sharp bend westward.

Pass about 200 yards eastward and 100 yards northeastward of Clough Point buoy, and steer 299° true (NW mag.), passing about 150 yards off the south end of Davis Island (marked by earthworks and a blockhouse). Pass southward and about 100 yards westward of Middle Ground red buoy, and steer about 344° true (N mag.) for wharves. Anchorage may be had about midway between the buoy and the wharves, in 5 to 7 fathoms.

KENNEBEC RIVER

(charts 314, 288, and 289) is northward of Seguin Island and 20 miles eastward of the entrance to Portland Harbor. It is the approach to the cities of Bath and Augusta, the towns of Woolwich, Richmond, and Gardiner, and numerous smaller villages and summer resorts. The river has considerable trade in vessels, the deepest draft being about 21 feet to Bath and 14 feet to Augusta.

The least depth is about 28 feet in a natural channel to Bath, 12 miles above the entrance, but there are unmarked rocky shoals with less depth close to the channel. From Bath to the south end of Swan Island, 20 miles above the entrance, the river has a natural channel with a depth of at least 17 feet. From this point to Gardiner, 33 miles above the entrance, the channel has been improved by dredging where necessary to a depth of 16 feet and width of 150 feet, and from Gardiner to Augusta, at the head of navigation, 39 miles above the entrance, it has been improved by dredging where necessary to a depth of 11 feet and width of 125 feet. The main 16-foot channel leads eastward of Swan Island. A channel has also been dredged westward of the island to a depth of 12 feet and width of 100 feet.

Kennebec River formerly had a large trade in ice, and there were numerous ice houses and wharves on the river. In 1917 the ice houses were unused, and the wharves generally in ruins or in bad repair. Considerable lumbering is done on the river above Augusta, and numerous log booms are found in the river between Gardiner and Augusta.

Sprague and **Morse Rivers**, between Cape Small and the entrance of Kennebec River, are nearly bare at low water at their entrances, and seldom entered even by local boats.

Islands and rocks off the entrance.—The entrance to the river is somewhat obstructed by an area of islands and rocks and very broken ground, not closely examined, extending southward for a distance of 4½ miles from the entrance. The most southerly known danger is

Digitized by Google

SEGUIN SSW LEDGE, having a least found depth of 6 fathoms and lying 3/8 mile southeastward of Seguin Island red whistling buoy. The other dangers outside of Seguin Island are MILE LEDGE, having a least found depth of 10 feet and marked by a horizontally striped buoy, and CAMEL GROUND, lying 1 mile west-southwestward of Seguin Island lighthouse, and having a least found depth of 3½ fathoms; Camel Ground is unmarked, and the sea breaks on it in heavy weather.

SEGUIN ISLAND is 145 feet high, bare of trees, and marked on the top by a lighthouse; it is the most prominent mark in this vicinity.

SEGUIN ISLAND LIGHTHOUSE is a white cylindrical tower connected with dwelling. The light is fixed white, 180 feet above the water, and visible 20 miles. The fog signal is a steam whistle (blast 5 seconds, silent 15 seconds).

ELLINGWOOD ROCK, 400 yards northward of the north end of Seguin Island, is a bare islet about 20 feet high.

SEGUIN LEDGES, ½ mile northeastward of Ellingwood Rock, are about 5 feet high, and have submerged ledges extending 300 yards northeastward and southwestward from the bare ledge.

POND ISLAND BAR is the rocky shoal lying southward and southwestward of Pond Island. It has depths ranging from 5 to 21 feet over it, and in heavy gales is covered with breakers. A black bell buoy marks the southeastern end of the bar and lies 5/8 mile southward of Pond Island lighthouse. Vessels should not pass between this buoy and Pond Island.

POND ISLAND, a bare island on the west side of the entrance to Kennebec River, is about 30 feet high and marked on the top by a lighthouse.

POND ISLAND LIGHTHOUSE is a white tower connected with dwelling. The light is fixed white, 52 feet above the water, and visible 10 miles. The fog signal is a bell (one stroke every 10 seconds).

WOOD ISLAND, ¼ mile westward of Pond Island, is high and wooded on the west side. The channel between Wood and Pond Islands should not be used by strangers.

WHALES BACK is a bare rock about 8 feet high on the eastern side of the entrance to the river and nearly 5/8 mile eastward of Pond Island. A shoal extends about 100 yards southward from it. **Salter Island**, northward of Whales Back, is wooded.

Stage Island Bay, Sagadahoc Bay, and **Heals Eddy**, on the east side of Kennebec River at the entrance, are shoal inside, have no wharves, and are of little importance.

South and **North Sugar Loaf** are high, rounded, bare, rocky islets in the middle of Kennebec River just inside the entrance. A ledge extends 100 yards southward from South Sugar Loaf; **Jack Rock**, bare at low water and marked by a spindle, is near the end of a ledge which extends 125 yards northeastward from South Sugar Loaf. Ledges extend 150 yards southward and 125 yards northwestward from North Sugar Loaf.

Popham Beach is a summer resort on the west side of Kennebec River just inside the entrance. Steamers between Boston and Augusta stop here. The steamer landing is just northward of the Coast Guard station, and has a depth of about 15 feet. There are also two wharves westward of Fort Popham, with depths of about 7 feet.

Digitized by Google

Fort Popham is an unused stone fort. Just southward of it is a light (white pyramidal tower) and a fog bell.

Bay Point is a summer resort on the east side of Kennebec River, east-southeastward of Fort Popham. The steamer wharf has a depth of about 15 feet.

Gilbert Head is high and prominent, wooded except near the end, and marked by a single house.

Shag Rock, on the eastern side of the channel, between Gilbert Head and Cox Head, is awash at high water and marked by a tripod beacon.

Cox Head is high and prominent. There is a steamer landing with a depth of 10 feet on the point at the south end.

Todd Bay, on the east side of Kennebec River northeastward of Cox Head, is almost entirely bare at low water. There is a quarry on the east side, from which stone is taken on barges at high water.

Perkins Island, on the east side of the main channel 3 miles above the entrance, is wooded on the south end and bare on the north end. Perkins Island lighthouse, on the west side, is a white tower.

Parkers Head is a village on the west side of the river westward of a prominent headland of that name. The approach to the village is by a narrow channel, shoaling gradually to about 3 feet at the wharf. The channel to the wharf is sometimes marked by bush stakes. The river steamers land at a wharf on the main channel of the river, about ¼ mile northward of the southeast end of Parkers Head and about 1 mile from the village.

Back River is a narrow, crooked, and unmarked thoroughfare connecting Kennebec River with Sassanoa River and Hockomock Bay. It is bare at low water near the north end, and little used. A fixed bridge crosses the thoroughfare near the middle; it is said to have a headroom of about 8 feet at half tide. **West Georgetown** is a steamer landing on the east side of Back River, just inside its southern entrance. It has a depth of about 10 feet.

Seal Rock, on the west side of the channel at the upper end of Parkers Flats, is awash at high water. There is a black buoy northeastward of it.

Phippsburg is a village on the west side of Kennebec River 5½ miles above the entrance. The steamer wharf (northerly) has a depth of about 8 feet, and the other wharf a greater depth. There is a yard for building wooden vessels.

Goat Island, northeastward of Phippsburg, is wooded, and the smaller islands near it are bare and grassy.

Pettis Rocks, in the middle of the river 6½ miles above the entrance, are awash in the highest part at extreme high water and marked at the south end by a spindle. **Ram Island**, just northward of Pettis Rocks, is low and grassy, and marked near the middle by a tripod beacon. A reef, bare at low water, extends nearly 100 yards northwestward of the island. Vessels passing westward of the island frequently ground on this reef.

Winnegance is a village on **Winnegance Creek**, ½ mile from the main channel of Kennebec River. The channel is shoal and navigable only by small craft.

Bath is a city on the west side of Kennebec River 12 miles above the entrance. It has important shipbuilding industries and considerable trade by water. There are depths of 10 to 25 feet at the wharves,

Digitized by Google

the deepest being at the coal wharf. Small craft land at a public float landing on the south side of a wharf with red buildings and just northward of a water-pipe sign. Directions for anchoring off the city are given following.

Sassanoa River, leading eastward from Kennebec River opposite the south end of Bath, is described beginning on page 173.

Woolwich is a village opposite Bath. It is connected with Bath by ferry. Railroad freight and passenger cars are also ferried across the river here.

Two miles above Bath the channel of Kennebec River is divided by **Lines Island** into two channels, **East Branch** and **West Branch.** East Branch is used by local boats up to 7 feet draft at low water, but the channel is narrow and unmarked, leads between reefs on either side, and is not safe for strangers. West Branch is deep and clear and is generally used. A rock, bare at low water, 50 yards off the southwest end of Lines Island, should be avoided.

Chops is the narrow passage between two headlands ¾ mile above Lines Island. Two steel towers supporting a telegraph line across the channel are prominent. There is ample headroom under the wires.

Merrymeeting Bay is a shoal bay making westward from Kennebec River 17 miles above the entrance. It is the approach to the towns of **Brunswick,** on the **Androscoggin River,** and **Bowdoinham,** on the **Cathance River,** 8 and 4 miles, respectively, above Kennebec River. Boats of 7 feet draft can go to Brunswick and 12 feet to Bowdoinham at high water. The channels are narrow and unmarked, except by a few bush stakes, and local knowledge is necessary for their navigation. The rise and fall of tides varies from 3 to 5 feet at Brunswick, depending on the stage of the river. A fixed railroad bridge with headroom of 20 feet at high water crosses the river just below Brunswick.

The channel west of Swan Island, dredged to a depth of 12 feet and width of 125 feet, is marked by buoys. It is used principally by the passenger steamers drawing up to 10 feet making landings at Richmond; vessels of this draft do not use it at low water. The principally used channel leads eastward of the island.

Richmond is a town on the west bank of the river 28 miles above the entrance. The deepest draft coming here is 14 feet. The steamer wharf is on the channel leading westward of Swan Island, and has a depth of about 12 feet.

Dresden Landing (Cedar Grove) is a small settlement and steamer landing on the east side 2 miles above the north end of Swan Island.

South Gardiner is a village on the west side of the river 30 miles above the entrance. There are lumber mills and wharves with depths of 8 or 9 feet.

Gardiner is a town on the west side of Kennebec River 33½ miles above the entrance. The deepest draft coming here is about 14 feet. The wharves have depths of 6 to 17 feet.

Randolph is a village on the east side, opposite Gardiner. It is connected with Gardiner by a drawbridge having a center pier draw, with openings 68 feet wide on either side. The west opening was obstructed in 1917.

Hallowell is a town on the west side of the river 37 miles above the entrance.

Digitized by Google

Augusta, at the head of navigation on Kennebec River, 39 miles above the entrance, is the capital of the State of Maine. It has considerable trade in regular passenger steamers up to 10 feet draft and coasting vessels up to 14 feet draft. The principal wharves are on the western side just below the lower bridge, and have ample depth for any of the vessels coming here.

Anchorages.—The holding ground at the entrance below Fort Popham is poor, and vessels should not anchor unless forced to do so. If obliged to anchor when inside Pond Island, it is advisable to come-to in the channel abreast the wharf just above the Coast Guard station with a long scope of chain; if not blowing strong, a moderate-sized vessel may ride here if care is taken to keep the anchor clear.

Anchorage can be had on the eastern side of the channel southward of Perkins Island South Ledge buoy in 6 to 8 fathoms. On the eastern edge of the channel at the anchorage the depths shoal abruptly from 5 fathoms to a few feet; drift ice coming down the river generally follows the western shore.

The best and most frequently used anchorage is on the western side of the channel off Parker Flats in 4 to 6 fathoms. Large vessels sometimes anchor on the eastern side in this vicinity. Above Parker Flats vessels anchor wherever they find good holding ground and suitable depth, keeping out of the strength of the current.

ANCHORAGE OFF BATH.—The following are extracts from the regulations prescribed for the anchorage of vessels off the city of Bath:

Vessels may anchor within the following specified limits only:

1. To the northward of a line drawn from the north side of Passmore's wharf in Bath to a mark erected on the shore in Woolwich, 500 feet north of the Maine Central Railroad ferry slip.

2. To the southward of a line drawn from the derrick on the Bath Iron Works wharf to Sassanoa Point, in Woolwich.

3. One vessel may be anchored between the Maine Central Railroad ferry slip on the Bath side of the river and the line of the Maine Water Co.'s pipe; provided that such vessel's anchor be not less than 500 feet from the water-pipe line, and that the vessel be so anchored as not to swing below the north side of the entrance to the ferry slip.

4. Vessels in the north anchorage must be so anchored as to leave a clear fairway 150 feet outside of the established harbor lines at Bath and a clear fairway 200 feet from the east, or Woolwich, shore for the passage of steamers, tows, rafts, etc.

Passmore's wharf is a lumber wharf just north of the passenger ferry wharf, and shows between a clock tower and a church spire a little back of the water front. The Bath Iron Works are near the south end of the water front, and just south of the Maine Central Railroad ferry slip; the derrick on the wharf is prominent. The Maine Central Railroad ferry is for passenger and freight cars and should not be confused with the passenger ferry farther north. Sassanoa Point is the point on the north side of the thoroughfare leading eastward from Kennebec River. The water-pipe line is marked by a sign on each side. Deep-draft vessels usually anchor north of the prohibited anchorage. The harbor regulations are enforced by a harbor master.

Pilots will come out to a vessel making signal when near Pond Island. There are pilot lookouts at the entrance of the river; the

Digitized by Google

principal lookout is at Popham Beach, from which there is communication with the city of Bath by telephone. Strangers in vessels generally take a pilot, or, if a sailing vessel, a towboat. Strangers of over 17 feet draft should take a pilot. Under no circumstances should a stranger attempt to enter at night. Pilots for the upper part of the river can be secured at Bath.

Towboats are stationed at Bath and can be ordered from there by making signal when near Pond Island.

Supplies.—Coal can be obtained alongside the wharves at Bath and Augusta, and a limited quantity at Gardiner. Water can be had alongside the wharves at Bath, Richmond, Gardiner, and Augusta; the water in the river is fresh at Richmond and above. Gasoline, provisions, and ship chandler's stores can be obtained at Bath, and gasoline and provisions at any of the cities and towns on the river. Bay Point is the most convenient gasoline station near the entrance.

Repairs.—Bath has excellent facilities for repairing steel vessels or the machinery of steamers. There are several large shipyards at which large steamers are built. There is no marine railway on the river. There are machine shops for ordinary repairs at Gardiner and Augusta.

Communication.—Bath and the principal cities and towns on the Kennebec River above are on or near the line of the Maine Central Railroad. The cities and towns on the river have communication with each other, with Boston, and with the towns eastward along the coast by steamer.

Freshets occur in March and April, also after heavy rains in the fall, but they are not dangerous to shipping unless accompanied by ice. A height of 9 feet above mean high water usually occurs several times a year at Augusta, but the height diminishes rapidly southward.

Ice usually closes the river to navigation above Bath from December to April. In severe winters the river may be closed below Bath for a limited period. Sailing vessels entering the river do so on the flood tide, and if unable to reach Bath on one tide, anchor below Perkins Island on account of the drift ice which makes an anchorage in other parts of the river dangerous. Steamers, or vessels assisted by steam, are rarely delayed by ice below Bath.

The tidal currents have considerable velocity at the entrance and in the narrow parts of the river, especially from Pond Island to Fort Popham, Bluff Head to Fiddlers Reach, and Telegraph Point to the Chops; some local knowledge of their set is necessary to insure safety to vessels under sail. The direction of the currents at the entrance is influenced by strong winds, especially easterly gales. During spring tides and freshets, the velocity of the ebb current is increased and requires special attention. No complete observations have been made to determine the set and velocity of the currents.

Tides.—The mean rise and fall of tides is 8.3 feet at the entrance, 6.4 feet at Bath, 5 feet at Gardiner, and 4.1 feet at Augusta.

DIRECTIONS, KENNEBEC RIVER.

This area is a region of rocks and very broken ground and has not been examined by means of a wire drag. Strangers in vessels should therefore proceed with extreme caution, and should avoid crossing

Digitized by Google

broken ground where the charted depth does not greatly exceed the draft.

There are two approaches to the entrance, the eastern between Whales Back and the shoals southwestward, and the western between Pond Island Bar bell buoy and the shoals eastward. The eastern channel has a least found depth of about 5½ fathoms, and the western a least found depth of 4 to 5 fathoms on the sailing lines. Both are used, but vessels of over 18 feet draft generally enter by the eastern channel. The entrance has strong tidal currents, and if the wind is opposed to the current an ugly chop sea is encountered. Strangers in vessels should not attempt to enter in unfavorable weather; sailing vessels entering with an ebb current require a strong fair wind.

The principal dangers in the river are marked, but the channel is narrow in places. The narrowest place below Bath is eastward of Pettis Rocks, where it is only 75 yards wide. The sections of the dredged channel between the south end of Swan Island and Augusta are not sufficiently well marked to enable strangers to keep in them. With the aid of the charts and the following directions, strangers should, in clear weather, be able to carry a draft of 15 feet to Bath, 10 feet to Gardiner, and 5 feet to Augusta. The best time is on a rising tide.

1. **From eastward or southward.**—Having come from Boothbay Harbor or Fisherman Island Passage, pass close to Cuckolds black bell buoy and steer 244° true (W⅞S mag.) for 5 miles, passing about midway between The Sisters and Black Rocks, and pass southward and southwestward of Whales Back, rounding it at a distance of about ¼ mile. Then follow the directions in section 2. This course leads close to a depth of 4½ fathoms southward of Whales Back.

Coming from eastward outside the islands, pass ¼ mile southward of Bantam Rock gas and whistling buoy and steer 294° true (NW⅜W mag.) for nearly 6 miles, heading for Pond Island lighthouse, and passing ⅜ mile southwestward of Toms Rock buoy, ¼ mile northeastward of White Ledge buoy, and to a position ¼ mile southwestward of Whales Back. Then follow the directions in section 2.

Approaching from southward, pass southward and eastward of Mile Ledge buoy, and eastward of Seguin Island, giving it a berth of over ½ mile; then steer 6° true (NNE mag.). When Pond Island lighthouse bears 294° true (NW⅜W mag.) steer for it and pass ¼ mile northeastward of White Ledge buoy and to a position ¼ mile southwestward of Whales Back. Then follow the directions in section 2.

1A. From westward.—The directions reversed of section 10, page 53, will lead to a position nearly midway between Seguin Ledges and Pond Island Bar black bell buoy. Then steer 358° true (N by E¼E mag.) with Seguin lighthouse astern, and pass about ¼ mile eastward of the bell buoy and to a position ¼ mile southwestward of Whales Back. Then follow the directions in section 2.

Or steer for Seguin lighthouse on any bearing northward of 68° true (E ½ N mag.), pass preferably westward of the Camel Ground, and stand northeastward, passing between Ellingwood Rock and Jack Knife Ledge buoy and between Seguin Ledges and Pond Island Bar black bell buoy, as in the preceding paragraph.

Digitized by Google

2. Entrance to Parker Flats.—From a position ¼ mile southwestward of Whales Back steer 313° true (NNW⅝W mag.) for the end of the wharf southward of Fort Popham and pass 200 yards northeastward of Pond Island, 50 yards eastward of the horizontally striped buoy just above the island, and nearly 200 yards southwestward of South Sugar Loaf; this course leads 150 yards westward of an unmarked 3½ fathom spot. Pass in mid-channel westward of North Sugar Loaf, steer 337° true (N½W mag.), and pass midway between the light off Fort Popham and Gilbert Head.

When about ¼ mile below Shag Rock tripod steer 1° true (N by E⅝E mag.), pass about 200 yards westward of the tripod and 150 yards eastward of Cox Head. Then steer 346° true (N¼E mag.) for the eastern end of Parkers Head until nearly up with Perkins Island South Ledge red buoy. Pass 75 yards westward of this buoy, steer 1° true (N by E⅝E mag.), and pass 150 to 200 yards westward of Perkins Island, 100 yards eastward of Perkins Island North Ledge black buoy, and continue the course ¾ mile past Perkins Island to a position 250 yards westward of Back River red buoy.

3. Parker Flats to Bath.—From a position 250 yards westward of Back River buoy steer 319° true (NNW⅛W mag.) and round Squirrel Point lighthouse at a distance of about 200 yards. Then steer 6° true (NNE mag.) for about ½ mile, passing eastward of Goat Island (wooded). Pass in mid-channel southeastward of Lee Island Rock black buoy and steer about 37° true (NE¾E mag.) to a position 75 yards eastward of the spindle on the southernmost bare rock of the Pettis Rocks. Pass eastward of Pettis Rocks, slightly favoring the rocks, and when about 75 yards eastward of the northernmost grassy rock of the group, steer about 12° true (NNE ⅝ E mag.) and pass in mid-channel eastward of Ram Island, slightly favoring, if anything, the island side.

When past the tripod beacon on the northern end of Ram Island steer 0° true (N by E½E mag.) on the line of Doubling Point lighted range (white towers), taking care to go nothing westward of the range when about ¼ mile above Indian Point white tripod beacon, to insure clearing a rock with 7 feet over it which lies about 125 yards from the western bank. Keep in mid river in the narrow part for a distance of a little over 1 mile above Bluff Head, and then stand on the Doubling Point range, or go nothing westward of it, to avoid rocks with 8 and 10 feet on them. These rocks are marked by two black buoys, which are frequently towed under during the strength of the current. When past the second buoy haul westward in mid-channel through Fiddlers Reach and round Doubling Point lighthouse at a distance of 200 yards.

Pass about 75 yards eastward of the black buoy lying ¼ mile northwestward of Doubling Point lighthouse, steer 2° true (N by E¾E mag.), and pass about 100 yards eastward of Lincoln Ledge black buoy. Anchor about ¼ mile above black buoy No. 13 or continue up the river in mid-stream and anchor northward of the ferry on the east side within the limits prescribed by the regulations.

4. Bath to Abagadasset Point.—Favor the east side for 1 mile above the upper wharves at Bath, and pass eastward of the black buoys marking Wilson and Stetson Rocks, and between a red buoy and a horizontally striped buoy just north of Stetson Rock. Round Tele-

Digitized by Google

graph Point, on the south side, at a distance of about 100 yards, and steer northwestward, passing southwestward of the red buoy marking the south end of Thorne Island Ledge, and northeastward of a black buoy east of Wood Island.

After passing the black buoy steer 308° (NW⅞N mag.) for ½ mile and round the southwest end of Lines Island at a distance of 100 yards or more. There is a rock awash close to the island. Follow the western shore of Lines Island northeastward, pass westward of a red buoy 400 yards northward of the island, and steer 28° true (NE½N mag.) to pass eastward of a black buoy ¼ mile above. Then haul north-northwestward, and pass in mid-channel through the Chops (towers on each side). The course then leads north-northeastward for ⅜ mile, passing eastward of a black buoy and westward of a red buoy, and then northeastward for 1 mile, following the eastern shore at a distance of 150 to 200 yards, until on Abagadasset Point lighted range.

5. Abagadasset Point to north end of Swan Island.—Steer 341° true (N⅛W mag.) on the range (white structures) astern for ⅜ mile, and pass close eastward of a black buoy and 100 yards westward of a red buoy. Steer 25° true (NE¼N mag.) for ⅝ mile from the red buoy, to a position 150 yards northwestward of Ames Ledge light, and then 39° true (NE by E mag.) for 1 mile to the entrance of the dredged channel. The dredged channel follows the training wall on the east side at a distance of 150 yards for ⅝ mile, and is marked by buoys. It then leads 100 yards westward of a spindle marking a bare rock, and 100 yards off the points on the west side for ½ mile above the spindle. It passes eastward of a black buoy ⅞ mile above the spindle, and favors the east side in the bend from Reed Rock to Goodwin Point, and leads in mid-channel from there to Stearns Point.

6. Swan Island to Gardiner.—Keep in mid-channel for 1 mile above Swan Island to the entrance of the dredged channel off Court House Point. The dredged channel is on the west side of the river, eastward of two black buoys, and the course through it is 15° true (NNE⅞E mag.). The best water favors the east side off Cedar Grove, ½ mile above the second black buoy, the west side at Camp Meeting Point, ⅜ mile above Cedar Grove, and the east side past several unused ice houses and wharves, and leads eastward of a horizontally striped buoy. It leads 200 yards off Indian Point, westward of two red buoys, and then favors the west side, 50 yards off the points, for about ⅝ mile to Eastman Point. The channel leads 100 feet westward of buoy No. 28, and then on a 29° true (NE⅛E mag.) course for ½ mile to red buoy No. 28a. It then turns eastward and passes in mid-channel between Nehumkeag Island (high and wooded) and the eastern shore. The best water then leads about in mid-channel, or slightly favoring the western shore for ¾ mile, passing westward of two red buoys, and then favors the eastern shore for ½ mile until past two ice houses. It then hauls across to the western shore and favors it until between a red and a black buoy. The channel is in mid-river or slightly favoring the eastern side for 1 mile above the buoys, then leads through a dredged channel along the eastern side, eastward of a row of black buoys, to the wharves at Gardiner. Above Gardiner, the chart is the guide. Strangers are advised to run only on a rising tide.

Digitized by Google

CASCO BAY, EASTERN PART.

The part of Casco Bay between Cape Small on the east and Halfway Rock lighthouse and Harpswell Neck on the west (chart 315) is full of small island, ledges, and rocks, between which narrow but deep channels lead to the bays and sounds at the head. These arms afford good anchorages for small vessels, but are little used except by local fishing boats and pleasure craft. There are several small villages in this part of the bay, but no towns. Small steamers from Portland make landings as far east as Orrs Island. The settlements eastward are usually connected in summer by small boat with the railroad and electric road at the head of New Meadows River.

Cape Small is the wooded point on the east side of Casco Bay at the entrance. The distinguishing marks are a water tower 1 mile from the end, visible from eastward or westward; **Glover's Rock**, a low, bare islet ¼ mile southward of the point; **Bald Head**, a bare round knob on the west side of the point; and **Bald Head Ledge**, bare at half tide and marked by a spindle. There are submerged rocks and very broken ground, not closely examined, in the vicinity of the cape.

East Brown Cow, 1½ miles west-northwestward of Bald Head, is low and bare. **Mark Island**, ¾ mile northward of East Brown Cow, is high and thickly wooded on top. **Mark Island Ledge**, ¼ mile westward of Mark Island, is bare at low water.

White Bull, 1 mile westward of Mark Island, is high, round, and bare. **Bold Dick**, ⅝ mile west-southwestward of White Bull, is a bare rock about 4 feet high.

Small Point Harbor, on the east side of Casco Bay, 1½ miles northward of Bald Head, is considerably used as an anchorage by local fishermen, but seldom by strangers. The principal dangers are marked, but the holding ground is poor. **Small Point** is a small village at the head of the harbor; there is a wharf with a depth of about 8 feet. Small craft can find sheltered anchorage in **Cape Small Harbor**, at the head of the harbor, the entrance to which is eastward of **Goose Rock** (bare) and has a depth of 5 feet over a sand bar.

Small Point Harbor can be entered either southward or northward of **Wood Island** and **Little Wood Island** in the entrance. Wood Island is rocky and sparsely wooded, and Little Wood Island is thickly wooded. **Gooseberry Island Ledge**, on the south side of the southern entrance, is awash at low water and marked by a red buoy.

Carrying Place Cove is a thoroughfare, navigable at high water only, on the north side of Small Point Harbor eastward of **Carrying Place Head**. There are wharves for small craft at both ends of the thoroughfare, and it is the headquarters of many small fishing craft. Gasoline and some provisions are obtainable.

The thoroughfare leading eastward of **Burnt Coat Island** is marked by buoys. Strangers in small craft should have no trouble in going through it. There are small wharves on the eastern side of the thoroughfare.

Jamison Ledge, ⅝ mile westward of Burnt Coat Island, is ⅜ mile long, bare at low water, and marked at its south end by a spindle. **Flag Island Ledge**, between it and Flag Island, is bare at low water and unmarked. **Flag Island** is high and thickly wooded. **Long Ledge**, ⅜ mile northwestward of Flag Island, is grassy. **Goudy Ledge**, ⅝ mile northward of Flag Island, is bare at half tide and marked by a

Digitized by Google

spindle. **Rogue Island,** on the west side at the entrance to New Meadows River, is low, with scattered trees. The bottom in this vicinity is very broken and has not been closely examined.

Sebasco Harbor is a good anchorage for small vessels eastward and southward of Harbor Island and 3½ miles northward of Bald Head. **North Blacksnake** is a large bare ledge in the entrance; its northern end should be given a berth of over 100 yards, and the broken ground extending 300 yards eastward from the ledge should be avoided. The entrance is between North Blacksnake and the black buoy lying about 200 yards southward of Harbor Island. Anchorage can be selected 250 to 300 yards off the cove on the eastern side in 5 to 6 fathoms; also in midchannel off the landing inside Harbor Island in 4 fathoms. The thoroughfare leading northward from Sebasco Harbor, inside Harbor Island, is bare at low water.

The thoroughfare leading northward of **Harbor Island** and eastward of **Malaga Island** is marked by two buoys near the southern end, and is easily navigated by small craft. It is considerably used as an anchorage by small fishing craft. **Sebasco** is a settlement on the east side. There is a wharf with a depth of 8 feet near the north end of the thoroughfare and several smaller wharves farther south. A ledge covered at high water extends 350 yards north-northeastward from Bear Island and is marked at its end by a red buoy.

New Meadows River.—This river, at the northeastern end of Casco Bay, is about 8½ miles long from BEAR ISLAND at the entrance to a highway and an electric-railway bridge at the head of navigation. The channel has a least depth of about 12 feet to within ½ mile of the head, and the principal dangers are buoyed. Above that point the channel is crooked and unmarked and has a depth of about 7 or 8 feet to the head. Local knowledge is necessary to carry the best water above FOSTERS POINT, 3 miles from the head. The river is seldom used except by local fishing boats and small pleasure craft. Small craft can enter New Meadows River from westward 6 miles above its entrance through Simons Gurnet (described on page 194).

CUNDY HARBOR is a good anchorage for small vessels on the west side of New Meadows River, 1 mile above its mouth. The harbor is clear and has depths of 4 to 6 fathoms. A black buoy marks the south end of the bare ledges on the northeast side of the harbor. Cundy Harbor is a village on its western side. The wharves have depths of 6 to 15 feet. Gasoline and provisions are obtainable.

THE BASIN, a cove on the east shore, about 1¼ miles above Cundy Harbor, has a narrow entrance and is used only by small local craft.

WINNEGANCE BAY, on the east side of New Meadows River, 3 miles above the entrance, is a large bight with secure anchorage in 3 to 5 fathoms. The southeast side of the bay is foul. BUSHY and HEN ISLETS are near the edge of the foul ground, and HEN ISLAND LEDGE, bare at its end at low water, extends ¼ mile westward from the south islet. The north side of the bay is clear.

NEW MEADOWS is a small village at the fixed bridges crossing New Meadows River at the head. It is frequented by many small pleasure craft. There are float landings and a railway for hauling out launches of 4-feet draft and 50-feet length.

Directions, New Meadows River.—Entering from eastward, boats should pass southward of Glovers Rock and Bill Wallace ground, and westward of Bald Head Ledge spindle. Passing about ⅜ mile west-

Digitized by Google

ward of the spindle, steer 340° true (N¼W mag.) for the eastern edge of Flag Island for 2⅜ miles, passing a little over ¼ mile westward of Wood Island. When the north end of Little Wood Island opens from the north end of Wood Island, steer 8° true (NNE ⅛E mag.) for the western edge of Harbor Island, and pass 250 yards eastward of Jamison Ledge spindle. Pass about 300 yards westward of North Blacksnake (the bare ledges at the entrance of Sebasco Harbor), steer 335° true (N¾W mag.) for the entrance of New Meadows River, and pass 350 yards westward of Bear Island.

ENTERING FROM WESTWARD.—Vessels can enter from southwestward, passing between White Bull and Mark Islands, then between Long Ledge and Flag Island, and then between Goudy Ledge spindle and the black buoy northward. A more protected route, generally used by small craft, leads close to the red bell buoy southward of Jaquish Island, then on a 22° true (NE ½ N mag.) course for 2⅞ miles, following the eastern side of Bailey Island and passing westward of the red buoys marking Middle Ground and Littlejohn Rock. Pass northward of the latter buoy and steer 61° true (ENE ⅞ E mag.) for 1¼ miles, to a position close southward of the red buoy southward of Oak Island (marked by a few pines); then steer 91° true (ESE ½ E mag.) for 1¼ miles, passing close southward of two red buoys. From the second buoy the course is 86° true (ESE ⅞ E mag.) to a perpendicularly striped bell buoy, and then 43° true (NE by E ¼ E mag.), passing between Goudy Ledge spindle and the black buoy northward, to the entrance of the river.

FROM THE ENTRANCE TO NEW MEADOWS.—Keep in mid-channel until up with the southern point at the entrance of Cundy Harbor, and then steer 29° true (NE mag.) to a mid-channel position southeastward of Sheep Island Ledge black buoy. Then steer 7° true (NNE mag.) for Birch Point until abreast the southern end of Long Island. If going to an anchorage, a 49° true (NE by E ¾ E mag.) course will then lead into Winnegance Bay, taking care to keep the northern shore best aboard, distant ¼ mile or less. Bound up the river, pass between Birch Point and Long Island, and follow a mid-channel course northward for 1 mile. Pass midway between Bragdon Island and the spindle ¼ mile eastward, and steer north-northwestward in mid-channel for 1¼ miles to the south end of Middle Ground.

Pass westward of the red buoy at the south end of Middle Ground and steer 358° true (N by E ¼ E mag.) to a position close eastward of a black buoy, then 17° true (NE by N mag.) to a position close westward of a red buoy. Pass close northward of the buoy to avoid a shoal about 100 yards northward of it, and haul east-northeastward to the eastern shore. Favor the eastern shore until the river narrows, and then keep in mid-channel for ¾ mile above the south end of Howard Point to a place where the best water leads close to the eastern shore, eastward of a bare reef; the channel favors the eastern side just above in the opening underneath the telegraph line and is in mid-channel to the fixed bridges ⅛ mile above.

Ridley Cove is eastward of Yarmouth Island and just westward of the entrance to New Meadows River. It has good anchorage in 5 to 7 fathoms, but is exposed to southerly and southwesterly winds. It should be avoided by strangers on account of numerous unmarked

Digitized by Google

ledges and rocks which lie off the entrance. From its northern end a narrow, deep channel leads close northward of George Island into Hen Cove, and a narrow obstructed channel, suitable only for small craft in the absence of local knowledge, leads to Quohog Bay. **Hen Cove** has extensive shoals, but is a good anchorage for small craft.

Of the dangers off the entrance to Ridley Cove, **Jenny Island** is 10 feet high and grassy, **North Jenny Ledge** is bare at lowest tides and marked by a horizontally striped buoy at the south end, **Jenny Ledge** is bare 3 feet at low water. **Ballaststone Ledge** is 5 feet high and grassy, and there are numerous bare spots on **Yarmouth Island Ledges.**

Quohog Bay is a narrow arm extending about 4 miles in a northeasterly direction; it has good anchorage for small vessels, but is seldom entered by strangers. Numerous unmarked ledges and many small islands lie off its entrance, which is between Yarmouth Island and ledges on the east and Long Point on the west. The buoyed channel from New Meadows River to Orrs and Bailey Islands leads across the entrance. There is also a good channel between **Saddleback Ledge** (bare rocks), **Ragged Island** (high and scantily wooded on top), **Blacksnake Ledge** (bare at low water), **Yellow Rock,** and **Two Bush Ledge** (grassy) on the east and **Round Rock** (awash at high water), **Middle Ground Rock,** and **Cedar Ledges** (bare) on the west; the course through to the entrance is 14° true (NNE⅝E mag.). There are a number of unmarked ledges and sunken rocks in Quohog Bay. **South Ledge** (covered at high water) and **North Ledge** (covered at half tide) extend ⅜ mile southwestward and northeastward, respectively, from Pole Island.

The Gurnet is a narrow unimportant arm making northward on the east side of Orrs Island. There are no wharves. The point on the east side is wooded and has a house on the end.

Lowell Cove, in the south end of Orrs Island, is used as an anchorage by local fishermen. There is a wharf at the head. **Horse Cove,** in the north end of Bailey Island, is foul near the shores and is little used.

Ram and **Pond Islands,** southeastward of Lowell Cove, are round and grassy. **Pond Island Ledges,** extending ½ mile southwestward of Pond Island, have many spots bare at low water.

Halfway Rock, about in the middle of Casco Bay at its south side, is a low, rocky islet, marked by a lighthouse. Ledges extend ¼ mile southwestward and northward from it.

Halfway Rock lighthouse is a white granite tower attached to a dwelling. The light is fixed white alternating with fixed red, with a red flash of 5 seconds' duration in the red period every 90 seconds, 76 feet above the water, and visible 14 miles. The fog signal is a reed horn (blast 8 seconds, silent 4 seconds; blast 4 seconds, silent 44 seconds).

Drunkers Ledge, 2 miles north-northeastward of Halfway Rock, consists of two ledges ¼ mile apart. The southeast one has 4 feet over it and is marked at its southwest end by a red buoy; the northwest one is bare at half tide, and is marked near its western end by a spindle. Between Drunkers Ledge and Jaquish Island there is broken ground with depths of 16 to 24 feet, and in heavy weather the sea breaks on the shoaler places.

Whale Rock, a bare ledge nearly awash at high water, lies ⅜ mile southwestward of Little Mark Island.

Digitized by Google

Mericoneag and Harpswell Sounds are of little commercial importance, but they are the approach to a good and convenient anchorage. Vessels of the deepest draft can enter and find anchorage in 3½ to 10 fathoms, good holding ground. If in the vicinity of Halfway Rock and unable to beat into Portland against a northwesterly wind, this is the best harbor than can be made.

The entrance lies 3¼ miles north-northeastward of Halfway Rock lighthouse, and is marked on its western side by a stone monument on Little Mark Island. The sounds extend in a northeasterly direction 10 miles, and for the first 4 miles the prominent dangers are marked. Above this strangers should not go without a pilot, as the channel is narrow and flats make out some distance from the shore in several places. Directions to the entrance of Mericoneag Sound from eastward are given on page 53, and from westward through Potts Harbor on page 198.

Jaquish Island, on the east side of the entrance to Mericoneag Sound, is partly wooded on the southwest end, and has several cottages on the northeast end. **Turnip Island**, westward of it, is low and grassy.

Little Mark Island, on the west side of Mericoneag Sound at the entrance, is grassy and marked by a pyramidal monument. **Great Mark Island** is bare and grassy.

Mackerel Cove, in the southwestern shore of **Bailey Island**, the eastern point at the entrance to Mericoneag Sound, is a good and frequently used anchorage for small craft, with 5 to 11 fathoms. It is open southwestward, but a heavy sea never enters. The post village of Bailey Island is on the cove; it is connected with Portland by steamer. There are no dangers; the water shoals gradually toward its head. The entrance lies 1½ miles 54° true (ENE¼E mag.) from the monument on Little Mark Island.

Orrs Island is a village and summer resort on the south end of the island of that name. It is connected with Portland by steamer. The steamer wharf has a depth of 12 feet and the fish wharves less. There is a shoal a little southwestward of the steamer wharf. Gasoline and provisions are obtainable and pilots for any part of Casco Bay. The approach to the wharves is northward of a red buoy and spindle marking the end of a ledge bare at low water, extending from Bailey Island.

Wills Straits is a thoroughfare between the south end of Orrs Island and the north end of Bailey Island. It is used by local boats up to 7 feet draft at low water, but is narrow and difficult, and should not be used by strangers except in small craft and on a rising tide.

Harpswell Harbor, on the west side of Mericoneag Sound, 3½ miles above Little Mark Island, is a good anchorage in from 3 to 6 fathoms, shoaling gradually to the head. There is a landing for small craft on the west side, and a small settlement on the main road back of the landing.

Ram Island, on the west side of Mericoneag Sound northward of the thoroughfare leading into Potts Harbor, is bare and grassy. Ledges, bare and submerged, extend ¼ mile southward of the island to a red buoy. There is a channel northwestward of the island having a depth of at least 8 feet at low water. It leads between shoals on each side, and should not be used by strangers.

Digitized by Google

There is a thoroughfare from the north end of Harpswell Sound through **Ewins Narrows**, **Princes Gurnet**, and **Simons Gurnet** to New Meadows River. It is used by local boats, but the channel is narrow and unmarked, and has many dangers, the tidal currents are strong, and the thoroughfare should not be used by strangers. The most difficult parts of the channel are sometimes marked by bush stakes in summer. Simons Gurnet is crossed by a fixed bridge with two openings 40 feet wide, and a head room of 8 feet at high water. The southern opening has a depth of about 7 feet at low water and is said to be the shoalest place on the route. The northern opening is shoal and unused. The current through Simons Gurnet is very strong at strength (estimated at 7 to 8 knots) and boats go through only at slack water. The current runs eastward on the ebb. Low water slack occurs a little before low water at Portland.

CASCO BAY, WESTERN PART.

The part of Casco Bay westward of Harpswell Neck (chart 315) has numerous sounds, bays, and rivers, separated by islands lying in a northeasterly and southwesterly direction. Portland Harbor, at the western end of the bay, is the principal port of Maine. There are many summer resorts and landings on the islands and shores of the bay, and small steamers from Portland run as far east as Orrs Island, calling at the landings between. There are broad channels into the bay through Broad, Luckse, and Hussey Sounds, and secure anchorage for vessels of any draft can be found, but vessels seldom enter for an anchorage. The bay is frequented by many yachts and small pleasure craft, and some fishing boats. The steamers running to the landings are of 6 to 9 feet draft, and most of the wharves on the islands are built for vessels of about this draft.

In 1917 there were **steamer landings** and summer resorts on the following islands: Cushing, Peak, Little Diamond, Great Diamond, Long, Little Chebeague, Great Chebeague, Crotch (Cliff), Cousins, Littlejohn, Bustin, and Birch; and also on the mainland at Mare Point, Harpswell Center (southeast of Birch Island), and South Harpswell (Potts Harbor). Many of the other islands are inhabited and have landings for small craft. There are post offices and stores near most of the steamer landings.

Potts Harbor is a large irregular bight in the southern end of Harpswell Neck and has **Haskell** and **Upper Flag Islands** and the ledges between them on its southern side. It is a good anchorage, with depths of 4 to 5½ fathoms. **South Harpswell** is a village and landing on its eastern shore. There are two entrances to the harbor; the eastern one, from Mericoneag Sound, is buoyed, but it is narrow and crooked, with strong tidal currents, and is suitable only for small craft, or small vessels with local knowledge; the western entrance, between Upper Flag Island and Horse Island, is straight and about 225 yards wide at its narrowest part, between Horse Island and the edge of the shoal between Upper Flag Island and **Thrumb Cap**, a grass-covered rock. Upper Flag, **Little Birch**, and **Horse Islands** are grass covered. Directions through Potts Harbor from eastward are given on page 198.

Outer Green Island, 3¾ miles westward of Halfway Rock lighthouse, is grassy. **Junk of Pork**, a high rock with surrounding bare

Digitized by Google

ledges, lies 250 yards southward of it. **Johnson Rock**, lying ¼ mile northeastward of Outer Green Island, with foul ground between, has 7 feet over it and is marked on its north side by a black buoy. **Green Island Reef** is about ¼ mile long and bare at low water, and lies ½ mile southwestward of **Inner Green Island** (low and grassy), with foul ground between; it is marked on its southwest side by a red buoy. **Green Island Passage**, leading between a red and a black buoy, has a width of ¼ mile and is used to some extent by small vessels; when using it be careful to avoid the southeast end of Green Island Reef eastward of the red buoy.

Jewell Island and **Crotch (Cliff) Island** are partly wooded, and there are numerous cottages and a landing on the northwest side of the latter. **Crotch Island Ledge**, with 3 feet over it in places, extends ⅜ mile southwestward from the southern end of Crotch Island. Its end, with 10 feet, is known as **John Rock** and is marked by a red buoy. There is no safe passage for vessels between the buoy and the island. Jewell Island has a cove with good anchorage for small craft, on the northeast end. There is a landing for small craft at the head of the cove.

Broken Cave is a group of bare rocks and small islets, connected by ledges, extending ⅝ mile northeastward from **West Brown Cow**, a grass-covered islet. The beacon on Stockman Island in range with or open eastward of the northeast point of Ministerial Island leads eastward of the ledges.

Eagle Island is high, wooded, and prominent, and has a house and flagstaff on the northeast side. A ledge, bare at one-quarter ebb, extends 300 yards westward from it. **Eagle Island Ledge**, awash at high water, lies 300 yards southeastward of the southern end of Eagle Island; ledges with 8 to 10 feet over them extend 300 yards southeastward and 500 yards eastward from the rock that shows bare. Partly bare ledges extend 350 yards northeastward from Eagle Island.

Bates and **Ministerial Islands** are grassy, and each has a single house. They are surrounded by extensive ledges. **Stave Island** is partly wooded, and has several houses. **Stave Island Ledge** is bare at low water.

Hope Island is sparsely wooded and has a prominent house and flagstaff on the southwest end. There is a private wharf on the west side with a depth of about 8 feet. **Rogue** and **Sand Islands**, northeastward of Hope Island, are low and grassy. The channel between them is marked by two buoys, and by a private spindle on the end of the ledge on the north side. **Crow Island** is low and grassy. **Little Bangs** and **Stockman Islands** are bare and grassy, and Stockman Island has a tripod beacon at the southwest end. **Goose Nest** has an islet about 5 feet high, and **Goose Nest Ledge** is bare at a little below high water.

Whaleboat and **Little Whaleboat Islands** are partly wooded and have no prominent marks.

Middle Bay makes northeastward on the west side of Harpswell Neck. The principal wharf is a steamer landing on the east side just south of The Lookout. **Harpswell Center** is a post village on the main road back of the wharf. The bay has good anchorage, but is little used. **Lower Goose** and **Upper Goose Islands**, on the west side, are wooded and have no prominent marks.

Digitized by Google

Mare Point Bay, shallow and obstructed by flats, lies between Birch and White Islands on the east side and **Mare Point Neck** on the west. There is a steamboat landing on the eastern side of Mare Point Neck near its southern end, and another on the northwest side of **Birch Island.**

Maquoit Bay makes northeastward on the western side of Mare Point Neck, the entrance lying north of the Goose Islands. It is obstructed by flats, with 1 to 4 feet over them, through which a channel with 19 to 24 feet leads for a distance of 2¼ miles from its entrance.

The chain of islands between Sister and Bustin Islands are wooded, and there are flats between and northward of them. **Sister Island Ledge**, northward of **Sister Island**, is partly bare at high water. **Bustin Island** has numerous cottages, and there is a steamer landing on its western end. **Little Bustin Island** is marked by a house and a clump of trees in the center.

Bibber Rocks, southward of Bustin Island, are bare. **French Island** is sparsely wooded, and there is a wooded islet on its north side.

Freeport River, also known as **Harraseeket River**, is west of Maquoit Bay; the approach lies between Bustin Island on the east and **Great Moshier Island** (sparsely wooded) on the west. The entrance of the river is between Moore Point on the east and Stockbridge Point on the west, and is narrow, with a least depth of 20 feet. From the entrance the channel leads between flats, mostly dry at low water, in a northerly direction, 1¾ miles; a dredged channel, shoaled to about 4 feet deep, then leads to the town of Freeport. The principal wharf is bare at low water. The principal dangers in the approach and entrance to the river are marked by buoys; the channel above the entrance is unmarked. **Freeport** has no commerce except in small craft. **South Freeport**, on the west side ¾ mile above the entrance, has a clubhouse wharf with a depth of about 10 feet.

Littlejohn and **Cousins Islands**, northward of Great Chebeag Island, are connected by a trestle and have numerous cottages. There are steamer landings on the south side of both islands.

Yarmouth River is a narrow, crooked stream westward of Freeport River; its approach is westward of Cousins Island, in the northwestern part of Casco Bay. The river takes a northwesterly direction about 1¾ miles to the town of **Yarmouth.** The depth to Yarmouth is about 4 feet at low water. The river has some trade in fishing boats of about 5 feet draft, and small schooners up to about 10 feet draft. The channel is very crooked, leads between flats bare at low water, and is usually marked by bush stakes, but local knowledge is necessary to keep in the channel. The best time for strangers to enter is at low water, when the flats are visible, or on a rising tide. **Cousins River**, a narrow, shallow stream, empties into the mouth of Yarmouth River from northward. It has no business by water.

Great Chebeag Island, the largest island in Casco Bay, is an important summer resort. There are three steamer landings on the east side and one on the west end northward of **Indian Point.** **Chebeag Island** is the post office.

Chandler Cove is formed by a bight in the southwestern end of Great Chebeag Island and by Little Chebeag Island; it is a good anchorage with 5 to 10 fathoms, but is little used. The entrance from southward is through **Luckse Sound** and between the northeastern point of

Digitized by Google

Long Island and Deer Point, the southern point of Great Chebeag Island.

Little Chebeag Island has a patch of woods and a few houses, and a wharf on the southeast side. The western entrance, between the north end of Long Island and the south end of Little Chebeag Island, is somewhat obstructed by rocks, which are marked by buoys. Directions through the cove from eastward are given in section 11, page 53, and from westward on page 198.

Long Island, southwestward of Great Chebeag Island, has several landings on its northwest side. **Mariner** and Long Island are post offices near its northern and western ends, respectively. The islands southward are described with Portland Harbor.

Broad Cove is a shallow cove in the northwestern part of Casco Bay. There is good anchorage in the middle of the cove, southwest of Prince Point, in 15 to 17 feet. It is open southward and eastward. There is a private wharf on the eastern side of Prince Point, a landing for small craft on the west side of Broad Cove, and several landings on the western shore southwestward of Sturdivant Island.

Sturdivant Island is grassy and has several cottages. **Sturdivant Island Ledge** is bare in several places at low water. **Basket Island** is wooded in the center. **Upper Basket Ledge** is bare at low water, **Lower Basket Ledge** is bare at half tide, and both are marked by spindles. **Clapboard Island** is wooded and has a private landing on the west side. It is surrounded by ledges, bare and submerged. **Cow Island Ledge** is bare at low water and marked by a spindle. Presumpscot River and Back Cove are described with Portland Harbor.

Anchorages.—In the eastern part of Casco Bay the best anchorage for strangers in vessels is in New Meadows River. Local fishermen frequently use Tabasco and Cundy Harbors. Potts Harbor, Harpswell Harbor, and Mackerel Cove are good anchorages in the middle of the bay for small vessels and yachts. Mericoneag Sound and Harpswell Sound and the whole of Casco Bay westward of Harpswell Neck afford good anchorage for large vessels, except in heavy northeast gales. Vessels can enter through Broad Sound, Luckse Sound, or Hussey Sound, and select an anchorage under the lee of some of the many islands, a suitable depth and good holding ground being found in most places. Portland Harbor is a secure anchorage on the western side of the bay, and is generally used by vessels.

Pilots.—Vessels from eastward can sometimes obtain a pilot at Small Point Harbor or vicinity; one can always be had there for the waters northeastward of Halfway Rock. Vessels from westward can take a pilot at Portland, or, standing into Hussey or Luckse Sounds, take one from some one of the islands in the bay if a fisherman is not found outside.

Towboats are seldom used in Casco Bay. They can be obtained at Portland.

Supplies.—Gasoline and provisions can be obtained at any of the villages on the bay. Water has to be taken in casks from wells or ice ponds. Portland is the most convenient place for supplies for vessels.

Repairs.—There are no facilities for repairing vessels except at Portland. There is a railway for hauling out small craft at the head of New Meadows River.

Digitized by Google

Ice.—Considerable ice forms at the heads of the numerous arms extending northward in Casco Bay, but the principal anchorages are available at any season of the year.

Currents.—The tidal currents are not strong, but on the flood there is a perceptible set northward and on the ebb southward in the bay and across the entrance.

Tides.—The mean rise and fall of tides in the bay is about 9 feet.

DIRECTIONS, CASCO BAY.

This region is an area of rocks and ledges, and, except in the approaches to Portland Harbor, has not been examined by means of a wire drag. Vessels should therefore proceed with caution when crossing broken ground where the charted depth does not greatly exceed the draft.

Directions for approaching New Meadows River from eastward and westward are given on page 190. Vessels can enter the western part of Casco Bay through either Broad, Luckse, or Hussey Sounds. Chart 315 is the guide for entering by these channels. The following directions from Portland to Mericoneag Sound, through Chandler Cove and Potts Harbor, are by the route generally used by the small steamers and motor boats bound between these points and making landings at the islands. Several other routes are possible and sometimes used. Directions through Casco Bay from eastward are given on page 53.

Portland to Mericoneag Sound.—From a position 100 yards northward of the black bell buoy northward of Portland Breakwater lighthouse, steer 82° true (E¾S mag.) for 1¼ miles, passing southward of the red buoys southward of Fort Gorges and Little Diamond Island, and to a position southward of the red buoy southeastward of Little Diamond Island. Pass eastward of this buoy and haul northnortheastward to pass close to the wharf on the east side of Little Diamond Island and the wharf at the southeast end of Great Diamond Island, and northwestward of the black buoy ⅜ mile above. The course is then 41° true (NE by E⅛E mag.) for 1⅜ miles to a position northward of the black buoy off the south end of Long Island, then 53° true (ENE⅛E mag.) for 1¼ miles to a position southward of the red buoy marking Channel Rocks. Haul a little more northward to pass northward of a black buoy off the north end of Long Island, then steer eastward and pass northward of the black buoy off Crow Island, and then southeastward and pass midway between Deer Point Rock horizontally striped buoy and Deer Point.

Give the southeast side of Deer Point a berth of 150 yards, and steer 55° true (ENE⅜E mag.) for 1¼ miles to a position northward of the black buoy northeastward of Sand Island, then steer 72° true (E⅛N mag.) for 1⅛ miles, passing 150 yards southward of Little Bangs Island, to a position northward of Stave Island Ledge black buoy. The course is then 80° true (E⅝S mag.) for 1⅛ miles to a position 200 yards southward of Little Birch Island bell buoy, and then 62° true (E by N mag.) into Potts Harbor, passing 200 yards southward of Horse Island, 200 yards northward of Thrumb Cap, and to a position 50 yards northward of the black buoy northeastward of Thrumb Cap. Pass northeastward of this buoy and steer 163° true (S mag.) for ⅜ mile to a position close eastward of buoy

Digitized by Google

No. 3, and continue about the same course to pass between the red and the black buoys ⅛ mile beyond. Haul close around the red buoy and steer eastward, passing close northward of buoy No. 1, then steer southeastward and pass southward of the red buoy southwestward of Ram Island.

If bound to New Meadows River or vicinity, boats can steer southward, pass southward of Turnip Island Ledge red buoy and the red bell buoy off Jaquish Island, and follow the directions on page 191. Or if bound to Orrs Island or points northward, haul northeastward in Mericoneag Sound.

PORTLAND HARBOR

(chart 325), at the western end of Casco Bay, is the most important harbor on the coast of Maine. It has a large coastwise and some foreign trade, the deepest draft being about 30 feet. It is divided into an outer and an inner harbor, the inner harbor being inside a line joining Portland Breakwater lighthouse and Fort Gorges.

Channels.—The main entrance is from southward, westward of Cushing Island, and has a depth of 6 fathoms or more to the entrance of the inner harbor. There are several ledges off the entrance, most of them marked, which makes the approach to the harbor dangerous in thick weather for deep-draft vessels. There is a 30-foot rock ⅜ mile southeastward of Portland Head lighthouse, and a 29-foot rock ¼ mile eastward of Spring Point Ledge lighthouse, both unmarked. A project for their removal to a depth of 40 feet has been approved. In clear weather vessels can easily avoid the rocks and ledges off and in the entrance.

In addition to the main entrance from southward there are several entrances from eastward between the islands, but these entrances are seldom used except by local vessels familiar with them and by small craft.

The inner harbor has a depth of about 30 feet at present to the fourth bridge, 2½ miles above Portland Breakwater lighthouse. A large area northwestward of Fort Gorges has been dredged to a depth of 30 feet to form an anchorage. Work was in progress in 1918 to dredge a channel 35 feet deep and 1,100 to 1,900 feet wide into the inner harbor to a point about ⅜ mile westward of Portland Breakwater lighthouse.

The broken ground in the approach to Portland Harbor southeastward and eastward of Cape Elizabeth has been examined by means of a wire drag, and the dangers are shown on the charts. A detailed description of them is not necessary.

The approach to Portland Harbor from southward is marked by Portland light vessel and Cape Elizabeth lighthouses, and from eastward by Halifax Rock lighthouse (described on p. 192). The entrance to the harbor is marked by Portland Head lighthouse on the western side and Ram Island Ledge lighthouse on the eastern side.

Portland light vessel, 5¼ miles southeastward of Cape Elizabeth lighthouses, has a red hull with "Portland" on each side, and two masts with a red grating at the foremast head. The light, shown from the foremast, is occulting white (light 1 second, eclipse 1 second), 70 feet above the water, and visible 12 miles. The fog signal is

Digitized by Google

a chime whistle (blast 3 seconds, silent 27 seconds). A submarine bell sounds "7–4" every 33 seconds.

Cape Elizabeth lighthouses are two white conical towers 308 yards apart. The northeastern has a fixed white light, 129 feet above the water, and visible 17 miles; and the southwestern a fixed white light with a flash of 6 seconds' duration every 60 seconds, 130 feet above the water, and visible 17 miles. There is a Coast Guard station and numerous houses near the lighthouses.

Portland Head lighthouse is a white conical tower connected to a dwelling. The light is fixed white, 101 feet above the water, and visible 16 miles. The fog signal is a reed horn (blast 5 seconds, silent 15 seconds).

Ram Island Ledge lighthouse is a light gray conical tower on Ram Island Reef (bare at low water). The light is group flashing white (flash 0.3 second, eclipse 1.2 seconds, flash 0.3 second, eclipse 4.2 seconds), 77 feet above the water, and visible 14 miles.

Cushing Island, on the east side just inside the entrance to Portland Harbor, is mostly grass covered and has two prominent radio towers at its northeast end. **White Head** is a high bluff at its northeastern end. Steamers from Portland land at a wharf on the west side, and there is another wharf in a cove on the northeast side.

Whitehead Passage, between Cushing and Peaks Islands, has a depth of about 4 fathoms, and is sometimes used by vessels up to about 12 feet draft, entering from eastward. The principal dangers are marked, but the channel is narrow, and strangers in vessels are advised to use the main channel.

To go through Whitehead Passage avoid the broken ground which extends ⅝ mile northeastward from Ram Island. Enter the passage between two spindles, which mark rocks bare at low water, favoring, if anything, the southern one, and pass southward of a red buoy just inside them. Then steer 243° true (W by S mag.) for nearly ¼ mile, giving the shore of Cushing Island a berth of about 125 yards. Then steer 299° true (NW mag.), and pass southward of the red bell buoy at the western end of the passage. Pass 100 yards westward of the bell buoy, steer 351° true (N ⅝ E mag.), and pass 100 yards eastward of the black buoy off the north end of House Island. Pass 150 yards northward of House Island light, steer 274° true (WNW ¼ W mag.), and pass northward of the black buoy northward of the Breakwater lighthouse into Portland Harbor.

House Island, on the east side of the main channel northward of Cushing Island, is the site of the quarantine station; an old fort on the southwest end is visible. There is a light on each end of the island.

Peaks Island, the large island northeastward of Cushing Island, is used as a summer resort. It has communication with Portland by ferry and steamers. There are several wharves on the west side. Peak Island (**Forest City Landing**) is a post office on the south end and **Trefethen** a post office on the north end.

Great and **Little Diamond Islands**, northward of Peaks Island, are connected by a trestle. Little Diamond Island has many houses visible, and Great Diamond Island has a prominent water tank. Steamers from Portland make landings at wharves at the southwest end of Little Diamond Island and the south end of Great Diamond Island.

Digitized by Google

There is a buoy depot and wharf on the east end of Little Diamond Island.

The channel between Peaks Island and Little and Great Diamond Islands has a depth of 15 feet and is used by many small vessels and motor boats bound to points in Casco Bay. The principal dangers are marked. Directions from Portland through it are given on page 198

Diamond Roads, formed by Peaks, House, and Little Diamond Islands, is a good anchorage for vessels, but is little used as an anchorage except by yachts and small craft making their headquarters at Peaks Island. The dredged anchorage northwestward of Fort Gorges is generally used by vessels.

Spring Point Ledge lighthouse is a white conical tower on a black pier on the northeast end of a ledge, bare in places at low water.

Fort Gorges, 5/8 mile north-northeastward of Spring Point Ledge lighthouse, is a gray stone structure on **Diamond Island Ledge**. The ledge has a large area bare at low water and a few spots bare at high water.

Portland is on the north side of the inner harbor; it is on several railroads and is a terminus of the Grand Trunk Railroad running through Canada. It also has steamer communication with New York, Boston, and most of the towns eastward along the coast. It has considerable foreign trade, especially during the season of closed navigation in the St. Lawrence River. There are depths of 30 feet at the Grand Trunk Railroad wharves near the eastern end of the water front and at the wharves just below and above the first bridge. The other wharves have less depths. There is a public float landing for small craft on the west side of the Portland Pier, near its head. There is a ferry slip on the outer end of the pier.

South Portland is a town on the south side of the inner harbor opposite Portland. It is connected with Portland by ferry and a highway bridge. There is a shipyard here for the repair of wooden vessels.

Fore River is the name given to the part of Portland Inner Harbor above the first bridge. A channel 30 feet deep and 300 feet wide has been dredged in the river to the upper Boston and Maine Railroad bridge, 1¼ miles above the first bridge. There are a railroad wharf and several oil wharves on this channel, and the river is used by many vessels. The flats on each side are bare at low water, and this is the best time for strangers to enter. From the upper end of the dredged channel the river has a narrow, crooked, unmarked channel with a least depth of about 4 feet for 1½ miles, and is little used. The flats on each side are bare at low water.

Bridges.—Fore River is crossed by four bridges, all with draw openings.

PORTLAND BRIDGE, the lower, is a highway and street railway bridge with a single opening 100 feet wide, and a headroom of about 30 feet at high water when closed; it is opened to vessels on signal between 5 a. m. and 7 p. m. from October 1 to April 1, and between 4 a. m. and 8 p. m. from April 1 to October 1, and at other hours on notification to the draw tender. BOSTON AND MAINE RAILROAD LOWER BRIDGE, ¼ mile above Portland Bridge, has a center pier draw, both openings 60 feet wide, and a head room of 6 feet at high water when closed. VAUGHN BRIDGE, 1⅛ miles above Portland Bridge, has a

Digitized by Google

center pier draw, both openings 60 feet wide, and a headroom of 5½ feet at high water when closed; it is opened on a signal of five blasts at any time on week days between 7 a. m. and 5 p. m. from October 1 to April 1, and between 6 a. m. and 6 p. m. for the remainder of the year, and on Sunday or at other hours on previous notice to the draw tender. THE UPPER BOSTON AND MAINE RAILROAD BRIDGE, 1¼ miles above Portland Bridge, has a swing draw with a single opening 40 feet wide.

Back Cove is on the north side of Portland. It has been improved by dredging a channel 30 feet deep and 300 feet wide to the Grand Trunk Railroad bridge at the entrance, 14 feet deep to Tukey Bridge ¼ mile above, and 12 feet deep and 300 feet wide to the head of the cove. Vessels go to a wharf at the first bridge, to a wharf on the north side between the bridges, and to wharves at the head of the cove. The channel is unmarked and leads between flats bare at low water.

Bridges.—GRAND TRUNK RAILROAD BRIDGE has a center pier draw with a single clear opening (south) 88 feet wide, and a headroom of 5½ feet at high water when closed. TUKEY BRIDGE is a center pier draw with one clear opening (south) 67 feet wide, and a headroom of 5 feet at high water when closed.

Presumpscot River, northward of the entrance to Broad Cove, has a narrow, crooked channel with a depth of 8 feet to Martin Point at the entrance and 6 feet for 1 mile above. The channel is unmarked and leads between flats bare at low water. There is no business by water. **Martin Point**, on the west side at the entrance, is marked by a prominent building (marine hospital) and flagstaff.

Pilots.—Between October 1 and May 1 a pilot boat will usually be found cruising outside Portland Head, and vessels desiring a pilot will be boarded when making signal. In the summer, pilots are on the lookout for vessels requiring their services, and vessels making signal for a pilot should stand off and on outside of Portland Head until boarded. There are licensed pilots for this port, but pilotage is not compulsory. Strangers entering the port in vessels generally take a pilot. The rates are $2.50 per foot draft entering, and $1.25 per foot draft leaving the port.

Towboats can be obtained by making signal outside. They are used by vessels going alongside the wharves or through the bridges. Regular rates have been adopted for towing vessels within the harbor, but for towing in from sea an agreement is made between the vessel and the towboat.

Anchorage.—The usual anchorage for large vessels is in the 30-foot dredged anchorage northwestward of Fort Gorges. The northeastern limit of this anchorage has a 306° true (NW ⅝ N mag) direction from the southwest end of Little Diamond Island, and is marked by a white buoy. Vessels can also find good anchorage in Diamond Island Roads. The anchorage in the inner harbor is on the south side, south of a line of white buoys. Small vessels anchor on the south side of the inner harbor, eastward of the ferry slip on the north side; and yachts and small craft anchor on the south side, between the ferry slip and the first bridge. The quarantine anchorage is eastward of Fort Gorges.

Digitized by Google

Anchorage and harbor regulations.—The following are extracts from the regulations prescribed for Portland Harbor. The harbor master has charge of the enforcement of the regulations:

SEC. 1. No owner, master, pilot, or other person having charge of any vessel, and no owner, master, pilot, or other person having charge of any vessel towing or otherwise conducting another vessel to anchorage in the harbor and bay of Portland shall place such vessel in anchorage in said harbor and bay in any anchorage ground other than that hereinafter described, and all persons shall conform to the following rules and regulations:

SEC. 2. Vessels not exceeding 500 tons burden may be anchored on the southerly side of the line ranging with the white buoy off the breakwater and a white buoy on a westerly course, thence on a line ranging with said white buoy and the draw pier of Portland Bridge, but not west of a line drawn from the northerly end of the slip of the Portland and South Portland ferry, Portland, to the northerly end of said ferry company's wharf at South Portland.

Vessels of larger tonnage may also be anchored on the above-described grounds, provided the anchorage grounds designated for such vessels shall be crowded, but not so as to obstruct the free entrance or egress of regular lines of steamers to or from their docks on the northerly side of the harbor.

SEC. 3. Vessels not exceeding 150 tons may anchor to the westward of above lines drawn from northerly end of the ferry wharves and south of line ranging from the white buoy above mentioned with southeasterly end of draw of Portland Bridge.

SEC. 4. Vessels exceeding 500 tons shall be anchored easterly of a line drawn from the southeasterly end of the Portland Company's wharf (¼ mile west of Fish Point) as now built and the westerly end of the Bay View wharf at Peaks Island. This line shall be marked by three white buoys.

SEC. 5. Vessels anchoring within above-described limits must anchor entirely within said boundaries, so that no portion of the hull, spars, or booms shall extend beyond said boundaries after veering chain or when riding to the tide.

SEC. 6. Permits may be granted by the harbor master of the city of Portland to wrecking plants to anchor outside of the above limits for the purpose of recovering sunken property, subject to his supervision. Such plants must comply with all the navigation laws in regard to lights, fog signals, and other requirements, and must move in ample season to give safe and clear passage to arriving and departing regular lines of steamers.

SEC. 7. Vessels may be anchored south of a line ranging with the Spring Point lighthouse and the white buoy off the breakwater.

SEC. 8. All vessels at anchor in the harbor shall display a distinct white light forward not less than 6 feet above the forecastle deck during the night. All vessels at anchor shall keep their foresails and jibs furled during the night. Anchor watch shall be kept and fog signals sounded in fogs or thick weather.

SEC. 9. Vessels ordered to quarantine shall be anchored on the northeasterly side of a line ranging with the United States Marine Hospital and Fort Gorges, which anchorage shall be designated as the quarantine anchorage.

SEC. 10. All steamers passing up and down the harbor near the ends of the wharves shall run at a slow rate of speed.

Quarantine is enforced in accordance with the regulations of the United States Public Health Service. The quarantine station is on House Island, and vessels subject to visitation do not go above until they have been granted pratique.

Marine Hospital.—The Marine Hospital is on the Presumpscot River 1 mile from the city. There is also an office at the customhouse.

Supplies.—Coal in any quantity can be had alongside the wharves or from lighters. Water can be obtained alongside the wharves or from water boats. Gasoline, provisions, and ship-chandler's stores are to be had in the city. Gasoline and provisions are also obtainable at Peaks Island.

Repairs.—The facilities for repairing wooden vessels are good. There are two marine railways on the Cape Elizabeth side of the

Digitized by Google

harbor. The greatest draft taken out is 13 feet forward and 16 feet aft, and the capacity is vessels up to 1,300 registered tons. The facilities for repairs to machinery of steamers are good. There are several machine shops where building and repairing can be done.

Storm warnings are displayed from a building opposite the post office and can be readily seen by the shipping in the harbor.

Ice seldom obstructs navigation; when it does, it is only for a limited time. The towboats keep a clear channel to the wharves.

Tides.—The mean rise and fall of tides is 8.9 feet.

DIRECTIONS, PORTLAND HARBOR.

Portland Harbor and approach have been examined by means of a wire drag from Fort Gorges, at the entrance to the inner harbor, out to a depth of about 18 fathoms off the entrance, and a little farther in places. This dragged area covers all of the broken ground eastward and northeastward of Cape Elizabeth, except those dangers within a distance of ½ to 1 mile of the shore.

The broken ground off the entrance to Portland Harbor renders the entrance of vessels dangerous in thick weather unless sure of the position. The following courses, if made good, are available for vessels up to 30 feet draft, but lead close to dangers; strangers in deep-draft vessels are advised to take a pilot.

From eastward.—Directions good for vessels up to 12 feet draft entering Portland Harbor from eastward inside the islands in Casco Bay are given on page 53. Local vessels up to 12 feet draft sometimes enter through Whitehead Passage (described on page 200.) Deep-draft vessels usually make Bantam Rock gas and whistling buoy and Seguin Island whistling buoy, and pass close to Halfway Rock whistling buoy. From this buoy steer 261° true (W ¾ N mag.) for 6¼ miles to a position 100 yards southward of Witch Rock gas buoy; this course leads ½ mile northward of an unmarked ledge with a least depth of 34 feet. Then steer 291° true (NW⅝W mag.) for 1⅝ miles to a position 150 yards southwestward of the gas buoy off the southwest end of Cushing Island.

From southward.—Vessels entering Portland Harbor from southward usually make Portland light vessel. From the light vessel steer 319° true (NNW¼W mag.) for 3 miles, heading for Portland Head lighthouse, to a position ½ mile northeastward of Corwin Rock black bell buoy and ⅝ mile southwestward of West Cod Ledge Rock red buoy. Then steer 344° true (N mag.) for 3¼ miles, with the east side of Peaks Island ahead, until 1 mile from Witch Rock gas buoy and with it in range with Ram Island Ledge lighthouse; then steer 298° true (NW mag.) for 2⅝ miles, passing ¼ mile southwestward of Witch Rock gas buoy and ⅜ mile northeastward of Jordan Reef buoy, to a position 150 yards southwestward of the gas buoy off the southwest end of Cushing Island.

Cushing Island to Portland.—Pass 150 yards westward of the gas buoy at the southwest end of Cushing Island and steer 337° true (N⅝W mag.), passing ¼ mile westward of House Island and 250 yards eastward of Spring Point Ledge lighthouse. If going to the anchorage northwestward of Fort Gorges, continue about the same course, pass 200 yards westward of the red buoy southwestward of Fort Gorges (stone structure), and at least 200 yards westward of the most

Digitized by Google

westerly bare part of Diamond Island Ledge, and anchor northwestward or north-northwestward of Fort Gorges. If bound to Portland, continue the 337° true (N⅝W mag.) course for ⅜ mile past Spring Point Ledge lighthouse to a position 250 yards southwestward of the red buoy southwestward of Fort Gorges. Then steer 271° true (WNW½W mag.), and pass 400 yards northward of Portland Breakwater lighthouse, and 125 yards northward of the black bell buoy northward of the lighthouse. The course can then be shaped to the wharves, or they can be followed, 150 yards off, to the first bridge.

COAST FROM PORTLAND TO PORTSMOUTH.

This stretch of coast (chart 1205) extends about 37 miles in a general southwesterly direction from Cape Elizabeth, with but few harbors indenting it, they being principally the resort of fishermen and small coasters seeking shelter in bad weather. Richmond Island Harbor, Wood Island Harbor, and Cape Porpoise Harbor are the only anchorages available for strangers. There are many summer resorts along the coast, most of them reached by electric road from Portland or Portsmouth.

Cape Elizabeth lighthouses and Portland light vessel are described on page 199.

Seal Cove (chart 327) is on the southeast side of Cape Elizabeth northeastward of Richmond Island. It has numerous rocks and ledges and is frequented only by boats of local fishermen. There are no wharves.

Richmond Island Harbor (chart 327), formed by Richmond Island (grassy, with a house and a few trees in the center) and a breakwater extending to the shore, lies 2½ miles southwestward of Cape Elizabeth lighthouses and 6¼ miles 32° true (NE¼E mag.) from Wood Island lighthouse. It is sheltered from northerly and westerly winds, but is exposed to southeasterly and southerly winds, and vessels should leave the harbor on indications that the wind will veer southward of east. Foul ground extends ⅜ mile from the northern side of the harbor, leaving an anchorage about ⅜ mile wide near Richmond Island, where the depths shoal gradually from 8 fathoms at the entrance to 3 fathoms ¼ mile from the breakwater at the head. It is little used as an anchorage.

Chimney Rock, lying ⅜ mile from the north side of Richmond Island Harbor, is awash at low water and is marked on its southeast side by a black buoy. Vessels must pass southward of the buoy. A rock with 16 feet on it lies 400 yards east-southeastward of Chimney Rock buoy. **Ram Island**, low and grassy, lies ¼ mile northwestward, and **The Brothers**, three small bare rocks, lie 300 yards north-northeastward of Chimney Rock.

Old Proprietor is a ledge, bare at low water, lying nearly 1 mile from shore and 1⅞ miles westward of the western end of Richmond Island. It is marked on its south side by a black buoy. A ledge with 11 feet over it lies nearly ½ mile northeastward of Old Proprietor.

Between Richmond Island and Wood Island lighthouse, a distance of 6¼ miles, the shore forms a large open bight, the southern part of which is **Saco Bay.**

Digitized by Google

Spurwink and **Scarboro Rivers**, on the north side of the bight, can be entered only by small craft at half tide or higher with a smooth sea. They are seldom entered. **Higgins Beach**, on the west side at the entrance to Spurwink River, has many cottages visible.

Prout Neck, a prominent point nearly 3 miles westward of Richmond Island, is the northern point of Saco Bay; it is partly wooded and has many houses visible. The shore of the bay is known as **Scarboro Beach**, **Old Orchard Beach**, and **Ferry Beach**, in the order named from northward. The large hotels, pier, and standpipe at Old Orchard Beach are prominent. A rock with 12 feet over it lies ⅞ mile from shore in the northern part of Saco Bay and is marked on its south side by a red buoy. About ⅝ mile westward of the buoy and the same distance northeastward of the pier at Old Orchard there is a ledge with 2 feet over it which extends ½ mile from shore.

Stratten and **Bluff Islands**, grass covered, lie off the northern part of Saco Bay, 1 mile southward of Prout Neck, with deep water between. The islands are joined by ledges, which also extend ¼ mile eastward from Stratten Island. Stratten Island has a house and barn.

In the southern end of Saco Bay there are islands and ledges which extend 1¼ miles from shore, and inside of them are Wood Island Harbor and the entrance of Saco River. **Eagle** and **Ram Islands** are rocky and grass covered; vessels should pass eastward of them, giving them a berth of ½ mile.

Saco River, having its entrance in the south end of Saco Bay westnorthwestward of Wood Island lighthouse, is the approach to the cities of **Biddeford** and **Saco**, at the head of navigation, about 5 miles above the entrance. The entrance is between two jetties; the channel is being improved to obtain a depth of 7 feet and a width of 100 to 200 feet to Biddeford and Saco. A depth of 7 feet has been obtained in the river . The depth across the bar is subject to change, but is usually 4½ to 5 feet.

The deepest draft entering are vessels up to 13 feet draft, carrying coal. The entrance is marked by buoys; the channel inside the entrance is unmarked and local knowledge is necessary to keep in the best water. A pilot can be obtained at The Pool, southward of the entrance. The depths are 6 to 10 feet at the principal wharf at Saco and 10 feet at the wharf at Biddeford.

Small craft can enter with a smooth sea and on a rising tide by passing between **Ram Island Ledge** and **Negro Ledge** buoys, steering westward and passing southward of the red buoy marking **Sharps Rocks**, then passing close to the perpendicularly striped buoy off the ends of the jetties, and favoring the south jetty until near its inner end. The south jetty is covered at high water and marked by pyramidal stone beacons at frequent intervals. The north jetty is visible at high water. Ice closes the river from January to April. The mean rise and fall of tide is 8.8 feet.

Wood Island, eastward of the entrance to Saco River and 7¾ miles southwestward of Cape Elizabeth, has a patch of woods in the center, and is marked at the east end by **Wood Island lighthouse** (white tower connected with dwelling). The light is fixed red, with a red flash of 3 seconds' duration every 60 seconds, 71 feet above the water, and visible 14 miles. The fog signal is a bell (1 stroke, silent 25 seconds, 2 strokes, silent 25 seconds).

Digitized by Google

Wood Island Harbor is an anchorage for small vessels of about 12 feet or less draft, lying on the south side of the ledge extending westward from Wood Island, and has a width of about 250 yards. It is exposed to easterly winds. The anchorage with best shelter is about 200 yards northeastward, northward, or northwestward of Philip Rock spindle (the easterly spindle inside the harbor), in a depth of 15 feet. Anchorage can also be had 200 to 300 yards northwestward of the red buoy west-southwestward of Negro Island in 15 to 18 feet.

The south side of the anchorage is formed by **Gooseberry Island** (grassy on top and showing but little above high water), and ledges westward of it which extend 300 yards from Fletcher Neck. **Philip Rock**, near the edge of the channel 450 yards westward of Gooseberry Island, is marked by a black spindle with two cages. The southwest end of the harbor is filled by shoals, with 7 to 12 feet over them, the edge of which extends from Philip Rock to Stage Island, and lies 150 yards southwestward of the red buoy west-southwestward of Negro Island. A black spindle with cage marks a rock bare at low water lying about 600 yards westward of Philip Rock and on the south side of the channel leading to The Pool.

To enter Wood Island Harbor from northeastward, give the north side of Wood Island a berth of over ½ mile and steer 232° true (WSW mag.) for Stage Island monument, passing about midway between Negro Island Ledge black buoy and Ram Island Ledge red buoy. When Negro Island is abeam steer about 187° true (SSW mag.), and pass about 150 yards eastward of the black buoy eastward of Stage Island. Pass 150 to 200 yards northwestward, and not over 100 yards southward, of the red buoy west-southwestward of Negro Island.

Approaching from southward, steer for Wood Island lighthouse on a 343° true (N ⅛ W mag.) course; Dansbury Reef buoy should be made a little on the starboard bow. Pass midway between the buoy and Washman Rock spindle on a 325° true (N by W ¾ W mag.) course, heading for a 2½-story house on the southern side of Wood Island, and pass 200 yards eastward of Gooseberry Island. Pass midway between Gooseberry and Wood Islands, and steer 272° true (WNW ⅜ W mag.), with the red buoy west-southwestward of Negro Island a little on the starboard bow.

Negro Island (low and grassy on top) lies just westward of Wood Island; ledges extend nearly 200 yards northwestward and 300 yards southwestward from Negro Island, and are marked at the southwest end by a red buoy.

Stage Island is marked by a prominent white stone monument. The harbor southwestward of a line joining Philip Rock, Stage Island, and the entrance of Saco River is shoal. **Stage Island Shoal**, partly bare at low water, extends 300 yards east-northeastward from the island and is marked at its end by a black buoy. **Basket Island** has several cottages.

The Pool is a shallow bay making southwestward from Wood Island Harbor inside of Fletcher Neck. The entrance is about 50 yards wide, and the tidal currents have considerable velocity. Small craft can anchor just inside the entrance. **Biddeford Pool** is a post village on the south side of Wood Island Harbor, extending from The Pool nearly to the eastern point of Fletcher Neck. There is a wharf on

Digitized by Google

the east side of the entrance to The Pool. Gasoline and some provisions are obtainable.

Washman Rock, bare at half tide, is near the end of a reef which extends nearly 600 yards southeastward from the eastern point of Fletcher Neck, and is marked by a black spindle with cask.

Dansbury Reef is a small ledge with 5 feet over it, lying ½ mile southward of Wood Island lighthouse. It is marked on its southeast side by a red buoy. There are several shoal spots between the reef and Wood Island, and strangers should not enter between them.

A number of rocks and ledges extend ⅝ mile southeastward of **Fletcher Neck.** Vessels will avoid these dangers by keeping Wood Island lighthouse bearing northward and westward of 350° true (N ½ E mag.).

Goose Fair Bay is a shallow cove, full of rocks and ledges, lying 2 miles northeastward of Goat Island lighthouse.

Stage Island Harbor is a small slough, ½ mile northeastward of Goat Island lighthouse, that is used by boats and small local craft. The entrance is about 50 yards wide between reefs, making northward from Cape Island and southward from Little Stage Island and is not safe for strangers.

Cape Porpoise Harbor (chart 1205) is an anchorage which has been dredged to a width of 500 to 600 feet, with a depth of 15 feet, lying between the islands and rocks northwestward of Goat Island lighthouse. The channel at the entrance has been straightened by cutting off the points of ledges and has a width of 190 feet and depths of 18 to 35 feet. Small local craft sometimes anchor on the flats on the west side of the dredged anchorage and lie aground in the soft mud at low water. Vessels of over 100 tons should not attempt to enter the harbor for refuge on account of the small area of the anchorage; it is advisable for strangers to run either for Portland or Portsmouth if caught in a blow. Vessels of 18 feet draft loaded with coal have been brought into the harbor to the wharf on the west side of Bickford Island.

The Old Prince is a ledge with 5 feet over it lying 400 to 500 yards southeastward of Goat Island lighthouse; the ledge is marked by a red bell buoy placed about 200 feet south-southwestward from it, and the buoy should be kept fairly close aboard to avoid the southeast point of the ledge making out from Folly Island. **Folly Island** is grassy and marked by a shanty. Folly Island beacon, a large white tripod, is placed on the partly bare ledge extending eastward from Folly Island; the beacon lies 180 feet from the westerly edge of the dredged channel.

Goat Island lighthouse is a white tower with a covered way to a dwelling. The light is fixed white, 38 feet above the water, and visible 10 miles. The fog signal is a bell (one stroke every 20 seconds).

A red spindle is placed on a ledge bare at low water, and lies 370 feet west-southwestward of Goat Island lighthouse and 30 feet from the easterly edge of the channel. About 300 yards above the lighthouse the west side of the channel is marked by a black buoy, placed on the northeast side of **Lobster Rock,** which has 4 feet over it. Abreast the buoy is an islet, nearly awash at high water, marked by

Digitized by Google

a beacon (pile of stones), which lies 275 feet northeastward of the easterly edge of the channel.

Approaching Cape Porpoise Harbor, give the islands northeastward of the entranch a berth of ½ mile and the shore southwestward of the entrance a berth of 1½ miles. Steer for Goat Island lighthouse on a 330° true (N by W ¼ W mag.) course until up with The Old Prince bell buoy, which lies 600 yards from the lighthouse. Pass close westward of the bell buoy, steer about 315° true (NNW ⅝ W mag.), and pass 100 to 150 feet westward of the red spindle abreast the lighthouse and 50 to 60 feet eastward of the black buoy lying 300 yards above the lighthouse. Continue the course about 150 yards above the buoy and then steer 347° true (N ¼ E mag.) for the wharf on the west side of Bickford Island. Anchor on or a very little westward of this line, keeping 200 yards or more southward of the wharf.

The wharf has a depth of about 12 feet, at the outer half; the inner half is nearly bare. It is used by many fishing boats. Gasoline is obtainable, and provisions in **Cape Porpoise**, a village near the wharf. There is communication by electric railway.

Southwestward of Goat Island lighthouse is an area of broken ground, with depths of 3¼ to 5½ fathoms, which has not been closely examined. Its southern end is a 5½-fathom spot lying 1¼ miles from shore and 2¼ miles south-southwestward of Goat Island lighthouse. The lighthouse bearing 0° true (N by E ½ E mag.) leads eastward of the broken ground.

Kennebunk River, about 2½ miles westward of Goat Island lighthouse, is the approach to the summer resort of **Kennebunkport**, just inside its entrance. The beach for ¾ mile eastward and 1¾ miles westward of the entrance is lined with hotels and summer houses. The entrance to the river is between two stone jetties, the easterly one being marked by a light on the end. In 1917 there was a depth of about 4 feet at low water across the bar at the entrance, and in a narrow channel inside to the wharves just below the bridge, 1 mile above the entrance.

The channel is sometimes marked by stakes inside the entrance, but local knowledge is necessary to carry the best water across the bar and inside. The deepest draft entering is an occasional vessel of 12 feet draft, loaded with coal. The river is frequented mostly by small pleasure craft. The bridge 1 mile above the entrance has a draw 46 feet wide. There is a yard just above the bridge for building wooden vessels. Gasoline and provisions are obtainable at the wharves near the bridge. Kennebunkport has railroad and electric road communication.

Fishing Rock, bare at half tide and marked by a black spindle, lies ⅝ mile southwestward of the entrance of Kennebunk River. About 600 yards eastward of the spindle is a black buoy, placed off the southeast side of rocks that are awash at lowest tides. A rock with 9 feet over it lies ½ mile southward of Fishing Rock spindle, and is marked on its south side by a black buoy.

Oaks Reef extends ½ mile south-southwestward from the shore west of Kennebunk River entrance. A rock near the middle of the reef is marked by a black spindle. Near the south end of the reef is an-

Digitized by Google

other black spindle, which lies about 3/8 mile west-northwestward of Fishing Rock spindle.

Kennebunk Beach is a post village extending 1 mile westward of Kennebunk River entrance. Ledges extend 3/4 mile from shore southward of the village. There is a prominent yellow bluff at the western end of Kennebunk Beach.

Wells Beach extends 6 1/2 miles southwestward from Kennebunk Beach to the village of **Ogunquit**. The beach southward of **Webhannet River** has numerous cottages. The principal outlying dangers are Fishing Rocks, and **Bibb Rock**, which is bare at low water and lies 7/8 mile from shore and 3 1/2 miles north-northeastward of Bald Head Cliff. The principal marks are a standpipe a little northeastward of **Wells**, the cupola of the town hall at Wells, a church spire 1 1/4 miles southwestward of Wells, and a standpipe at Ogunquit. There is an inlet abreast the village of Wells, said to have a depth of 2 to 3 feet at low water in 1917, across the bar to a fish wharf inside, and used by small local boats at half tide or higher. It is unsafe for strangers.

Bald Head Cliff is a high, prominent point 3 miles north-northeastward of Cape Neddick. It is marked by a hotel and outbuildings, not prominent until close to.

Cape Neddick Harbor is a foul bight 3/4 mile northward of Cape Neddick. It is sometimes used as an anchorage by local boats, but is exposed, has many dangers, and should not be used by strangers. Buoys mark the entrance, but the dangers inside are unmarked.

Cape Neddick is a prominent headland extending out about 1 mile from the main shore; off its eastern end is a small, high islet, called **Cape Neddick Nubble**, on which is Cape Neddick lighthouse. **York Beach** is a large village and much frequented summer resort in the bights northward and southward of the cape. There are no wharves.

Cape Neddick lighthouse is a white conical tower. The light is fixed red, 88 feet above the water, and visible 14 miles. The fog signal is a bell (one stroke every 15 seconds).

Boon Island, lying 5 3/4 miles southeastward of Cape Neddick, is a small, low, rocky islet marked by Boon Island lighthouse, an important offshore aid. A black spindle is placed 250 yards westward of the lighthouse. The island is surrounded by deep water, but there are numerous detached ledges in the vicinity. The easternmost is **Boon Island Ledge**, 2 3/4 miles eastward of the lighthouse; it is bare at extreme low water and marked at the south end by a gas and whistling buoy. Vessels should not pass between this buoy and the lighthouse; and if passing westward of the lighthouse, should give it a berth of 1 3/4 to 3 1/2 miles to insure a depth of over 5 fathoms.

Boon Island lighthouse is a white conical tower connected with dwelling. The light is fixed white, 133 feet above the water, and visible 18 miles. The fog signal is a bell, sounded in answer to signals.

York Harbor.—This harbor (chart 228), 2 1/2 miles southwestward of Cape Neddick and 5 1/2 miles northeastward of Portsmouth Harbor entrance, is the approach to the town and summer resort of York Harbor, on the north side just inside the entrance. It is used by many fishing boats and small pleasure craft and an occasional vessel loaded with coal or bricks, the deepest draft being 12 feet. There is a depth of 10 feet in the channel through the entrance and for nearly

Digitized by Google

2 miles above, but the entrance is crooked and narrow and leads between rocks, bare and submerged, on either side. The width of the channel, with a depth of 10 feet, is only 150 feet in several places in the entrance. The channel is buoyed in the entrance and easily entered by small craft in clear weather with the aid of the chart. There are no marks above the entrance.

BLACK ROCKS are two bare rocks on the north side of York Harbor at the entrance. A red buoy lies southward of them. STAGE NECK is the name given to the peninsula, ¼ mile long on the north side, a little inside the entrance. A large hotel (Marshall House) and a brick chimney on a smaller building are prominent. A rock with a depth of 3 feet lies 100 yards southward of the eastern end of Stage Neck and is marked by a red buoy. ROCKS NOSE is a bare ledge extending 150 yards northeastward from the shore on the south side, southward of the middle of Stage Neck.

YORK HARBOR is a town and summer resort on the north side of York River. There are depths of 8 to 9 feet at the wharves in the bend northward of the western end of Stage Neck. Gasoline and provisions are obtainable. There is good anchorage off the wharves in 10 to 20 feet. York Harbor has communication by railroad and electric roads.

YORK RIVER ABOVE YORK HARBOR.—This section of the river is crossed by four bridges within a distance of 3½ miles of the entrance, all having draw openings, the least width of openings being 32 feet. It is frequented mostly by vessels to the brick yards between the third and fourth bridges, the deepest draft being 10 feet. The channel is unmarked and difficult without local knowledge. The river is navigable for small vessels for about 4 miles above the entrance.

DIRECTIONS, YORK HARBOR.—Vessels approaching York River entrance should give the shore northward or southward a berth of at least ¼ mile, or they can shape the course to the bell buoy 1 mile off the entrance. From the bell buoy steer 298° true (NW ⅛ W mag.) for 1 mile to a position midway between a red and a black buoy at the entrance. Then steer 268° true (WNW ¾ W mag.) for ⅜ mile, passing 50 yards southward of a red buoy and to a position 70 yards northward of the northerly bare rock of Rocks Nose. Then steer 245° true (W ⅞ N mag.), passing close southward of a red buoy. Pass 50 yards westward of the western end of Stage Neck and follow the northwest side of Stage Neck at a distance of 70 yards to the wharf abreast the hotel; then head for the wharves on the north side or anchor in the channel off the wharves.

Between Cape Neddick and the entrance to Portsmouth Harbor, a distance of 8 miles, the shore has no marked indentations except York River. Lying offshore 2½ miles are two dangerous ledges; **York Ledge**, the northernmost of these, lies southeastward of York River entrance and is marked by a spindle. **Murray Ledge**, 1½ miles southwestward of York Ledge, has a least depth of 1 fathom and is marked by a horizontally striped buoy. The bottom is very broken between these ledges and the shore, and vessels are advised to pass outside of the whistling buoy 1 mile outside the ledges. Broken ground, with depths of 5¼ to 6½ fathoms, extends 2 miles south-southeastward of Murray Rock buoy.

Digitized by Google

PORTSMOUTH HARBOR

(chart 0329), lying 37 miles southwestward of Cape Elizabeth and about 26 miles northward of Cape Ann lighthouses, is the only harbor of refuge for deep-draft vessels between Portland and Gloucester. The entrance is marked by Whaleback and Portsmouth Harbor lighthouses, and the principal outlying dangers are marked, so that no difficulty should be experienced when entering in clear weather, either in the daytime or at night. Portsmouth Harbor is formed by the mouth of Piscataqua River, and is the approach to the cities of Portsmouth and Dover and the towns of Newcastle, Kittery, South Newmarket, and Exeter; on the north side of the harbor, opposite Portsmouth, is the United States navy yard.

Portsmouth has considerable trade in large coasting vessels and barges, principally in coal; their draft seldom exceeds 20 feet, although the depth into the harbor is sufficient for the largest vessels with local knowledge.

Prominent objects.—In approaching Portsmouth Harbor from sea, the most prominent objects are Whaleback lighthouse in the entrance, a red hotel and detached tower on the north side of the entrance, and a large white hotel on the southwest end of Newcastle Island. Several marks in Portsmouth and at the navy yard are also visible. **Portsmouth Harbor lighthouse**, on the northeast end of Newcastle Island, is a white tower attached to a brown building on a white foundation.

Whaleback lighthouse is a gray conical tower connected to red fog-signal house. The light is group flashing white (flash 0.4 second, eclipse 1.4 seconds, flash 0.4 second, eclipse 7.8 seconds), 59 feet above the water, and visible 13 miles. The fog signal is a reed horn (blast 5 seconds, silent 25 seconds).

A number of rocks and ledges, some of them bare at low water, extend about 1½ miles eastward of Whaleback lighthouse and to a distance of ¾ mile from the shore. They are marked by a red buoy on the east side and another on the south side.

Little Harbor is a good anchorage for small craft and vessels of about 10 feet draft, and lies on the west side of the entrance to Portsmouth Harbor, ¾ mile westward of Whaleback lighthouse. Vessels should not attempt to enter in bad southeasterly weather, when the sea breaks across the entrance. The entrance is between two breakwaters, the ends of which are marked by lights, and two buoys mark the entrance outside the breakwaters. Inside the breakwaters an anchorage basin has been dredged 2,000 feet long and 600 feet wide, with a depth of 11 feet or more, and is marked on its north side by red buoys. There is room only for very small craft to anchor in the channel above the inner red buoy. The Wentworth is a large white hotel on the north side of the harbor.

To enter Little Harbor, from a position 600 yards southwestward of Kitts Rocks whistling buoy steer 303° true (NW ¼ N mag.) for the cupola of the Wentworth showing just northward of the light on the end of the south breakwater. Pass between the two buoys at the entrance, pass about 100 yards southwestward of the light on the end of the north breakwater and midway between it and the light on the south breakwater, and pass midway between the latter light and the red buoy lying 400 feet northeastward of it. Then steer 269°

Digitized by Google

true (WNW ¾ W mag.) and anchor 200 to 400 feet southward of the line of red buoys.

A narrow thoroughfare, bare at low water, connects the western end of Little Harbor with Portsmouth Harbor between **Marvin** and **Goat Islands.** It is crossed by two bridges and is little used.

Pepperell Cove is on the eastern side of the harbor, northeastward of Portsmouth Harbor lighthouse, and on the north side of **Fishing Island** (grassy, with two shanties). It has been dredged to a depth of 12 feet for an anchorage, and is used by many small coasting vessels and yachts. A red buoy marks the south side at the entrance. **Kittery Point** is a village at the head of the cove. There is a wharf, nearly bare at low water, on the northeast side of the cove abreast the village.

Newcastle is a village on the south side of the harbor and the north end of **Newcastle Island.** It is reached from Portsmouth by crossing several bridges which connect the islands on the south side.

Portsmouth is on the south side of Piscataqua River, about 4 miles above the entrance to the harbor. Vessels of 23 feet draft can lie afloat at the principal wharves.

The United States Navy Yard is on **Seavys Island,** on the north side of the river opposite Portsmouth. It is connected with Kittery, on the north shore, by a fixed bridge. The channel northeastward of Seavys Island has several dangers and is little used except by a few boats going to the navy yard.

Kittery is a town on the north side of Piscataqua River opposite Portsmouth, with which it is connected by a highway bridge and by ferry. There are landings for small craft and one wharf to which small vessels go. The approach to the wharves is between Badgers and Squash Islands on the northwest and Pumpkin Island on the southeast and requires local knowledge for anything except small craft.

Piscataqua River above Portsmouth (chart 229).—The river above Portsmouth forms the approach to Cochecho, Bellamy, Oyster, Lamprey, and Exeter Rivers, the towns of Durham, Newmarket, and Exeter, and the city of Dover, all on the railroad. It has ample depth for 3½ miles above the bridge at Portsmouth to the fork, and the principal dangers are buoyed to this point. The channels in the several branches are narrow and crooked and shoal at the heads, and local knowledge is necessary to keep in them. Some of them have been improved by dredging. There is little business by water above Portsmouth, except in small craft and an occasional cargo of coal, the deepest draft being about 10 feet at high water. The tidal currents are very strong in places. Pilots or towboats can be obtained at Portsmouth.

A combined railroad and highway drawbridge crosses Piscataqua River just above the wharves at Portsmouth. It has a lift draw on the east side of the river, with an opening 57 feet wide. There are several openings for small craft without masts underneath the bridge.

Another drawbridge crosses the western branch of Piscataqua River 3½ miles above the first bridge. It has a center-pier draw, northerly opening 49 feet, southerly opening 48 feet wide, and a headroom of 8 feet at high water when closed.

Digitized by Google

Cocheco River has a depth of about 6 feet in a narrow, crooked, unmarked channel to the city of Dover, 10 miles above Portsmouth. Local knowledge is necessary to keep in the channel. There are several factories at Dover, but little business by water.

Bellamy River has a depth of about 4 feet in a narrow, crooked, and unmarked dredged channel to within ¼ mile of a woolen mill at Dover, above which it is shoal to the mill. Local knowledge is necessary to keep in the channel. It is seldom used.

Oyster River has a narrow, crooked, and unmarked channel, bare at low water, to the village of Durham, 8½ miles above Portsmouth. It is seldom used.

Lamprey River has a depth of about 4 feet in a narrow, crooked, and unmarked channel to the village of Newmarket, 12 miles above Portsmouth. It has little business by water.

Exeter River has a depth of about 4 or 5 feet in a narrow, crooked channel, dredged in places, to the town of Exeter, 16½ miles above Portsmouth. The approach to the river is through Little Bay and Great Bay, and the channel through these bays is partially marked by buoys and sometimes by bush stakes. Local knowledge is necessary to keep in the channel through these bays and the river above. There is little business by water.

Pilots.—Pilotage into Portsmouth Harbor is compulsory for all vessels engaged in foreign trade, but not for vessels engaged in the domestic trade. There are licensed pilots for Portsmouth Harbor and Piscataqua River; sailing vessels, if bound to the wharves at Portsmouth or any of the towns on the Piscataqua River or its branches, take a towboat from the anchorage. A pilot to the anchorage is not necessary in clear weather when the aids can be seen. The towboat captains are usually licensed pilots.

Towboats are on the lookout for vessels expected to arrive, and if the tide is slack will tow alongside the wharves without any delay. A vessel desiring a towboat while outside Whaleback lighthouse can obtain one by making the usual signal (flag in rigging). From the anchorage, steamers generally take a towboat when going to the wharves or to the navy yard.

Anchorages.—The anchorage for large vessels is anywhere on the east and north sides of the channel between Wood Island (the island north of Whaleback lighthouse) and Clark Island (the small island on the north side about ¾ mile above Fort Constitution), in 8 to 11 fathoms. With a southerly wind the best anchorage is above Fort Constitution on the south side of the channel, in 8 to 10 fathoms, bottom generally clay. There is no anchorage above Clark Island. See also the description of Little Harbor and Pepperell Cove preceding. Yachts and small coasting vessels generally anchor in Pepperell Cove.

Supplies.—Coal can be obtained at the wharves at Portsmouth, water from the towboats or alongside the wharves; gasoline, provisions, and a limited supply of ship-chandler's stores are obtainable in Portsmouth.

Repairs.—There is a small marine railway at the yacht club at Portsmouth that will take out small craft not over 55 feet long and 7 feet draft. Vessels requiring repairs to hull and machinery usually go to Portland or Boston. There are machine shops at Portsmouth for minor repairs.

Digitized by Google

Storm-warning displays are made at Portsmouth, the navy yard, and Wood Island.

Ice.—In ordinary winters Portsmouth Harbor is free from ice, but during severe winters there is considerable drift ice which comes down the river with the ebb current; it is seldom an obstruction to navigation and never interferes with vessels at anchor below Clark Island.

Currents.—The tidal currents have great velocity and require special care. It is slack water about 1½ hours after high and low water at Portland, and the duration of the stand is about 10 minutes. The current attains its maximum velocity about 1½ hours before high and low water at Portland. The mean maximum velocity of the flood and ebb current, above Fort Constitution, is about 3 knots; but during spring tides it is much greater, probably 6 knots.

Tides.—The mean rise and fall of tides is 8.7 feet at Portsmouth and about 6½ feet at the heads of the tributaries.

DIRECTIONS, PORTSMOUTH HARBOR.

The broken ground off the entrance to Portsmouth Harbor, and the main channel in the harbor as far as Clark Island, have been examined by means of the wire drag. The outer limit of the dragged area off the entrance is about 1½ miles eastward of Boon Island Ledge gas and whistling buoy and 4 miles eastward of the Isles of Shoals. The northerly limit is about 2½ miles north-northeastward of Boon Island lighthouse, and the southerly limit about 6½ miles southwestward of Isles of Shoals. The dangers close along the shore were not covered with the wire drag.

From northeastward.—The channel westward of York Ledge spindle and Murray Rock buoy is safe only for small craft with a smooth sea, and all strangers are advised to pass outside of these dangers. Directions to York Ledge whistling buoy from northward are given on page 46. The following courses lead in a least depth of 6½ fathoms, which is found on spots 2½ miles northeastward of Isles of Shoals. From York Ledge whistling buoy, steer 196° true (SSW ¾ W mag.) for 2⅜ miles, heading for the tripod beacon on Duck Island, at the north end of Isles of Shoals, until 2 miles from it and Whaleback lighthouse bears 286° true (NW by W ¼ W mag.); then steer 275° true (WNW ¼ W mag.) for 4⅜ miles to a position ¼ mile southward of Kitts Rocks whistling buoy, and pass ⅜ mile westward of it.

From southward.—Small vessels of 12 feet or less draft can approach the entrance of Portsmouth Harbor from southward by following the shore at a distance of 1 mile or more. They should avoid Hampton Shoal Ledge, and pass outside of Gunboat Shoal bell buoy; or the following course can be used by vessels of the deepest draft. From White Island whistling buoy, lying 1¾ miles southwestward of Isles of Shoals lighthouse, steer 340° true (N ⅜ W mag.) for 6½ miles, passing ½ mile eastward of Gunboat Shoal bell buoy, and to a position ⅜ mile westward of Kitts Rocks whistling buoy.

Kitts Rocks to Portsmouth.—The following courses lead over a least depth of about 36 feet southwestward of Whaleback lighthouse, and close westward of a rocky spot with a depth of 34 feet, eastward of Portsmouth Harbor lighthouse. Strangers in deep-draft vessels should not go above the anchorage without a pilot or towboat. Pass

Digitized by Google

⅜ mile westward of Kitts Rocks buoy and steer 344° true (N mag.) heading for Portsmouth Harbor lighthouse, for ¾ mile, passing a little over ¼ mile westward of Whaleback lighthouse, and to a position 300 yards westward of the red buoy northwestward of the lighthouse. Then steer 0° true (N by E ⅜ E mag.) for ¾ mile to a position 350 yards eastward of Portsmouth Harbor lighthouse, and anchor on the north side of the channel northward of the lighthouse or in Pepperell Cove, according to draft.

If going to Portsmouth, pass ¼ mile northward of the lighthouse and 250 yards northward of the black buoy northward of the lighthouse, and steer 264° true (W ⅞ N mag.) for 1⅛ miles, passing 150 yards southward of Clark Island and midway between a black gas buoy and the south side of Seavys Island; the current in this vicinity is strong and care should be taken not to be set on the ledge on the south side of the channel, marked by the black gas buoy. Round the southwest point of Seavys Island at a distance of 100 yards and steer 325° true (N by W ¾ W mag.) for ⅜ mile to a position 300 yards north-northeastward of a stone beacon with spindle, and 125 yards from Seavys Island, then steer 272° true (WNW ½ W mag.) to the wharves of Portsmouth, passing 125 yards southward of a light and a spindle marking the shoals between Seavys and Badger Islands.

ISLES OF SHOALS.

This group of islands (chart 330 or 1206) lies from 5 to 6 miles offshore southeastward of Portsmouth Harbor entrance. It comprises seven islands and a number of rocks and ledges. The group is about 3 miles long in a northeasterly direction and is marked at its southwest end by Isles of Shoals lighthouse. There are several channels between the islands, but they are used only by local fishermen, who sometimes seek shelter there in easterly winds.

Isles of Shoals are frequented mostly by the people connected with the Coast Guard station and lighthouse, a few fishermen, and some summer residents. Small steamers sometimes run from Portsmouth to the islands in summer, but none were in operation in 1918. Storm warning displays are made. Gosport Harbor is well protected except from westerly winds and is considerably used as an anchorage by local fishermen and sometimes by small coasting vessels and yachts.

Duck Island, the northernmost of the group, is low, rocky, and surrounded by ledges, and should be given a berth of ½ mile. In 1917 there was a large skeleton tripod beacon near the middle of the island.

Appledore Island, the largest of the group, lies about 1 mile southwestward of Duck Island. It is high and has several summer cottages and hotels near the middle of the island, and a landing on its western side. The channel between Duck and Appledore Islands has depths of 5½ to 15 fathoms, irregular bottom. There is a small 8-foot spot marked by a black buoy 300 yards northwestward of the island.

Smuttynose Island lies southward of Appledore Island, with a narrow channel between them having a depth of 3¼ fathoms. There are several houses near the western end of this island and a small cove, **Haley Cove**, where boats lie aground at low water.

Cedar Island is southward of Smuttynose, and is connected with it by a breakwater; westward of this breakwater is **Gosport Harbor**, a

Digitized by Google

small anchorage used by fishermen and others during easterly winds. Another breakwater has been built between Cedar and Star Islands.

Star Island, westward of Cedar Island, has on its northern side several houses and a steamboat landing with a depth of about 18 feet.

Lunging Island is a low, bare, rocky islet, surrounded by ledges and lying ½ mile westward of Star Island. The channel between these islands is obstructed by rocks which are marked by a buoy.

White Island is the southernmost of the group and is marked by Isles of Shoals lighthouse; ledges extend ¼ mile southwestward and westward from the island.

Isles of Shoals lighthouse is a white conical tower. The light is flashing white and red (white flash 3.7 seconds, eclipse 11.3 seconds, red flash 3.7 seconds, eclipse 11.3 seconds), 82 feet above the water, and visible 15 miles. The fog signal is an air siren (blast 3 seconds, silent 27 seconds).

Anderson Ledge, bare at half tide and marked by a spindle, lies 1 mile east-southeastward of Isles of Shoals lighthouse, and is the farthest outlying danger. The ledge is about 200 yards in diameter and has good water around it.

Cedar Island Ledge shows bare at low water and lies ⅜ mile southeastward from Cedar Island; it is about 300 yards long east and west, and is surrounded by deep water.

Remarks on approaching and passing Isles of Shoals.—The islands can be seen a distance of 10 miles on a clear day, the houses being most prominent, and vessels passing westward can avoid all danger by giving them a berth of ½ mile. Passing eastward, care should be taken to avoid Cedar Island and Anderson Ledges; giving the islands a berth of 1¼ miles leads well clear. Isles of Shoals lighthouse covers the entire horizon, but the houses on the islands northward shut the light out occasionally when approaching the islands from that direction. A stranger desiring to land on the islands should be guided by chart 330.

COAST FROM PORTSMOUTH TO NEWBURYPORT.

From Portsmouth Harbor entrance to Hampton Harbor, a distance of about 10 miles, the coast has a general southwesterly trend, with no marked indentations. It presents the appearance of a succession of sand beaches separated by ledges extending out about ½ mile, with occasional hotels and summerhouses back of the high-water line.

Wallis Sands, 2¾ miles southwestward of Whaleback lighthouse, is marked by the yellow building of a Coast Guard station where storm-warning displays are made. At the southern end of Wallis Sands, **Foss Ledges,** partly bare at low water, extend ½ mile offshore.

Rye Harbor is a small cove, almost entirely bare at low water. About ⅝ mile southwestward of the cove is Rye Beach Coast Guard station, where storm-warning displays are made. **Rye Beach** is a summer resort extending about 1 mile southwestward from the station. At the southern end of the beach, **Rye Ledge,** partly bare at high water, extends over ⅜ mile from shore.

Little Boars Head is a yellow bluff 7 miles southwestward of Whaleback lighthouse. A summer resort of the same name extends over ½

Digitized by Google

mile northeastward from the bluff. A bare ledge lies ⅜ mile off the bluff.

Great Boars Head is a bluff point making out ¼ mile at the southern end of Hampton Beach and 9½ miles southwestward of Whaleback lighthouse. The summer resort of **Hampton Beach** extends northward and southward from the point. On the point is a prominent, tall standpipe, which is the best mark for this part of the coast. A ledge partly bare at low water extends 400 yards off the point.

Hampton Harbor, or **Hampton River**, a shallow stream used only by very small local craft, lies 1½ miles southwestward of Great Boars Head. The entrance is not safe for strangers. There is a trestle across the mouth of the river, under which small craft can pass. A bar and ledges make off from the river to **Old Cellar Rock**. The latter is a reef, ¾ mile long and partly awash at high water, the northeast end of which lies ⅞ mile from shore. **Hampton Shoal Ledge**, with 19 feet over it, lies 2½ to 2¾ miles from shore off Hampton River and 131° true (SE by S mag.) from Great Boars Head. It is unmarked.

From Hampton Harbor the coast extends 4½ miles in a southerly direction to the entrance of Merrimac River and is known as **Salisbury Beach**. **Cushing**, a summer resort, extends along the beach from the Coast Guard station southward to the entrance of the river, a distance of nearly 2½ miles. A ledge, with a reported depth of 3 feet over it, lies ¾ mile offshore eastward of the station, and is marked at its northeast end by a red buoy.

MERRIMACK RIVER AND NEWBURYPORT HARBOR.

Merrimack River is the largest and most important river in the eastern part of Massachusetts. It is the approach by water to the cities of Newburyport and Haverhill, and the towns of Amesbury, Merrimacport, Groveland, and Bradford, and is used by vessels of 10 feet draft at high water up to Haverhill and 17 feet draft at high water to Newburyport. The river is seldom entered for refuge, but the towns on its banks have some coastwise trade, mostly in coal.

The entrance (Newburyport Harbor, chart 331) is obstructed by a shifting bar, with 10 to 13 feet over it (according to the condition of the bar), which is dangerous to cross in heavy weather. It is marked by Newburyport lighthouse on its southern side and two range lights on its northern side, in addition to the buoys. The range does not always lead in the best water across the bar and the buoys should be followed. Jetties with an opening 1,000 feet wide between the ends have been built from both points at the entrance out to the bar.

Channel.—After crossing the bar, Merrimack River has a least depth of about 12 feet at low water for a distance of 7 miles above the entrance to a point ½ mile above the entrance of Powow River, except on a bar 2½ miles inside the entrance, where the depth is only 10 feet. From that point to Haverhill, about 18 miles above the entrance, the river has been improved by dredging a channel 150 feet wide and 7 feet deep at low water.

Newburyport Harbor lighthouse, on the south side of Merrimack River entrance, is a white conical tower. The light is fixed white, 50 feet above the water, and visible 12 miles.

Digitized by Google

Newburyport is a city on the south bank of the river 3 miles above the entrance. It has considerable trade, mostly in coal. The deepest draft going to the town is about 17 feet, and the usual draft does not exceed 14½ feet; vessels always enter at high water. There are depths of 12 to 15 feet at the wharves. It is on the Boston & Maine Railroad. A high yellow chimney is the most prominent mark from outside.

Amesbury is a town on the **Powow River** 1 mile above Merrimack River and 7½ miles above Merrimack River entrance. There are coal wharves on the main channel of Merrimack River to which vessels of 13 feet draft go, and on Powow River to which vessels up to 9 feet draft go.

Merrimacport is a village on the north side of Merrimack River about 10 miles above the entrance. It has a coal wharf to which vessels of 6 to 9 feet draft go.

Groveland is a town on the south side of the river 15 miles above the entrance. There is a coal wharf to which vessels of 6 to 9 feet draft go.

Haverhill is a city on the north bank at the head of navigation on Merrimack River, 18 miles above the entrance. It has some trade, mostly coal brought up in barges, the deepest draft being 10 feet and usual draft 6 to 8 feet. Some of the wharves have depths of 10 feet or more. **Bradford** is a town opposite Haverhill, with which it is connected by a highway bridge.

Bridges.—Merrimack River is crossed by eight bridges between Newburyport and the head of navigation at Haverhill. All except the two upper have draw openings. The following are their distances above the ends of the jetties at the entrance, the least width of the draw openings, and the clear height above mean high water when closed:

Highway bridge (Newburyport), 3.2 miles, 76 feet (north) 71 feet (south), 13 feet.

Boston & Maine Railroad, 3.3 miles, 69 feet (north) 64 feet (south), 13 feet.

Deer Island (North Channel, highway), 5.3 miles, 54 feet, 8 feet.

Rocks (highway), 11.3 miles, 54 feet, 17 feet.

Groveland (highway), 14.7 miles, 64 feet, 14.5 feet.

Haverhill (highway), 17.2 miles, 38 feet, 19 feet.

Boston & Maine Railroad, 17.7 miles, no draw, headroom 37 feet.

County bridge (highway), 17.8 miles, no draw, headroom 30 feet.

The draws of all bridges will be opened at all times on a signal of two long blasts followed by two short blasts of a whistle or horn, except when a tram, car, or other vehicle is passing over the bridge or approaching it so closely that they can not be safely stopped before reaching the draw. The signal from the bridge shall be three long blasts if the bridge can be opened immediately or two long blasts if it can not be opened immediately.

Prominent objects.—In approaching the entrance of Merrimack River the most prominent objects are the cottages on both sides at the entrance, the large hotels at Cushing, 1½ miles north of the entrance, and a prominent yellow chimney, and other marks at Newburyport. The jetties are also distinguishing marks when close in.

Digitized by Google

Anchorage.—The usual and best anchorage in the river is in the channel just above Black Rock beacon and 1¼ miles inside the ends of the jetties in 13 to 16 feet.

Pilots.—Strangers entering the river should take a pilot, and it is advisable for all vessels of over 9 feet draft to take one, as the channel over the bar changes after heavy easterly gales. Vessels bound up the river above Newburyport should take a pilot or towboat. Pilots can be had by making signal outside the bar, standing off and on outside the whistling buoy until boarded. Pilotage is compulsory only for vessels engaged in the foreign trade, of which none enter.

Towboats can be had at Newburyport; most vessels entering the river, and sailing vessels bound up the river, usually take one. The towboat captains are usually licensed pilots.

Supplies.—Coal in large quantities can be obtained in Newburyport alongside the wharf or in lighters. The water in the river is fresh for about seven months in the year. Water and some ship-chandlers' stores can be had at Newburyport, and gasoline and provisions at any of the towns on the river.

Repairs.—There is a railway at Newburyport, for hauling out launches up to 15 tons, and machine shops for ordinary repairs.

Storm-warning displays are made at Newburyport.

Freshets sometimes occur in the spring, but as a rule they do not interfere with navigation.

Ice seldom obstructs navigation as far as Newburyport; drift ice may sometimes interfere with vesels under sail, but steamers and vessels assisted by towboats can usually work their way through. Westerly winds carry the drift ice out to sea; during their continuance the flood current has no effect upon the local formations or drift ice. With the wind from any other direction, the flood current will prevent the drift ice from leaving the river.

Tides.—The mean rise and fall of the tides is 7.9 feet at the entrance and about 5 feet at Haverhill at low river stage.

Directions, Merrimack River.—The river for a distance of 5½ miles above the entrance is shown on chart 331. Above that point no chart is available. There is a whistling buoy outside the bar, and the channel across the bar is marked by a lighted range and by buoys, but is subject to some change, and strangers in vessels are advised to take a pilot. The lighted range does not always mark the best water, but the buoys are usually shifted to conform with changes in the channel. Small craft may enter with a smooth sea and on a rising tide by following the buoys. The river can not be entered with a heavy sea.

After crossing the bar, the channel is well marked and easily followed to Newburyport. A lighted range leads across a bar with a depth of about 10 feet just before reaching the wharves at Newburyport. The channel on the range leads between a red and a black pyramidal beacon with spindle, marked "north base" and "south base" on the chart. The range shows about 50 yards to the right of a high yellow chimney, and a few feet to the left of a low square chimney farther back.

The channel between Newburyport and Haverhill is marked by buoys at the most difficult points, but it is narrow and crooked, leads close to rocks in places, and local knowledge is necessary to keep in it. A pilot can be obtained at Newburyport.

Digitized by Google

Merrimack River can be entered by small craft from Plum Island Sound through Plum Island River (described below).

MERRIMACK RIVER TO CAPE ANN.

From Merrimack River entrance the coast is sand dunes and trends southward for about 7½ miles to the entrance of Plum Island Sound and Ipswich River. There are many cottages on the south side of Merrimack River entrance, and scattered cottages southward along the beach. Inside the beach is Plum Island Sound and several tributaries forming the approach to villages at their heads.

Plum Island River forms a thoroughfare for small craft between Merrimack River, just inside its entrance, and Plum Island Sound. It is bare at low water and is said to have a depth of 7 or 8 feet at high water, but the deepest draft using it at high water with local knowledge is about 5 feet. The channel is narrow and unmarked, does not always lead in mid-channel, and local knowledge is necessary for its navigation. It is crossed by a drawbridge having a draw opening 30 feet wide. The approach to the north end of the thoroughfare is between the east side of Woodbridge Island and the west end of a dike, covered at high water and unmarked.

Plum Island Sound (chart 1206) is the approach to several small rivers and villages and is frequented by many small craft. Vessels seldom enter. It had a depth in 1917 of about 6 feet at low water across the bar. The channel is marked by a lighted range and by buoys; it is subject to change, and the range does not always mark the best water. In 1917, the best water led across the bar on a west-southwesterly course, and then followed the south shore, as shown on the chart, until inside the bay. After crossing the bar, the channel through the bay has a least depth of about 7 feet to the entrances of Parker River and Plum Island River. The channel is marked by buoys, but is narrow and crooked, and difficult without local knowledge.

Ipswich River, emptying into the south end of Plum Island Sound from westward, has been improved by dredging in the lower end to a depth of 6 feet, but the channel at the entrance had shoaled in 1917 to about 3 feet, and this was the most difficult point. After entering the river, there was a depth of about 4 feet to the town of **Ipswich,** on the railroad 2½ miles above the entrance. The channel above the entrance was well marked in 1917 by private spindles, on which lights are maintained during the summer. The river is frequented by many pleasure craft. Gasoline and provisions are obtainable at Ipswich. **Little Neck** is a summer settlement on a prominent hill on the east side at the entrance of Ipswich River. It has a wharf with a depth of about 5 feet.

Rowley River, emptying into Plum Island Sound near its middle, has a depth of about 2 feet to a landing near the railroad station of **Rowley,** 2 miles above the entrance. The village of Rowley is about 1 mile from the station.

Parker River, emptying into the north end of Plum Island Sound from westward, has a depth of about 5 feet in a very narrow channel to a fixed bridge at **Newbury Old Town,** 1¾ miles above the entrance. The channel is marked by buoys, some of them private, but is difficult without local knowledge. Newbury Old Town is a summer settle-

Digitized by Google

ment, and has a wharf just below the bridge with a depth of about 12 feet, and several float landings. Gasoline and some provisions are obtainable in summer. It has communication by electric road with Newburyport. The river is navigable by small craft for several miles above Newbury Old Town, but is little used. All of the bridges are fixed.

Ipswich Bay is the bight between the northern point of Cape Ann and Plum Island Beach. Between these points it is about 6 miles wide and makes in southward about 3 miles. The bay is the approach to Ipswich, Essex, and Annisquam Rivers, and has a depth of 4 to 15 fathoms, except in its southern and southwestern sides, where the shore should be given a berth of a little over 1 mile to avoid the shoals off the river entrances.

Essex Bay and **River** (chart 243) lie midway between Ipswich and Annisquam lighthouses. The entrance is over a shifting bar, over which a depth of about 3 or 4 feet can be carried at low water through a narrow buoyed channel. The river is navigable to the town of **Essex**, 4 miles above its mouth, through a narrow channel about 3 feet deep at low water. Vessels of 12 feet draft, with local knowledge, have been taken over the bar to an anchorage inside the entrance. By communication with Essex, arrangements may be made to have a pilot come off to a vessel outside the entrance; a pilot or towboat may be had at Gloucester. There are shipyards at Essex where wooden vessels are built, and otherwise there is no traffic except by local fishermen and launches. Local knowledge is necessary to follow the channel across the bar and in the river. Two houses on the east side at the entrance are prominent.

CAPE ANN.

Under this heading is described Annisquam River and all of the cape eastward of this thoroughfare except Gloucester Harbor. It is shown on chart 243.

Cape Ann is very rocky and broken, 235 feet high in its highest point, and covered with numerous summer homes. There are also several granite quarries. Communication is by railroad to Gloucester and Rockport, and by electric road entirely around the cape.

Annisquam River.—This is a thoroughfare leading from the eastern part of Ipswich Bay, north of Cape Ann, to Gloucester Harbor, on the south side of the cape. It has a depth of about 7 feet on a bar at the north end, and from inside the bar has been dredged where necessary to a depth of 8 feet at low water through to Gloucester Harbor. It is narrow and crooked, but is marked by buoys and beacons, and extensively used by many small craft and by vessels up to 10 feet draft. Strangers in small craft should have no trouble in going through with a smooth sea with the aid of chart 243; the best time is on a rising tide. The bar at the north end can not be crossed in a heavy sea. The mean rise and fall of tides is 8.8 feet.

The thoroughfare is crossed by two drawbridges near the south end. The southerly is a red highway bridge at the entrance from Gloucester Harbor, and forms the most distinguishing mark by which the entrance may be recognized. It is a double-leaf lift, with a single opening 50 feet wide and a headroom of 7.5 feet at high water when closed. The railroad bridge, 5/8 mile northward, has a single lift

Digitized by Google

opening 40 feet wide and a headroom of 23 feet at high water when closed.

ANNISQUAM HARBOR LIGHTHOUSE, on the east side at the northern entrance to Annisquam River, is a white cylindrical tower with a covered way to a dwelling. The light is fixed red, 45 feet above the water, and visible 7 miles.

ANNISQUAM is a village and summer resort on the east side of Annisquam River just inside its north end. There are several float landings, and anchorage for small craft in 5 to 8 feet in LOBSTER COVE, on the southeast side of the town, anywhere below the bridge. This harbor is frequented by numerous small craft in summer. A channel 6 feet deep and 50 feet wide has been dredged into Lobster Cove to near the bridge. The best water leads 50 feet southward of the stone beacon on the north side at the entrance and then leads the same distance off the wharves.

MILL RIVER is a tributary of Annisquam River, on the east side, ⅜ mile southward of Annisquam. A channel 6 feet deep and 60 feet wide, with an anchorage basin of the same depth, has been dredged into the river for a distance of ¾ mile from the entrance. There are numerous summer houses and float landings on the river, and it is used by many small craft in summer.

DIRECTIONS ANNISQUAM RIVER.—The following directions are intended only for small craft of 5 feet or less draft, with a smooth sea on the bar, and in clear weather. The best time is on a rising tide.

Steer for Annisquam lighthouse on about a 165° true (S mag.) course, and cross the bar between a red and a black buoy. Pass 100 yards westward of the lighthouse, 50 yards westward of Lobster Rock stone beacon ¼ mile south-southwestward of the lighthouse, and pass Babson Point, the southwest end of Annisquam, at a distance of 100 yards to avoid rocks close to the point, sometimes marked by bush stakes. Pass 75 yards off the yacht club wharf and bring the club house astern on a 177° true (S by W mag.) course until ¼ mile from it, then steer southwestward, pass 40 yards off the west side of Wheeler Point (covered with cottages), and close westward of the black beacon off Thurston Point.

Then steer south-southwestward for 300 yards close along the shore on the east, and pass close eastward of a red beacon. The channel then leads southwestward for ⅜ mile, passing close eastward of two red buoys and about 80 yards westward of the shore at Riverview (marked by many cottages). From the second red buoy, haul a little more southward to pass close westward of a black beacon, and then steer about 151° true (S by E ¼ E mag.) for ¼ mile, and pass eastward of two red buoys off Wolf Hill.

From the second red buoy, steer south-southwestward for 200 yards to pass close westward of a black beacon; pass 125 feet off the end of the point on the east side and 50 feet southwestward of the black beacon just southward of the point. Then steer 102° true (SE by E ½ E mag.) for a little over ¼ mile, and pass 60 feet northeastward of the red beacon just north of the railroad bridge. After passing through the railroad bridge, the course in the channel is 174° true (S ⅞ W mag.) for ¼ mile to a position 75 feet westward of a black beacon, then 129° true (SE ¾ S mag.) to its outlet into Gloucester Harbor. The channel in the south end is well defined by the banks.

Digitized by Google

Bay View is a village on **Hodgkins Cove**, ¾ mile northeastward of Annisquam lighthouse. There is a quarry and a long stone pier with a depth of 15 feet on the outer half of the southwest side, in a channel about 70 feet wide. The cove at the inner end of the pier on the northeast side has a depth of about 2 feet at the entrance and 3 or 4 feet inside. There are unmarked rocks in the entrance.

Lanes Cove, 1⅜ miles northeastward of Annisquam lighthouse, is a small cove protected by stone walls at the entrance, forming a harbor for small craft. It has a depth of 12 feet at the entrance and 10 feet in the middle inside. **Lanesville** is a village on the cove. The wharf forming the southwest side of the harbor has a depth of 7 feet at its outer end. The wharf on the east side is nearly bare at low water. Gasoline and some provisions are obtainable.

Folly Cove, on the north side of Cape Ann, 2½ miles east-northeastward of Annisquam lighthouse, has a quarry on the east side, and a wharf with a depth of 15 feet at the outer part, at which vessels load to a draft of 17 feet. The stone wharf on the northwest side of **Folly Point** is in ruins.

Ocean View is a summer settlement on Andrews Point, at the north end of Sandy Bay. There are no wharves.

Sandy Bay is the large bight in the northeastern shore of Cape Ann, between Straitsmouth Island on the east and Andrews Point on the west. Between these points the bay is 2 miles wide and about 1½ miles long to its head (Rockport Harbor). A breakwater has been partially completed to form a harbor of refuge. It extends 1,200 yards northward from Avery Ledge, then 830 yards northwestward toward Andrews Point. In 1917 it was awash at low water except for a distance of about 300 yards near the middle, where it was above high water. There is a gas buoy off the northwest end and a red bell buoy off the south end. In its present state the breakwater affords little protection from the sea, and there are no present plans for its completion. The bay and approaches have been examined by means of a wire drag. The depths inside the breakwater are 7 to 14 fathoms, with several rocky spots of less depth in the southern part. A 12-foot rock on the south side is marked by a black buoy. The bay is frequently used as an anchorage by schooners and tows. It is exposed in northeasterly weather, and at such times Gloucester or Salem Harbors are generally used.

The entrance to Sandy Bay between Straitsmouth Island and the red bell buoy marking Avery Ledge has broken bottom and a rocky spot with a depth of 22 feet in the middle, which strangers may be unable to avoid. Strangers should not use this channel with a greater draft than 18 feet. A ledge, bare in places at low water and having a depth of 2 feet near the end, extends 270 yards northeastward from the northeast end of Straitsmouth Island. The entrance to the bay westward of the gas buoy at the northwest end of the breakwater is deep and clear.

Pigeon Cove, bearing 298° true (NW ⅛ W mag.) from Straitsmouth lighthouse, is a small cove protected by a breakwater and having depths of 6 to 12 feet inside. It is a good harbor for small craft. There are bulkhead wharves around the harbor from which granite is shipped. The best water is on the northeast side. There is a foundry at the head. **Pigeon Rock**, 50 yards off the east point outside the jetty, is nearly bare at extreme low water.

Digitized by Google

Lying 3/8 and 1/2 mile southward of Pigeon Cove are two stone piers built out from the shore. The northerly is in bad repair and not used. The southerly has depths of 12 to 15 feet and is used by vessels loading granite.

Dodge, Bartlett, and **Mitchell Rocks** lie in a cluster nearly 1/4 mile from the western shore of Sandy Bay between the two piers southward of Pigeon Cove. Dodge Rock is bare at low water and is marked by a spindle. The western end of the rocks lies 100 yards eastward of the south pier. The south rock has 14 feet over it and lies 275 yards southward of the spindle. Mitchell Rock, with 4 feet over it, and another, with 16 feet over it, lie 230 and 350 yards, respectively, northward of the spindle and 350 yards eastward of the north pier.

Sandy Bay Ledge is partly bare at high water and extends 200 yards from the western shore of Sandy Bay, southward of the south pier.

Harbor Rock, with 3 feet over it, lies 150 yards northeastward of the end of the north breakwater at the entrance of Rockport Harbor, and is marked on its southeast side by a red buoy. Inside the rock a shelving ledge extends 75 yards east-northeastward from the end of the north breakwater.

Rockport Harbor, at the southwest end of Sandy Bay, is used as a harbor by many small craft. The entrance is about 200 feet wide between two breakwaters. A channel 12 feet deep and 100 to 200 feet wide, has been dredged from the entrance to the wharf at the west end. The channel leads south of a red buoy just outside the entrance, north of a black buoy in the entrance, and 75 feet southward of the end of the breakwater on the north side, heading for the north edge of the southerly wharf until inside, and then for the middle of the wharf.

There are ledges near the shores, especially on the north side between the end of the breakwater and the first wharf on the north side. Boats should go nothing northward of a line from the end of the north breakwater to the end of the first wharf on the north side, and nothing south of a line from the end of the south breakwater to the south edge of the wharf at the head. The wharves have depths of 6 to 7 feet. The deepest draft entering is about 9 feet. Gasoline and provisions are obtainable, and coal is sometimes obtainable in limited quantities. There is water on the wharves. The houses and church spires at the village of **Rockport** are prominent from outside. Rockport has communication by railroad and electric road.

Straitsmouth Island is low and grassy and has a lighthouse and a few buildings at its eastern end. **Straitsmouth lighthouse** is a white cylindrical tower. The light is fixed white, 46 feet above the water, and visible 9 miles. There is a Coast Guard station on Gap Head, westward of Straitsmouth Island; storm warnings are displayed there.

Flat Ground is a dangerous ledge 1/2 mile long, with 2 to 12 feet over it, lying 7/8 to 1 3/8 miles north-northeastward of Straitsmouth lighthouse and 1/4 to 5/8 mile northeastward of Sandy Bay Breakwater. The ledge is marked by two buoys, a red buoy at its south end and a black at its north end.

Dry Salvages is a bare ledge near the middle of a reef about 1/4 mile long in a northerly direction. The ledge is marked by a large red

Digitized by Google

tripod beacon, which lies a little over 1 mile east-northeastward of Straitsmouth lighthouse.

Little Salvages is a ledge showing well bare at low water; it lies about ¼ mile westward of Dry Salvages. Shoal water extends out a little more than 200 yards from the western side of the bare part of the ledge, and a rock, bare at lowest tides, lies between it and Dry Salvages.

Cape Ann lighthouses, on **Thatcher Island,** ½ mile off the eastern side of Cape Ann and 1⅜ miles southward of Straitsmouth Island, are two gray stone towers, 300 yards apart. The lights, shown from each tower, are fixed white, 166 feet above the water, and visible 19 miles. The fog signal is an air diaphone, sounding a group of three blasts, each of 3 seconds' duration, silent intervals 3, 3, and 45 seconds.

The Londoner is a ledge about ⅜ mile long in a northeasterly direction; it has general depths of 7 to 11 feet over it, and lies ½ mile east-southeastward of Cape Ann lighthouses. Near the southern part of the ledge, on a cluster of rocks which show bare at low water, is a red spindle. There is a passage with 12 to 26 feet between The Londoner and Thatcher Island; it should not be attempted by a stranger.

Sandy Bay and approaches, and an area 2½ to 10 miles wide, northeastward, eastward, and southeastward of Cape Ann, have been examined by means of a wire drag.

GLOUCESTER HARBOR

(chart 243) is the most important fishing port in the United States and an important harbor of refuge; it lies 5 miles southwestward of Emerson Point, the easternmost point of Cape Ann. The entrance is marked on its eastern side by Eastern Point lighthouse. There is an outer and an inner harbor, the former with a general depth of 4 to 6 fathoms and the latter 2½ to 4 fathoms.

Eastern Point lighthouse is a white conical tower with a covered way to a dwelling. The light is flashing red (flash 2 seconds, eclipse 3 seconds), 57 feet above the water, and visible 10 miles. The fog signal is a bell, sounding a group of two strokes every 20 seconds.

A breakwater extends 750 yards northwestward from the shore near Eastern Point lighthouse, and is marked at its end by Gloucester Breakwater light. The entrance westward of the breakwater is about ⅝ mile wide; but **Round Rock Shoal** lies nearly ¼ mile westward of the end of the breakwater, leaving a channel 150 yards wide and about 3 fathoms deep eastward of the shoal, and ⅜ mile wide and 4¾ to 9 fathoms deep westward of the shoal. During heavy southeast gales, the sea at times breaks nearly the whole distance across the entrance. Strangers should enter westward of Round Rock Shoal.

Normans Woe, on the west side at the entrance to Gloucester Harbor, is a rocky headland with no distinguishing marks. **Normans Woe Rock,** ¼ mile northeastward of Normans Woe and ⅛ mile offshore, is a high dark rocky islet surrounded by extensive ledges. There is a black bell buoy ¼ mile southeastward of it.

Southeast Harbor is the cove in the eastern part of Gloucester Harbor, northward of Black Bess Point and southward of Tenpound Island. It has good anchorage in about 4 to 5 fathoms, and is generally used by vessels seeking shelter.

Digitized by Google

Western Harbor is the cove, of semicircular shape, in the northern part of Gloucester Harbor, northward of Tenpound Island. It has good anchorage in from 4 to 5 fathoms, taking care to give the shore a berth of 300 yards, but is not much used. A part of the town of Gloucester is built on its northern shore, but there are no wharves on this side.

A dredged channel 8 feet deep and 50 feet wide, with a least width of 40 feet through the bridges, leads from Western Harbor to **Annisquam River** and forms a thoroughfare to Ipswich Bay, on the north side of Cape Ann; vessels of as much as 10 feet draft are taken through at high water to Ipswich Bay. The tidal currents have considerable velocity through the bridges. It is described on page 222. The red bridge at the south end is the most distinguishing mark at the entrance. A black buoy marks the west side of the approach channel.

Tenpound Island is marked by a light on the west side, and has a house and wharf on the north end.

Rocky Neck is a high and partly wooded island, with several buildings, on the east side at the entrance of the inner harbor. It is connected with the shore eastward. **Black Rock,** 100 yards off the western end of Rocky Neck, is bare at half tide and marked by a spindle.

Inner Harbor is ¾ mile long and has depths of 2 to 4 fathoms. **Harbor Cove,** on the northwest side just inside the entrance to the inner harbor, has been dredged to a depth of 15 feet for the entire area 50 feet outside the harbor lines. A channel 12 feet deep and 100 feet wide has been dredged along the front of the wharves on the north side from Fivepound Island northeastward to the head of the inner harbor. **Smith Cove,** on the east side of Rocky Neck, has a depth of 15 feet in the entrance, and shoals gradually to 7 feet 100 yards from the head, above which it is bare at low water.

Wharves.—There are several wharves at Gloucester having depths of 10 to 18 feet. Vessels are usually required to pay wharfage. There is a public wharf of stone at the extreme head of Harbor Cove, with a depth of about 3 feet, at which small craft can land.

Pilots.—Pilotage is compulsory for all vessels of over 7 feet draft engaged in the foreign trade, but not for vessels engaged in the coastwise trade. A pilot may be had by making signal outside the entrance. The pilotage rates are the same as for the port of Boston.

Towboats are stationed at Gloucester and will go outside to a vessel making signal. Large vessels are generally towed in and out. Vessels are reported to Gloucester by telephone from Eastern Point.

Anchorage.—The best and generally used anchorage in the outer harbor, for vessels coming in for shelter or bound to Gloucester, is in Southeast Harbor, locally known as Pancake Ground. Vessels of 15 feet or less draft anchor almost anywhere in the inner harbor, not less than 150 feet from any wharf. Regulations prescribed for Gloucester Harbor require that from Tenpound Island to Fivepound Island, a sufficient passageway of not less than 200 feet in width on the northerly side of said harbor, leaving Babson Ledge buoy on the port hand going in, and a passageway of not less than 150 feet in width from any wharf in Upper Cove, Smith Cove, and Harbor Cove in said harbor, shall be at all times kept open for the passageway of vessels; and no vessel shall be anchored or allowed to lie at anchor in

Digitized by Google

said passageways or in the track of the ferryboats regularly running in said harbor.

Quarantine, when in force, is enforced in accordance with the regulations of the United States Public Health Service.

Repairs.—Gloucester has marine railways for hauling out the class of vessels that ordinarily trade from here, the largest capable of hauling out vessels of 200 tons, 125 feet length, and 16 feet draft. There are machine shops for ordinary repairs to machinery. Boston is the nearest place at which repairs to large vessels and extensive repairs to machinery can be made.

Supplies.—Coal is obtainable from the wharves or from lighters, and water from the wharves or from the towboats. Ship chandlery and all other supplies are also obtainable.

Storm-warning displays are made at the customhouse.

Communication.—Gloucester is on the Boston & Maine Railroad, and has steamer communication with Boston. There is communication by electric road with the other towns on Cape Ann.

Ice seldom extends outside Tenpound Island, at the entrance to the inner harbor. The towboats and steamers generally keep the inner harbor open.

Tides.—The mean rise and fall of tides is 8.9 feet. The highest tides result when easterly and southeasterly gales occur at full and change.

Currents.—The tidal currents do not to any great degree interfere with the movements of vessels, as they set directly in and out of the harbor and their velocity is comparatively small. In the narrows, however, between Fort Point and Rocky Neck the current is stronger, especially at half ebb, and the ebb sets onto Black Rock. Vessels coming out on the ebb favor the northwestern side of the channel in passing between Fort Point and the spindle on this rock. The ebb also sets onto Tenpound Island.

DIRECTIONS, GLOUCESTER HARBOR.

Gloucester Harbor and approaches have very broken ground and many rocks and ledges, some of them unmarked, and careful navigation is necessary, especially in thick weather. The harbor and approaches have been examined by means of a wire drag, and the dangers are charted. The principal dangers for vessels of 24 feet or less draft, to an anchorage in Southeast Harbor, and 18 feet or less draft into the inner harbor, are marked, and strangers are advised not to enter with a greater draft. Strangers in vessels are advised to enter westward of Round Rock Shoal. In heavy southeasterly gales the sea breaks across the eastern side of the entrance from the breakwater to Round Rock Shoal, and at times breaks nearly the whole distance across to Normans Woe Rock.

1. **Approaching.**—Passing 1 mile or more eastward and southeastward of Cape Ann lighthouses and ½ mile or more eastward and southeastward of The Londoner beacon, steer 233° true (WSW mag.); this course leads ¼ mile southeastward of an unmarked 33-foot rocky spot ⅝ mile southward of Milk Island. Give the shore eastward of Eastern Point lighthouse a berth of about ½ mile, and pass close to Eastern Point whistling buoy, lying nearly ⅝ mile southward of the lighthouse. Then steer 306° true (NW ½ N

Digitized by Google

mag.) for 1 mile to a position 300 yards southwestward of Round Rock Shoal gas buoy, and follow the directions in section 2.

Approaching from southwestward, from the whistling buoy outside of Newcombs Ledge, steer 38° true (NE ¾ E mag.) for Eastern Point lighthouse; or, coming from Salem, bring Baker Island lighthouses astern on a 64° true (E by N mag.) course, heading for Eastern Point lighthouse. When Tenpound Island lighthouse bears 30° true (NE mag.), steer for it to a position 350 yards southeastward of Normans Woe bell buoy and with Eastern Point lighthouse bearing 75° true (E mag.).

To Anchor in Southeast Harbor, steer the 25° true (NE ½ N N mag.), passing 200 yards westward of Round Rock Shoal gas buoy, 75 yards westward of a red buoy, and 100 yards westward of a horizontally striped buoy marking the ledges southwestward of Tenpound Island, and to a position 300 yards northwestward of Tenpound Island lighthouse. Then steer about 52° true (ENE mag.) into the inner harbor, passing southward of Babson Ledge black buoy and northward of Black Rock spindle. Anchorage may be had in the middle of the inner harbor below Fivepound Island.

To Anchor in Southeast Harbor, steer the 25° true (NE ½ N mag.) course of the preceding paragraphs until ¼ mile past Round Rock Shoal gas buoy and Eastern Point lighthouse bears 120° true (SE mag.). Then steer 53° true (ENE mag.) and anchor in about 4 to 5 fathoms anywhere southward of Tenpound Island, giving the island a berth of 250 yards and the shore southeastward of it a berth of not less than 350 yards.

2A. Entering eastward of Round Rock Shoal.—The least depth by this channel is about 18 feet, rocky bottom. Strangers of over 10 feet draft are advised to use the deeper channel westward of Round Rock Shoal. Steer 19° true (NE by N mag.) for Tenpound Island lighthouse and pass 200 yards westward of the light on the end of the breakwater and midway between a red and a black buoy marking the bar. Or, from Eastern Point whistling buoy steer 323° true (NNW mag.) until the light on the end of the breakwater is abeam, and then haul northward and pass 200 yards westward of it. From a position 200 yards westward of the light on the end of the breakwater, steer 15° true (NNE ¾ E mag.) for 1⅛ miles to a position 150 yards northwestward of Tenpound Island, passing eastward of a red and a horizontally striped buoy; then steer 40° true (NE by E mag.) for the middle of the entrance to the inner harbor and enter in mid-channel.

GLOUCESTER HARBOR TO SALEM HARBOR.

Off the shore eastward of Manchester Harbor entrance, between Gloucester entrance and House Island, are a number of islands, rocks, and ledges, which extend about ¾ mile from shore. The farthest outlying ones, named in order from eastward, are: **Kettle Island** (grass-covered and rocky), **Great Egg Rock** (high and bare), **Boo-hoo Ledge** (bare at low water), **Salt Rock** (shows at high water), **Picketts Ledge** (bare at low water), **Gales Ledge**, and **Pilgrim Ledge**. There are several coves, but Manchester Harbor is the only one of interest to navigation.

Digitized by Google

Magnolia Harbor is a foul cove about 1½ miles westward of the entrance to Gloucester Harbor and inside of Kettle Island. **Magnolia** is a prominent summer resort on the eastern side. There are private wharves for small craft on the eastern side of the harbor.

Manchester Harbor (chart 244) is about 5 miles westward of Gloucester Harbor, and is formed by an arm of the bay extending behind **Gales Point** in a northeasterly direction for 1 mile to the village of **Manchester**. The entrance to the outer harbor is northward of Baker Island lighthouses, between **House Island** (partly wooded) on the east and Great Misery Island on the west.

There is anchorage in the outer harbor inside Great Misery and House Islands. Vessels desiring to anchor for the night or in head winds may here find fair holding ground and good shelter except in southerly gales. The anchorage is ¾ mile wide, and has from 3 to 6 fathoms.

Whales Back is a dangerous ledge lying in the entrance of the outer harbor of Manchester. It is about 400 yards long east and west, and 200 yards wide. Near the middle of its northern side is a rock bare at low water, which is marked by a spindle. There is a clear channel 300 yards wide between the ledge and House Island; the channel westward of the ledge is ¼ mile wide.

Sauli Rock, bare at half tide, lies 300 to 400 yards eastward of the northeast end of Great Misery Island, and is marked on its south side by a horizontally striped buoy.

White Ledge, bare at low water, lies 300 yards northward of House Island, and is marked on its northwest side by a red buoy. A rock covered at half tide lies 250 yards north-northeastward of White Ledge, and is marked off its northwest side by a red buoy.

Chubbs Islet, bare and rocky, lies 300 yards from the north shore of the outer harbor of Manchester, and should be given a berth of over 200 yards.

The dredged channel leading up to Manchester from the outer harbor is 100 to 500 feet wide and 6 feet deep as far as the wharves near the railroad bridge, above which it has a depth of 4 feet to the town wharves. The draft of boats going to Manchester averages about 3 to 7 feet, and the deepest draft is about 12 feet. The dredged channel is well marked by buoys, some of them private.

Pilots are usually taken by strangers in vessels bound up to the town, vessels anchoring in the harbor below until pilots are obtained. Small craft seldom take a pilot.

Supplies and repairs.—Water, gasoline, provisions, and all kinds of motor-boat supplies are obtainable in Manchester. There is a marine railway for hauling out yachts up to 9 feet draft and 90 feet in length.

Wharves.—There are public float landings with depths of 6 feet on the east side of the harbor just below the bridge, and a public wharf at the head of the channel above the bridge. The depth at the boat yard wharf, on the west side just below the bridge, is about 10 feet, obtained by dredging. The bridge has a draw opening 50 feet wide, and a headroom of 6½ feet at high water when closed; it is opened on notice to the agent at the railroad station.

Ice.—The harbor is usually closed by ice for about two months each winter.

Tides.—The mean rise and fall of tides is about 9 feet.

Digitized by Google

Directions, Manchester Harbor.—Pass ¼ to ⅜ mile northward of Baker Island and bring the lighthouses astern on a 351° true (N ½ E mag.) course, passing 350 yards westward of Whales Back spindle and to a position 100 yards eastward of Sauli Rock horizontally striped buoy. Bring this buoy astern on a 27° true (NE ¼ N mag.) course to the buoys at the entrance of the dredged channel. The courses through the dredged channel are 41° true (NE by E mag.) for a little over ¼ mile, following the buoys to a position close westward of the red buoy off the yacht club, then eastward for 100 yards to pass southeastward of a black buoy marking a ledge bare at low water, and then about 34° true (NE ⅜ E mag.), and keep in mid-channel to the head. The harbor is dredged for its full width in the upper end below the bridge.

SALEM, BEVERLY, AND MARBLEHEAD HARBORS.

These harbors (chart 244) form a large, irregular indentation in the shore of Massachusetts Bay, 11 miles southwestward of Cape Ann, and 12 miles northeastward of Boston Harbor entrance. Gales Point is the northern and Marblehead Neck the southern point at the entrance to this large indentation, which includes within its limits the harbors of Manchester, Beverly, Salem, and Marblehead, the distance between the two points being 4 miles. This wide space is studded with islands, bare rocks, and sunken ledges, through which lead the several channels into the harbors.

Salem Harbor is considerably used as a harbor of refuge; Salem and Beverly have considerable coasting trade, mostly in vessels carrying coal and oil, the deepest draft being about 25 feet. Marblehead Harbor is frequented by many yachts and small craft, and has an occasional cargo of coal.

Channels.—Three main channels lead through the islands and rocks at the entrance. They are known as Main Ship Channel, Cat Island Channel, and Marblehead Channel. There are several other channels of less importance, used only by local boats.

Main Ship Channel, the most northerly, leads between Baker and Great Misery Islands, and northward of Great and Little Haste. It has a depth of about 5 fathoms until up to Little Haste if the range is closely followed, but there are unmarked rocky spots with depths of 20 to 25 feet close to the sailing line. This channel is used by most deep-draft vessels.

Cat Island Channel, the middle channel, has its entrance near Halfway Rock, and leads in a northwesterly direction, between Cat and Eagle Islands. The least depths found in Cat Island Channel are about 18 feet in the channel northward of Gooseberry Ledge, 19 feet between Gooseberry Ledge and Satan Rock, and 23 feet on the eastern side of the channel between Satan Rock and Cat Island, with deeper water in mid-channel. The latter channel is the best. The least depth in Cat Island Channel between Eagle and Cat Islands is about 26 feet.

Marblehead Channel, the westerly channel, leads in a northerly direction between Cat Island and Marblehead Neck. There are numerous unmarked shoals with 14 to 24 feet close to the channel, on which the sea breaks in easterly gales. It is not recommended for strangers with a greater draft than 12 feet.

Digitized by Google

SOUTH CHANNEL, a branch of Marblehead Channel, leads along the northern shore of the peninsula between Marblehead and Salem Harbors, and southward of the numerous rocks and ledges on the east side of the entrance to Salem Harbor. The principal dangers are marked, but the channel is less than 100 yards wide in its narrowest part; it has a least found depth of about 15 feet, but has not been closely examined, and should not be used by strangers except in small craft.

Islands and rocks along Main Ship Channel.—BAKER ISLAND, on the south side of the entrance to Main Ship Channel, has houses scattered over it and two lighthouses at the northern end.

BAKER ISLAND LIGHTHOUSES are two white towers, 15 yards apart. Each light is fixed white, the southerly 111 feet above the water and the northerly 91 feet above the water, and both visible 12 miles. The fog signal is an air siren, sounding a blast of 3 seconds duration every 30 seconds.

An extensive area of rocks and reefs extends for 2 miles southeastward of Baker Island. A whistling buoy marks the southeast end and vessels should pass outside of it. MIDDLE and INNER BREAKERS are partly bare at low water, and Middle Breaker is marked by a spindle.

GREAT MISERY ISLAND, on the north side of Main Ship Channel at the entrance, has scattered houses and a lowwater tank on the top. There are float landings and a harbor for small craft, inclosed by jetties, in a cove on the north side.

HARDY ROCKS, 5/8 mile westward of Baker Island lighthouses and nearly 3/8 mile south-southwestward of the Main Ship Channel range, is bare at low water and marked by a beacon (black spar with two triangles), and a black buoy on the north side.

BOWDITCH LEDGE, 1 1/8 miles west-northwestward of Baker Island lighthouses and 350 yards south-southwestward of the Main Ship Channel range, is marked by a granite beacon with a black staff and cage.

GREAT HASTE, on the south side of the main channel 2 3/8 miles westward of Baker Island, is a bare rock surrounded by ledges. LITTLE HASTE, close northwestward of Great Haste, is bare at low water and marked by a beacon (black cask on wooden spar).

Islands and rocks along Cat Island Channel.—HALFWAY ROCK, 2 miles southward of Baker Island, is about 15 feet high and marked by a prominent beacon (keg on skeleton tower). It is surrounded by deep water.

NORTH and SOUTH GOOSEBERRY are high, rocky islets on the western end of the extensive ledges southward of Baker Island. DRY BREAKERS, the southerly part of the ledges, show at high water as a low, bare ledge.

POPES HEAD, 300 yards northwestward of North Gooseberry, is a rugged bare rock, surrounded by ledges to a distance of 150 yards. A black buoy marks the western side of the ledges.

SATAN ROCK, 1/2 mile east-southeastward of Cat Island, is a small, bare rock marked by a spindle with black cage; it should be given a berth of 150 yards on its eastern and western sides and 275 yards on its north side.

BRIMBLES is a rock bare at low water lying nearly 3/8 mile south-southeastward of Eagle Island. It is marked by a black spindle

Digitized by Google

with four arms (the two arms facing Cat Island Channel are red); the spindle should be given a berth of over 125 yards.

EAGLE ISLAND is small, grassy, and rocky, and lies 5/8 mile north-northeastward of the north end of Cat Island.

GRAYS ROCK, 5/8 mile northwestward of Cat Island, is about 10 feet high.

CONEY ISLAND is a low, grassy islet with a hut near its middle. CONEY LEDGE, the higher parts of which are covered at high water, is an extensive ledge extending southeastward and southward from Coney Island, and is marked at its easterly end by a black buoy.

Islands and rocks along Marblehead Channel.—Islands and rocks, sunken and bare, extend for 2 miles southward and southwestward from the south end of Marblehead Neck. Many of them are marked by buoys, and the channels between them are used by local boats, but the area should be avoided by strangers. A red bell buoy marks the southeastern end of the broken ground. Those showing above water are GREAT PIG ROCKS, bare at high water, and having rocks awash at low water southward of them; SAMMY ROCK, bare at low water; RAM ISLET, high, rocky, and grassy; LITTLE PIG ROCKS, awash at high water; ROARING BULL, bare at low water and marked by a spindle; and TINKERS ISLAND, marked by several houses. A bar with little depth connects Tinkers Island with the shore.

TOM MOORES ROCK, at the eastern end of a reef extending 400 yards from the middle of Marblehead Neck, is bare at one-third ebb and marked by a spindle.

MARBLEHEAD ROCK, 1/4 mile eastward of the northern part of Marblehead Neck, is a high bare rock with a conical beacon on the top.

CAT ISLAND, 7/8 mile northeastward of Marblehead Neck, is 3/8 mile long, bare, and has a few houses on the north end, and a wharf on the southwest side. It is surrounded by extensive ledges, bare and submerged. A spindle marks the bare rock at the south end.

Marblehead Harbor.—This harbor is about 1 mile long and 3/8 mile wide and is formed on the east and south by Marblehead Neck and a narrow strip of land called MARBLEHEAD BEACH connecting the south end of the neck with the mainland. Marblehead lighthouse, at the north end of Marblehead Neck, marks the easterly point at the entrance. Mablehead Harbor is an excellent anchorage and is much used by yachts during the summer. The depths in the harbor up to Skinners Head are 4 to 5 fathoms, and vessels up to about 20 feet draft can enter. There is 8 to 15 feet alongside the wharves. The greater part of the head of the harbor southward of Skinners Head and Boden Point is shoal.

MARBLEHEAD LIGHTHOUSE, on the north end of Marblehead Neck, is a pyramidal skeleton tower inclosing a cylindrical tower. The light is fixed white, 130 feet above the water, and visible 10 miles.

MARBLEHEAD is an important summer resort on the west side of Marblehead Harbor. There are numerous float landings. The float landings at the foot of the streets are public and have depths of 3 to 12 feet. The lower public landing is just below the yacht-club landing. There are several private float landings on the east side of the harbor. General information for the harbor is given on page 235 and directions on page 238.

Digitized by Google

Salem Harbor.—The harbor proper is about 1½ miles long in a southwesterly direction. The channel favors the eastern side of the harbor and has depths of 3½ to 4 fathoms in the outer part and about 15 feet to the entrance of the dredged channel leading to South River. There are two long coal wharves on the northwest side of the harbor, to which channels have been dredged to a depth of about 15 feet, and a few other wharves in this vicinity, bare or nearly so, at low water. The head of the harbor for a distance of about 1 mile is shoal and has no wharves.

The entrance to Salem Harbor is between ABBOT ROCK BEACON (red spindle on stone base) and FORT PICKERING LIGHTHOUSE (brown cylindrical tower) on the west, and GREAT AQUA VITAE BEACON (black spindle on stone base) on the east.

SOUTH RIVER, on the northwest side of Salem Harbor, separates Salem and South Salem and forms an important approach to the city of Salem. Its entrance is on the west side of DERBY WHARF, a long stone jetty with a light (red square tower) on the end. South River has been dredged to a depth of 10 feet and width of 200 to 300 feet to the outer end of Derby Wharf, and to a depth of 8 feet inside to near the head. There is a large mill and brick stack on the west side just inside the entrance. A drawbridge with an opening 43 feet wide crosses the river about ¼ mile above the outer end of Derby Wharf. There are several wharves with depths of 8 to 10 feet in the river to which vessels go, and a public float landing for small craft on the south side at the bridge. The dredged channel at the entrance to the river is marked by buoys and is easily followed by small craft. The mid-channel is clear inside.

Beverly Harbor.—This harbor lies north of Salem Neck, at the west end of Salem outer harbor, and is formed by the confluence of Danvers River, Beverly Creek, and North River. It forms the approach to the city of Beverly. It has considerable trade in coal and oil, carried in barges and vessels up to 25 feet draft. The channel has been improved by dredging and the removal of rocks to obtain a depth of 18 feet and a width of 200 to 300 feet to the highway bridge. The principal dangers are marked, but the channel is narrow and crooked, and there are shoals with less depth close to it.

BEVERLY is a city on the north side of Beverly Harbor just inside the entrance. There are depths of about 24 feet at low water at the coal and oil wharves, and 12 to 16 feet at the others.

BRIDGES.—Two drawbridges cross Beverly Harbor just above the principal wharves at Beverly. The lower, a highway bridge, has a single opening 40 feet wide, and a headroom of 10.3 feet at high water when closed. The railroad bridge, 100 yards above the highway bridge, has a single opening 38 feet wide, and a headroom of 6.2 feet at high water when closed.

BEVERLY CREEK, a tributary of Beverly Harbor from northward just above the bridges, has been improved by dredging a channel 9 feet deep for about 1 mile above the entrance to near the head. There is a lumber wharf and a wharf to which coal vessels go, on the east side of the river. The channel leads between flats bare at low water, and is most easily followed at that time. It is sometimes marked by bush stakes. It is crossed by a drawbridge ¾ mile above the entrance, having a single opening with a width of 40 feet, and a headroom of 4.5 feet at high water when closed.

Digitized by Google

DANVERS RIVER is the continuation of Beverly Harbor northwestward. It has a depth of about 6 feet at low water for 1¾ miles above Beverly to within ⅜ mile of the village of DANVERSPORT, and about 2 feet to Danversport. Coal and lumber vessels go to Danversport at high water. The channel is narrow and unmarked, leads between flats bare at low water, and is difficult without local knowledge. A drawbridge with an opening 50 feet wide and headroom of 9.4 feet at high water when closed crosses the river ½ mile above the bridges at Beverly.

NORTH RIVER, a tributary of Beverly Harbor from southward just above the bridges, is nearly bare at low water in a narrow unmarked channel. It is little used.

Prominent objects.—APPROACHING FROM EASTWARD, Baker Island, with two lighthouses on its northern end and numerous houses scattered over the island; and Great Misery Island, the high, grassy island, with a clubhouse and water tank near its highest part, lying northward of Baker Island, are the most prominent.

APPROACHING FROM SOUTHWARD, Halfway Rock, a bare rock about 15 feet high, with a beacon on it, will be seen about 1⅞ miles south of Baker Island. Southward of Baker Island lie two high, rocky islets, North and South Gooseberry Islands, and 1¼ miles southwestward of these is Cat Island, long and narrow with a number of houses near the northern end. Marblehead Neck is high and rocky, and has many summer houses; Marblehead lighthouse is on its northern point. Marblehead has several prominent marks.

Anchorage.—SALEM HARBOR is much used as a harbor of refuge, particularly during the autumn. It is especially convenient for vessels seeking shelter bound eastward and met by an easterly gale, as the direction of the harbor is such that a foul wind for proceeding is a fair wind into the harbor, and a fair wind for proceeding is also a fair wind out. Strangers should not attempt to beat into Salem Harbor on account of the numerous ledges and shoals.

There is good anchorage for vessels in what is known as the outer harbor, westward of Bowditch Ledge and northward or eastward of Little Haste, in 5 to 7 fathoms. The most generally used anchorage for vessels is eastward of the entrance to Beverly Harbor and northward of Middle Ground, in 3½ to 6 fathoms. Small vessels, especially sailing vessels, also anchor on the east side of Salem Harbor just inside of Naugus Head, in 3½ to 4 fathoms.

IN BEVERLY HARBOR, the best anchorage is between Rams Horn and Lobster Rock beacons, a little south of the line joining them, in 3 to 4 fathoms. Small vessels and motor boats usually anchor on the south side of the channel between Lobster Rock beacon and the bridge, in 12 to 15 feet.

IN MARBLEHEAD HARBOR the anchorage is anywhere in the middle, in 24 to 30 feet, good holding ground, and is sheltered from all but northeasterly winds. With good ground tackle vessels have no difficulty in riding out a northeaster. It is much used as an anchorage by yachts.

Pilots are seldom taken. They can be obtained from a Boston pilot boat, or sometimes at Gloucester or from fishing boats at work off the entrance.

Towboats.—There are no towboats, but one can be obtained from Gloucester or Boston.

Digitized by Google

Supplies.—Coal and water can be obtained at the wharves at Salem and Beverly, and usually from water boats at Marblehead. Gasoline, provisions, and motor-boat supplies are obtainable at all of the cities.

Repairs.—There is a railway at Salem for hauling out small craft of about 10 tons, and railways at Marblehead for hauling out yachts up to 75 tons, 100-feet length, and 10½-feet draft. There are machine shops for ordinary repairs to machinery at all of the cities.

Ice.—The head of Salem Harbor on the flats is usually closed by ice every winter during the months of January and February, but the formations rarely extend beyond the coal piers except in unusually severe winters, when they have been known to reach as far out as The Haste, and occasionally as far as Eagle Island. Northerly and northwesterly winds are most favorable to local formation in Salem Harbor. Winds from southward and westward, during light formations, have a tendency to carry the ice off to sea, while those from eastward usually break up the formations both in the harbor and its approaches.

Marblehead Harbor is rarely obstructed by ice to such an extent as to become a hindrance to navigation. Fishermen have made it a refuge when it was impossible to get into Gloucester, Salem, or Lynn Harbors. The formation of ice in Marblehead Harbor is entirely local, and remains but a short time.

Tides.—The mean rise and fall of tides is about 9 feet.

Currents.—The tidal current in Salem and Marblehead Harbors has little velocity. In Beverly Harbor it has considerable velocity, and sets across the channel in places. During the first half of the ebb the current sets across the shoal extending northward from Old Hospital Point.

DIRECTIONS, SALEM, MARBLEHEAD, AND BEVERLY HARBORS.

The approaches to these harbors have very broken ground, and all of the channels lead between islands and rocks, bare and submerged. Caution is necessary for their navigation at all times, and strangers should not attempt to enter or leave in thick weather. All of the channels in the harbors and their approaches, except the channels between Baker Island and Bowditch ledge beacon, between the black buoy and the horizontally striped buoy northward of Little Haste, through South Channel and through Marblehead Harbor, have been examined by means of a wire drag and the dangers are shown on the charts. Strangers should exercise great care in navigating through areas not examined by means of a wire drag. For a description of the channels and depths, see page 231.

DIRECTIONS, SALEM HARBOR.

1. Through Main Ship Channel.—With Baker Island lighthouses bearing between 244° true (W by S mag.) and 284° true (NW by W ½ W mag.), steer for them; or, coming from Gloucester, bring Eastern Point lighthouse astern on a 244° true (W by S mag.) course heading for Baker Island lighthouses; this course leads 350 yards southward of a red buoy marking a 17-foot spot.

Pass ¼ mile northward of Baker Island lighthouses and 200 yards northward of the black buoy off them, and steer 276° true (WNW

Digitized by Google

⅛ W mag.) for 1 mile, passing 250 yards southward of Little Misery Island and to a position 300 yards northward of Bowditch Ledge beacon; on this course Hospital Point light (white tower showing against the trees) is in range with the tallest church spire at Beverly, and the range should be closely followed. At night Hospital Point light is more brilliant when on the sailing line than on either side. Pass 300 yards northward of Bowditch Ledge beacon and steer 267° true (W by N mag.) for 1½ miles to a position ⅜ mile northward of Little Haste beacon, and 100 yards northward of a horizontally striped buoy. Pass 150 yards westward of the buoy and steer 219° true (SW ¾ W mag.), passing about 300 yards southeastward of Abbot Rock beacon and Fort Pickering and 400 yards northwestward of Great Aqua Vitae beacon. Anchorage can be had in the middle of the harbor off the coal wharves, or the course can be continued to the buoys at the entrance of the dredged channel leading into South River.

2. Through Cat Island Channel.—Vessels approaching Cat Island Channel from southward can pass ½ mile southeastward of Outer Breakers bell buoy and steer for Halfway Rock beacon on a 39° true (NE ¾ E mag.) course for 2⅜ miles until 1¼ miles from the beacon and Marblehead lighthouse is a little abaft the beam, distant 2⅛ miles. Then steer 338° true (N ⅝ W mag.) for 2 miles with the west end of Eagle Island ahead, passing midway between Satan Rock spindle and Cat Island, and to a position midway between Brimbles spindle and Martin Rock black buoy. Then steer 302° true (NW ⅛ N mag.) for ½ mile to a position 100 yards southwestward of Mid-Channel Rock red buoy, and then 333° true (N by W mag.) for 1¼ miles, passing 100 yards eastward and northward of buoy No. 5; then steer 277° true (WNW mag.) for ½ mile to a position 100 yards northward of the horizontally striped buoy northward of Little Haste beacon, and follow the directions in the preceding paragraph.

3. Through Marblehead Channel.—The following directions are intended for vessels of 12 feet or less draft with a smooth sea. Deeper draft vessels are advised to enter by Cat Island or Main Ship Channels. Vessels should shape the course to make Outer Breakers bell buoy.

Pass about 200 yards eastward of the bell buoy and steer 26° true (NE ⅜ N mag.) for Baker Island lighthouses, passing nearly ½ mile eastward of Tinker Island and to a position ¼ mile east-southeastward of Volunteer Rock buoy. Then steer 343° true (N ¼ W mag.) for 1¼ miles, passing 150 yards eastward of Marblehead Rock beacon.

Then bring Marblehead Rock beacon astern on a 4° true (N by E ⅝ E mag.) course for ¾ mile, and pass about 100 yards westward of Archer Rock buoy and to a position about 300 yards eastward of Chappel ledge buoy. Then steer 345° true (N mag.) for 1¼ miles, and pass about 400 yards eastward of the black buoys marking Coney Ledge and Coney Island Rock, and about 100 yards eastward and northward of buoy No. 5, northeastward of Great Haste, then steer 267° true (W by N mag.) and pass 100 yards northward of the black buoy northward of Great Haste. From here steer 232° true (WSW mag.) for ⅝ mile until ¼ mile from Abbott Rock beacon, then steer 219° true (SW ¾ W mag.) to the buoys at

Digitized by Google

the entrance of the dredged channel leading to South River, or anchor in mid harbor off the coal piers.

4. Through South Channel.—This channel should be used by strangers only in small craft. Follow the direction in section 3 until up to Marblehead Rock beacon. Pass 200 yards northward of it and steer 331° true (N by W ¼ W mag.) for Hospital Point lighthouse to a position 100 yards eastward of Kettlebottom spindle. Then steer 305° true (NW ⅜ N mag.) to a mid-channel position between buoys Nos. 7 and 4. Then steer about 256° true (W mag.) and pass southward of buoy No. 6, and then steer northwestward and pass northward of buoy No. 9. Then steer 264° true (W ¾ N mag.) for the end of the Philadelphia & Reading coal pier, pass southward of two red buoys and give the shore a berth of 250 yards. Anchor in mid harbor off the coal pier, in 3½ to 4½ fathoms, soft bottom, or steer west-southwestward to the buoys at the entrance of the dredged channel leading into South River.

DIRECTIONS, MARBLEHEAD HARBOR.

From northeastward.—Follow the directions in section 1 of the directions for Salem Harbor to a position 300 yards northwestward of the black buoy off the north side of Baker Island; then steer 216° true (SW ½ W mag.) for the northwest end of Cat Island, with the east side of House Island astern, and pass 300 yards southeastward of Hardy Rock buoy and beacon. When about ¼ mile east of Eagle Island steer 236° true (WSW ¼ W mag.) with Baker Island lighthouses astern, pass 200 yards southward of Eagle Island, and to a position about 400 yards southeastward of Chappel Ledge buoy. Then steer 225° true (SW by W ¼ W mag.) for the middle of the entrance to Marblehead Harbor, and anchor off the town, favoring if anything the westerly side of the harbor, in 4 to 5 fathoms, soft bottom.

From eastward.—Unmarked detached rocks and ledges with depths of 15 to 25 feet lie off the eastern entrance to Marblehead Harbor, and strangers may have trouble in avoiding them. The following course is recommended for vessels of 12 feet or less draft. Bring Halfway Rock beacon astern on a 277° true (WNW mag.) course, and pass 350 yards southward of Cat Island beacon, 500 yards northward of Marblehead Rock beacon, and 100 yards northward of the black buoys off the north end of Marblehead Neck. Vessels can then haul southwestward in the harbor.

From southward.—Follow the direction in section 3 of Salem Harbor until up to Marblehead Rock beacon. Pass 200 yards northward of the beacon, steer northwestward and pass 100 yards northward of the black buoys off the north end of Marblehead Neck, then steer southwestward into the harbor.

DIRECTIONS, BEVERLY HARBOR.

Strangers of over 15 feet draft should not enter without a pilot, as the channel is narrow and crooked in places and, although well marked by aids, requires some local knowledge to keep in the best water. No attempt should be made to enter at night.

Follow the direction of sections 1 or 2 of Salem Harbor to a position 100 yards northward of the horizontally striped buoy north-

Digitized by Google

ward of Little Haste beacon, then steer 247° true (W ¾ S mag.) for ½ mile, to a position 150 yards southward of the red buoy southward of Hospital Point lighthouse; or follow the directions of section 3 of Salem Harbor to a position 100 yards northward of the black buoy northward of Little Haste beacon and steer 266° true (W by N mag.) to a position 150 yards southward of the red buoy southward of Hospital Point lighthouse.

Then steer 273° true (WNW ⅜ W mag.), pass 50 yards northward of buoy No. 1, and then 301° true (NW mag.) and pass midway between buoys Nos. 2 and 3 and 75 yards northward of buoy No. 3 A. Then steer southwestward and south-southwestward, passing southeastward of Porters Rock red buoy and about 200 feet westward of Monument Bar beacon. Pass 100 feet eastward of a red buoy and the same distance westward of a black buoy between Monument Bar and Rams Horn beacons, and 100 feet southward of the red buoy northwestward of Rams Horn beacon. Then haul gradually westward, steer about 323° true (NNW mag.), and pass about 100 yards northeastward of Lobster Rocks beacon. Then follow the wharves at a distances of about 75 yards.

COAST FROM MARBLEHEAD TO BOSTON HARBOR.

The islands and rocks eastward, southward, and southwestward of Marblehead Neck are described under "Salem Harbor and approaches" on page 233.

Phillips Point is high and rocky, and its western and higher part is wooded. A rock with 12 feet over it lies 600 yards eastward of **Grass Head**, the eastern end of the point. A reef with bare heads extends 350 yards southward from Phillips Point, and **Dread Ledge**, bare at half tide and marked by a red spindle, lies 500 yards southward of the point.

Nahant Bay is 2 miles wide between Phillips Point and Nahant, and about the same long to Lynn Beach. The village of **Swampscott** is on its northern shore westward of Phillips Point, and the eastern part of the city of Lynn is on its northwest side. Temporary anchorage, exposed to easterly and southerly winds, can be had in the bay in 3 to 6 fathoms, but it is little used. The usual anchorage is off Swampscott, southwestward or westward of the southern end of Fishing Point. Small craft can anchor westward of the point in 8 to 15 feet. The bay is clear; 18 feet is found ½ to ¾ mile from its northwest side, shoaling thence to the shore. **Fishing Point, Blaneys Rock,** and **Red Rock** are rocky points on the northern side of Nahant Bay.

Lynn Beach is a narrow strip of sand separating Nahant Bay from Lynn Harbor, and is about 1 mile long in a southerly direction to **Little Nahant**, a high, grassy head with several houses. Little Nahant is joined to Nahant by a strip of beach nearly ½ mile long, called **Little Nahant Beach.**

Egg Rock, about 60 feet high and marked by a lighthouse, lies on the southern side in the entrance of Nahant Bay ⅝ mile northeastward of Nahant. The eastern and northern sides of the rock should be given a berth of over 200 yards.

Egg Rock lighthouse is a white tower attached to a dwelling. **The light is fixed red, 90 feet above the water, and visible 7 miles.**

Digitized by Google

Broad Sound, about 4 miles wide between Nahant on the northeast and Deer Island on the southwest, forms the approach to Nahant and the city of Lynn at its north end, and a continuous line of summer resorts on its west side. It has depths of 3 to 8 fathoms in the entrance, but is shoal near the shores.

Nahant is a high peninsula about 1⅜ miles long, with bluff seaward faces. It is occupied by a town and summer resort. It is connected with Lynn by electric railway. A standpipe is the most prominent mark.

Nahant Harbor is the cove on the south side of Nahant. The principal wharf is on the northeast side of the harbor and has a depth of 9 feet. Entering between Joe Beach Ledge buoy and Bass Rock spindle, temporary anchorage can be selected off the wharf in 3 or 4 fathoms, hard bottom. There are wharves on the westerly side of Nahant, northward of Bass Point, with depths varying from 3 to 11 feet.

Shag Rocks are a group of bare rocks extending 300 yards southward from the southeast end of Nahant. A ledge, awash at lowest tides, extends 100 yards southward from the southernmost Shag Rock.

Lynn Harbor.—This harbor, the northerly end of Broad Sound, is full of shoals, largely bare at low water, through which several channels have been dredged to the city of Lynn. Lynn has considerable trade, the deepest draft being about 22 feet. The principal cargoes are coal, lumber, and building materials.

The easterly channel has been dredged 15 feet deep and 300 feet wide, with a turning basin of the same depth 500 feet square at the head. Several private channels have been dredged to depths of 8 to 15 feet to give access to the wharves from the turning basin. A basin approximately 200 yards wide and 400 yards long, to form an anchorage for yachts, has been dredged to a depth of 6 feet eastward and southeastward of the 15-foot turning basin at the head, and extending southward from the Lynn Yacht Club. The anchorage is not marked and there are shoals, bare at low water, on the north and east sides. The easterly channel into Lynn Harbor is marked by buoys at the entrance and by lights at frequent intervals, and leads between flats, bare, or nearly so, at low water. Some local knowledge is necessary to carry the best water, but strangers in small craft should have no trouble in going to Lynn with the aid of the chart.

Directions to Lynn by the Eastern Channel.—These directions are intended only for motor boats or small vessels. Large vessels are advised to take a pilot. The best time to enter is on a rising tide. Pass close westward of the red bell buoy ¾ mile west-northwestward of Nahant, and steer 9° true (NNE ⅛ E mag.), following the buoys, for ¼ mile to a position 200 feet eastward of White Rock light. Then steer 32° true (NE ⅛ E mag.) for ½ mile, to a position 200 feet southeastward of a light, then 22° true (NE ¾ N mag.) for ⅝ mile, gradually approaching Lynn Beach, to a position 200 feet southeastward of a light and 400 feet from the beach. Follow the beach at about this distance for ⅜ mile to a position 200 feet eastward of the next light, then steer 333° true (N by W ⅛ W mag.) for ¼ mile to a position 250 feet westward of a light, and then 354° true (N ¾ E mag.) to the head.

Black Rock Channel, a branch of the easterly channel, leading along the western side of Nahant, is unmarked and suitable only for small craft. There are shoals nearly bare at low water on either side.

Digitized by Google

A privately dredged channel about 9 feet deep leads from the eastern channel 1 mile from its head, north-northwestward to a gas and electric plant. The channel is unmarked and leads between flats bare at low water. It is used only by vessels loaded with coal.

WESTERN CHANNEL of Lynn Harbor leads into SAUGUS RIVER at the western end of Lynn. A channel 12 feet deep has been dredged through the flats at the mouth and in the river, to the General Electric Co. wharf, ½ mile above the bridges at the entrance. The depth at the wharf is 18 feet. The river has been improved by dredging to a depth of 6 feet for ¾ mile above this wharf to a lumber wharf. Western Channel is partially marked across the flats at the entrance by buoys, but local knowledge is necessary to keep in the best water. The channel in the river is unmarked and difficult.

BRIDGES.—Three bridges cross Saugus River between the entrance and the General Electric Co. wharf, and one between that point and the lumber wharf. All have draw openings. The least width of opening through the first three bridges is 50 feet, and through the fourth bridge 40 feet.

REPAIRS—There is a marine railway at Lynn for yachts of 40 feet length and 7 feet draft. All kinds of repairs to machinery can be made.

PILOTS.—Pilotage is not compulsory for Lynn Harbor. There are licensed pilots at Nahant, which may be obtained on a signal of five blasts of a whistle. Strangers in vessels usually take a pilot, on account of the narrow crooked channels. The pilotage rates are given on page 252.

TIDES.—The mean rise and fall of tides is 9.2 feet at Lynn.

Revere and **Winthrop** are towns and summer resorts occupying most of the west and southwest sides of Broad Sound. At Revere Beach a breakwater has been built out from the shore on **Cherry Island Bar**, forming an anchorage for small craft, with depths of 4 to 6 feet. Northward of the breakwater there is a long wharf built out to a depth of about 3 or 4 feet at low water.

Winthrop Head, a hill 103 feet high and covered with houses, is marked by a silvered standpipe, the most prominent mark in this vicinity.

Shirley Gut, separating Point Shirley from Deer Island, forms an approach from Broad Sound to the northern part of Boston Harbor. The channel is 80 yards wide and about 9 feet deep. It is considerably used by yachts and small craft, but seldom by vessels, on account of the narrow channel and strong tidal currents. The principal dangers on both sides are marked by buoys. It has been closed to navigation for the period of the war.

Deer Island, on the south side of Shirley Gut and separating Broad Sound from Boston Harbor, is described on page 245.

BOSTON HARBOR.

The entire harbor is shown on chart 246, and the inner harbor on chart 248. The entrance, between Point Shirley on the north and Point Allerton on the south, is about 4¾ miles wide. A group of islands and shoals lie in and off the entrance, through which several

Digitized by Google

channels lead. There is a depth of 35 feet to Boston through Broad Sound North Channel, and less through the others. Great Brewster, 104 feet high, is the most prominent of the islands in the entrance.

OUTER HARBOR AND CHANNELS.

Under this heading are described the approach channels, and the islands and shoals from the entrance to President Roads. Hingham, Quincy, and Dorchester Bays are described under separate headings.

Channels.—Three main channels, all obtained by dredging, lead through the shoals at the entrance, to President Roads. There are several other channels of less importance, used by local vessels.

Broad Sound North Channel leads from Broad Sound to President Roads from northeastward, eastward of Deer Island. It has been dredged 35 feet deep and 1,500 feet wide, and is well marked by lighted buoys and an unlighted range.

Broad Sound South Channel leads from Broad Sound in a southwesterly and westerly direction to President Roads. It has been dredged 30 feet deep and 1,200 feet wide, and is well marked by buoys and lighted ranges.

The Narrows is the channel leading into Boston Harbor from southeastward, between Boston lighthouse and Lovells Island on the northeast, and Point Allerton, St. Georges Island, and Gallups Island on the southwest. It has been dredged 27 feet deep and 1,000 feet wide, and is well marked. There are unmarked shoals with depths of 21 to 23 feet in the southeastern approach, which may be avoided in the daytime and with clear weather.

Shirley Gut, a narrow approach to Boston Harbor from northward, is described on page 241.

Hypocrite Channel is a natural channel leading between Green Islands on the north and Little Calf Island on the south. It has ample depth, but there are unmarked dangers, and the greatest draft that can be taken through it to Broad Sound South Channel at low water is about 18 feet. It is not recommended for strangers.

Black Rock Channel, leading into The Narrows from eastward, between Great Brewster Spit and Lovells Island, has an unmarked ledge with a least found depth of 9 feet nearly in mid-channel, which strangers may be unable to avoid. It is used only by small local vessels, and is not recommended for strangers.

There is a channel 250 yards wide, leading into The Narrows from westward, between St. Georges Island and Gallups Island. There is a light near the end of the shoal off the southeast end of Gallups Island. This channel is suitable only for quick-working vessels, on account of the sharp turn into The Narrows.

The Nubble Channel, leading from Nantasket Roads to President Roads between Nixes Mate and Long Island, has been dredged 15 feet deep and 300 feet wide, and is well marked by buoys and a beacon. The course through the channel is about 335° true (N by W mag.), heading about 100 yards to the left of Deer Island lighthouse, following the buoys, and passing 200 feet eastward of the beacon.

Sculpin Ledge Channel leads between Long Island and Spectacle Island, and is good for vessels of about 8 feet draft to Hingham Bay by the passage southward of Peddock Island. The deeper water

Digitized by Google

favors Long Island, and in coming from President Roads the island should be followed at a distance of about ¼ mile until up with the red buoy off the easterly end of Sculpin Ledge. Pass close eastward of the buoy, and round the southwesterly end of Long Island at a distance of about 400 yards.

The channel leading from Nantasket Roads to Boston, southward of Long Island and Spectacle Island, is partially marked by buoys, and can be used by boats of 8 feet draft with the aid of the chart. Directions to Hingham Bay through this channel are given on page 266.

Boston light vessel, off the entrance to Boston Harbor 6 miles eastward of Boston lighthouse, has a red hull with "Boston" on each side and a mast with black lantern. The light is fixed white, 48 feet above the water, and visible 12 miles. The fog signal is an air siren (blast 3 seconds, silent 17 seconds). A submarine bell strikes "5–4" every 18 seconds.

Thieves Ledge, with 4½ to 6 fathoms over it, is ¾ mile long and about ¼ mile wide. It is dangerous in heavy easterly gales, when the sea breaks on it. The ledge is marked northward of its shoalest part by a whistling buoy, which lies 2⅝ miles east-southeastward of Boston lighthouse. There are spots with 5¾ fathoms over them lying ½ mile eastward and 1⅛ miles southeastward of the buoy, upon which the sea sometimes breaks in heavy easterly gales.

Harding Ledge, 2⅜ miles southeastward of Boston lighthouse and 1½ miles from the shore, is an extensive ledge, bare at low water, and marked by a spindle on its shoalest part, and a gas buoy and a bell buoy ⅜ mile northeastward of the spindle. There is a rock, bare at low water, 300 yards southwestward of the spindle, and very broken ground, not closely examined, between the ledge and the shore westward. Vessels should keep outside the gas and bell buoys.

Point Allerton has shoals extending eastward and northward from it. **Ultonia Ledge,** the eastern end of the broken ground, has very broken bottom and unmarked spots, with depths of 3¾ fathoms, ¾ to 1¼ miles eastward of the point. Point Allerton beacon (black cone on granite pyramid) is 350 yards northward of the point and near the end of the part of the shoal, which is bare at low water.

Boston lighthouse, on the north side of the entrance to Boston Harbor from southward, is a white conical tower on a small island. The light is flashing white (flash 8 seconds, eclipse 22 seconds), 102 feet above the water, and visible 16 miles. The fog signal is a steam siren, sounding a group of two blasts of 5 seconds' duration each every 60 seconds. An auxiliary light, 13 yards from Boston lighthouse, shows a fixed white light with two fixed red sectors covering the dangers in Nantasket Roads.

Shag or **Egg Rocks** are bare, rugged ledges lying ¼ to over ½ mile eastward of Boston lighthouse. They are surrounded by extensive submerged ledges.

Great Brewster, Middle Brewster, Outer Brewster, and **Calf Islands** are the larger of the islands lying northward and northeastward of Boston lighthouse. Great Brewster is 104 feet high, has a bluff at the north end, and is the most prominent. These islands are surrounded by several smaller islands and extensive shoals, bare and submerged.

Great Brewster Spit, extending 1 mile westward from Great Brewster Island, is bare at low water and marked at the west end by

Digitized by Google

Narrows lighthouse (white dwelling on piles) and a beacon, and by another beacon (spindle on granite base) on the south side ¼ mile eastward of the lighthouse.

The Graves are a group of bare rocks and ledges about ½ mile long in a northeasterly direction, and are marked near the southwest end by The Graves lighthouse. **Northeast Grave** is a rock bare at low water 700 yards northeastward of the lighthouse. A gas and whistling buoy is moored about ½ mile northeastward of the ledge and ⅞ mile northeastward of the lighthouse.

The Graves lighthouse is a conical granite tower. The light is group flashing white (flash 0.2 second, eclipse 1.3 seconds, flash 0.2 second, eclipse 4.3 seconds), 98 feet above the water, and visible 16 miles. The fog signal is a reed horn, sounding a group of two blasts, each of 3 seconds' duration, every 20 seconds.

The material from the dredged channels in Boston Harbor is dumped in Broad Sound 1 to 3½ miles northeastward and north-northeastward of The Graves lighthouse. A gas buoy and bell buoy, painted white and marked "DG," are maintained on the dumping ground, and are moved to indicate the locality where dumping is in progress. The only place where marked shoaling has occurred lies 1½ miles 20° true (NE by N mag.) from The Graves lighthouse, and this shoal has been removed to a least depth of 7 fathoms.

Roaring Bulls, ½ to ⅞ mile southwestward of The Graves lighthouse, is bare in the highest parts before low water and unmarked.

Green Island, 1¼ miles southwestward of The Graves lighthouse, is about 30 feet high, and is surrounded by several smaller islets and bare and submerged ledges.

Devils Back, ⅝ mile westward of Green Island, is bare at the northeast end at low water.

Lovells Island, on the northeast side of The Narrows and south side of South Channel, has several buildings, and the lights of the Lovells Island range (white conical towers) at the north end. **Ram Head Flats** and **Ram Head** (bare at low water) extend to a greatest distance of ¾ mile northeastward of the island.

Nixes Mate is an extensive reef on the south side of the eastern end of President Roads; near the center is a low grassy island marked by Nix Mate beacon (pyramid on granite base), and at its northwest end is North Channel Front beacon (barrel on spindle on planked dolphin).

Gallups Island, westward of Lovells Island, is the site of the United States quarantine station. It has several houses and a wharf on the south side.

St. Georges Island, southward of Lovells Island and on the north side of Nantasket Roads, has a large fort and several houses. There is a wharf on the west side.

Nantasket Roads, westward of the southern entrance to The Narrows and southward of St. Georges Island, is a good anchorage. The depths range from 8 to 12 fathoms. On the westerly side of St. Georges Island the depths range from 4 to 6 fathoms, and better bottom and shelter will be found here in easterly winds. This anchorage is frequently used by vessels seeking shelter in easterly gales.

To ENTER NANTASKET ROADS, follow the directions of section 1B for Boston Harbor to a position nearly ½ mile southward of Boston lighthouse. Then steer 258° true (W ¼ N mag.), and pass 250 to 300

Digitized by Google

yards northward of Hunt Ledge horizontally striped buoy. Then bring Boston lighthouse astern on a 234° true (WSW mag.) course; at night this course will lead in the white sector of Boston (auxiliary) light, which is 40 feet from Boston light and will be in range with it on this course. The course leads southward of two red buoys, marking spots with 16 feet and 14 feet. When the eastern end of St. Georges Island closes on the west end of Lovells Island, haul westward and anchor south of St. Georges Island, keeping Narrows lighthouse open southward of the island.

Vessels of less than 18 feet draft can anchor westward of St. Georges Island by following the preceding directions until Deer Island lighthouse is in range with the west end of Gallups Island, bearing 326° true (N by W ¾ W mag.). Then steer this course, pass between St. Georges Island and the black buoy northeastward of Hospital Shoal, and anchor anywhere westward of St. Georges Island and southward of Gallups Island, in 4 to 6 fathoms. St. Georges Island is fairly bold on its west side and Gallups Island on its south side.

Rainsford Island, nearly 1 mile westward of St. Georges Island, is occupied by buildings of city institutions and has a wharf on its south side. Extensive shoals lie southward and southwestward of Rainsford Island.

Long Island, on the south side of President Roads, is 1½ miles long and marked at the north end by **Long Island Head lighthouse** (white tower with a covered way to a dwelling). There are numerous houses on the middle of the island.

Deer Island, on the north side of President Roads, and separating Broad Sound from Boston Harbor, is mostly cultivated land in the center, and has some brick buildings and chimneys near its northwest end. **Great Faun Bar** and **Little Faun Bar** extend eastward from Deer Island to Broad Sound North Channel. A stone beacon with red spindle is placed on Great Faun Bar 650 yards northwestward of the edge of the channel and near the easterly end of the part of the bar that is bare at low water. A ledge bare at low water, extending ¼ mile southward from Deer Island, is marked near the end by Deer Island lighthouse (brown tower on black pier).

Shirley Gut is described on page 241.

President Roads, a wide and good anchorage, lies between Deer Island lighthouse and the easterly end of Governors Island Flats. The shoals on the northwest side of the Roads are marked by buoys. The depths in the roads range from 5 to 10 fathoms with Deer Island lighthouse bearing about 87° true (E by S mag.), distant ¼ to 1¼ miles. The quarantine anchorage, on the north side of the Roads, is defined by the harbor master (see "Anchorages"). The Main Ship Channel leads along the southern side of the Roads.

Spectacle Island, on the south side of President Roads at its western end, consists of two islands connected by a gravel spit. It is marked on the northeast end by the lights of the Spectacle Island range (white conical towers). There are chimneys and a water tank on the southwest side of the island.

BOSTON INNER HARBOR.

Channel.—The Main Ship Channel of Boston Harbor has been dredged 35 feet deep and 1,200 feet wide from President Roads to the upper end of the navy yard at Charlestown. This depth has also

Digitized by Google

been obtained by dredging to the lower bridges in Mystic, Chelsea, and Charles Rivers, but in 1917 slight shoaling had occurred at the mouths of these rivers. An anchorage basin 30 feet deep, 350 yards wide, and 7/8 mile long, has been dredged along the northeast side of the Main Ship Channel, southwestward of Bird Island Flats, and considerable dredging has been done to depths of 35 to 40 feet at other places along the sides of the 35-foot channel. For the channels in the tributaries of Boston Harbor, see their description following.

Governors Island Channel, formerly leading northward and westward of Governors Island Flats, is being filled by the dumping of material from the dredging channels, and is no longer navigable.

The northern part of Boston Harbor, northward of the Main Ship Channel and between the entrance and East Boston, is full of extensive flats, bare at low water, between which crooked natural channels lead. Several channels have been dredged through the flats to depths of 6 to 8 feet to yacht clubs at the head. These channels are usually marked by bush stakes or private spindles in summer. The best approach is from southeastward, between the western end of Deer Island Flats and the eastern end of Apple Island Flats. The easterly channel was dredged 8 feet deep, and leads to the west side of **Winthrop Beach**. An anchorage basin of the same depth was dredged at the head. A light marks the west side of the entrance of the dredged channel.

Castle Island, on the southwest side of Main Ship Channel 1 mile northwestward of Spectacle Island, is marked by Fort Independence, and is connected with the shore westward by a dike.

Governors Island, on the northeast side of Main Ship Channel and 1/2 mile north-northeastward of Castle Island, is about 100 feet high, grassy, and marked by Fort Winthrop on its summit,

Reserved Channel, leading westward from Main Ship Channel at a point 1/4 mile above Castle Island, has been dredged 30 feet deep and 300 feet wide to L Street Bridge and 12 feet deep and 400 feet wide for 1/4 mile above the bridge to the head. It gives access to some of the wharves of South Boston and is marked by buoys. The bridge has a single opening 39.8 feet wide and a headroom of 6.4 feet above mean high water when closed. The bridge will be opened at any time on a signal of two long and two short blasts of a whistle.

The **city of Boston** includes within its limits **East Boston, Charlestown, South Boston, Roxbury, Dorchester**, and **Neponset**. East Boston is on the northeastern side of the harbor, and is separated from the city of Chelsea by Chelsea River. Chelsea is separated from Charlestown, on the western side of the harbor, by the Mystic River, and Charlestown from Boston proper by the Charles River. The **United States Navy Yard** occupies a large part of the deep water front of Charlestown. South Boston is on the peninsula southeast of the city proper, from which it is separated by South Bay and Fort Point Channel.

Fort Point Channel and **South Bay** separate Boston proper from South Boston. In a distance of 1 mile from its entrance in Boston Harbor, Fort Point Channel is crossed by nine bridge. A dredged channel 175 feet wide and 23 feet deep leads from the entrance to Dorchester Avenue Bridge, a distance of nearly 3/4 mile. From the latter bridge to the head of South Bay the depth is 12 feet. Sailing

Digitized by Google

vessels employ towboats if bound into Fort Point Channel or South Bay.

Bridges, Fort Point Channel.—The draws of the bridges crossing Fort Point Channel are kept closed at certain hours. See "Bridge regulations" on page 254. The following are the drawbridges crossing the channel, named in order from the mouth, the least width of draw openings, and the clear height above mean high water when closed:

Northern Avenue (highway), 75.6 feet, 7.6 feet.
Congress Street (highway), 51.2 feet (east), 6.4 feet.
Summer Street (highway), 51 feet, 4.6 feet.
Dorchester Avenue (highway), 42 feet, 4.6 feet.
Atlantic Avenue (highway), 41.5 feet, 11.7 feet.
New York, New Haven & Hartford Railroad, 44.3 feet, 8.4 feet.
New York, New Haven & Hartford Railroad (Y connection), 50 feet.
Broadway (highway), 50 feet.
Dover Street (highway), 40.7 feet, 15.4 feet.

Charles River, on the western side of the harbor between Boston proper and Charlestown, is the approach by water to the city of **Cambridge** and **Watertown**. The entrance of the river to the first bridge has been dredged for its full width to a depth of 35 feet. Thence to the **Charles River Dam**, a distance of ½ mile, the depth is about 21 feet. The lock in the Charles River Dam is 350 feet long between gates, with a clear width of 45 feet, and has a depth of 17 feet at low water on the lower sill; the upper sill has 21 feet over it at the level of the river above the dam. Charles River above Charles River Dam is maintained at a height of 7.4 feet above mean low water; a depth of 14 feet can be taken 3 miles above the dam to Western Avenue Bridge, thence 2¼ miles to Arsenal Street Bridge 13 feet, thence 2 miles to the head of navigation at the dam at Watertown 9 feet. Charles River above the dam is used by small vessels and many yachts and small craft. No toll is charged for passage through the lock.

Bridges, Charles River.—Nine bridges, all with draws, cross Charles River between the entrance and Charles River Dam. They are closed during certain hours, as described under "Bridge regulations," on page 254. The first bridge has two draw openings 50 feet wide and a headroom of 23 feet at high water when closed. The others have a least draw width of 36.5 feet and no headroom at high water when closed. The following are the bridges named in order from the mouth: Charlestown, Warren, Boston & Maine (formerly Fitchburg Railroad for teams, Boston & Maine (formerly Fitchburg) Railroad, Boston & Maine Railroad, Boston & Maine (formerly Eastern) Railroad, Boston & Maine (formerly Lowell Passenger) Railroad, Boston & Maine (formerly Lowell Freight) Railroad, and Boston Elevated Railway.

Between Charles River Dam and the head of navigation, ten bridges cross the river. Six have draw openings, with a least width of 36.5 feet, and four are without draws, and have a least headroom of 12 feet above water level. The following are the bridges, named in order from the dam: Charles River Dam, Cambridge (fixed, headroom 30 feet), Harvard, Grand Junction Railroad, Brookline Street

Digitized by Google

(fixed, headroom 29 feet), Cambridge Street, Western Avenue, Stadium (fixed, headroom 12 feet), Arsenal Street (Western Avenue), North Beacon Street (fixed, headroom 12 feet).

Mystic River, entering the north end of Boston Harbor from northwestward, between Charlestown and Chelsea, is the approach to several wharves near the lower end, and to the towns of MEDFORD and Malden. The channel in Mystic River has been dredged 30 feet deep and about 900 feet wide for a distance of 1 mile above Chelsea Bridge at the entrance, and 30 feet deep and about 500 feet wide, for a further distance of about 3/8 mile, to a point 350 yards below the second bridge. The river above has been improved by dredging a channel 6 feet deep and 100 feet wide to Dennings coal wharf, 2¾ miles above the entrance, and 4 feet deep and 100 to 50 feet wide to Medford, 4⅜ miles above the entrance. There is a lock at Medford, 15 feet wide and 45 feet long, and the river has a navigable depth of 4 to 7 feet for 2 miles above the lock to LOWER MYSTIC LAKE. The deepest draft using the lower part of the river is 28½ feet, and the deepest draft ordinarily going to Medford is 10½ feet, mostly coal barges. The channel above the second bridge is crooked and very narrow in places.

BRIDGES, MYSTIC RIVER.—Mystic River is crossed by six drawbridges between the entrance and Medford. The bridges remain closed at certain hours as described under "Bridge regulations" on page 254. The following are the bridges, named in order from the mouth, and the width of the draw openings:

Chelsea (north), each opening 125 feet, 13 feet above high water.
Malden, 75 feet.
Boston Elevated, 75 feet.
Boston and Maine (eastern division), 75 feet.
Boston and Maine (western division), 43.5 feet.
Wellington, 50 feet.

ISLAND END RIVER, a tributary of Mystic River from northward ½ mile above the entrance, has been dredged by private interest 26 feet deep and 140 feet wide from its entrance past the New England Coal and Coke Co., wharf, a distance of about 500 yards, and to a depth of 13 feet for a further distance of about 150 yards, to the wharf of the Barrett Co., above which it has a depth of about 1½ feet in a narrow crooked channel for about 5/8 mile to the head. There is considerable business to the wharves near the entrance, principally vessels up to 25½ feet draft, carrying coal and oil. A rocky shoal on the east side at the entrance, and the current of Mystic River running across the entrance, make navigation difficult for large vessels. A towboat is usually employed to assist such vessels.

MALDEN RIVER, a tributary of Mystic River from northward, 1¾ miles above its entrance, has been improved by dredging a channel 100 feet wide and 12 feet deep at high water (2.4 feet at low water) from the entrance to Medford Street Bridge at MALDEN, about 1½ miles above. The deepest draft going to Malden at present are coal barges drawing 10½ feet.

BRIDGES.— Malden River Bridge, crossing Malden River ½ mile above its entrance, has a draw opening 50.3 feet wide, and a headroom of 7.7 feet in the center at high water when closed. Medford Street Bridge, crossing Malden River just above the head of the dredged channel, has a draw opening 35.9 feet wide, and a headroom

Digitized by Google

of 3.9 feet at high water when closed. The bridges are opened at all times on a signal of two long and two short blasts. See "Bridge regulations" on page 254. Three bridges cross Mystic River below the mouth of Malden River, as described under Mystic River.

Chelsea River, emptying into Boston Harbor from eastward between East Boston and Chelsea, is the approach to important wharves near the entrance, and to the town of REVERE at the head, 2⅝ miles above the entrance. The 35-foot dredged channel of Boston Harbor leads to Meridian Street Bridge, just inside the entrance. From this bridge to Chelsea Street Bridge, ¾ mile above, the channel has been dredged 25 feet deep and 150 feet wide. A channel 25 feet deep has been dredged by private interests to the Mexican Petroleum Co. wharf, ¼ mile above Chelsea Street Bridge. In 1917 there was less depth through the bridge, but this was to be dredged to 25 feet. The channel has been dredged 8.4 feet deep at low water and 150 feet wide from this point to the head of navigation at Revere. The usual limit of draft of vessels using the lower end of the river is 24 feet, and the upper end 15 feet, mostly coal barges.

BRIDGES.—Three drawbridges cross Chelsea River between the entrance and the head of navigation. Meridian Street Bridge has an opening 100 feet wide on the south side and 30 feet wide on the north side, and a headroom of 5 feet at high water when closed. Chelsea Street Bridge has two openings 60 feet wide, and a headroom of 4 feet at high water when closed. Grand Junction Railroad bridge has a single opening 60 feet wide, and a headroom of 0.4 foot at high water when closed. The bridges are opened at all times on a signal of two long and two short blasts, as described under "Bridge regulations" on page 254.

GENERAL INFORMATION.

Anchorage.—President Roads and Nantasket Roads are the usual anchorages for vessels in the lower bay. The anchorage for vessels and yachts in the inner harbor is limited, but good holding ground in 3¾ to 5 fathoms will be found on both sides of the channel above Governors Island, within the limits prescribed by the harbor master. The anchorage for deep-draft vessels is in the 30-foot dredged anchorage basin on the northeast side of the channel off Bird Island Flats; the northeasterly side of the anchorage is marked by beacons. Yachts and Government vessels anchor off the entrance of Fort Point Channel, between Boston and South Boston, and northward of the New York, New Haven & Hartford Railroad piers, as defined by the anchorage regulations following.

Harbor and anchorage regulations.—The limit of speed for any steam vessel in Boston Harbor within 100 yards of any wharf is 5 miles per hour. The signal for the harbor master or police steamer is three short blasts and one long blast of the whistle. The following anchorage regulations are in force:

UPPER HARBOR, BIRD ISLAND ANCHORAGE.

1. All vessels anchoring in this basin shall anchor within the following marks, viz:

The westerly end of the Quincy Market cold storage building on Eastern Avenue in range with the easterly end of the gasometer at the North End Gas Works and southeast of a line of the large tower on the brewery on Marginal Street in

Digitized by Google

range with the coal elevators on the pier of the Massachusetts Wharf Coal Co. (adjoining the terminal of the Boston, Revere Beach & Lynn Railroad) in East Boston, and 600 feet from the wharves in East Boston. Vessels of light draft to take the inside berth. An area northwest of a line drawn southwest by west from dolphin D on the northeast side of this anchorage basin is reserved for steamers exclusively. No light vessel shall anchor on this anchorage without permission of the harbor master.

SOUTH BOSTON ANCHORAGE.

2. All vessels anchoring on South Boston flats shall anchor within the following marks, viz:

The round chimney on the cold storage building on Richmond Street in range with the granite block on Long Wharf and southeast of the Metropolitan Coal Co.'s channel.

YACHT ANCHORAGE.

3. This anchorage is reserved for yachts and vessels of the United States Government, and they shall anchor within the following marks, viz:

The round chimney on the cold storage building on Richmond Street, between Commercial Street and Atlantic Avenue, in range with the granite block on Long Wharf; to the westward of the dock between Pier 1 and Pier 2, New York, New Haven & Hartford Railroad; the flagstaff on freight house No. 2, on the Fort Point Channel side of the New York, New Haven & Hartford Railroad Docks in range with the northerly side of the Atlas Stores building in South Boston; and not less than 500 feet from Pier 1, New York, New Haven & Hartford Railroad Docks.

4. No vessel shall anchor northwest of these ranges without permission from the harbor master.

5. No vessel shall anchor in the dredged channel to the Metropolitan Coal Co.'s wharf in South Boston nor in the reserved channel to L Street bridge.

6. Before loading or discharging cargo or coal into or from a vessel at anchor in the upper harbor the master, consignee, or stevedore must obtain a permit from the harbor master. (Such vessel if not anchored in a proper place must be assigned a berth before such permit is granted.)

7. No vessel shall receive or deliver gasoline or other supplies in the streams or channels of the harbor outside of the anchorage areas.

LOWER HARBOR, PRESIDENT ROADS AND QUARANTINE ANCHORAGE.

8. All vessels shall anchor northeast of a line from Deer Island light in range with Little Calf Island and west of a line from the westerly end of the main prison building of the House of Correction at Deer Island in range with the water tower on Winthrop Head.

9. All vessels anchoring between Spectacle and Castle Islands shall anchor southwest of a line drawn from the barn on the hill on Spectacle Island and the southwest end of the fort on Castle Island.

NANTASKET ROADS ANCHORAGE.

10. Between April 1 and November 1 in each year all vessels shall anchor southwest of a line of the northeasterly end of the most northeasterly barracks building on Long Island in range with the lighthouse on Long Island Head or northeast of a line of the sea wall on the east head of Long Island in range with the tree on the southeast end of Apple Island and 500 feet from the shore of Georges Island.

11. No vessel shall anchor in The Narrows or the entrance thereto.

12. No vessel shall anchor in Lighthouse Channel southwest of a line between Kellys Ledge and Nashs Rock buoys or northeast of a line between Hunts Ledge and the buoy on Point Allerton Bar.

13. No vessel shall anchor in the dredged channels in Broad Sound or so as to obstruct the view of any range light in any part of the harbor.

Pilots.—Pilotage into Boston Harbor is compulsory, with a few unimportant exceptions which seldom occur, for all vessels engaged in the foreign trade, but not for vessels engaged in the coasting trade.

Digitized by Google

Pilots cruise in pilot boats, which are designated by the numbers painted in black figures 4 feet high. The outer one usually cruises outside The Graves and the inner one inside. The following are extracts from pilotage regulations for Boston Harbor and tributaries:

Every vessel bound into the harbor of Boston liable to pilotage, which shall arrive within a line drawn from Hardings Ledge to The Graves and thence to Nahant Head, without having been offered the service of a pilot, shall be exempt from the payment of pilotage fees; but if thereafter she requests and receives such services, she shall pay the regular rates.

Any vessel of not more than 350 tons register, bound into the port of Boston, declining the services of a pilot shall, if otherwise liable under the provisions of law to the payment of pilotage fees, be liable only for one-half of the regular fees; but if such vessel request and receive such services, the regular fees shall be paid therefor.

No vessel of under 350 tons register bound out from the port of Boston shall be held to pay pilotage fees for services tendered and declined; but if such vessel request and receive such services, the regular fees shall be paid therefor.

All coastwise steam vessels not sailing under register, vessels regularly employed in the coasting trade, all fishing vessels other than whalers, and all vessels of less than 7 feet draft of water shall be exempt from the compulsory payment of pilotage.

Whenever any vessel exempt from the compulsory payment of pilotage requests the aid of a pilot any pilot so requested shall serve such vessel in like manner as vessels not so exempt and shall be entitled to the regular compensation therefor.

The established pilot signal by day is a white and blue flag, white next to the mast, and in the night a white light at the masthead.

A vessel taking steam by the desire of the master thereof shall pay full pilotage fees, but when steam is taken by direction of the pilot in charge such vessel shall be held to pay but 75 per cent of the regular fees.

National vessels, both when inward and when outward bound, shall, if they employ a pilot, pay the same rates as vessels in the merchant service.

When a vessel is anchored for 12 hours or more under any regulation relative to quarantine or to alien passengers the pilot in charge, upon piloting such vessel to her port of destination, shall be entitled to an addition of 25 per cent to the regular fees.

When a pilot, without any fault or negligence of his own or of his associates, is unable to leave the vessel under his charge and is carried to sea he shall be entitled to $2 for each day on which he is necessarily detained from home.

It shall be the duty of every pilot, after having brought a vessel to the inner harbor of Boston, to have such vessel properly moored in the stream or secured to a wharf (below the bridges), at the option of the master, within 24 hours after arrival, weather and tide permitting, without extra charge.

The fees for hauling a vessel from the stream to a wharf (below the bridges), after the expiration of 24 hours from arrival, shall be $4, and for hauling a vessel from the wharf to the stream, provided the vessel does not proceed to sea within 24 hours from the time of anchoring, $4.

If any vessel outward board, having a pilot on board, should anchor in Nantasket Roads, it shall be the duty of the pilot to remain on board said vessel, if requested by the master, until the next high water; and if detained after that time, he shall be entitled to receive $3 per day for each and every day so detained.

No pilot shall leave a vessel outward bound, until outside of Boston light, without permission of the master of said vessel.

NEPONSET RIVER.—The pilotage for the several landing places in the towns of Dorchester and Neponset shall not be compulsory. When the services of a pilot are required the rates of pilotage authorized by the commissioners shall be $1 per foot on inward draft. Outward vessels without cargo, $5 per vessel; with cargo, same as inward.

HINGHAM, EAST WEYMOUTH, QUINCY, QUINCY POINT, WEYMOUTH, EAST BRAINTREE, AND NANTASKET.—The pilotage for the above places shall not be compulsory. When the services of a pilot are required and are offered outside of a line drawn from Nantasket Point to the east point of Petticks Island, from thence a line drawn to the northwest point of said Petticks Island, from

Digitized by Google

thence in a line to Sunk Island, from Sunk Island in a direct line to Hangmans Island, the rates of pilotage authorized by the commissioners shall be, viz:

East Weymouth.[1]			Quincy Point.			Hingham.		
Draft of water.	Rate per foot.	Amount.	Draft of water.	Rate per foot.	Amount.	Draft of water.	Rate per foot.	Amount.
Feet.			*Feet.*			*Feet.*		
7	$0.88	$6.16	7	$0.72	$5.04	7	$0.92	$6.44
8	.90	7.20	8	.72	5.76	8	.95	7.60
9	.92	8.28	9	.72	6.48	9	.97	8.70
10	.93	9.30	10	.80	8.00	10	1.00	10.00
11	.99	10.89	11	.92	10.12	11	1.00	11.00
12	1.10	13.20	12	1.00	12.00	12	1.10	13.20
13	1.25	16.25	13	1.25	16.25	13	1.25	16.25
14	1.40	19.60	14	Same as East Weymouth.				
15	1.50	22.50	15					
16	1.60	25.60	16					
17	1.70	28.90	17					
18	1.80	32.40	18					
19	1.90	36.10	19					
20	2.00	40.00	20					
21	2.10	44.10	21					
22	2.20	48.40	22					
23	2.30	52.90	23					
24	2.40	57.60	24					
25	2.50	62.50	25					

[1] Nantasket, Quincy, Weymouth Landing, and Baintree, same rates as East Weymouth. Inward and outward rates the same.

LYNN.—The pilotage for the harbor of Lynn shall be $1 per foot inward. Same outward. For Saugus River, $1.25 per foot. Not compulsory.

RATES OF PILOTAGE FOR BOSTON HARBOR.

Outward rates.			Inward rates.		
Draft of water.	Rate per foot.	Amount.	Draft of water.	Rate per foot.	Amount.
Feet.			*Feet.*		
7	$1.65	$11.55	7	$2.64	$18.48
8	1.66	13.28	8	2.69	21.52
9	1.67	15.03	9	2.73	24.57
10	1.70	17.00	10	2.77	27.70
11	1.74	19.14	11	2.80	30.80
12	1.78	21.36	12	2.85	34.20
13	2.00	26.00	13	2.95	38.35
14	2.00	28.00	14	3.45	48.30
15	2.10	31.50	15	3.50	52.50
16	2.25	36.00	16	3.55	56.80
17	2.50	42.50	17	3.75	63.75
18	2.75	49.50	18	3.80	68.40
19	3.00	57.00	19	4.00	76.00
20	3.25	65.00	20	4.25	85.00
21	3.50	73.50	21	4.50	94.50
22	3.75	82.50	22	4.50	99.00
23	4.00	92.00	23	5.00	115.00
24	4.25	102.00	24	5.00	120.00
25	5.00	125.00	25	5.00	125.00
26	.....	130.00	26	.....	130.00
27	.....	135.00	27	.....	135.00
28	.....	140.00	28	.....	140.00
29	.....	145.00	29	.....	145.00
30	.....	150.00	30	.....	150.00
31	.....	155.00	31	.....	155.00
32	.....	160.00	32	.....	160.00
33	.....	165.00	33	.....	165.00
34	.....	170.00	34	.....	170.00
35	.....	175.00	35	.....	175.00

Reporting stations.—Vessels are reported to Boston from reporting stations at The Highlands (Cape Cod) and from Hull.

Digitized by Google

Towboats.—Towboats can be ordered from Boston by making signal off the reporting stations. They can also be obtained by applying at the various towboat offices. Fire and wrecking tugs are to be obtained, and will take tows to or from any point on the Atlantic coast between Nova Scotia and the Gulf of Mexico. Steam lighters can be obtained.

Quarantine.—Quarantine for the port of Boston is enforced in accordance with the regulations of the United States Public Health Service. The quarantine station is on Gallups Island, and vessels are boarded in President Roads. Vessels undergoing quarantine are anchored in President Roads as directed by the port physician. See "Anchorage regulations" preceding.

Marine hospital.—There is a marine hospital at Chelsea. The service has an office and dispensary at the customhouse, Boston, where out-patients are treated by an officer of the service, who is also the proper person to whom to apply for admission to the hospital.

Wharves.—The wharves of Boston have depths sufficient for the largest vessels, the greatest depth being 40 feet, which exists at the Commonwealth Pier. There are public float landings for small craft in Fort Point Channel, at the eastern end of the first bridge and the western part of the third bridge. A float landing at the head of the slip on the south side of the United Fruit Co.'s wharf, Boston proper, is used by many small craft with the consent of the agent.

Repairs.—There are a number of dry docks and marine railways, as listed in the table on page 28. A dry dock with a length of 1,200 feet, a width of 120 feet, and a depth of 35 feet on the sill at mean low water, is being constructed by the State of Massachusetts. There are excellent facilities for repairing the hulls of iron and wooden vessels and the machinery of steamers at Boston and Quincy Point.

Storm-warning displays are made at Hull, Boston Yacht Club at Hull, City Point (Boston Yacht Club), South Boston (city coast-guard station), Boston (post-office building), Charlestown (navy yard), the Boston Yacht Club at Dorchester, and the Savin Hill Yacht Club at Dorchester.

A United States branch hydrographic office is established at the customhouse. Bulletins are posted here giving information of value to seamen, who are also enabled to avail themselves of publications pertaining to navigation and to correct their charts from standards. No charge is made for this service.

A Coast and Geodetic Survey suboffice is located at the customhouse, where complete files of the Coast and Geodetic Survey charts, coast pilots, tide tables, and other publications relating to navigation may be consulted and information affecting navigation obtained without charge. The suboffice is also a sale agency for Coast and Geodetic Survey publications.

Time ball.—A time ball is dropped daily at noon, seventy-fifth meridian time, from the Ames Building, Boston, and is visible from the harbor.

Ice rarely forms in the main channels. Occasionally during severe winters the greater part of the harbor is frozen, but towboats and steamers keep the main channels open. The Charles, Mystic, and Chelsea Rivers, and the minor passages in the harbor are sometimes frozen during severe weather. When ice is prevalent, the buoys may be displaced or even carried away by it.

Digitized by Google

Tides.—The mean rise and fall of tides is 9 feet at Boston lighthouse and 9.6 feet at Boston Navy Yard. The predicted times and heights of high and low water for every day in the year at the navy yard are given in the tide tables, published by the Coast and Geodetic Survey.

BRIDGE REGULATIONS.

The following are extracts from the rules and regulations prescribed by the Secretary of War to govern the opening of the drawbridges across Boston Harbor and tributaries:

BRIDGES WITHOUT CLOSED HOURS.

1. The draw in each and every bridge hereafter named in this paragraph shall, upon the signal prescribed in paragraph 7 below being given, be opened promptly at all hours for the passage of any vessel or vessels or other water craft not able to pass underneath it: *Provided*, That when the draw in any of the said bridges shall have been open for 10 minutes or longer it may be closed for the crossing of trains, cars, vehicles, or individuals, if any be waiting to cross, and after being so closed for 10 minutes or for such shorter time as may be necessary for the said trains, cars, vehicles, or individuals to cross, it shall be again opened promptly for the passage of vessels or other water craft if there be any such desiring to pass. The requirements of this paragraph shall apply to each and every one of the following-named bridges, so called, to wit:

Across Chelsea Creek or Chelsea River.—Meridian Street Bridge, Chelsea Street Bridge, and Grand Junction Railroad Bridge.

Across Mystic River.—Wellington Bridge.

Across Malden River.—Malden River Bridge on Revere Beach Parkway and Medford Street Bridge at Malden.

Across Charles River.—Grand Junction Railroad Bridge, Cambridge Street Bridge, Western Avenue Bridge, North Harvard Street Bridge, Arsenal Street (Western Avenue) Bridge, and North Beacon Street (Market Street) Bridge.

Across Reserved Channel.—L Street Bridge, South Boston.

Across Neponset River.—New York, New Haven & Hartford Railroad Bridge, Neponset Avenue Bridge, and Granite Bridge.

Across Weymouth Fore River.—Quincy Point Bridge and East Braintree Bridge.

Across Weymouth Back River.—Hingham Bridge.

Across Crystal Cove.—Boston, Revere Beach, and Lynn Railroad bridge.

Across Tenean Creek.—Commercial Point or Tenean Bridge.

BRIDGES WITH CLOSED HOURS.

2. Between the hours of 9 a. m. and 4.30 p. m. and between the hours of 7 p. m. and 6.30 a. m. on week days, and at all hours on Sunday and on legal holidays observed in the locality, the draws in each and every bridge hereafter named in this paragraph shall, upon the signal prescribed in paragraph 7 below being given, be opened promptly for the passage of any vessel or vessels or other water craft not able to pass underneath it: *Provided*, That when the draw in any of the said bridges shall have been open for 10 minutes or for such shorter period as may be necessary for the passage of vessels or other water craft desiring to pass, between the hours aforesaid, it shall be closed for the crossing of trains, cars, vehicles, or individuals if any be waiting to cross, and after being so closed for 10 minutes or for such shorter time as may be necessary for said trains, cars, vehicles, or individuals to cross, it shall be again opened promptly for the passage of vessels or other water craft if there be any such desiring to pass. Between the hours of 6.30 a. m. and 9 a. m. and between the hours of 4.30 p. m. and 7 p. m. the draws in the bridges hereafter named in this paragraph shall not be required to be opened on week days for the passage of any vessel, vessels, or other water craft except during the periods between 7.05 a. m. and 7.15 a. m., between 8 a. m. and 8.10 a. m., between 5.20 p. m. and 5.30 p. m., and between 6.20 p. m. and 6.30 p. m., and excepting also as provided in paragraphs 4, 5, and 11 of these rules and

Digitized by Google

regulations. The requirements of this paragraph shall apply to each and every one of the following-named bridges, so-called, to wit:

Across Mystic River.—Chelsea Bridge South, Chelsea Bridge North, Malden Bridge, Boston & Maine (Eastern Division) Railroad bridge, and Boston & Maine (Western Division) Railroad bridge.

Across Charles River.—Harvard Bridge.

Across Fort Point Channel.—Northern Avenue Bridge, Congress Street Bridge, and Summer Street Bridge.

3. Between the hours of 9.10 a. m. and 4.15 p. m. and between the hours of 7.40 p. m. and 6.15 a. m. on week days, and at all hours on Sundays and on legal holidays observed in the locality, the draws in each and every bridge hereafter named in this paragraph shall, upon the signal prescribed in paragraph 7 below being given, be opened promptly for the passage of any vessel or vessels or other water craft not able to pass underneath it: *Provided*, That when the draw in any of the said bridges shall have been opened for 10 minutes or for such shorter period as may be necessary for the passage of vessels or other water craft desiring to pass, between the hours aforesaid, it shall be closed for the crossing of trains, cars, vehicles, or individuals, if any be waiting to cross, and after being so closed for 10 minutes or for such shorter time as may be necessary for the said trains, cars, vehicles, or individuals to cross, it shall be again opened promptly for the passage of vessels or other water craft, if there be any such desiring to pass. Between the hours of 6.15 a. m. and 9.10 a. m. and between the hours of 4.15 p. m. and 7.40 p. m. the draws in the bridges hereafter named in this paragraph shall not be required to be opened on week days for the passage of any vessel, vessels, or other water craft, excepting that when the tide is high at Charlestown Navy Yard between 6.15 a. m. and 9.10 a. m. the drawbridges hereafter named in this paragraph shall be opened for a period between 6.15 a. m. and 9.10 a. m. not exceeding 10 minutes and within 45 minutes before or after said high tide for the passage of all vessels or other water craft when of a draft of 12 feet or over, if there be any such desiring to pass; the exact time of opening within the prescribed limits of 45 minutes before and after said high tide to be prescribed by the railroad companies, due regard being had for causing minimum interference with railroad schedules, highway traffic, and the interests of navigation. The opening time of each bridge shall be so fixed as to permit continuous passage through the next and following bridges located in direction of course of vessel or other water craft.

Across Charles River.—Charlestown Bridge, Warren Bridge, Boston & Maine (formerly Fitchburg) Railroad bridge, for teams; Boston & Maine (formerly Fitchburg) Railroad bridge, Boston & Maine Railroad bridge, Boston & Maine (formerly Eastern) Railroad bridge, Boston & Maine (formerly Lowell passenger) Railroad bridge, Boston & Maine (formerly Lowell freight) Railroad bridge, Boston Elevated Railway bridge, and Charles River Dam Bridge.

Across Fort Point Channel.—Dorchester Avenue Bridge, Atlantic Avenue (Cove Street) Bridge, New York, New Haven & Hartford Railroad bridge, New York, New Haven & Hartford (Y connection) Railroad bridge, Broadway Bridge, Dover Street Bridge, and New York, New Haven & Hartford (South Bay Junction) Railroad bridge.

Because of the narrowness of the channel below the bridge and the necessity for the unhampered movement of vessels therein in the conduct of certain naval operations during the present emergency of war, * * * between the hours of 3.15 a. m. and 4.30 a. m. daily, including Sundays, the draw of the bridge known as the Charlestown Bridge across the Charles River shall be kept closed, and no traffic from above the bridge shall be permitted to pass through during these hours. This regulation shall continue in force only until the proclamation of peace.

4. The draw in Chelsea Bridge, North, shall, upon the signal prescribed in paragraph 7 below being given, be opened promptly at all hours for the passage of any vessel, vessels, or other water craft whose draft is 18 feet or more; and any vessel, vessels, or other water craft proceeding upstream that during any of the periods on week days from 7.05 a. m. to 7.15 a. m., 8 a. m. to 8.10 a. m., 5.20 p. m. to 5.30 p. m., and 6.20 p. m. to 6.30 p. m., shall have passed through Chelsea Bridge, North, or through any other bridge across Mystic River between Cheslea Bridge, North, and Boston & Maine (Western Division) Railroad bridge, shall be passed promptly on signal through each and all of the bridges located upstream from Chelsea Bridge, North, the provisions of paragraph 2 of these rules and regulations to the contrary notwithstanding; and any vessel, vessels, or other water craft proceeding downstream that during

Digitized by Google

any of the aforesaid periods shall have passed through Boston & Maine (Western Division) Railroad bridge or through any other bridge across Mystic River between Boston & Maine (Western Division) Railroad bridge and Chelsea Bridge, North, shall be passed promptly on signal through each and all of the bridges located downstream from Boston & Maine (Western Division) Railroad bridge, the provisions of paragraph 2 of these rules and regulations to the contrary notwithstanding.

5. The draws in Northern Avenue Bridge, Congress Street Bridge, and Summer Street Bridge shall upon the signal prescribed in paragraph 7 below being given be opened promptly at all hours for the passage of any vessel, vessels, or other water craft whose draft is eighteen (18) feet or more.

Any vessel, vessels, or other water craft proceeding upstream through Northern Avenue Bridge shall be afforded continuous passage through Congress Street Bridge and Summer Street Bridge; and any vessel, vessels, or other water craft proceeding downstream through Summer Street Bridge shall be afforded continuous passage through Congress Street Bridge and Northern Avenue Bridge, the provisions of paragraph 2 of these rules and regulations to the contrary notwithstanding.

6. The length of time that a draw has been open shall be computed from the time that the draw span begins to move in opening, and the length of time that a draw has been closed shall be computed from the time that the draw span ceases to move in closing.

7. When a vessel or other water craft intends to pass through the draw of one of the bridges covered by these rules and regulations the master or pilot of the vessel or craft shall, on approaching within signaling distance, signify his intention to pass through the bridge by sounding with a whistle or horn the signal prescribed below, viz:

For Meridian Street Bridge: Two long blasts, followed immediately by two short blasts and one long blast.

For all other bridges: Two long blasts, followed immediately by two short blasts.

For Chelsea Bridge, North, by vessels drawing 18 feet or more: Four long blasts.

For Northern Avenue, Congress Street, and Summer Street bridges, by vessels drawing 18 feet or more: Four long blasts.

The signal given by a master or pilot shall be immediately answered from the bridge by three long blasts of a whistle or horn unless under these rules and regulations a delay in opening the draw is permitted, and in case of such delay the signal shall be immediately answered by two long blasts. A long blast of a whistle or horn as herein provided shall continue for three seconds and a short blast for one second.

8. Upon hearing or perceiving the signals prescribed in paragraph 7, or upon verbal request from the master or pilot of any vessel or other water craft waiting at the bridge, the tender or operator of the draw of the bridge signaled shall at once open the draw for the prompt passage of any vessel or other water craft unless under these rules and regulations a delay in opening the draw is permitted: *Provided*, That the draw may not be opened if there is a train, car, or other vehicle at the time passing over said draw or if a train or car is approaching so closely that it can not be safely stopped before reaching the draw, but the draw shall be opened as soon as it can be cleared, and no person, vehicle, car, or train shall be permitted to begin to cross the draw after it has been signaled to open, excepting as herein provided.

9. Trains, cars, vehicles, or persons shall not be stopped on any draw span for the purpose of delaying the opening of the draw, nor shall any vessel or other water craft be so handled or placed as to delay the opening or closing of any draw span, but all passage over, under, or through a draw span shall be prompt, so as to reduce delays to water and bridge traffic to a minimum. Upon notice from the Secretary of War so to do, the owner or owners of any bridge whose draw is held closed, as authorized in paragraph 2 of these rules and regulations, shall station and maintain at such bridge a tug to aid vessels and other water craft in passing expeditiously through the draw thereof.

10. The owner or owners of every bridge covered by these rules and regulations shall maintain in good and efficient order the draw span and the machinery and appliances for operating the same and for assisting vessels while passing through the draw. The said owner or owners shall also provide and maintain at the draw span such number of draw tenders or operators as may be necessary to open and close the same promptly; and they shall also provide

Digitized by Google

and maintain in good order on the bridge piers or fenders such fixtures as may be necessary to vessels in mooring or making fast while waiting for the draw span to open.

11. These rules and regulations shall not apply to steam vessels owned or leased by the United States, nor shall they apply to vessels employed by the city of Boston or other municipality for police and fire protection. All such United States and municipal vessels shall be passed without delay through the draws of all bridges at any hour of the day or night upon signaling by four long blasts of the whistle.

CURRENTS, BOSTON HARBOR.

The time of current from Boston light vessel to the navy yard does not differ by more than 15 minutes. The strength of the flood at Boston light vessel occurs about 2¾ hours before high water, and at the navy yard about 2½ hours before high water. The strength of the ebb at the light vessel occurs about 2¾ hours before low water, and at the navy yard about 2½ hours before low water. Slack water in the harbor occurs about ¼ hour after the time of high and low water at Boston.

The currents at Boston light vessel are described on page 41.

In Broad Sound the velocity of the current at strength in most places is less than ½ knot. This increases to about 1 knot on approaching the entrances of the channels leading into Boston Harbor.

In Hypocrite Channel the velocity at strength is a little over 1 knot.

In South Channel, north of Ram Head, the velocity at strength is almost 2 knots.

Between Deer Island light and Long Island Head, in the channel, the velocity at strength is 2 knots.

In the Main Ship Channel, from Spectacle Island to the navy yard, the velocity at strength varies between 1 and 1½ knots.

Between Boston lighthouse and Point Allerton, near the middle of the channel, the velocity at strength is about 2 knots. On the northern side of the channel, southward of Great Brewster Spit, the current turns nearly 30 minutes earlier than in the middle of the channel, and the velocity is about half as great.

In Nantasket Roads, in the middle of the channel, the velocity at strength is 1½ knots.

In Nantasket Gut the velocity at strength is between 2½ and 3 knots.

In Black Rock Channel the velocity at strength is between 1 and 1½ knots. The flood sets southwestward through the channel and the ebb northeastward, and should be kept in mind when passing through The Narrows.

Between Georges Island and Gallups Island the velocity at strength is between 1 and 1½ knots. The flood sets westward and the ebb eastward.

Between Gallups Island and Long Island Head the velocity at strength is about ½ knot. The flood current sets southward to southwestward and the ebb in the opposite direction.

Between Moon Head and Long Island the velocity at strength is about ½ knot, the flood setting northwestward and the ebb southeastward.

Between Thomsons Island and Spectacle Island the velocity at strength is about ½ knot. The flood sets northwestward and the ebb southeastward.

Digitized by Google

In Shirley Gut the velocity at strength is between 2 and 2½ knots

A current diagram, showing the state of the current in the middle of the channel from Boston light vessel to the navy yard, is given in the tide tables, published annually by the Coast and Geodetic Survey.

GENERAL REMARKS ON APPROACHING BOSTON HARBOR.

General remarks on approaching and standing along the coast are given on page 43.

Approaching from Cape Ann.—The soundings in the vicinity of Cape Ann are very irregular and can not be depended on to locate even approximately the vessel's position. The southern end of Jeffrey Ledge, with depths of 19 to 30 fathoms, extends 15 miles eastward from Cape Ann, and depths of over 50 fathoms are found a few miles eastward and a short distance southward from the edge of the bank. A 229° true (SW by W ¾ W mag.) line drawn from the spindle on The Londoner just clears the offshore dangers between Cape Ann and Nahant, but leads over broken ground for a distance of 1½ miles from The Londoner.

At night a number of lights will be visible, and they are sufficiently numerous to locate the position readily by cross bearings. In clear weather the course should be shaped to pass well northward of The Graves lighthouse and enter through the Broad Sound North Channel.

Approaching from Cape Cod.—Approaching the easterly side of the cape, soundings of 20 fathoms indicate a distance of 2 to 3½ miles from the shore, but off the north side of the cape the 20-fathom curve draws closer inshore and the soundings are not so regular. Vessels standing for Boston light vessel will cross the southwesterly end of Stellwagen Bank in depths of 12 to 15 fathoms; this bank, with depths of less than 20 fathoms on it, begins 5 miles northward of the north end of Cape Cod and extends in a northerly direction for 17½ miles, its width varying from 8 miles at its southerly end to about 2 miles near its northerly end. Soundings on Stellwagen Bank can not be depended on to locate a position on the bank, except in the case of soundings in a depth of 9½ fathoms, the shoalest water, which is found near its extreme southwest end. The prevailing depths over the shoaler parts of the bank are 12 to 15 fathoms.

As the entrance to Boston Harbor is approached, after crossing Stellwagen Bank, soundings of 20 fathoms or more (at low water) insure a distance of 5 miles or more from the shore and well outside of outlying rocks. Inside the depth of 20 fathoms the soundings are very irregular, and they can not, as a rule, be depended on to keep a vessel out of danger.

At night in clear weather Minots Ledge and The Graves lights will be sighted shortly after the lights on Cape Cod (Cape Cod and Race Point lights) are dropped. The course should be shaped for Boston light vessel to avoid the rocks and shoal spots lying eastward and northward of Minots Ledge, and on which the sea breaks in heavy gales.

Tidal currents.—For some distance northwestward of Cape Cod the tidal currents have a slight set southward into Cape Cod Bay on the flood and eastward out of the bay on the ebb. Along the north shore of Massachusetts Bay the flood sets in a general westerly or

Digitized by Google

northwesterly direction and the ebb in a southerly or southeasterly direction. The velocity of the currents is influenced greatly by the force and direction of the wind. Off the entrance to Boston Harbor the flood sets westward and ebb eastward, increasing slightly in velocity as the entrance is approached.

Fogs.—In thick weather Boston light vessel should be steered for when approaching from either Cape Ann or Cape Cod, and the water should not be shoaled to less than 20 fathoms unless the fog signal of the light vessel is heard and the vessel located. From the light vessel a course may be laid for Boston lighthouse; and the fog signal of the latter, with a frequent use of the lead, will enable a vessel to reach an anchorage inside of Point Allerton. Unless the light vessel is located no attempt should be made to enter the harbor, and the water should not be shoaled to less than 20 fathoms.

Vessels when in the vicinity of Cape Cod, if overtaken by fog or thick easterly weather, may find it convenient to anchor in Provincetown Harbor or on the west side of the cape south of Provincetown, where there is a good lee and holding ground in 7 to 11 fathoms.

DIRECTIONS, BOSTON HARBOR.

Boston Harbor and approaches has very broken, rocky bottom, and caution is necessary. The area from the entrance of Nantasket Roads and Broad Sound North and South Channels, out to a depth of 25 fathoms or more, has been examined by means of a wire drag, and the dangers are shown on the charts. The area examined in this way extends northeastward to beyond Cape Ann and southward to Cape Cod Canal, the outer limit usually being from 4½ to 7 miles from the shore.

For the period of the war, all channels into Boston Harbor are closed to navigation, except Broad Sound North Channel. The following directions do not take into account the special regulations prescribed for the period of the war.

1. Entering through Broad Sound North Channel to President Roads.—From a position 1 mile southeastward of Cape Ann lighthouses, steer 226° true (SW by W ⅜ W mag.) for 22⅜ miles to the red gas and bell buoy marking Finns Ledge, off the entrance to Broad Sound North Channel; this course leads 1¼ miles southeastward of Eastern Point lighthouse, ½ mile southeastward of Newcombs Ledge whistling buoy, and 1¾ miles northwestward of The Graves lighthouse.

Or, from Boston light vessel steer 299° true (NW ⅛ W mag.) for 5 miles, and pass ¼ mile northeastward and northward of Graves gas and whistling buoy. Then steer 252° true (W ¼ S mag.) for 2⅝ miles, to the red gas and bell buoy marking Finns Ledge, off the entrance to Broad Sound North Channel.

Pass midway between the red gas and bell buoy and the black gas buoy ¼ mile southward, and bring the red gas and bell buoy astern on a 208° true (SW ¼ S mag.) course for 2⅛ miles, passing through the middle of the dredged channel and being guided by the buoys until ¼ mile past the buoys marking the inner end and on the Spectacle Island lighted range; on this course, through the dredged channel, North Channel range, each structure a barrel on spindle on planked dolphin, is in line ahead, showing between Long and Gallups Islands. When on Spectacle Island range (white towers), steer 250°

Digitized by Google

true (W ½ S mag.) for ½ mile on this range to a position ¼ mile north-northwestward of Long Island Head lighthouse and 200 yards northward of a black buoy. If going to Boston, follow the directions in section 2.

1A. Entering through Broad Sound South Channel to President Roads.—From a position 1 mile southeastward of Cape Ann lighthouse make good a 224° true (SW by W ¼ W mag.) course for 22 miles to the gas and bell buoy at the entrance of Broad Sound South Channel. The course leads 1½ miles southeastward of Eastern Point lighthouse, ¾ mile northwestward of Graves gas and whistling buoy and nearly 1 mile northwestward of The Graves lighthouse.

Or, from Boston light vessel, steer 299° true (NW ⅛ W mag.) for 5 miles and pass ¼ mile northeastward and northward of Graves whistling buoy. Then steer about 237° true (WSW ⅜ W mag.) for 1⅞ miles to the gas and bell buoy at the entrance of Broad Sound South Channel.

Steer 215° true (SW ⅜ W mag.), keeping the lights of the Lovells Island range (white towers) in line ahead, and pass midway between the buoys marking the sides of the outer section of Broad Sound South Channel. When between buoys Nos. 5 and 6 steer 250° true (W ½ S mag.), keeping the lights of the Spectacle Island range (white towers) in line ahead, pass midway between the buoys marking the sides of the channel, and pass ¼ mile southward of Deer Island lighthouse and ¼ mile northward of Long Island Head lighthouse. Then follow the directions in section 2.

1B. Entering through The Narrows to President Roads.—The following courses and distances made good will lead to Boston light vessel:

From Cape Ann whistling buoy steer 211° true (SW mag.) for 20½ miles.

From a position 3 miles northeastward from Cape Cod lighthouse steer 295° true (NW ½ W mag.) for 36 miles, passing close to the gas and whistling buoy off Peaked Hill Bar.

From a position 1 mile southwestward of Wood End lighthouse steer 309° true (NW ¾ N mag.) for 31¾ miles.

I. From Boston light vessel.—Steer 258° true (W ¼ N mag.) for 6 miles, passing about 400 yards northward of Thieves Ledge whistling buoy, 400 yards northward of Point Allerton Bar bell buoy, and to a position nearly ½ mile southward of Boston lighthouse.

From a position nearly ½ mile southward of Boston lighthouse steer 266° true (W by N mag.) for Georges Island Rocks gas buoy, and pass about 250 yards southward of the red buoys marking Nash and Kellys Rocks. When Deer Island light is in range with Narrows light, change course gradually to 295° true (NW ½ W mag.) for the eastern end of Gallups Island, and pass about 175 yards southwestward of Narrows lighthouse. Care should be taken not to be set off the course by the tidal currents setting to or from Black Rock Channel and the passage between St. Georges and Gallups Islands. When past the southerly end of Lovells Island, steer 312° true (NW by N mag.) with Deer Island lighthouse a little on the port bow, and pass midway between Gallups Island and Lovells Island and about 200 yards northeastward of Nix Mate gas and bell buoys. When past these buoys change course gradually to 250° true (W ½ S mag.), keeping the lights of the Spectacle Island range in line ahead, and

Digitized by Google

pass ¼ mile southward of Deer Island lighthouse and ¼ mile northward of Long Island Head lighthouse. Then follow the directions of section 2.

II. ALONGSHORE FROM SOUTHEASTWARD.—Vessels should pass outside the buoys marking the broken ground along the shore southeastward of Minots Ledge lighthouse, and pass 1½ miles northeastward of that lighthouse. Coming from Plymouth, the directions on page 272 can be reversed; or, from Cape Cod Canal, the directions on page 283 can be reversed.

2. President Roads to Boston.—From a position on the Spectacle Island range line about ¼ mile north-northwestward of Long Island Head lighthouse, steer 268° true (W by N mag.), with Nix Mate gas and bell buoys in range with the north end of Great Brewster astern for 1¼ miles, passing 500 yards northward of Spectacle Island and to a position midway between gas buoys Nos. 1 and 2. Then steer 290° true (NW by W mag.) for ⅜ mile, heading for Fort Independence, the stone fort on Castle Island, until midway between gas buoys Nos. 3 and 4. From here steer 310° true (NW ¾ N mag.) for 1¼ miles, being guided by the buoys, to a position between gas buoys Nos. 5 and 10. Then steer 301° true (NW mag.) for ¾ mile to a position between buoys Nos. 7 and 12; then steer more northward, keeping near the middle of the harbor. The anchorage in the inner harbor is on either side of the channel abreast Bird Island Flats, as directed by the harbor master. See "Anchorages" in the description preceding.

DORCHESTER BAY

(chart 246) extends southwestward from President Roads between Spectacle and Thomson Islands on the east and South Boston on the west. The bay is filled by extensive flats, large areas of which are nearly bare at low water and rise abruptly from the edge of the channel. A channel 175 feet wide and 18 feet deep is dredged up to Commercial Point. The principal traffic is in coal and building material, which is brought by barges and other vessels that are towed to Commercial Point, Neponset, and Milton Mills. Vessels can select anchorage in the channel of Dorchester Bay below buoy No. 6, the best place being northwestward of Thomson Island and east-northeastward of the buoys marking the northerly end of the dredged cuts. Above buoy No. 6 there is scant swinging room for anchorage for vessels of a greater draft than 8 feet.

Old Harbor, on the south side of South Boston, is filled by flats with little water over them. Two anchorage basins for yachts have been dredged on the north side of the harbor; the easterly one has a depth of 9 feet and the westerly one 6 feet. There is a recreation pier on the north side at the entrance.

Commercial Point is on the west side at the entrance of Neponset River. On the north side of the point is an anchorage basin with depths of 9 to 22 feet, mostly used by small yachts. A middle ground, 400 feet wide and with 1 to 4 feet over it, lies on the easterly side of the basin, between it and the dredged channel; a horizontally striped buoy is placed on the westerly side of the dredged channel at the northerly end of the middle ground.

Digitized by Google

Neponset River is ¼ mile wide at the entrance, and narrows to 100 yards at **Milton Mills**, the head of navigation. A channel 100 feet wide and 15 feet deep has been dredged for a distance of 1¼ miles above Commercial Point to the highway bridge at **Neponset**, and is buoyed to this point. Thence to Milton Mills, a distance of 2¼ miles, the channel has been dredged 75 to 100 feet wide and 6 feet deep.

Bridges.—Four drawbridges cross Neponset River between the entrance and Milton Mills. The bridge crossing the river near the entrance has a draw opening 50 feet wide, and a headroom of 6.4 feet at high water when closed. New York, New Haven & Hartford Railroad bridge at Neponset has a draw opening 52.3 feet wide, and a headroom of 5.9 feet at high water when closed. Neponset Avenue Bridge at Neponset has a draw opening 36.5 feet wide, and a headroom of 4.5 feet at high water when closed. Granite Bridge, 1 mile above Neponset, has a draw opening 36.4 feet wide, and a headroom of 5.2 feet at high water when closed. The bridges are opened at all times on a signal of two long and two short blasts, as described under "Bridge regulations" on page 254.

A channel has been dreged 12 feet deep from the 18-foot dredged channel northward of Squantum Point to a wharf on the north side of the point. It is marked by buoys.

Pilots are generally taken by strangers, and may be had by making signal off Thomsons Island, anchoring there if necessary; they are not always taken by light-draft vessels bound to Neponset. Pilotage is not compulsory; the rates for the lower part of Neponset River are given on page 252.

Towboats are taken by most vessels in going up and down Neponset River, the master of the tug doing the piloting below Neponset Bridge, where, if bound for Milton, a special pilot is taken and the vessel being towed pays this pilotage.

Directions, Dorchester Bay.—The following directions are good for a draft of 8 feet to the anchorage basin northward of Commercial Point.

From President Roads pass about ¼ mile northward of Spectacle Island and steer 238° true (WSW ⅜ W mag.) for the red buoy lying ⅜ mile westward of Spectacle Island. Pass close eastward of the buoy and continue the course, passing about 400 yards northwestward of Thomsons Island and heading for the buoys marking the northerly end of the dredged cuts. Pass between the buoys and steer 216° true (SW ½ W mag.) with buoy No. 6 on the starboard bow. As the buoy is approached, haul westward, pass 100 feet southward of it, and steer 256° true (W mag.) for a red and black horizontally striped buoy.

Pass northward of this buoy on a 267° true (W by N mag.) course, and anchor in the anchorage basin westward of the middle ground. The westerly edge of the middle ground is marked by a range of two white beacons on the northerly side of Commercial Point, bearing 179° true (S by W ⅛ W mag.); the front beacon is a pile, and the rear one a circular daymark on a shed. The dredged channel to Commercial Point leads eastward of the middle ground, and is marked by a black buoy and by a range of two beacons (white, diamond-shaped daymarks) on the wharf on the easterly side of Commercial Point.

Digitized by Google

QUINCY BAY

(chart 246) indents the southerly shore of Boston Harbor between the peninsula of Squantum and Hough Neck. The general depths in the bay are 8 to 10 feet, but shoals partly bare at low water extend ½ to ¾ mile from its southerly side. **Hangmans Islet**, small and rocky, lies near the middle of the entrance to the bay; the reef extending over ¼ mile southwestward from the islet is marked near its end by a black spindle. A ledge with 5 feet over it lies ⅜ mile northward of Hangmans Islet, with foul ground between. **Sunken Ledge**, dry at low water, lies ⅝ mile northeastward of Hangmans Islet and is marked by a stone beacon with staff and cage.

Wollaston Channel, near the westerly end of the bay, has been dredged 60 feet wide and 8 feet deep to the yacht club house at Wollaston. The channel is marked by buoys; the course through it is 215° true (SW ⅜ W mag.).

Eastward of Squantum and connected with it by a causeway lies **Moon Head**, which is recognized by the grassy hill and bluff on its easterly end. The entrance to Quincy Bay from westward is between Moon Head and Long Island, and is good for a depth of about 8 feet at low water. From here the **Back** or **Western Way** leads in a northerly direction between Spectacle Island and Thomsons Island to the Main Ship Channel, and the Sculpin Ledge Channel in a northeasterly direction along the northwesterly shore of Long Island into President Roads.

Hough Neck is marked at its northeasterly end by a green hill 100 feet high, called **Quincy Great Hill**, which is mostly settled; a standpipe on the hill is prominent. **Nut Islet**, marked by a power station, lies 300 yards northward of Quincy Great Hill, with a causeway between. There is a channel into Hingham Bay between Nut Islet and Peddock Island.

HINGHAM BAY

(chart 246) is that part of Boston Harbor lying southeastward of Peddock Island. It is the approach to Weymouth Fore River, Weymouth Back River, Hingham Harbor, and Weir River. The easterly part of the bay is shoal, and extensive shoals make out from the southerly shore and surround the islands in the bay. The easterly entrance is through Nantasket Gut, but there is also an entrance southward of Peddock Island that is frequently used by vessels bound into Weymouth Fore or Back Rivers.

Nantasket Gut is a narrow channel between Peddock Island and Windmill Point, and leads into the bay from Nantasket Roads. The tidal currents have considerable velocity, but generally follow the direction of the channel; the flood sets southward and ebb northward. There is an unmarked 16-foot spot in midchannel.

Windmill Point, on the east side of Nantasket Gut, is marked on its southerly side by a light. Prominent on Windmill Point is a large hotel with a steamboat landing (**Pemberton**) southward of it, which is the terminus of the Nantasket Beach Railroad. Eastward, on the slopes of the hill, are the town of **Hull** and the Hull yacht club houses. The usual and best anchorage is off the steamboat landings at Hull and Pemberton. Hull is connected with Boston by steamer.

Digitized by Google

Weymouth Fore River has its entrance on the southwest side of Hingham Bay between Hough Neck and Grape Island, and is the approach by water to **Quincy Point, Weymouth, East Braintree,** and a number of landings. The channel has been improved by dredging, and has a width of 300 feet and depth of 18 feet for a distance of 2½ miles from the entrance to the Fore River Ship & Engine Co.'s shipyard at Quincy Point. Thence for a distance of about 2 miles to the head of navigation at East Braintree (**Weymouth**) there is a narrow channel with a depth of 6 feet. Plans have been approved for dredging a channel 24 feet deep and 300 to 600 feet wide from the entrance to the bridge at Quincy Point, but no work had been done in May, 1918. The river has considerable trade in vessels of 18 to 25 feet draft to Quincy Point. The channel above Quincy Point is narrow and unmarked, and leads between shoals bare at low water. There is a small amount of trade by water. The anchorage in Weymouth Fore River is in the channel between buoys Nos. 6 and 8.

Bridges.—Two bridges cross Weymouth Fore River. Quincy Point Bridge, crossing the river at Quincy Point, has two openings, each 125 feet wide, and a headroom of 8 feet at high water when closed. East Braintree Bridge, near the head of navigation, has a draw opening 37 feet wide, and a headroom of 5.3 feet at high water when closed.

Town River Bay, on the northwesterly side of Weymouth Fore River northward of Quincy Point, has a narrow channel between extensive shoals, and is not safe for strangers. There is a depth of 9 feet in the channel to the deep hole about ⅜ mile inside the entrance. Thence to the wharves at **Quincy,** a distance of nearly 1 mile, a channel has been dredged 100 feet wide and 4 feet deep. It leads between flats bare at low water.

Weymouth Back River lies just eastward of Weymouth Fore River and southward of Grape Island. The channel from Weymouth Fore River to the wharf of the fertilizer works on **Eastern Neck,** a distance of 1¼ miles, is buoyed, and has a least width of 200 feet and depth of 12 feet. A depth of 12 feet has been obtained by dredging for ⅞ mile above the fertilizer works to the naval magazine wharf just above Hingham Bridge. The channel is buoyed, but strangers desiring to enter the river in vessels should take a pilot or towboat. There is good anchorage at the entrance, ¼ to ⅜ mile westward of Grape Island. Hingham Bridge has a draw opening 50 feet wide, and a headroom of 10 feet at high water when closed. It is opened at all times on a signal of two long and two short blasts.

Hingham Harbor and **Weir River** are shallow and lie in the southeasterly end of Hingham Bay. Their common entrance lies close westward of Bumkin Island. The channel, 250 yards wide, with a depth of over 3 fathoms, leads for ½ mile in a southeasterly direction from the westerly end of **Bumkin Island,** and then divides. The branch leading eastward takes the name Weir River. The channel leading to Hingham Harbor trends southward, is narrow, and has a depth of 18 feet up to **Crow Point (Downers Landing),** the entrance of the harbor.

Hingham Harbor is a cove 1 mile long, with an average width of about ⅝ mile. At low water it is a dry flat, through which a narrow and tortuous channel winds, with a depth of 6 feet to the wharves at the town of Hingham. The upper end has been dredged to a depth

Digitized by Google

of 6 feet. There are coal and lumber wharves, and a yacht club wharf at Hingham. The channel is sometimes marked by bush stakes in summer.

Weir River leads to the wharf at **Nantasket**, near the southerly end of **Nantasket Beach**. It is filled by extensive flats, mostly bare at low water, between which is a channel with a least width of 100 feet and depth of 12 feet. The channel is used by steamers running from Boston to Nantasket, and is marked by lights on piles during the summer; the piles remain in position until carried away by ice. A channel 12 feet deep has been dredged by private interests through an extensive shoal in the river, cutting off a sharp bend in the original channel. The cut is marked by private spindles. Nantasket has a large steamer wharf and a public float landing for small craft north of it.

Pilots.—Pilotage is not compulsory for Hingham Bay and tributaries, but pilots are usually taken by vessels going into Weymouth Fore River or Weymouth Back River. There are licensed pilots at Hull, and one can be obtained on signal. A pilot for Weymouth Fore River above Quincy Point can be obtained at Quincy Point. Vessels waiting for a pilot can anchor in Nantasket Roads or between Nantasket Gut and Sheep Island. Rates are given on page 252.

Towboats are employed by all large vessels entering the tributaries of the bay, being generally taken from Boston.

Repairs.—The shipyard at Quincy Point has facilities for the construction and repair of the largest ships and engines of steamers.

Tides.—The mean rise and fall of tides is about 9 feet.

Additional general information is given under Boston Harbor, on page 249.

DIRECTIONS, HINGHAM BAY.

1. Entering through Nantasket Gut.—The directions of this section lead in a least depth of about 16 feet at low water.

From Nantasket Roads pass through Nantasket Gut on a course about 154° true (S by E mag.), passing 150 yards westward of Windmill Point. When through Nantasket Gut good anchorage will be found about ¼ mile southward of Windmill Point in 4½ to 7½ fathoms. A pilot can be had here for the tributaries of the bay, or proceed as directed in paragraph I or II following.

I. To Weymouth Fore River.—When through Nantasket Gut bring the large hotel on Windmill Point astern on a 202° true (SW ¾ S mag.) course and pass between the red and the black buoys off Harrys Rock. When 200 yards eastward of buoy No. 8 and Sheep Island is in range with the south side of Bumkin Island, bearing 93° true (ESE ½ E mag.), steer 157° true (S ¾ E mag.) for the westerly end of Grape Island open from the easterly side of Lower Neck and pass westward of a black buoy and 100 to 150 yards eastward of buoy No. 2. Then steer 208° true (SW ¼ S mag.) with the high water mark at the west end of Sheep Island in range with the summit of the hill at Hull astern; the standpipe on Nantasket Hill will be seen eastward of Hull. On this course pass about 300 yards westward of the red buoy at the entrance to Weymouth Back River, 100 yards westward of Jackknife Ledge black buoy, and 100 yards eastward of buoy No. 4.

Digitized by Google

Then steer 241° true (WSW ¾ W mag.) and anchor in the channel between buoys Nos. 6 and 8. Above this point the channel is too narrow to afford anchorage for vessels of any size. To go to Quincy Point, continue the 241° true (WSW ¾ W mag.) course until close to the wharves just below the bridge at Quincy Point, passing about 50 yards southward of buoys Nos. 8 and 10. Then if going above the bridge head for the draw.

II. To the Entrance of Hingham Harbor and Weir River.—From Nantasket Gut steer 154° true (S by E mag.), passing 150 yards westward of Bumkin Island Shoal gas buoy. When the high-water mark on the northerly side of Sheep Island is in range with the standpipe on Quincy Great Hill, bearing 252° true (W ⅜ S mag.), steer 131° true (SE ⅞ S mag.). Pass 200 yards westward of Bumkin Island and 100 yards westward of Bumkin Island black buoy; continue the course nearly ½ mile past this buoy, and anchor 150 yards north-northeastward of Crow Point Flats red buoy, marking the entrance to Hingham Harbor, or be guided by the chart to Hingham or Nantasket.

1A. Entering southwestward of Peddock Island.—This channel is used by the deepest draft vessels, bound to Weymouth Fore River or Weymouth Back River, and is good for a depth of about 23 feet to the mouths of these rivers. It is also used by light-draft vessels and motor boats, entering by the channel southward of Long Island. The following directions are good for a draft of about 8 feet at low water.

From Boston by the Back or Western Way.—Pass eastward of Castle Rocks gas buoy, lying east-southeastward of Castle Island, and steer 160° true (S ½ E mag.) for the easterly end of Moon Head. When midway between the northerly ends of Spectacle and Thomson Islands steer 142° true (SSE ⅛ E mag.) with Fort Independence (on Castle Island) astern. On this course leave a black buoy northeastward of Thomson Island 200 yards on the starboard hand, a red buoy southward of Spectacle Island 200 yards on the port hand, a red buoy 200 yards off the southwesterly end of Long Island 100 yards on the port hand, Sunken Ledge beacon 350 yards on the port hand, and Wreck Rock red buoy 250 yards on the starboard hand. Continue the course to a position 350 yards northeastward of Nut Islet, and then steer 93° true (ESE ½ E mag.) for Sheep Island in range with the southerly side of Bumkin Island, being guided by the buoys and passing about 350 yards northward of Pig Rock light. When about ⅜ mile from Sheep Island, steer 157° true (S ¾ E mag.) for the westerly end of Grape Island open from the easterly side of Lower Neck, and proceed as directed in section 1, paragraph I, for Weymouth Fore River.

To the Entrance of Hingham Harbor or Weir River.—Follow the directions preceding, and bring Pig Rock light astern on a 45° true (NE by E ¼ E mag.) course, heading for the standpipe on Nantasket Hill until up with the black buoy off Harrys Rock. Then steer 76° true (E mag.) for Bumkin Island Shoal gas buoy until 200 yards from it. Then steer 154° true (S by E mag.) and proceed as directed in paragraph II, section 1, preceding.

Digitized by Google

COAST FROM BOSTON TO PLYMOUTH.

Point Allerton, on the south side at the entrance of Boston Harbor, is a grassy hill, covered with houses, and the base of the sea face is protected by a sea wall. Point Allerton Bar, Ultonia Ledge, Harding Ledge, and other dangers lying northward and eastward of the point are described with Boston Harbor.

Nantasket Hill, nearly 1 mile westward of Point Allerton, is marked by an old earthwork and standpipe on its summit; storm warnings are displayed on the hill. The town of Hull is on the lower hill southwestward of Nantasket Hill.

From Point Allerton the coast trends southward for 3 miles, and is called **Nantasket Beach**. The beach is occupied by summer cottages, and at its southerly end is **Nantasket**, a popular summer resort. There are three grassy hills on the beach, the most prominent of which is **Strawberry Hill** (about 1 mile southward of Point Allerton), marked at its summit by a prominent standpipe; the other two hills southward are **White Head** and **Sagamore Head**. The wharves at Nantasket and the approach from westward are described on page 265.

From Nantasket Beach the coast, presenting a general hilly appearance, trends 3 miles east-southeastward to Cohasset Harbor. Rocks and sunken ledges extend ½ mile from shore in places. **Black Rock** and **Little Black Rock** are rocky islets, the inner one high.

Cohasset Harbor (chart 242) is a large, shallow cove lying southwestward of Minots Ledge lighthouse and 5 miles southeastward of Point Allerton. It is of little commercial importance and is not available for strangers, but is the resort of numerous yachts and fishing craft. Anchorage in 8 to 10 feet can be had in the so-called outer harbor, but boats seldom anchor here. A dredged channel, 60 to 90 feet wide and 6 feet deep, marked by buoys and lights, leads to the inner harbor. The latter is sheltered by a breakwater which extends 400 yards northward from near the westerly end of Bassing Beach at the entrance. An anchorage basin 6 feet deep has been dredged in the inner harbor and a channel about 4 feet deep leads from it to the town landing, on the south side. The fish wharves at the extreme head of the harbor are nearly bare at low water; gasoline and provisions are obtainable.

Numerous rocks and ledges lie in Cohasset Harbor and extend off to Minots Ledge lighthouse. The most prominent inside the lighthouse are **East** and **West Shag Rocks**, which show at high water. There are three channels to the entrance of Cohasset Harbor—**Western** or **Brush Island Channel**, entering between **Brush Island Ledge** and **Chittenden Rock**; **Gangway Passage**, leading between **West Hogshead Rock** and **The Grampuses**; and **Eastern Channel**, which leads between **Enos Ledge** and **West Willies**. All of the channels are marked by buoys, but the dangers are numerous; the least depth crossed in entering is about 5 feet. Gangway Passage is the widest and best entrance for strangers. Strangers, even in small craft, should enter only in clear weather and with a smooth sea. The best time is on a rising tide. The dredged channel leading into the harbor is bare at low water on either side. Chart 242 is the guide for entering.

Minots Ledge lighthouse, on **Outer Minot**, is a gray conical granite tower. The light is group flashing white (flash 1–4–3 every 30 seconds, each flash of 0.2 second duration), 85 feet above the water,

Digitized by Google

and visible 15 miles. The fog signal is a bell, sounding one stroke every 30 seconds.

Minots Ledge lighthouse is on the outer of the dangers visible at low water, but submerged rocks and very broken ground, on which the sea breaks in heavy weather and which should be avoided by vessels, extend 1½ miles northeastward and 2½ miles eastward of the lighthouse. The outer limit of the broken ground is marked by a black buoy lying 2½ miles eastward of the lighthouse.

Stellwagen Ledges is the name applied to the large number of rocks and sunken ledges which fringe the coast from Minots Ledge to Scituate Harbor. Some of these sunken ledges lie over 1 mile from shore and have from 7 to 14 feet over them in surrounding depths of 4 to 9 fathoms. When in this vicinity strangers in vessels should keep over 3 miles from the shore.

Scituate Harbor (chart 109), lying 4½ miles southward of Minots Ledge lighthouse, is suitable only for small craft with local knowledge and a smooth sea. It is a shallow cove, largely bare at low water except where dredged, and is partially protected by breakwaters which have been built out from the points at the entrance. A channel 12 feet deep and 150 feet wide has been dredged through the entrance to a point just inside the north breakwater, and 8 feet deep and 100 feet wide from this point to the wharves at **Scituate.** An anchorage basin about 360 feet wide, 800 feet long, and 8 feet deep has been dredged in the middle of the harbor along the south side of the dredged channel; and a channel 4 feet deep has been dredged from the west end of the anchorage basin, north-northwestward to the yacht club wharf. The channels are subject to shoaling.

The channel into Scituate Harbor is marked by a buoy on each side at the entrance, a light on the end of the north breakwater, and numerous buoys and beacons to mark the dredged channel inside the entrance. The best water leads 200 feet south of the end of the north breakwater and 350 feet north of the end of the south breakwater. The harbor can not be entered during heavy easterly winds. Strangers are advised to take a pilot, which may be obtained by setting a signal outside the entrance. The best time to enter is on a rising tide. There is a depth of 8 feet on both sides and at the end of the town wharf, the northerly wharf at the head, and 5 to 8 feet at the end of the coal wharf southward of it; gasoline and provisions are obtainable.

Cedar Point, on the north side of Scituate Harbor, is marked by a disused white light tower. On the high land about 2 miles 267° true (W by N mag.) from the entrance of Scituate Harbor, is a prominent high tower with pointed top, which can be seen for many miles seaward.

Four conspicuous yellow bluffs with low beaches between extend 2½ miles southward from Scituate Harbor. There is a lookout on **Second Cliff,** and houses on all except **Fourth Cliff.**

New Inlet, on the north side of Fourth Cliff and 2 miles southward of Scituate, is the approach to North River and South River. The inlet had a depth of about 4 feet at low water on the bar in 1917, and is marked by a bell buoy, but is subject to change and never entered except by boats with local knowledge. Some sand and gravel are shipped from a point about 1 mile inside the inlet in barges up to about 7 feet draft.

Digitized by Google

North River, emptying through New Inlet from westward, has been cleared of bowlders in a channel not less than 100 feet wide to the village of **Hanover**, about 10 miles above the entrance. The depth to this point is about 3 feet at low water and 9 feet at high water, except at a point just inside the inlet, where it is nearly bare at low water. The river is little used. The bridges crossing it have draws, but they are seldom opened.

South River, emptying through New Inlet from southward, is shoal and seldom used.

Brant Rock is a post village and summer resort on **Green Harbor Point**, 7¾ miles southward of Scituate Harbor. A water tank and radio mast at the village are prominent.

Green Harbor, having its entrance on the south side of Green Harbor Point, was bare at low water at the entrance and inside in 1917. It is used by a few small local fishing and pleasure boats, but is not safe for strangers. There are small jetties at the entrance, covered at high water.

Several rocks lie off Green Harbor Point to a distance of 1½ miles. **Bartlett Rock** is bare at low water and marked by a red buoy. **Howland Ledge**, ½ mile eastward of Bartlett Rock, has a least found depth of 7 feet and is marked by another red buoy. **Farnham Rock**, ¾ mile north-northeastward of Howland Ledge, has a least found depth of 14 feet and is marked by a bell buoy and a spar buoy, both red. Scattered rocky spots with depths of 4 to 5 fathoms lie northeastward of Green Harbor Point to a distance of 4½ miles and are marked on the northeast side by a red buoy. Vessels should pass eastward of this buoy. The broken ground has been examined by means of a wire drag.

High Pine Ledge, bare at lowest tides, is marked on its easterly side by a red buoy which lies ⅞ mile from shore and 2 miles northward of Plymouth (Gurnet) lighthouse. The ledge extends from the buoy nearly to the shore, and vessels should not attempt to pass westward of the buoy.

PLYMOUTH HARBOR

(chart 338), the most northerly and westerly harbor in Cape Cod Bay, affords excellent and safe anchorage and is composed of three different harbors—Duxbury Bay, Kingston Bay, and Plymouth Harbor proper. The common entrance is just southward of Gurnet Point, marked by Plymouth (Gurnet) lighthouse and beacon, and is 17 miles southward of Minots Ledge lighthouse and about 15 miles northward of Cape Cod Canal.

Plymouth Harbor is frequented by many fishing boats and pleasure craft and by cargo vessels up to 17 feet draft, the principal cargoes being coal. The depth through the entrance channel to an anchorage inside or to the junction of the channels leading to Plymouth Inner Harbor, Duxbury Bay, and Kingston Bay, is about 21 feet, although there is an unmarked 16-foot rocky spot which strangers may not be able to avoid. The channel is well marked to this point and easily entered in clear weather. The channels into the tributaries are described under their headings.

Plymouth (Gurnet) lighthouse and beacon are two lighthouses 30 feet apart on Gurnet Point at the north side of the entrance of Plymouth Harbor. The lights are fixed white, 102 feet above the

Digitized by Google

water, and visible 16 miles. There are a Coast Guard station and several houses near the lighthouses. The fog signal is a reed horn sounding a blast of 3 seconds duration every 15 seconds.

Saquish Head, on the north side 1⅜ miles westward of Gurnet Point, is a bare hill marked by a large house and several shacks.

Duxbury Pier lighthouse, marking the north side of the channel and the south end of the shoal between the main channel and the Cowyard, is a brown conical tower and has a fog bell.

Duxbury Bay, between Duxbury Beach on the east, **Saquish Neck** on the southeast, and the mainland on the west, is about 3 miles long, with an average width of 2 miles. It is full of flats, mostly bare at low water, through which several narrow crooked channels lead. These channels are usually marked by private buoys or bush stakes, but are difficult to follow without local knowledge.

Cowyard is a good anchorage in the southerly part of Duxbury Bay. The anchorage with best swinging room is 300 yards to ⅜ mile west-northwestward and northwestward of Duxbury Pier lighthouse, between the buoys marking the entrances to Plymouth Channels on the south and the buoys marking the entrance to the narrow part of the Cowyard on the north, in 6 to 11 fathoms. The channel leading north-northeastward in the Cowyard has a width of about 200 yards and is not marked except at the entrance. Shoals with little water in places rise abruptly on both sides, and at low water the edges of the shoals show by discolored water. Small vessels can pass about 50 yards westward of buoy No. 2, lying 400 yards north-northwestward of Duxbury Pier lighthouse, and steer 14° true (NNE ½ E mag.) through the Cowyard. Anchor with the south end of Clark Island bearing about 99° true (ESE mag.), distant 650 yards; the width of the channel at the anchorage is about 350 yards.

From the north end of the Cowyard abreast **Clark Island**, a crooked natural channel leads north-northwestward for about 1¾ miles to within ½ mile of **Duxbury**, above which a channel was dredged in 1916, 6 feet deep and about 50 feet wide through the flats to the yacht club wharf at Duxbury, with an anchorage basin of the same depth and 100 yards wide off the wharf. There is a depth of about 6 feet to the coal and lumber wharf just south of the yacht club.

From the north end of the Cowyard a natural channel leads northward along the east side of Duxbury Bay to the mouth of **Back River**. There is a depth of 7 feet to the bridge at the entrance of Back River, and 4 feet in Back River for about ½ mile above the bridge, above which the channel is bare or nearly so at low water. The channel as far as the bridge was partially marked in 1917 by private buoys and bush stakes, but is difficult without local knowledge. It is frequented only by small local craft. The bridge has a draw opening, but it is seldom opened.

Kingston Bay, contained between the mainland and the western point of Duxbury Bay, has a diameter of about 1½ miles, but is so full of flats as to render it unfit for navigation except with a pilot and at high water. The village of **Kingston** is built upon its western shore (about ¾ mile back from the water) on a small stream called **Jones River**. The bay is of little importance as a harbor or port. Several channels lead between the flats of this bay, but they are narrow and crooked. The northernmost and deepest is **Miles or South Channel**, and by it about 6 feet at low water can be taken to within

Digitized by Google

⅝ mile of the mouth of Jones River and 3 feet to the mouth. The river is bare at low water.

From the southerly end of the Cowyard westward of Duxbury Pier lighthouse a channel has been dredged to the **Plymouth Cordage Co.'s wharf,** 1¾ miles northwestward of Plymouth, with a turning basin at the wharf. The channel is 250 feet wide and 20 feet deep through the bar at the entrance from the Cowyard, and is marked by buoys. The upper part of the channel for a distance of ¾ mile below the wharf is 150 feet wide and 18 feet deep; the curve in this part of the channel is marked on its southerly side by black pile dolphins maintained by private parties.

Plymouth Inner Harbor is about 1 mile wide at its northern end, gradually narrowing for 2¼ miles to its southern end. The larger part of the harbor is dry at low water, and its narrow channels are unfit for navigation for strangers except in motor boats or small vessels.

The principal channel leading to Plymouth is marked by buoys, and has been dredged to a depth of 18 feet and width of 200 feet, widened at the turns. The dredged channel leads to **Long Wharf,** just south of a prominent yellow chimney and marked by a clubhouse (yellow building).

An anchorage basin 12 to 18 feet deep has been dredged off the wharves southward of Long Wharf. The easterly limit of the anchorage basin is 400 feet southeastward of the end of Long Wharf and 250 feet eastward of the end of the wharf 200 yards southward of Long Wharf. Another anchorage basin 12 feet deep, about 250 feet wide, and 450 feet long, has been dredged northward of Long Wharf. The center of this anchorage basin is 300 feet north-northeastward of the end of Long Wharf. From the westerly end of this anchorage basin a channel about 10 feet deep leads to the east side of the coal wharf 150 yards northwestward of Long Wharf. The depths at the principal wharves at Plymouth vary from 10 to 18 feet, and some are bare at low water.

A channel 12 feet deep and 60 feet wide has been dredged from the inner end of **Goose Point Channel** southward for about ⅜ mile to within 250 yards of the shore. Wharves are expected to be built at its inner end.

Prominent objects.—Captains Hill, on the peninsula between Duxbury and Kingston Bays, is about 200 feet high and on its top is Standish Monument, which shows prominently from all directions when approaching the harbor. Manomet Hill, about 5 miles southward of Gurnet Point, is over 390 feet high, heavily wooded, and is a conspicuous landmark in approaching the entrance. The buildings and several prominent objects at Plymouth are visible from eastward and northeastward.

Anchorage.—The best anchorage is in the Cowyard, but small light-draft vessels often find good anchorage under the lee of Long Beach, in 3 to 4 fathoms, hard bottom. Yachts and small craft anchor in the anchorage basins off the wharves at Plymouth.

Pilots.—There are regular pilots, and one can sometimes be had by making signal if going beyond the Cowyard, and always by inquiry at Plymouth.

Towboats are not obtainable at Plymouth, but may be ordered from Boston.

Digitized by Google

Supplies.—General supplies can be had from Boston by rail. Coal, water, and some ship chandlery can be obtained at Plymouth.

Tides.—The mean rise and fall of tides is 9.2 feet at the entrance and 9.6 feet at Plymouth.

The tidal currents have considerable velocity, the greatest velocity being between Gurnet Point and Duxbury Pier and at the entrance to the Cowyard. The set is generally in the direction of the channel; but the ebb sets southward and eastward across Browns Bank, while the flood sets northward and westward above Saquish Head, and sweeps strongly around Duxbury Pier lighthouse northward into the Cowyard.

Ice.—Beginning about the middle of January, this harbor is usually closed to navigation for a few weeks every winter by local ice; when there is ice in the harbor the Cowyard is not a safe anchorage. In winter the safest anchorage from ice is in the channel southward or eastward of Saquish Head, and vessels sometimes go to sea on account of drift ice at this anchorage. Westerly winds have a tendency to carry the ice out in fields.

DIRECTIONS, PLYMOUTH HARBOR.

The western side of Cape Cod Bay out to a distance of 4½ to 7 miles from the shore, from Boston Harbor to Cape Cod Canal entrance, has been examined by means of a wire drag. The dangers within a distance of ½ to 1 mile of the shore were not generally covered with the drag. The channels in Plymouth Harbor and tributaries generally have soft bottom, but there are many small bowlders scattered through them. The channel through the entrance is well marked and easily followed in clear weather. Above the Cowyard the channels are narrow and crooked, lead between flats bare or nearly so at low water, and local knowledge is necessary to carry the best water. The best time for strangers to navigate the channels inside the harbor is at low water when the flats are visible.

The following directions for approaching will lead to Gurnet Point whistling buoy, which lies ⅝ mile southeastward of Plymouth (Gurnet) lighthouses. In approaching, Plymouth lighthouse may be steered for on any course between 183° true (S by W ½ W mag.) through west to 312° true (NW by N mag.) until within 1 mile from it.

From Boston.—Steer 104° true (SE by E ½ E mag.), with Boston lighthouse in range with Deer Island lighthouse astern, until 2½ miles from Boston lighthouse and midway between the buoys marking Thieves Ledge and Harding Ledge. Then steer 110° true (SE by E mag.) for 6½ miles to a position ⅛ mile northeastward of black buoy No. 1, which marks a 3½-fathom spot. Then steer 143° true (SSE mag.) for 9½ miles, passing close eastward of whistling buoy No. 2 and to a position ⅛ mile eastward of buoy No. 4. Then steer 183° true (S by W ½ W mag.) for 9 miles to Gurnet Point whistling buoy.

From Cape Ann.—From a position 1 mile east-southeastward of Cape Ann lighthouses a 183° true (S by W ½ W mag.) course made good for 38 miles will lead to Gurnet Point whistling buoy. Manomet Hill should be made ahead on this course.

Digitized by Google

From Cape Cod.—Passing about 1½ miles northward of Cape Cod and 2 miles northward of Race Point lighthouse, a 249° true (W ⅝ S mag.) course made good for 15¾ miles will lead to Gurnet Point whistling buoy.

Or, having come from Provincetown, from a position ¾ mile southward of Wood End lighthouse a 268° true (WNW ⅞ W mag.) course for 17½ miles will lead to Gurnet Point whistling buoy.

From Cape Cod Canal.—From the black bell buoy off the entrance of Cape Cod Canal, a 354° true (N ¾ E mag.) course for 8½ miles will lead to a position ¼ mile eastward of the red buoy off Manomet Point, then a 321° true (NNW ¼ W mag.) course for 6⅛ miles will lead to Gurnet whistling buoy.

Gurnet whistling buoy to the Cowyard.—Pass close to Gurnet whistling buoy and steer 256° true (W mag.) with Duxbury Pier lighthouse in range with the right-hand stack at the Plymouth Cordage Co. factory and pass 100 yards southward of buoy No. 4 and to a position 100 yards northward of gas buoy No. 3. Then steer 241° true (WSW ¾ W mag.) for 1 mile to a position 100 yards northward of buoy No. 5, then 266° true (W ⅞ N mag.) for ⅞ mile, and pass 150 to 300 yards southward of Duxbury pier lighthouse. When the lighthouse is abeam haul gradually northward and anchor 300 yards to ⅜ mile west-northwestward or northwestward of it.

Cowyard to Plymouth.—The best time to navigate this channel is at low water, when the flats are visible, or on a rising tide. Pass close to the black buoy at the entrance and steer 203° true (SW ¾ S mag.) for ¼ mile, passing 50 yards westward of the second black buoy. When 200 yards past this buoy haul southeastward and steer 145° true (S by E ⅞ E mag.) for ¾ mile, being guided by the buoys and following the beach at a distance varying from 90 to 200 yards. Then haul gradually southwestward, leaving the buoys at the bend at a distance of about 40 yards, and from abreast buoy No. 17 steer 232° true (SW by W ⅞ W mag.) for ⅜ mile, heading 200 yards to the left of a prominent chimney at Plymouth, until between a red and a black buoy. Then steer 238° true (WSW ⅜ W mag.), heading 100 yards to the left of the yellow chimney, to the wharves at Plymouth. For the limits of the anchorage basin see the description preceding.

CAPE COD BAY

(chart 1208) is contained between the peninsula of Cape Cod on the east and south and the mainland of Massachusetts on the west. Between these limits it is about 20 miles in diameter, with deep water, the soundings varying from 10 to 27 fathoms, except close to the shore and in its southeasterly part. Race Point, the northwesterly extremity of Cape Cod, is the eastern and Gurnet Point the western point at the entrance. Within the limits of Cape Cod Bay are embraced several harbors—those of Plymouth on the western shore, Sandwich and Barnstable on the southern, and Wellfleet and Provincetown on the eastern shore. It is also the approach to Cape Cod Canal, connecting Cape Cod Bay with Buzzards Bay. A railroad and improved highway runs the length of the cape to Provincetown. The western side of Cape Cod Bay, out to a distance of 4½ to 7 miles from the shore, from Boston Harbor to the entrance of Cape

Digitized by Google

Cod Canal, has been examined by means of a wire drag, and the dangers are shown on the charts.

Cape Cod is a long peninsula, forming the easterly extremity of Massachusetts. It makes out from the mainland, first in an easterly direction for 31 miles, and then northward for a little over 20 miles—this latter portion forming what is usually termed the Hook of the Cape. It is composed almost entirely of sandy lands, with high, bare sand hills, and low, nearly level plains, and is well settled. Cape Cod Bay is on its northern side, and Nantucket Sound on its southern. The name Cape Cod is also generally applied to the south coast of Massachusetts between Monomoy and Falmouth.

Rocky Point lies 3¼ miles southward of Gurnet Point, with a large open bay called Plymouth Bay between. **Warren Cove**, at the southwest end of Plymouth Bay, can be used as a temporary anchorage in southerly winds, in 3 to 5 fathoms, sandy bottom. A reef with 16 feet at its end extends ½ mile northward from Rocky Point.

Between Rocky Point and Manomet Point, a distance of 2½ miles, there are a number of outlying rocks which will be avoided by giving the shore a berth of ½ mile. The shore is backed by high wooded hills, the most conspicuous of which is **Manomet Hill**, 390 feet high. **Manomet Point** is a bluff and is marked by a water tank. **Manomet** is a post office and summer resort near the point. There are a few houses on the shore at **White Horse Beach**, 1 mile northwestward of Manomet Point.

Mary Ann Rocks, two rocks bare at low water, lie ¾ and ⅞ mile southeastward of the northerly end of Manomet Point, and are marked on the easterly side by a red buoy.

Stone Horse Rocks, bare at low water, lie southwestward of Mary Ann Rocks and are a part of a reef that extends ¾ mile southeastward from Manomet Point.

Stellwagen Rock, with 6 feet over it and unmarked, lies 1¾ miles southward of Manomet Point and ⅞ mile from shore.

From Manomet Point to **Peaked Cliff**, a distance of 7 miles, the shore is a line of high bluffs backed by woods. Just southward of Center Hill Point, shoals with little water in places extend ¾ mile from shore. From Peaked Cliff the shore trends southeastward and is low. There are houses on the shore at **Sagamore Beach**, 2 miles northwestward of Cape Cod Canal.

In 1917 work was in progress to dredge a harbor for small craft ½ mile northward of Lookout Point. The basin inside the beach is to be dredged to mean low water and the entrance channel to 2 feet above mean low water. The spoil banks are prominent when close to.

Cape Cod Canal is described on page 281. There is a shoal with a depth of about 8 feet ½ mile southeastward of the outer end of the north breakwater and about ¼ mile from the shore, and midway between this shoal and the shore is a cluster of rocks awash.

Sagamore is a village on the south side of Cape Cod Canal, 1¾ miles inside its entrance. It has railroad communication. Twin yellow chimneys with a tank between them at the village are prominent.

Sandwich Harbor, 1 mile southeastward of the jetties at the entrance of Cape Cod Canal, is the approach to the village of **Sandwich**. The shore in front of the village is low marsh, faced by a sand beach.

Digitized by Google

The entrance to the harbor is between two small jetties and was being dredged in 1917 to a depth of 6 feet and width of 50 feet to a point just inside the beach. The depths at the anchorage inside are 3 to 8 feet. The channel to the wharf of the cold-storage plant near the town is bare at low water and has a depth of about 5½ feet at high water. The harbor is used only by small local fishing boats. The jetties should not be confused with the much larger ones at Cape Cod Canal. Sandwich has railroad communication.

From Sandwich Harbor, **Spring Hill Beach** extends 2¼ miles southeastward to Scorton Harbor; it is backed by lowlands, cultivated and settled. There is a water tank on **Scorton Neck**, ¾ mile south-southeastward of the entrance of Scorton Harbor. From this harbor, Scorton Neck and **Sandy Neck** extend 7 miles east-southeastward to Sandy Neck lighthouse, which is on the west side at the entrance of Barnstable Harbor.

Scorton Harbor, 3½ miles southeastward of the entrance of Cape Cod Canal, has a narrow entrance, bare at low water. It is sometimes entered at half tide or higher by small local fishing boats. At high water boats can go to the highway bridge ¾ mile above the entrance. There are no wharves. **Scorton Ledge**, an unmarked 13-foot ledge, lies ¾ mile north-northeastward of the entrance.

Barnstable Harbor.—This harbor (chart 339), 10 miles southeastward of Cape Cod Canal entrance, is the approach to the town of Barnstable and the village of Yarmouthport. It is used by many local fishing boats, but is seldom entered by strangers. The entrance is obstructed by a shifting bar with about 6 feet over it at low water. The harbor is nearly filled by flats and shoals, which also extend 2 miles off the entrance from the shore eastward of the lighthouse. The channel is partially marked by buoys, but is narrow and difficult for a stranger. Few vessels enter the harbor, the greatest draft being 12 feet. Strangers should make a signal and remain well outside the bar until a pilot comes out, keeping in a depth of over 6 fathoms. With northerly winds a heavy sea makes on the bar, and vessels bound to Barnstable should anchor in Plymouth or Provincetown until the weather moderates. Ice generally obstructs the harbor during a part of the winter.

After crossing the bar, the channel has a depth of about 8 feet for 3 miles to within ⅜ mile of the town wharf at BARNSTABLE. A channel was dredged in 1916 to a depth of 6 feet and width of 50 feet to the town wharf and cold-storage plant on MARASPIN CREEK, 300 yards above its entrance, and a turning basin of the same depth, 150 feet wide and 300 feet long, was dredged off the wharf. The channel is unmarked and some local knowledge is required to keep in it. Gasoline and provisions are obtainable. Barnstable has railroad communication.

The approach to the wharf and cold-storage plant at YARMOUTHPORT is through a narrow, crooked slough, bare at low water and having a depth of about 5 feet at high water. It is used only by a few local fishermen.

PROMINENT OBJECTS.—SANDY NECK LIGHTHOUSE, on the west side at the entrance of Barnstable Harbor, is a white tower 48 feet above the water. There are several small houses on the inside of the beach

Digitized by Google

near the lighthouse. A standpipe a little inland from Yarmouthport is visible above the trees.

Between Barnstable and Wellfleet there are a number of creeks that are used at high water by local boats and launches, but all of them are dry at low water. The 3-fathom curve is from ¼ to ⅜ mile from shore between North Dennis and Sesuit Harbor, but eastward of the latter it is ½ to 1½ miles from shore.

North Dennis, a village 3½ miles eastward of Sandy Neck lighthouse, is marked by a water tank and hotel. **Scargo Hill**, southeastward of North Dennis, is 170 feet high and the highest in the vicinity. There is a stone lookout tower on the hill.

Sesuit Harbor, 2½ miles eastward of the water tank at North Dennis, has a jetty on its east side; the entrance is bare before low water. **East Dennis** is a village ½ mile inland.

Wellfleet Harbor.—This harbor (chart 340 or 1208) is on the western side of the hook of Cape Cod, near its southern end. Extensive shoals lie in the entrance and extend about 5½ miles westward of BILLINGSGATE ISLAND LIGHTHOUSE (white frame tower), which marks the western side of the entrance to the harbor; MAYO BEACH LIGHTHOUSE (brown tower) is at the head of the harbor. The channel into the harbor leads between the shoals and is narrow in places, but it is marked by buoys, so as to be easily followed in the daytime in clear weather; it has a least depth of 14 feet until above Smalley Bar. From a little above Smalley Bar a channel 6 feet deep and 50 feet wide was dredged in 1916 to the town wharf 350 yards eastward of Mayo Beach lighthouse, and a basin 250 feet wide and 400 feet long was dredged to the same depth off the wharf. The channel above Smalley Bar is unmarked.

WELLFLEET is a town on the railroad at the head of Wellfleet Harbor. It is frequented by many small fishing and oyster boats and an occasional vessel, the deepest draft being 12 feet and usual draft 3 to 6 feet. In addition to the town wharf and an oyster wharf, to which the dredged channel leads, there are several oyster and fish houses and small wharves just below the railroad bridge crossing DUCK CREEK, the eastern tributary at the head of the harbor. The channel to them is bare about 2 hours before low water. The harbor is usually closed by ice for part of each winter. Gasoline and provisions are obtainable at Wellfleet. Storm warning displays are made.

Strangers in vessels intending to enter Wellfleet Harbor generally take a pilot, and should always do so. It is usual to go into Provincetown Harbor first and telegraph to Wellfleet for a pilot, who then joins the vessel at Provincetown. In going directly to Wellfleet entrance, vessels must depend upon obtaining a local fisherman for a pilot, the vessel anchoring meanwhile, if desirable, in the channel off the shoals, until one is obtained. Strangers in small craft should be able to enter with the aid of the chart.

ANCHORAGES.—The best anchorage is in the inner harbor, where the depth ranges from 10 to 15 feet. The anchorage in the outer harbor is somewhat exposed in westerly winds; the depth ranges from 14 to 31 feet between Billingsgate Island and Smalley Bar, and from 14 to 18 feet between Stony Bar and Billingsgate Island. In northerly gales vessels sometimes anchor on the lee side of Billings-

Digitized by Google

gate Shoal in 3 to 8 fathoms, the shoal breaking the sea so that vessels with good ground tackle can ride out a heavy gale from northward.

TIDES.—The mean rise and fall of tides is 10.7 feet. The tidal currents are weak.

DIRECTIONS, WELLFLEET HARBOR.—The directions are good for vessels of 8 feet draft, in daylight with clear weather, and lead to an anchorage in 14 to 19 feet just northward of Smalley Bar buoy. Strangers of over 8 feet draft should take a pilot at Provincetown or after coming to anchor south of Billingsgate Shoal.

Pass ¼ mile southward of the black buoy at the end of Billingsgate Shoal and steer 79° true (E ⅜ S mag.) for 4¼ miles, heading for the tall church spire at Eastham until 1 mile west-northwestward of Bibb Rock buoy and Billingsgate Island lighthouse bears 8° true (NNE mag.). Then steer 44° true (NE by E ¼ E mag.) for 1¾ miles, to a position 1⅜ miles south-southeastward of Billingsgate Island lighthouse and 100 yards southeastward of a black buoy. Then steer 2° true (N by E ½ E mag.) for ¾ mile, and then 312° true (NW by N mag.) for ½ mile to a position 50 yards westward of a red buoy and ⅜ mile east-southeastward of the lighthouse. The course is then 345° true (N mag.) for ⅜ mile to a position close westward of another red buoy, and then 33° true (NE ¼ E mag.) for 1⅜ miles to a position 50 yards southeastward of the black buoy marking Smalley Bar. Vessels can then steer 2° true (N by E ½ E mag.) and anchor ¼ mile above the buoy, or if in small craft, can follow the chart to the wharves, preferably on a rising tide. The dredged channel is unmarked, but the flats on each side are visible at low water.

Pamet River, 4½ miles southeastward of Long Point lighthouse, leads to the village of **Truro** and is used only by boats and launches; it is bare two hours before low water. A shoal extends 1 mile off the entrance. There are a prominent water tank and several houses on **Corn Hill**, on the north side of the entrance, and a prominent gray spire on the hill 1⅝ miles southward of the tank.

Ice in Cape Cod Bay.—Plymouth, Barnstable, Wellfleet, and other shallow harbors of Cape Cod Bay are usually closed to navigation a part of every winter. Instances are on record of this ice, and that forming in the shallower parts of Cape Cod Bay in severe winters, being driven by the winds out into the bay, where it masses into heavy fields or windrows, sometimes as much as 10 feet or more thick, making the navigation of parts of the bay unsafe or impracticable at times. The prevailing northerly winds drive it down to the southern end of the bay, but occasionally, at intervals of years, it has been known to obstruct Provincetown Harbor for a few days. The movements of the ice are dependent largely on the winds, the tidal currents apparently having little or no effect on it.

PROVINCETOWN HARBOR

(chart 341 or 1208) is formed by a turn in the northern end of the Hook of Cape Cod, and has a diameter of about 2 miles. It is one of the best harbors on the Atlantic coast, being of sufficient capacity for large fleets and having anchorage in 3 to 10 fathoms, with excel-

Digitized by Google

lent holding ground. Coasters and fishermen seek shelter here from gales from any direction.

The approach and entrance are free from danger and are marked by three lighthouses: Race Point lighthouse, on the northwestern point of Cape Cod; Wood End lighthouse, on the southern end of the Hook, where it turns eastward; and Long Point lighthouse, on the western point at the entrance to the harbor. At night Cape Cod lighthouse will show over the land westward of it when approaching the entrance on certain bearings.

Herring Cove, about ¾ mile southward of Race Point lighthouse, affords a temporary lee from easterly winds; small vessels sometimes anchor well inshore in from 10 feet to 4 fathoms, according to draft. The Naval Trial Course (1 mile long) is between Race Point and Wood End lighthouses, and is marked by range beacons (skeleton towers with mast) on shore and by white buoys which lie ⅝ to 1 mile from shore.

Provincetown, on the northwestern side of the harbor, is the home port of many vessels engaged mainly in the cod, mackerel, and whale fisheries, and to a limited extent in the coasting and foreign trade. The carrying trade of the port that is done by strangers is confined mostly to the transportation of coal, salt, lumber, and wood.

The depth of water at the entrance and in Provincetown Harbor is ample for vessels of deep draft, and there are no outlying dangers. There are a number of wharves, but their use is confined to vessels of less than 13-feet draft. The principal ones are the steamboat and railroad wharf, and a fish and cold-storage wharf. At mean low water the depth at the outer ends of these two is 8 feet for the former and 7 feet for the latter. The other wharves run dry or nearly dry at low water. The steamboat and railroad wharf is the easterly of the two long wharves. There is a float landing just inside its outer end.

Race Point lighthouse, at the extreme western end of Cape Cod, is a white tower. The light is fixed white, with a white flash of 4 seconds' duration every 90 seconds, 41 feet above the water, and visible 12 miles. The fog signal is an air whistle (blast 3 seconds, silent 3 seconds, blast 3 seconds, silent 51 seconds).

Shank Painter Bar, extending to a greatest distance of ⅝ mile off the shore between Race Point and Wood End lighthouses, rises abruptly from deep water. It is marked by a black buoy 1¼ miles southward from Race Point lighthouse and a black bell buoy off Wood End lighthouse.

Wood End lighthouse, on the south side of the sand spit forming the southwest side of Provincetown Harbor, is a white pyramidal tower 39 feet high. **Long Point lighthouse,** at the eastern end of the sand spit, is a white square tower 37 feet high. There are the ranges of a speed trial course on the sand spit between the lighthouses. A black buoy marks the end of the shoal extending eastward from Long Point lighthouse.

Prominent objects.—In making the northern part of Cape Cod in clear weather, the most prominent feature is PILGRIM MONUMENT, a stone structure about 350 feet high above the sea; a tall standpipe and several high church spires in Provincetown will also be seen. It is frequently difficult to recognize natural landmarks on Cape Cod

Digitized by Google

when approaching from seaward, owing to a lack of distinctive features. The Coast Guard stations and the lighthouses are about the only well-defined marks in places; of the latter, CAPE COD LIGHTHOUSE (white tower 183 feet above the water) is the most important, being the chief guide for this part of the coast. The four skeleton radio towers northward of Nauset Beach lighthouse are the most prominent day marks southward of Pilgrim Monument.

The northern and eastern side of Cape Cod is described in Atlantic Coast Pilot, Section B, Cape Cod to Sandy Hook. There is a reporting station on The Highlands, near Cape Cod lighthouse, from which vessels are reported to Boston.

Pilots are not necessary and are rarely taken by strangers in entering.

Towboats are not much used. During the stormy season towboats from Boston are sometimes to be found here; by telegraphing one can be called from there in six hours.

There are no special harbor regulations. The customhouse is near the head of the steamboat wharf.

Supplies.—Provisions and some ship chandler's stores can always be obtained. Coal can not, as a rule, be had for steamers; only a limited quantity is kept on hand. Water is furnished by a water boat; it can also be obtained at the wharves.

Storm-warning displays are made at Provincetown from High Pole Hill or Town Hill. The signals hoist 130 feet above the sea and are visible from all directions in approaching the coast. They are also made at Race Point and Cape Cod lighthouse.

Communication.—Provincetown has railroad communication, and steamers run daily during the summer to Boston.

Ice forms in Provincetown Harbor in severe winters only, and then only for short periods. Instances are on record of fields of heavy ice from the shallow harbors of Cape Cod Bay being driven northward by the wind and into the harbor, closing it to navigation for a few days. Such conditions are abnormal, occurring only at intervals of years, and under ordinary conditions the harbor is not obstructed by ice during the winter.

Tides.—The mean rise and fall of tides is 9.2 feet.

Currents.—Off Race Point the tidal currents have considerable velocity; the flood sets southwestward and the ebb in the opposite direction, and tide rips occur during heavy weather when the wind opposes the current. Westward of the stretch of coast forming the western side of the harbor the currents are nearly as strong; here the flood sets in a southeasterly direction, the ebb sets northwesterly. At the entrance and in the harbor the tidal currents have little velocity. With spring tides, at half flood the currents has somewhat greater velocity at the entrance and then sets westward, inside Long Point, and toward the western side of the harbor.

DIRECTIONS, PROVINCETOWN HARBOR.

These directions are good for vessels of the deepest draft. In thick weather great caution is required, as the lead can not always be depended on to give warning of too close an approach to the end of Cape Cod from westward on account of the abrupt shoaling of the water from 20 fathoms to 3 fathoms.

Digitized by Google

From Boston light vessel a 129° true (SE ¾ S mag.) course made good for 31¾ miles will lead to a position 1 mile southwestward of Wood End lighthouse.

From Cape Ann gas and whistling buoy a 161° true (S ⅜ E mag.) course made good for 36¼ miles will lead to a position ¾ mile westward of Race Point lighthouse.

Approaching from eastward around Cape Cod, give the northerly shore of the cape a berth of about 1½ miles until Race Point lighthouse bears southward of 210° true (SW mag.) to avoid Peaked Hill Bar. Race Point lighthouse can be approached as close as ½ mile, but the shore between it and Wood End should be given a berth of about 1 mile to avoid Shank Painter Bar. The following courses can be used at night:

Passing 2 miles or more northeastward of Cape Cod lighthouse, steer 300° true (NW mag.) for 5 miles until up with Peaked Hill Bar gas, whistling, and submarine bell buoys. Then bring the buoys astern on a 267° true (W by N mag.) course. When about 4½ miles from the buoys and Race Point lighthouse bears southward of 199° true (SW by S mag.), steer 210° true (SW mag.) for about 3 miles and pass ¾ mile or more northwestward and westward of Race Point lighthouse. Then steer 143° true (SSE mag.), giving the shore a berth of 1 mile or more, until Long Point lighthouse is open southward of Wood End lighthouse. Then steer for Cape Cod lighthouse on any bearing northward of 75° true (E mag.), pass southward of the black bell buoy lying ½ mile southwestward of Wood End lighthouse, and give the shore eastward of the lighthouse a berth of ⅜ mile.

Follow the trend of the shore between Wood End and Long Point lighthouses, giving it a berth of ⅜ mile, and pass southward and eastward of Long Point lighthouse and eastward of the buoy off it, giving the lighthouse a berth of at least ⅜ mile, until it bears southward of 255° true (W mag.). Then stand northwestward in the harbor and anchor according to draft, with the lighthouse bearing eastward of 165° true (S mag.); do not approach the eastern or northeastern shores of the harbor nearer than ¾ mile on account of extensive flats. Toward the northern shore the shoaling is gradual; toward the western shore it is abrupt from 9 to 2 fathoms.

In Thick Weather.—Lay courses that will lead farther offshore than the preceding, and pay particular attention to the fog signal at Race Point. After rounding Race Point care must be taken to stand far enough southward to clear Wood End; if the fog signal at Wood End lighthouse is not heard, and it is known that the vessel is southward of it, stand eastward, using the lead, until the vessels is in 11 fathoms. Then haul northward and northwestward, keeping in this depth, until Long Point fog signal is heard. Anchor north of this fog signal in 8 fathoms.

Or, if the wind is easterly, a good lee will be found in 8 to 10 fathoms on the westerly side of Cape Cod for a distance of 5 miles south of Provincetown Harbor.

Caution.—From a high bridge, Long Point light is visible at a number of points across Cape Cod when bearing between 208° true (SW ¼ S mag.) and 233° true (WSW mag.).

Digitized by Google

CAPE COD CANAL

connects the northern part of Buzzards Bay with Cape Cod Bay. It has a length of 11½ miles from Wings Neck lighthouse, in Buzzards Bay, to a depth of 5 fathoms in Cape Cod Bay. It shortens the distance between points north of Cape Cod and points west of Buzzards Bay by 53, 67, or 144 miles, according to the different routes considered, and avoids the outside run along the easterly side of Cape Cod and the exposed ocean route outside of Nantucket Shoals. The western approach to the canal is shown on chart 249 or 251 and the eastern approach on chart 1208.

The Cape Cod Canal is stated by the canal company to be open for navigation for vessels of about 22 feet draft. The general depth in the canal and approach channels is 25 feet. Mooring dolphins are erected at the entrances and approaches to bridges. Vessels have no difficulty in passing through the approach channels and canal, either with or against the current; even tows can proceed through the canal at all stages of tide. Better control of the vessel, however, will be had when making the passage against the current.

The entrance from Cape Cod Bay is protected on its north side by a breakwater 3,000 feet long, built out from the shore to a depth of 5 fathoms, and a short breakwater which extends from the shore on the south side of the entrance. A light (fixed white on black skeleton tower) is established on the north breakwater 1,700 feet from the outer end.

There is a red gas buoy off the north breakwater, a black spar buoy off the south breakwater, and a black bell buoy a little farther out. A perpendicularly striped gas and bell buoy lies 2½ miles 30° true (NE mag.) from the entrance.

In approaching the eastern entrance of the canal in clear weather, the jetties and the light at the entrance, and twin yellow chimneys with a tank between them on the canal 1¾ miles inside the entrance, are the guides. In thick weather the buoys are the guides. Strangers should not confuse the entrance jetties with the smaller ones at Sandwich Harbor, 1 mile southeastward. The fog is said to be always less dense inside the entrance than outside.

The approach channel from Buzzards Bay to a point 2,000 feet west of the railroad bridge has a bottom width of 250 feet, increased at the turns. The entrance to the canal off Wings Neck lighthouse, Buzzards Bay, is marked by two pairs of lighted buoys, one with a fog bell, which, in addition to the fog signal on Wings Neck, makes the entrance accessible in thick weather. From the entrance of the dredged channel to the canal proper there are gas buoys and lights, as well as fog signals, at frequent intervals; the lights on the west side are white, and those on the east side red. Two sets of range lights (rear lights fixed white, front lights flashing white) lead through the western approach.

From a point 2,000 feet west of the railroad bridge to the bridge the bottom width of the canal is 150 feet; then 100 feet width for a distance of 33,000 feet; then 200 feet width for a distance of 4,000 feet; then 300 feet width for a distance of 5,000 feet to deep water in Cape Cod Bay.

Digitized by Google

Fixed white lights on poles are erected at high-water mark on both sides of the canal at intervals of 500 feet between the Buzzards Bay railroad bridge and the breakwater at the east entrance.

Pilotage is not compulsory for vessels carrying a pilot licensed by the United States Steamboat-Inspection Service for the canal. Pilots or towboats may be obtained by making a signal upon approaching either end of the canal. A telephone office is established at Wings Neck lighthouse and also on the wharf at the east end of the canal, from which points vessels are reported.

Pilotage rates have not been fixed by law, but the following were the charges made in 1918: Steamers up to 1,000 gross tons, $10; over 1,000 gross tons, $20; towboats, $6 to $8; towboats with tow, $10; yachts up to 100 gross tons, $7; from 101 to 500 gross tons, $10; over 500 gross tons, $15.

Regulations for vessels using Cape Cod Canal are prescribed by the canal company. The following are extracts from them:

All steam vessels must conform to the requirements of the United States Steamboat-Inspection Service with reference to a licensed pilot on board when navigating these waters.

Masters or pilots can have their license indorsed for the canal by passing the examination before the United States Local Inspector, Boston, Mass.

All sailing craft must be towed through the canal and no vessel will be allowed to proceed through the canal with any sail set.

The maximum speed in the canal must not exceed 8 miles an hour. Vessels must at all times be navigated at reduced speed when passing others moored or anchored.

A vessel navigating through the canal with a favoring current will have the right of way subject to the Government Rules and Regulations relative to passing one another.

The vessel proceeding against the tide must give every facility to the vessel with favoring tide, tying up, if necessary, to the mooring piles.

When vessels proceeding in opposite directions are approaching one another each must be steered as closely as possible with safety to her own starboard side of the canal, so that they may pass on the port side of each other; each vessel must reduce her speed to "dead slow" or, if necessary, stop her engine while passing the other.

A following vessel must not approach nearer the leading one than 1,000 feet unless it has obtained a signal from the leading vessel for permission to pass.

If it becomes necessary during a passage through the canal to moor a vessel, she should use every endeavor to reach the mooring piles provided at various points for such emergency. The sets of mooring piles are placed at the 15-foot depth at low water.

No vessel will anchor in the canal or interfere with the passage of other ships unless in case of absolute necessity, but use every endeavor to reach the regular mooring piles.

When moored or anchored a white pennant must be displayed by day and two white lights at night where they can best be seen, one forward and one aft, on the side of the vessel which is open to the fairway.

The turning of vessels exceeding 600 feet over all in length in the canal is prohibited. When once pointed through the canal they must, unless compelled to make fast to the bulkheads or mooring piles through stress of weather or under orders, proceed to the other end of the canal. In case a large vessel has to be returned to the end of the canal from which she came, she must proceed to a set of mooring piles or to such other point where she can be turned with safety.

Small craft must keep entirely out of the track of seagoing vessels.

Vessels must report to the superintendent whenever, by accident or otherwise, any material of any kind falls overhead or is discharged in the waters of the canal. It is strictly forbidden to dump ashes or refuse of any kind overboard from Wings Neck to the eastward end of the breakwater in Cape Cod Bay.

No obstructions, except fenders, should project beyond the ship's hull while navigating the canal.

Digitized by Google

Before any vessel enters the canal, its destination being some point on the canal, its captain must notify the superintendent or his representative and before leaving its destination shall obtain the authority of the superintendent.

Directions, Cape Cod Canal.—The broken ground on the western side of cape Cod Bay and the coast northward, from Boston Harbor southward to the entrance of the canal, out to a distance of about 4½ to 7 miles from the shore, has been examined by means of a wire drag, and the dangers are shown on the charts. Vessels should give the shore a berth of 3 to 4½ miles between Boston Harbor and Plymouth Bay, and at least 1½ miles between Plymouth Bay and the entrance of the canal.

From Boston.—Steer 104° true (SE by E ½ E mag.), with Boston lighthouse in range with Deer Island lighthouse astern, until 2½ miles from Boston lighthouse and midway between the buoys marking Thieves Ledge and Harding Ledge. Then steer 110° true (SE by E mag.) for 6½ miles to a position ⅛ mile northeastward of black buoy No. 1, which marks a 3½-fathom spot. Then steer 143° true (SSE mag.) for 9½ miles, passing close eastward of whistling buoy No. 2 and to a position ⅛ mile eastward of buoy No. 4. Then steer 165° true (S mag.) for 20½ miles to Canal Approach gas and bell buoy, passing ½ mile eastward of the red buoy off Manomet Point. The course is then 209° true (SW ⅛ S mag.) for 2½ miles to the entrance between the jetties.

Directions from Cape Ann to Cape Cod Canal are given on page 46.

The best track for vessels through the canal is 430 feet south of the north jetty at the entrance, then through the middle of the canal to the railroad bridge at the west end, and 100 feet north of the mooring dolphins on the south bank of the canal west of the railroad bridge. From this point the channel is well marked, as shown on chart 251 or 249.

Supplies.—Coal, water, gasoline, and other supplies can be had at the canal company wharf near the eastern entrance of the canal.

Currents.—Slack water occurs about 2 hours before high and low water at Boston, the east current beginning before Boston low water and the west current before Boston high water. About halfway through the canal the average maximum westerly current occurs about ¾ hour after high water at Boston and the easterly current about ¾ hour after low water at Boston. Under ordinary conditions the currents have an average velocity at strength of 3.6 knots in midstream. Predictions for the times of slack water for every day in the year are given in the tide tables.

Bridges cross the canal at Sagamore, Bourne, and Buzzards Bay at distances of 1.6, 5.4, and 6 miles from the Cape Cod Bay entrance. The clearance between the fenders of all bridges is 140 feet. The railroad bridge at Buzzards Bay is a single-lift structure 2½ feet above extreme high water. The others are highway bridges, and are two-leaved lift structures, 30 feet in the clear above extreme high water.

The whistle signals for the bridges are as follows: Highway bridge, Sagamore, 2 long and 2 short blasts; highway bridge, Bourne, 1 long and 1 short blast; railroad bridge, Buzzards Bay, 3 long blasts.

For all the bridges there is a semaphore and light set about 2,000 feet on each side of each bridge on the right hand of the canal as a

Digitized by Google

vessel approaches the bridges. The semaphore is horizontal and the light red when the bridge is closed.

Vessels whose height will not permit them to pass under the bridge, before reaching the semaphore must give the whistle signal for the bridge, and if on reaching the mooring piles the bridge has not been opened, such vessels must stop and make fast to the mooring piles until the bridge is open. If passing at night, they will see an additional red light on the bridge when it is closed and a green light when it is open.

Storm-warning displays are made near Wings Neck lighthouse and from a tower near the inner end of the north breakwater at the eastern entrance to the canal.

Signals indicating whether the canal is clear to proceed are displayed at Wings Neck and on the wharf on the south side at the eastern entrance. A white ball or flag by day or a white light by night indicates "Canal clear, proceed," and a red ball or flag by day and a red light by night indicates "Stop, wait for orders."

Tolls, which are subject to change, are charged for all vessels passing through the canal. Vessels are advised to obtain the existing rates and a copy of the regulations from the Boston, Cape Cod & New York Canal Co., 43 Exchange Place, New York, N. Y., in advance of the passage. Toll and patrol boats are stationed at each end of the canal to collect the tolls and issue right-of-way permits authorizing vessels to proceed.

Ice.—The canal proper has never been closed by ice, but Buzzards Bay is closed at times, so as to prevent navigation through the canal.

Digitized by Google

APPENDIX.

COAST PILOTS, SAILING DIRECTIONS (PHILIPPINE ISLANDS), AND SUBOFFICES OF THE COAST AND GEODETIC SURVEY.

COAST PILOTS.

	Price.
U. S. Coast Pilot, Atlantic Coast, Section A, from St. Croix River to Cape Cod (this volume)	$0.50
U. S. Coast Pilot, Atlantic Coast, Section B, from Cape Cod to New York, including Long Island Sound	.50
U. S. Coast Pilot, Atlantic Coast, Section C, Sandy Hook to Cape Henry, including Delaware and Chesapeake Bays	.50
U. S. Coast Pilot, Atlantic Coast, Section D, Cape Henry to Key West	.50
U. S. Coast Pilot, Atlantic Coast, Section E, Gulf of Mexico, from Key West to the Rio Grande	.50
Inside Route Pilot, coast of New Jersey	.20
Inside Route Pilot, New York to Key West	.20
Inside Route Pilot, Key West to New Orleans	.20
U. S. Coast Pilot, Pacific Coast, California, Oregon, and Washington	.50
U. S. Coast Pilot, Pacific Coast, Alaska, Part I, from Dixon Entrance to Yakutat Bay	.50
U. S. Coast Pilot, Pacific Coast, Alaska, Part II, Yakutat Bay to Arctic Ocean	.50
U. S. Coast Pilot, West Indies, Porto Rico	.50
Coast Pilot Notes on Hawaiian Islands	Free.

SAILING DIRECTIONS, PHILIPPINE ISLANDS.

Section I. North and west coasts of Luzon and adjacent islands	Free.
Section II. Southwest and south coasts of Luzon and adjacent islands	Free.
Section III. Coasts of Panay, Negros, Cebu, and adjacent islands	Free.
Section IV. Coasts of Samar and Leyte and the east coast of Luzon	Free.
Section V. Coasts of Mindanao and adjacent islands	Free.
Sections VI and VII. Mindoro Strait, Palawan Island, and Sulu Sea and Archipelago	Free.

SUBOFFICES.

Boston, Mass., room 1502, customhouse.
New York, N. Y., room 403, customhouse.
New Orleans, La., room 503, Godchaux Building.
San Francisco, Cal., room 310, customhouse.
Seattle, Wash., room 202, Burke Building.
Manila, P. I., Intendencia Building.

At these offices complete files of United States Coast and Geodetic Survey charts, Coast Pilots, Tide Tables, and other publications relating to navigation may be consulted and information affecting navigation obtained without charge.

Light Lists, Buoy Lists, and Notices to Mariners are kept for free distribution to mariners.

The suboffices are also sales agencies for the Coast and Geodetic Survey publications.

A chart catalogue, giving lists of charts, coast pilots, tide tables, and agencies of the Coast and Geodetic Survey, can be obtained from any of the suboffices, or will be sent, free of charge, on application to the Coast and Geodetic Survey, Washington, D. C. Frequent changes occur in the agencies and the list of agencies is published in the first notice each month of the Notices to Mariners.

Digitized by Google

Meteorological table compiled by the United States Weather Bureau.

NANTUCKET, MASS.

Month.	Barometer at 32° F. and mean sea level.				Air temperature, in °F.							Average relative humidity.	Average amount of clouds 0–10.	Precipitation.			Wind.											Number of days with winds of 40 miles or over.	Number of days fog.
	Mean.	Extremes.			Mean.				Extremes.								Statute miles.	Average number of times (observations at 8 a. m. and 8 p. m.) from—											
	For month.	Highest.	Lowest.	Range.	For month.	Mean maximum.	Mean minimum.	Range.	Highest.	Lowest.	Range.			Average fall.	Number of days 0.01 inch or more.	Maximum fall in 24 hours.	Average hourly velocity.	Highest velocity.	N.	NE.	E	SE.	S.	SW.	W.	NW.	Calm.		
	Ins.	*Ins.*	*Ins.*	*Ins.*								%		*Ins.*		*Ins.*												
January	30.04	30.99	28.82	2.17	32.1	37.9	26.0	11.9	57	−4	61	81	6	3.42	13	2.47	15.6	83	6	6	3	4	5	9	14	15	0	6	5
February	30.04	30.81	28.89	1.92	32.6	36.1	24.6	11.5	55	−4	56	79	6	3.11	12	2.40	16.2	72	7	5	2	3	3	8	15	13	0	6	4
March	29.98	30.92	28.61	2.31	36.8	41.5	31.0	10.5	68	6	62	81	6	3.98	14	3.22	15.3	67	7	6	4	6	6	13	9	11	0	5	6
April	29.97	30.67	29.13	1.54	44.2	49.1	38.4	10.7	74	22	51	82	6	2.64	12	2.33	14.7	70	6	8	2	6	8	14	8	8	0	4	7
May	29.99	30.54	29.28	1.26	53.0	58.5	46.9	11.6	86	34	51	84	6	2.67	11	2.78	13.2	60	5	8	5	6	7	20	7	4	0	2	11
June	29.98	30.49	29.51	0 98	61.3	66.9	55.0	11.9	89	43	46	86	5	2.41	10	3.74	12.3	55	5	9	4	5	7	20	7	3	0	1	11
July	29.98	30.51	29.44	1.07	67.5	73.7	61.9	11.8	90	48	41	86	5	2.68	9	3.04	11.0	65	3	6	2	5	8	27	7	4	0	1	13
August	29.99	30.40	29.42	0.98	68.0	73.1	62.0	11.1	89	51	38	86	5	3 05	9	5.73	10.5	55	5	11	4	6	8	18	6	4	0	1	9
September	30.08	30.58	29.48	1.10	62.8	68.2	57.8	10.4	86	41	45	83	5	2.73	9	3.15	11.9	67	6	11	6	5	9	14	5	4	0	2	8
October	30.05	30.59	29.35	1.24	54.5	58.5	48.9	9.6	76	33	42	80	6	3.39	10	3.86	14.4	68	7	9	6	7	4	11	9	9	0	3	3
November	30.05	30.80	29.16	1.64	45.2	49.9	39.6	10.3	66	15	51	80	6	3.28	13	2.88	14.9	72	8	5	2	4	4	9	14	14	0	4	2
December	30.05	30.91	28.73	2.18	36.7	41.4	30.0	11.4	60	−1	61	79	6	3.64	14	2.62	15.2	76	6	6	3	5	3	8	16	15	0	5	2
Mean	30.02	.....	.....	.....	49.6	54.5	43.5	11.0	....	....	....	82	6	.....	.....	.....	13.8	.....	....	....	....	....	....	....	....	....	....	....	....
Total	.....	.....	.....	.....	.....	.....	.....	.....	....	....	....	.....	.....	37.00	136	.....	.....	.....	71	90	43	62	72	171	117	104	0	40	81

Digitized by Google

PORTLAND, ME.

January	30.05	30.88	28.64	2.24	22.0	30.1	14.8	15.3	65	−16	81	74	5	3.81	12	2.40	9.5	56	13	3	1	1	4	11	12	16	1	21	52
February	30.02	30.97	28.65	2.32	23.8	31.2	15.4	15.8	58	−17	75	71	5	3.65	11	3.06	9.8	61	11	3	1	2	4	9	12	14	1	16	35
March	29.96	30.97	28.79	2.18	32.0	38.7	15.5	23.2	78	− 7	85	71	5	3.75	13	3.50	10.1	60	10	4	2	3	8	10	10	14	1	13	56
April	29.96	30.72	28.86	1.86	43.0	50.4	35.2	15.2	81	14	67	70	5	3.11	11	3.82	9.9	50	9	6	3	4	8	8	8	13	0	10	75
May	29.97	30.58	29.28	1.30	53.5	61.1	45.4	15.7	94	27	67	72	5	3.67	12	4.86	9.1	43	7	6	6	4	14	9	7	9	1	5	91
June	29.95	30.54	29.34	1.20	62.6	70.7	54.1	16.6	96	38	58	74	5	3.36	11	4.15	8.4	40	5	6	5	5	12	9	8	8	1	1	88
July	29.95	30.48	29.20	1.28	68.0	76.4	60.1	16.3	103	48	55	76	5	3.25	12	3.97	7.9	40	5	4	4	5	15	12	8	8	2	2	143
August	29.98	30.46	29.37	1.09	66.2	74.0	58.7	15.3	95	45	50	78	4	3.57	10	2.47	7.4	48	6	4	4	4	13	11	8	10	2	4	165
September	30.05	30.66	29.05	1.61	59.6	67.6	52.0	15.6	94	32	62	79	4	3.20	10	5.28	8.1	50	7	4	3	4	10	12	8	11	1	3	115
October	30.04	30.72	29.04	1.68	49.1	56.8	42.2	14.6	84	22	62	76	5	3.66	10	3.93	8.7	52	9	3	2	3	7	12	10	13	1	10	99
November	30.04	30.83	28.49	2.34	37.6	44.9	31.5	13.4	72	− 6	78	74	5	3.80	10	3.76	9.5	50	11	3	1	2	5	13	11	13	1	16	59
December	30.03	30.97	28.76	2.21	27.1	34.2	20.3	13.9	65	−21	86	73	5	3.68	11	2.69	9.4	60	11	2	1	2	3	14	12	16	1	24	37
Mean	30.00				45.4	53.0	37.1	15.9				74	5				9.0											
Total														42.51	133				104	48	33	39	103	130	114	145	13	125	1,015

BOSTON, MASS.

January	30.05	30.86	28.67	2.19	27.0	35.5	19.4	16.1	70	−13	83	72	5	3.82	12	3.25	12.1	64	7	3	2	3	3	15	15	14	0	2	1
February	30.04	30.97	28.69	2.28	28.0	36.1	19.6	16.5	64	−11	75	70	5	3.44	10	4.45	13.1	60	7	1	3	2	3	10	17	13	0	1	0
March	29.97	30.96	28.56	2.40	35.0	42.8	27.6	15.2	78	− 8	86	69	5	4.08	12	3.04	12.6	72	7	4	3	4	4	10	16	14	0	1	1
April	29.97	30.72	28.86	1.86	45.3	54.0	38.0	16.0	87	11	76	67	5	3.55	10	3.18	11.9	60	5	7	6	5	4	10	10	13	0	0	1
May	29.98	30.56	29.19	1.37	56.6	65.4	48.3	17.1	97	31	66	70	6	3.51	11	3.00	10.8	48	6	5	9	4	4	13	11	10	0	0	0
June	29.96	30.57	29.31	1.26	65.8	75.0	57.5	17.5	98	42	56	71	6	3.03	10	5.35	10.1	41	7	5	8	3	3	14	12	8	0	0	0
July	29.96	30.51	29.38	1.13	71.3	80.4	63.4	17.0	104	46	58	71	5	3.36	10	4.46	9.6	60	4	4	5	4	5	20	13	7	0	0	1
August	29.99	30.43	29.34	1.09	68.9	77.6	61.7	15.9	98	47	51	75	5	4.03	10	4.99	9.0	48	5	6	6	4	7	14	11	9	0	0	1
September	30.07	30.65	29.18	1.47	62.7	71.4	55.4	16.0	102	34	68	76	4	3.19	9	4.26	9.6	60	7	4	4	4	5	15	10	11	0	0	2
October	30.05	30.75	29.19	1.56	52.3	60.5	44.7	15.8	90	25	65	73	4	3.86	8	4.92	10.8	54	5	4	4	4	5	13	15	12	0	1	2
November	30.05	30.86	28.73	2.13	41.2	49.0	34.2	14.8	76	− 2	78	73	5	4.10	10	5.43	11.4	65	4	3	2	2	4	13	20	12	0	0	1
December	30.05	30.96	28.80	2.16	31.6	38.8	24.0	14.8	69	−12	81	72	5	3.41	10	2.87	11.9	60	6	2	2	1	3	9	22	17	0	1	1
Mean	30.01				48.8	57.2	41.2	16.0				72	5				11.8											
Total														43.38	122				70	48	54	40	50	156	172	140	0	6	11

Digitized by Google

Meteorological table compiled by the United States Weather Bureau—Continued.

EASTPORT, ME.

Month.	Barometer at 32° F. and mean sea level.				Air temperature, in °F.							Average relative humidity.	Average amount of clouds 0–10.	Precipitation.			Wind.									Number of days with winds of 40 miles or over.	Number of days fog.
	Mean.	Extremes.			Mean.				Extremes.								Statute miles.		Average number of times (observations at 8 a. m. and 8 p. m.) from—									
	For month.	Highest.	Lowest.	Range.	For month.	Mean maximum.	Mean minimum.	Range.	Highest.	Lowest.	Range.			Average fall.	Number of days 0.01 inch or more.	Maximum fall in 24 hours.	Average hourly velocity.	Highest velocity.	N.	NE.	E	SE.	S.	SW.	W.	NW.	Calm.		
	Ins.	*Ins.*	*Ins.*	*Ins.*								%		*Ins.*		*Ins.*												
January	30.00	30.84	28.63	2.21	20.1	28.6	15.1	13.5	54	−20	74	76	7	3.84	15	2.78	14.0	78	7	4	3	3	6	12	15	12	0	4	2
February	29.98	30.92	28.51	2.41	21.4	28.3	13.7	14.6	52	−23	75	76	6	3.62	13	1.80	13.9	72	7	6	3	2	3	9	16	10	0	3	2
March	29.93	30.89	28.59	2.30	28.9	35.3	22.8	12.5	57	− 8	65	77	6	4.28	14	2.69	13.1	72	6	5	3	3	8	11	14	12	0	3	3
April	29.93	30.68	28.91	1.77	38.3	45.2	32.5	12.7	76	2	74	76	6	2.94	12	1.65	11.2	60	6	8	4	2	12	9	9	10	0	2	3
May	29.96	30.48	29.06	1.42	46.9	54.7	40.4	14.3	87	28	59	80	6	3.80	12	2.05	9.8	55	5	8	4	2	18	9	6	9	1	1	6
June	29.93	30.42	29.14	1.28	54.4	63.1	47.0	16.1	90	30	60	82	6	3.24	12	3.30	8.2	57	4	6	4	2	19	10	6	9	0	0	7
July	29.93	30.46	29.11	1.35	59.8	68.8	52.2	16.6	93	45	48	83	6	3.42	12	2.01	7.3	54	4	4	2	1	25	13	6	5	2	0	11
August	29.96	30.42	29.19	1.23	59.7	68.1	53.0	15.1	90	44	46	82	6	3.26	11	2.60	7.3	56	3	5	2	2	23	11	7	8	1	0	11
September	30.03	30.60	28.93	1.67	55.2	62.6	49.2	13.4	89	30	59	82	6	2.97	11	2.34	8.6	60	6	4	2	1	13	13	7	13	1	0	6
October	30.00	30.64	29.02	1.62	46.6	53.5	43.3	10.2	83	23	60	80	6	3.85	12	5.33	10.8	60	6	3	4	2	12	13	10	12	0	1	4
November	30.01	30.84	28.62	2.22	36.8	42.6	31.2	11.4	67	−13	80	78	7	4.08	12	2.08	12.7	70	7	4	2	2	6	14	15	10	0	2	2
December	29.98	30.97	28.24	2.73	25.3	32.4	18.5	13.9	57	−22	79	76	7	3.97	14	1.85	13.1	77	8	3	3	2	4	8	20	14	0	3	2
Mean	29.97				41.1	48.6	34.9	13.7				79	6				10.8												
Total														43.27	150				69	63	33	24	149	132	131	124	5	19	59

Digitized by Google

INDEX.

A.

	Page.
Abbott Rock beacon	234
Addison Point	76
Agencies, Coast and Geodetic Survey	8
Aids to navigation	25
Alden Rock	125
Allen Cove	107
Allen Island	156
Allen Shoal	155
Amesbury	219
Ammen Rock	39, 43
Anchorages	23
Bagaduce River	132
Belfast Bay	145
Beverly Harbor	235
Boothbay Harbor	171
Boston Harbor	249
Casco Bay	197
Damariscotta River	167
Deer Island Thoroughfare	118
Eggemoggin Reach	115
Frenchman Bay	87
Gloucester Harbor	227
Kennebec River	184
Marblehead Harbor	235
Merrimack River	220
Narraguagus Bay	80
Penobscot River	150
Pleasant Bay	80
Plymouth Harbor	271
Portland Harbor	202
Portsmouth Harbor	214
Rockland Harbor	142
St. George River	157
Salem Harbor	235
Anderson Ledge	217
Androscoggin River	183
Annisquam	223
Annisquam Harbor lighthouse	223
Annisquam River	222, 227
Appledore Island	216
Arey Cove, Frenchman Bay	87
Vinal Haven	133
Ark, The	169
Arrowsic Island	173
Asia Rip	38
Atlantic	106
Augusta	184
Avery Rock	66

B.

	Page.
Back Cove	202
Back River Cove	159
Back River, Kennebec River	182
Sassanoa River	173, 178
Sheepscot River	177
Back Way	263
Bagaduce River	131
Bailey Island	193
Bailey Ledge, St. George River	157
Baileys Ledge, Baileys Mistake	63
Baileys Mistake	63
Baker Island, Blue Hill Bay	103
Frenchman Bay	97
Lighthouse, Blue Hill Bay	97
Lighthouses, Salem	232
Salem Harbor	232
Bald Head	189
Bald Head Cliff	210
Bald Head Ledge	189
Bald Rock	96
Bald Rock Ledge	96
Ballast Island	71
Ballastone Ledge	192
Bangor	150
Bantam Ledge	125
Bantam Rock	169
Bar Harbor, Eastport Harbor	57
Frenchman Bay	95
Bar Island, Bar Harbor	96
Blue Hill Bay	107
Ledge	160
Muscongus Sound	160
St. George River	156
Barley Ledge	139
Barnstable	275
Barnstable Harbor	275
Barrel, The	124
Barter Island Ledges	120
Bartlett Harbor	134
Bartlett Island	105
Bartlett Narrows	105
Bartlett Rock, Cape Cod Bay	269
Sandy Bay	225
Barton Island	134
Barton Ledge	76
Basin, Casco Bay	190
Vinal Haven	134
Basket Island, Casco Bay	197
Wood Island Harbor	207

Digitized by Google

	Page.
Bass Harbor	104
Bass Harbor Bar	49, 103
Bass Harbor Head lighthouse	103
Bates Island	195
Bath	182
Batson Ledge	74
Bay Point	182
Bay View	224
Bayside post office	144
Bayville	170
Beach Ledges	125
Beals Island	72
Beans Island	92
Beans Ledge	92
Bear Island, Casco Bay	190
Frenchman Bay	99
Beauchamp Point	143
Beaver Island	164
Belfast	145
Belfast Bay	145
Belfast River	145
Bellamy River	214
Benjamin River	114
Benner Island	156
Berrys Cove	94
Beverly	234
Beverly Creek	234
Beverly Harbor	231, 234, 238
Bibb Rock	210
Bibber Rocks	196
Biddeford	206
Biddeford Pool	207
Big Black Ledge	85
Big Pot	75
Billings Cove	114
Billingsgate Island lighthouse	276
Birch Harbor	86
Birch Island, Casco Bay	196
Birch Islands, Pleasant Bay	76
Bird Rock	108
Black Duck Cove	74
Black Island, Blue Hill Bay	101
Western Bay	105
Black Ledge, Chandler Bay	70
Narraguagus Bay	78
Black Ledges, Little Machias Bay	64
Mistake Harbor	73
Black Point Cove	63
Black Rock Channel, Boston	242
Lynn	240
Black Rock, Gloucester	227
Metinic Island	126
Morgans Bay	108
Nantasket	267
Port Clyde	153
Black Rocks, Matinicus Island	125
Sheepscot River	175
York Harbor	211
Blacksnake Ledge	192
Blaneys Rock	239
Blue Hill	108
Blue Hill Bay	103, 110
Blue Hill Bay lighthouse	107
Blue Hill Harbor	108
Bluff Island	206
Bog Brook	63
Bold Dick	189
Bonny Chess Ledge	83
Boo-hoo Ledge	229
Boon Island	210
Boon Island Ledge	210
Boon Island lighthouse	210
Boot Cove	63
Boothbay Harbor	168, 171
Boston Harbor	241
Anchorages	249
Bridge regulations	254
Currents	257
Directions	259
General information	249
Inner harbor	245
Outer harbor and channels	242
Pilots	250
Remarks on approaching	258
Boston Island	177
Boston light vessel	243
Boston lighthouse	243
Bourne	283
Bowditch Ledge	232
Bowdoinham	183
Bowlders, The	113
Boxam Ledge	112
Bracy Cove	99
Bradford	219
Branch Hydrographic Office	253
Brandies, The	127
Brant Rock	269
Breakers Ledge	135
Brewer	150
Brewster Point Ledge	142
Bridges and regulations	26
Annisquam River	222
Beverly Harbor	234
Boothbay Harbor to Bath	173
Boston Harbor	254
Bucksport	149
Cape Cod Canal	283
Charles River	247
Chelsea River	249
Dorchester Bay	262
Fort Point Channel	247
Kennebec River	183
Machias River	66
Malden River	248
Merrimack River	219
Mount Desert Narrows	94
Mystic River	248
Piscataqua River	213
Portland Harbor	201
Saugus River	241
Weymouth Fore River	264
Brig Ledge	124
Brimbles	232
Brimstone Island, Blue Hill Bay	103
Penobscot Bay	133
Broad Cove, Casco Bay	197
Eastport Harbor	56, 61
Medomak River	160
St. George River	156
Broad Sound	240
Broad Sound North Channel	242, 259
Broad Sound South Channel	242, 260

Digitized by Google

	Page.
Broken Cave	195
Brooking Bay	173
Brooklin	114
Brothers, Cape Elizabeth	205
Englishman Bay	68
Port Clyde	153
Brown Bank	38
Brown Cow	128
Browney Island	74
Browns Head lighthouse	121
Brunswick	183
Brush Island Channel	267
Brush Island Ledge	267
Buck Harbor, Eggemoggin Reach	114
Bucks Harbor, Machias Bay	66
Bucks Neck	66
Bucksport	149
Bull Ledge	177
Bulldog, The	166
Bumkin Island	264
Bunker Harbor	86
Bunker Ledge, Bunker Harbor	86
Pleasant Bay	76
Buoyage, system of	24
Burial Islet	56
Burnt Coat Harbor	102
Burnt Coat Harbor lighthouse	102
Burnt Coat Island	189
Burnt Cove	128
Burnt Island, Boothbay Harbor	170
Ledge	141
St. George River	155
Bushy Islet	190
Bustin Island	196
Butter Island	129
Buzzards Bay	283

C.

	Page.
Calais	59
Caldwell Island	156
Calf Island Bar	91
Calf Island, Boston Harbor	243
Flanders Bay	91
Cambridge	247
Camden	143
Camden Harbor	143
Camel Ground	181
Cape Ann	222
Cape Ann lighthouses	226
Cape Cod	274
Cape Cod Bay	273
Cape Cod Canal	281
Cape Elizabeth lighthouses	200
Cape Harbor	169
Cape Island	169
Cape Jellison	146
Cape Neddick	210
Cape Neddick Harbor	210
Cape Neddick lighthouse	210
Cape Neddick Nubble	210
Cape Newagen	169
Cape Porpoise	209
Cape Porpoise Harbor	208
Cape Rosier	113
Cape Small	189
Cape Small Harbor	189
Cape Split Harbor	75
Capitol	170
Capitol Island	170
Captains Hill	271
Carrying Place Cove, Casco Bay	189
Dyer Bay	83
Quoddy Roads	63
Carrying Place Head	189
Carvers Cove	120
Carvers Harbor	133
Casco Bay	53, 189, 194, 198
Casco Passage	50, 106
Cashes Ledge	39, 43
Castine	132
Castine Harbor	131
Castle Island	246
Castle, The	83
Cat Island	233
Cat Island Channel	231, 237
Cat Ledges	175
Cathance River	183
Cedar Grove	183
Cedar Island, Isles of Shoals	216
Ledge	217
Penobscot Bay	136
Cedar Ledge	192
Cedar Point	268
Center Harbor	114
Chandler Bay	68, 70
Chandler Cove	196
Chandler River	70
Channel Rock, Blue Hill Bay	107
Eggemoggin Reach	113
Mistake Harbor	73
Muscle Ridge Channel	141
Penobscot Bay	128
Tripod	121
Character of the bottom	22
Charles River	247
Charles River Dam	247
Charlestown	246
Charts, use of	7
Chatto Island	114
Chebeag Island	196
Chelsea River	249
Cherry Island Bar	241
Cherryfield	79
Chimney Rock	205
Chittenden Rock	267
Chops	183
Christmas	166
Christmas Cove	166
Chubbs Islet	230
Citypoint	145
Clam Cove	142
Clam Island	160
Clapboard Island	197
Clark Cove, Blue Hill Bay	105
Clark Island, Plymouth Harbor	270
Clark Ledge	57
Clarks Cove, Tenants Harbor	152
Clarks Island, Tenants Harbor	152
Cliff Island	195
Clous Ledge	177

Digitized by Google

	Page.
Coast and Geodetic Survey sub-offices	253, 285
Coast Guard Stations	31
Coast pilots	8, 285
Cobscook Bay	57
Cocheco River	214
Cod Ledges	90
Codhead Ledge	68
Cohasset Harbor	267
Colby Ledge	120
Coles Ledge	75
Collins Rock	125
Columbia Falls	76
Commercial Point	261
Compass, variation of	33
Conarys Nub	108
Cone Island	75
Coney Island	233
Coney Ledge	233
Contents, table of	3
Corea	85
Corn Hill	277
Cousins Island	196
Cousins River	196
Cove Island	170
Cow and Calf Ledge	107
Cow Island Ledge	197
Cowyard	270
Cox Head	182
Crabtree Ledge	92
Cranberry Harbor	97
Cranberry Island	97
Cranberry Isles	97
Criehaven	124
Crockett Cove, Deer Isle	128
Vinal Haven	134
Crosby Narrows	151
Cross Island	64
Cross Island Narrows	64
Cross River	178
Crotch Island	195
Crotch Island Ledge	195
Crow Cove	139
Crow Island, Blue Hill Bay	106
Casco Bay	195
Damariscotta River	165
Crow Point, Head Harbor	73
Hingham Harbor	264
Crumple Island	74
Cubby Hole	120
Cuckolds lighthouse	169
Cuckolds, The	169
Cultivator Shoal	38
Cundy Harbor	190
Currents:	
Bay of Fundy	40
Beverly Harbor	236
Boston Harbor	257
Boston light vessel	41
Cape Cod Canal	283
Casco Bay	198
Coast of Maine	40
Damariscotta River	168
Deer Island Thoroughfare	118
Fox Islands Thoroughfare	121
Gloucester Harbor	228
Currents—Continued.	Page.
Gulf of Maine	39
Kennebec River	185
Plymouth Harbor	272
Portland light vessel	41
Portsmouth Harbor	215
Provincetown Harbor	279
St. Croix River and approaches	59
Salem Harbor	236
Sheepscot River	179
Cushing Island	200
Cushing, Merrimack River	218
St. George River	156
Cutler	63
Cutlers Cove	157
D.	
Damariscotta	167
Damariscotta River	165
Damiscove Harbor	169
Damiscove Island	169
Dansbury Reef	208
Danvers River	235
Danversport	235
Dark Harbor	137
Darling Island	107
Darling Ledge	108
Davis Island	156
Davis Straits	52, 156
Deep Cove	156
Deer Island, Boston Harbor	245
Eastport Harbor	58
Thoroughfare	117
Thoroughfare light	118, 120
Deer Isle, Penobscot Bay	114, 128
Dennysville	57
Devils Back	244
Devils Head	113
Devils Head Ledge	113
Dexter Ledge	124
Diamond Island Ledge	201
Diamond Roads	201
Diamond Rock	133
Diamond Rock Ledge	135
Dice Head lighthouse	131
Directions:	
Beverly Harbor	238
Blue Hill Bay	110
Boothbay Harbor	171
Boston Harbor	259
Carvers Harbor	134
Casco Bay	198
Chandler Bay	71
Coast of Maine, offshore	45
Damariscotta River	168
Deer Island Thoroughfare	118
East Penobscot Bay	129
Eastport Harbor and St. Croix River	61
Eggemoggin Reach	115
Englishman Bay	71
Frenchman Bay	88
Gloucester Harbor	228
Hingham Bay	265
Inside Passage, Boothbay to Bath	174
Jericho Bay	112
Kennebec River	185

Digitized by Google

Directions—Continued.	Page.
Machias Bay	67
Marblehead Harbor	238
Muscongus Bay	161
Narraguagus Bay	81
Penobscot River	151
Pleasant Bay	81
Plymouth Harbor	272
Portland Harbor	204
Portland to Boston and Cape Cod	45
Portsmouth Harbor	215
Provincetown Harbor	279
St. George River	157
Salem Harbor	236
Sheepscot River	179
South West Harbor	99
West Penobscot Bay	147
West Quoddy Head to Portland, inside passages	47
Dirigo Island	129
Dix Island	139
Dix Island Harbor	140
Docet Island	58
Dodge Point Ledge	141
Dodge Rock	225
Dog Fish Head	176
Dog Island	57
Dorchester	246
Dorchester Bay	261
Douglas Island Harbor	78
Douglas Islands	78
Dover	214
Downers Landing	264
Dread Ledge	239
Dredged channels	9
Dresden Landing	183
Drisco Islands	74
Drum Island	101
Drums, The	100
Drunkards Ledge	112
Drunkers Ledge	192
Dry Breakers	232
Dry docks	28
Dry Money Ledge	101
Dry Salvages	225
Duck Brook	96
Duck Cove	104
Duck Creek	276
Duck Island	216
Duck Rocks	155
Duck Trap Harbor	144
Dudley Island	56
Dunham Point	129
Durham	214
Duxbury	270
Duxbury Bay	270
Dyer Bay	82
Dyer Harbor	83
Dyer Island Narrows	77

E.

Eagle	129
Eagle Island, Casco Bay	195
Ledge	195
Penobscot Bay	129
Saco Bay	206
Salem	233
East Barge	107
East Boothbay	167
East Boston	246
East Braintree	264
East Branch	183
East Brown Cow	189
East Bunker Ledge	99
East Dennis	276
East Lamoine	94
East Machias River	66
East Penobscot Bay	126
East Shag Rock	267
East Sullivan	91
Eastern Bay, Frenchman Bay	94
Mistake Harbor	73
Eastern Black Ledge	124
Eastern Channel, Cohasset	267
Penobscot River	149
Eastern Duck Rock	155
Eastern Head	127
Eastern Head Ledges	63
Eastern Ledge, Damariscotta River	167
Penobscot Bay	123
Eastern Ledges, Englishman Bay	70
Eastern Neck	264
Eastern Point Harbor	92
Eastern Point lighthouse	226
Eastern Way, Gouldsborough Bay	84
Eastport	56
Eastport Harbor	56
Ebenecook Harbor	176
Egg Rock, Frenchman Bay	90
Great Wass Island	74
Ledge	129
Lighthouse	239
Nahant	239
Penobscot Bay	129
Pigeon Hill Bay	79
Egg Rocks, Boston Harbor	243
Eggemoggin	114
Eggemoggin Reach	113
Ellingwood Rock	181
Ellsworth	109
Emery Cove	94
Emery Island	141
Englishman Bay	68
Enos Ledge	267
Ensign Island	137
Erie (New York State Barge) Canal	85
Essex Bay	222
Essex River	222
Eve Island	120
Ewins Narrows	194
Exeter	214
Exeter River	214

F.

Farnham Rock	269
Farrel Island	120
Ferry Beach	206
Fiddler Ledge	121
Fish Hawk Islet	170
Fish Point Ledge	120
Fish weirs	26
Fisherman Island, Mistake Harbor	74
Two Bush Channel	139

Digitized by Google

	Page.
Fisherman Island Passage, Boothbay Harbor	53
Penobscot Bay	140
Fisherman Islands, Boothbay Harbor	169
Fishing Point	239
Fishing Rock	209
Five Islands	176
Five Islands Harbor	176
Flag Island	189
Flag Island Ledge	189
Flanders Bay	91
Flat Bay	77
Flat Ground	225
Flat Island, Moosabec Reach	74
Penobscot Bay	138
Fletcher Neck	208
Flint Island	75
Flint Island Narrows	76
Flye Island Ledge	107
Flying Passage	159
Fog	28, 259
Folly Cove	224
Folly Island, Blue Hill Bay	104
Cape Porpoise	208
Folly Ledge	135
Folly Point	224
Fore River	201
Forest City Landing	200
Fort Gorges	201
Fort Pickering lighthouse	234
Fort Point Channel	246
Fort Point Cove	149
Fort Point, Damariscotta River	167
Ledge	149
Penobscot River	149
Fort Popham	182
Foss Ledges	217
Foster Channel	65
Foster Cove	165
Foster Island, Harrington Bay	77
Foster Islands, Machias Bay	65
Foster Ledge	125
Fosters Point	190
Four-foot Rock	177
Fourth Cliff	268
Fox Islands Thoroughfare	51, 120
Frankfort	149
Franklin	93
Freeman Rock	73
Freeport	196
Freeport River	196
French Island	196
Frenchman Bay	87
Freshets:	
Kennebec River	185
Merrimack River	220
Penobscot River	150
St. Croix River	59
Friar Bay	56
Friar Roads	56
Friendship	159
Friendship Harbor	158
Friendship Island	159
Frost Ledge	58

G.

	Page.
Gales Ledge	229
Gales Point	230
Gallups Island	244
Gangway Passage	267
Garden Island	141
Garden Island Ledge	141
Gardiner	183
Garrison Island	158
Gay Cove	156
Gay Island	156
Georges Bank	38
Georges Harbor	156
Georges Islands	155
Georges Shoal	38
Georgetown Island	173
Gilbert Head	182
Gilkey Harbor	137
Gloucester Harbor	226
Glovers Rock	189
Goat Island, Kennebec River	182
Lighthouse	208
Portsmouth Harbor	213
Googin Ledge	94
Goose Cove, Blue Hill Bay	104
Rock	104
Western Bay	105
Goose Fair Bay	208
Goose Island	137
Goose Nest	195
Goose Nest Ledge	195
Goose Point Channel	271
Goose Rock, Casco Bay	189
Penobscot Bay	137
Passage	173
Goose Rocks lighthouse	121
Gooseberry Island, Jericho Bay	103
Ledge, Casco Bay	189
Ledge, Jericho Bay	103
Wood Island Harbor	207
Gosport Harbor	216
Gouldsborough Bay	83
Gouldsborough Harbor	84
Governors Island	246
Governors Island Channel	246
Gowdy Ledge	189
Grampuses	267
Grand Manan Channel	39
Grass Ledge	128
Graves lighthouse	244
Graves, The, Boston Harbor	244
Penobscot Bay	143
Grays Rock	233
Great Aqua Vitae beacon	234
Great Bay	214
Great Boars Head	218
Great Brewster	243
Great Brewster Spit	243
Great Chebeag Island	196
Great Diamond Island	200
Great Duck Island	100
Great Duck Island lighthouse	100
Great Egg Rock	229
Great Faun Bar	245
Great Gott Island	101

Digitized by Google

	Page.
Great Haste	232
Great Head	96
Great Hell Gate	174
Great Mark Island	193
Great Misery Island	232
Great Moshier Island	196
Great Pig Rocks	233
Great South Channel	44
Great Spruce Head Island	129
Great Spruce Ledges	70
Green Harbor	269
Green Island, Blue Hill Bay	107
Boston Harbor	244
Englishman Bay	69
Jericho Bay	103
Knob	135
Ledge	69
Mistake Harbor	73
Moosabec Reach	74
Passage	195
Reef	195
Seal Ledges	125
Vinal Haven	133
Green Islands, off Blue Hill Bay	101
Sheepscot River	177
Green Ledge, Eggemoggin Reach	115
Penobscot Bay	124
Vinal Haven	135
Green Mountain	87
Green Point Shoal	126
Greening Island	98
Greenland Cove	161
Greenlaws Cove	113
Greenleaf Ledge	178
Griffins Ledge	156
Griffith Head	175
Griffith Head Ledge	175
Grindel Point lighthouse	137
Grindstone Ledge, Blue Hill Bay	101
Winter Harbor	89
Grindstone Neck	89
Groveland	219
Gulf of Maine	37
Gulf of Mexico	36
Gull Ledge	129
Gull Rock	159
Gull Rock Ledge	155
Gull Rocks	79
Gunning Rocks	153
Gurnet, The	192
Gurnet lighthouse	269
Gut, The	166

H.

Haddock Island	160
Haddock Ledge, off Penobscot Bay	126
Penobscot Bay	144
Hadleys Point	94
Haley Cove	216
Half Tide Ledge	79
Halfway Rock, Casco Bay	192
Lighthouse	192
Salem Harbor	232
Halibut Hole	90
Halibut Ledge	134
Halibut Rock	139
Halibut Rocks	119
Halifax Island	69
Hall Bay	173
Hall Quarry	98
Hallowell	183
Hamilton Cove	63
Hampden	150
Hampton Beach	218
Hampton Harbor	218
Hampton River	218
Hampton Shoal Ledge	218
Hancock	94
Hancock Point	92
Hangmans Islet	263
Hanover	269
Harbor control:	
Bath	184
Boston	249
Portland	203
Harbor Cove	227
Harbor De Loutre	56
Harbor Island, Buck Harbor	114
Casco Bay	190
Jericho Bay	103
Naskeag Harbor	113
Harbor Ledge	124
Harbor masters	25
Harbor Rock, Buck Harbor	114
Sandy Bay	225
Harbors and ports	23
Harding Ledge, Boston Harbor	243
Sheepscot River	177
Hardwood Island, Blue Hill Bay	104
Moosabec Reach	72
Penobscot Bay	128
Hardy Rocks	232
Harpswell Center	195
Harpswell Harbor	193
Harpswell Sound	193
Harraseeket River	196
Harrington Bay	77, 81
Harrington River	77
Hart Bar	153
Hart Island	153
Hart Ledge	153
Haskell Island	194
Hat Island	103
Hatchet Cove	159
Haverhill	219
Hay Island	165
Hay Ledge	153
Haycock Harbor	63
Head Harbor, Moosabec Reach	72
Penobscot Bay	127
Head Harbor Island	73
Head Harbor Passage	61
Heal Cove	173
Heals Eddy	181
Heart Island	129
Hen Cove	192
Hen Island Ledge	190
Hen Islet	190
Hendricks Harbor	176
Hendricks Head lighthouse	176

Digitized by Google

	Page.
Herman Harbor	175
Heron Island, Demariscotta River	166
Jericho Bay	103
Winter Harbor	89
Heron Neck Ledge	135
Heron Neck lighthouse	133
Herrick Bay	107
Herring Cove	278
Herring Gut	153
Herring Ledge	125
Hewes Point	138
Hickey Island	68
Higgins Beach	206
High Clam Ledge	141
High Island	139
High Pine Ledge	269
Hingham Bay	263
Hingham Harbor	264, 266
Hockomock Bay	173
Hockomock Channel	159
Hodgdon Ledge	178
Hodgkins Cove	224
Hog Island, Eggemoggin Reach	115
Muscongus Sound	160
Naskeag Harbor	113
Penobscot Bay	139
Hogshead, The	124
Holbrook Ledge	170
Holmes Bay	66
Hooper Island	156
Hooper Shoal	126
Hope Island	195
Horse Cove	192
Horse Island	194
Horse Shoe Ledge	100
Horseshoe Cove	115
Hough Neck	263
House Island, Manchester	230
Portland	200
Howard Bay	66
Howland Ledge	269
Hudson River	35
Hull	263
Humpkins Islet	118
Hurricane Island	133
Ledge	141
Sound	133
Hydrographic Office, Boston	253
Hypocrite Channel	242
Hypocrites, The	169

I.

	Page.
Ice	29
Boothbay Harbor	171
Boston Harbor	253
Cape Cod Bay	277
Cape Cod Canal	284
Casco Bay	198
Castine Harbor	132
Damariscotta River	167
Deer Island Thoroughfare	118
Frenchman Bay	88
Gloucester Harbor	228
Kennebec River	185
Machias Bay	67
Manchester Harbor	230
Ice—Continued.	Page.
Merrimack River	220
Narraguagus Bay	80
Penobscot River	150
Pleasant Bay	80
Plymouth Harbor	272
Portland Harbor	204
Portsmouth Harbor	215
Provincetown Harbor	279
St. Croix River	59
St. George River	157
Salem Harbor	236
Sheepscot River	178
Sullivan River	93
Independence Island	170
Index map	7
Indian Cove	66
Indian Creek	133
Indian Harbor	85
Indian Island	148
Indian Island lighthouse	148
Indian Ledge	124
Indian Point	196
Indian River	72
Inland waterways	35
Inner Breaker	124
Inner Dawes Ledge	101
Inner Green Island	195
Inner Harbor	227
Inner Heron Island	166
Inner Heron Island Ledge	166
Inner Ledge, Camden Harbor	144
East Penobscot Bay	127
Inner Shag Ledge	156
Inside passages, Maine	42
Introductory	5
Ipswich	221
Ipswich Bay	222
Ipswich River	221
Iron Bound Island	90
Island End River	248
Isle au Haut	127
Isle au Haut Bay	126
Isle au Haut Thoroughfare	127
Isle of Springs	173
Isles of Shoals	216
Isles of Shoals lighthouse	217
Islesboro	136, 138
Islesboro Harbor	138
Isleaford	97

J.

	Page.
Jack Rock	181
Jameson Point, Muscongus Bay	163
Rockland	141
Jamison Ledge	189
Jaquish Island	198
Jeffreys Bank	89
Jeffreys Ledge	89
Jenks Ledge	156
Jenny Island	192
Jenny Ledge	192
Jericho Bay	112
Jerry Ledge	77
Jewell Island	195
Jewett Cove	178
Job Island	137

Digitized by Google

	Page.
John Island, Blue Hill Bay	105
John Rock	195
Johns Bay	164
Johns Island Dry Ledge	101
Johns Island, Johns Bay	164
Sunken Ledge	101
Swan Island	101
Johns River	165
Johnson Bay	56, 61
Johnson Rock	195
Jones River	270
Jonesboro	70
Jonesport	72
Jordan River	94
Jordans Delight	78
Jordans Delight Ledge	78
Jordans Island	90
Jordans Island Bar	91
Joy Bay	84
Julia Cove	63
Junk of Pork	194

K.

Kelp Ledge	156
Kenduskeag River	150
Kennebec River	180
Kennebunk Beach	210
Kennebunk River	209
Kennebunkport	209
Kent Ledge	120
Kents Cove	120
Kettle Island	229
Kidder Point	146
Kimball Island	127
Kimball Rock	127
Kingston	270
Kingston Bay	270
Kittery	213
Kittery Point	213
Knight Island	73
Knowles Rocks	164
Knubble Bay	174

L.

Ladle, The	75
Laireys Narrows	134
Lamoine	94
Lamoine Beach	94
Lamp Islet	107
Lamprey River	214
Lanes Cove	224
Lanesville	224
Large Green Island	125
Larrabee	66
Larrabees Cove	66
Lasell Island	137
Leadbetter Narrows	134
Libby Islands	65
Libby Islands lighthouse	65
Liberty Point	55
Liberty Point Ledge	55
Lighthouses, reference to list	25
Lime Island	137
Lincolnville	144
Linekin	170
Linekin Bay	168, 170
Linekin Neck	170
Lines Island	183
Little Bangs Island	195
Little Bay	214
Little Birch Island	194
Little Black Ledge	85
Little Black Rock	267
Little Boars Head	217
Little Bustin Island	196
Little Calf Island	91
Little Chebeag Island	197
Little Cranberry Island	97
Little Diamond Island	200
Little Docet Island	58
Little Duck Island	100
Little Faun Bar	245
Little Gott Island	101
Little Green Island	125
Little Harbor	212
Little Haste	232
Little Island	160
Little Kennebec Bay	68
Little Ledge	83
Little Machias Bay	64
Little Mark Island	193
Little Nahant	239
Little Nahant Beach	239
Little Neck	221
Little Pig Rocks	233
Little River, Damariscotta River	166
Ledge	63
Lighthouse	63
near Eastport	63
Little Sail Rock	55
Little Salvages	226
Little Sheepscot River	173
Little Spruce Ledge	70
Little Thoroughfare	128
Little Whaleboat Island	195
Little Wood Island	189
Littlejohn Island	196
Lobster Cove	223
Lobster Rock	208
Londoner, The	226
Long Cove, Damariscotta River	167
Ledge	146
Penobscot Bay	146
Sheepscot River	178
Tenants Harbor	152
Long Island, Blue Hill Bay	107
Boston Harbor	245
Casco Bay	197
off Blue Hill Bay	101
Penobscot Bay	136
Long Island Head lighthouse	245
Long Island Ledge	138
Long Island Sound	35
Long Ledge, Casco Bay	189
Little Machias Bay	64
Seal Harbor	140
Long Point	97
Long Point Cove	63
Long Point lighthouse	278
Long Wharf, Plymouth	271
Lookout	127

Digitized by Google

	Page.
Lovells Island	244
Lowell Cove	192
Lowell Ledge	141
Lowell Rock	143
Lower Basket Ledge	197
Lower Goose Island	195
Lower Mark Island	175
Lower Mystic Lake	248
Lower Narrows	161
Lubec	55
Lubec Channel lighthouse	55
Lubec Narrows	55, 61
Luckse Sound	196
Lunging Island	217
Lunts Harbor	101
Lynn Beach	239
Lynn Harbor	240

M.

Machias	66
Machias Bay	64
Machias River	64, 66
Machias Seal Island lighthouses	39
Machiasport	66
Mack Point	146
Mackerel Cove, Blue Hill Bay	105
Casco Bay	193
Mackerel Ledge	124
Mackerel Rock	78
Magnolia	230
Magnolia Harbor	230
Mahoney Island	113
Mahoney Ledge	113
Main Ship Channel, Salem	231, 236
Malaga Island	190
Malcolm Ledge	123
Malden	248
Malden River	248
Man Island	72
Manana Island	154
Manchester	230
Manchester Harbor	230
Manomet	274
Manomet Hill	271, 274
Manomet Point	274
Manset	98
Maple Juice Cove	156
Maquoit Bay	196
Maraspin Creek	275
Marblehead	233
Marblehead Channel	231, 237
Marblehead Harbor	231, 233, 238
Marblehead Island	139
Marblehead lighthouse	233
Marblehead Rock	233
Mare Point Bay	196
Mare Point Neck	196
Marine hospital	26
Marine railways	28
Mariner Island	197
Mark Island, Casco Bay	189
Islesboro	137
Moosabec Reach	71
Penobscot Bay	118
Winter Harbor	89
Mark Island Ledge, Casco Bay	189
Sheepscot River	177
Marsh Cove	124
Marsh Harbor	160
Marsh Island	160
Marsh River	149
Marshall Island	103
Marshall Ledge	112
Marshall Point lighthouse	154
Martin Point	202
Martinsville	153
Marvin Island	213
Mary Ann Rocks	274
Masons Bay	70
Matinicus	124
Matinicus Harbor	124
Matinicus Island	123
Matinicus Rock	123
Matinicus Rock lighthouses	123
Mayo Beach lighthouse	276
McFarling Cove	164
McFarling Ledges	164
McGee Island	156
McGuire Point	167
McIntosh	136
McKinley	104
Medford	248
Medomak	160
Medomak River	159
Meduncook River	158
Merchants Row	50, 119
Mericoneag Sound	193
Merrill Ledge	178
Merrimack River	218
Merrimacport	219
Merryman Ledge	115
Merrymeeting Bay	183
Meteorological tables	286
Metinic Green Island	126
Metinic Island	126
Metinic Island Ledge	126
Middle Bay	195
Middle Brewster	243
Middle Ground	55
Middle Cround Rock	192
Middle Ledge, Schoodic Harbor	87
Sheepscot River	177
Middle Ledges, Muscongus Bay	163
Middle Mark Island	177
Mile Ledge	181
Miles Channel	270
Mill River, Cape Ann	223
Harrington Bay	77
Millbridge	79
Milton Mills	262
Ministerial Island	195
Mink Island	76
Minots Ledge lighthouse	267
Minturn	102
Mistake Harbor	73
Mistake Island	73
Mitchell Cove	104
Mitchell Rock	225
Monhegan	155
Monhegan Fall	39

Digitized by Google

	Page.
Monhegan Harbor	154
Monhegan Island	154
Monhegan Island lighthouse	154
Montseag Bay	173, 178
Moon Head	263
Moore Harbor	127
Moosabec Reach	47, 71
Moose Cove	63
Moose Island, Blue Hill Bay	104
Eastport	56
Moose Peak lighthouse	73
Morgans Bay	108
Morse River	180
Morton Ledge	62
Mosquito Harbor	153
Mosquito Head	153
Mosquito Island	153
Moulton Ledge	82
Mount Desert Ferry	92
Mount Desert lighthouse	87
Mount Desert Narrows	94
Mount Desert post office	98
Mount Desert Rock	87
Mountainville	113
Mouse Island, Penobscot Bay	87
Boothbay Harbor	170
Mud Hole Channel	73
Murphy Ledge	159
Murray Hill	170
Murray Ledge	211
Muscle Ridge Channel	51, 139
Muscongus Bay	158
Muscongus Harbor	161
Muscongus Island	160
Muscongus Sound	160
Mystic River	248

N.

Nahant	240
Nahant Bay	239
Nahant Harbor	240
Nantasket	265, 267
Nantasket Beach	265, 267
Nantasket Gut	263
Nantasket Hill	267
Nantasket Roads	244, 250
Nantucket Shoals	38
Nantucket Shoals light vessel	39
Narraguagus Bay	75, 77, 81
Narraguagus lighthouse	78
Narraguagus River	79
Narrows, The, Damariscotta River	167
Boston Harbor	242
Narrows Island Ledge	76
Narrows lighthouse	244
Nash Island	75
Nash Island lighthouse	75
Naskeag	113
Naskeag Harbor	113
Naval coaling station	94
Navigation laws	25
Navigational aids	7
Neds Island	89
Negro Island, Lincoln Bay	170
Wood Island Harbor	207
Negro Ledge	206
Neponset	246, 262
Neponset River	262
New Harbor	160
New Harbor Dry Ledges	160
New Inlet	268
New Jersey	36
New Meadows	190
New Meadows River	190
New York to Key West	36
Newagen	169
Newbury Old Town	221
Newburyport	219
Newburyport Harbor	218
Newburyport Harbor lighthouse	218
Newcastle Island	213
Newcastle, Me	167
N. H	213
Newmarket	214
Newport Cove	96
Newport Ledge	96
Night Cap Island	76
Night Cap Ledge	76
Nixes Mate	244
No Mans Land	124
Normans Woe	226
Normans Woe Rock	226
North Blacksnake	190
North Brooksville	132
North Castine	132
North Deer Isle	114
North Dennis	276
North East Harbor	98
North Gooseberry	232
North Hancock	94
North Haven	121
North Haven Island	132
North Islesboro	138
North Jenny Ledge	192
North Ledge	192
North Lubec	57
North River, Beverly Harbor	235
near Scituate	269
North Sugar Loaf	181
North West Harbor, Machias Bay	65
Northeast Grave	244
Northeast Ledges	143
Northeast Passage	144
Northeast Point	143
Northeast Pond Ledge	139
Northern Triangles	125
Northport	144
Northport Camp Ground	144
Northwest Harbor, Penobscot Bay	128
Norton Island	76
Norton Island Ledge, Pleasant Bay	76
Norton Island Ledges, Whitehead	152
Nubble, The	97
Nubble Channel	242
Nut Islet	263

O.

Oak Island	128
Oaks Reef	209
Ocean Point	170
Ocean View	224
Oceanville	117

Digitized by Google

	Page.
Odom Ledge	149
Ogunquit	210
Oil, use of	16
Old Cellar Rock	218
Old Cilley Ledge	153
Old Cove	124
Old Harbor, Dorchester Bay	261
Vinal Haven	133
Old Horse Ledge	156
Old Man, Machias Bay	64
Prospect Harbor	85
Ledge	155
Old Orchard Beach	206
Old Prince	208
Old Proprietor	205
Old Woman	85
Old Woman Ledge	155
Orcutt Harbor	114
Orland	149
Orrs Island	193
Otis Cove	156
Otter Cliff Ledge	96
Otter Cove	96
Otter Creek Point	96
Otter Island	133
Otter Island Ledge	141
Otto Island Ledge	101
Outer Brewster	243
Outer Dawes Ledge	101
Outer Green Island	194
Outer Ledge	144
Outer Minot	267
Outer Sand Island	74
Outer Scrag Ledge	128
Outer Shag Ledge	156
Owlshead	140
Owlshead Bay	140
Owlshead Ledge	141
Oyster River	214

P.

	Page.
Pamet River	277
Parker Cove	138
Parker River	221
Parkers Head	132
Passamaquoddy Bay	58
Patten Bay	109
Peaked Cliff	274
Peaks Island	200
Pemaquid Beach	164
Pemaquid Falls	164
Pemaquid Harbor	164
Pemaquid Neck	160
Pemaquid Point lighthouse	160
Pemaquid River	164
Pemberton	263
Pembroke	57
Pennamaquan River	57
Penobscot	132
Penobscot Bay	122–148
Penobscot River	149
Pepperell Cove	213
Perkins Island	132
Perry Cove	121
Petit Manan	48
Petit Manan Bar	80
Petit Manan Island	80
Petit Manan lighthouse	80
Petit Manan Point	80
Pettis Rocks	132
Philip Rock	207
Phillips Point	239
Phippsburg	132
Pickering Island	129
Picketts Ledge	229
Pierson Ledge	68
Pigeon Cove	224
Pigeon Ground	125
Pigeon Hill	79
Pigeon Hill Bay	75, 79
Pigeon Rock	224
Pilgrim Ledge	229
Pilgrim Monument	278
Pilot rules	26
Pilots, see name of port and	25
Pinkham Bay	83
Piscataqua River	213
Placentia Island	101
Platts Bank	39
Pleasant Bay	75, 81
Pleasant Cove	167
Pleasant Cove Ledges	167
Pleasant Point	58
Pleasant Point Gut	156
Pleasant River	76
Plum Island River	221
Plum Island Sound	221
Plummer Island	74
Plymouth Harbor	269, 272
Plymouth Inner Harbor	271
Plymouth lighthouse	269
Point Allerton	243, 266
Point Francis	84
Poland South Ledge	161
Pomps Island	72
Pond Cove	70
Pond Island Bar	181
Pond Island, Blue Hill Bay	107
Casco Bay	192
Eggemoggin Reach	115
Kennebec River	181
Ledges	192
Lighthouse	181
Narraguagus Bay	78
Pool, The, Frenchman Bay	97
Wood Island Harbor	207
Pooles Landing	167
Popes Head	232
Popes Folly	56
Popham Beach	181
Port Clyde	153
Porterfield Ledge	143
Portland	201
Portland Harbor	199
Portland Head lighthouse	200
Portland light vessel	199
Portsmouth	213
Portsmouth Harbor	212
Portsmouth Harbor lighthouse	212
Pot Rock	75
Potts Harbor	194
Powderhorn Island	177
Powderhorn Ledge	177

Digitized by Google

	Page.
Powderhorn South Ledge	177
Powow River	219
President Roads	245
Presumpscot River	202
Pretty Marsh Harbor	104
Princes Gurnet	194
Prominent features	24
Prospect Harbor	85
Prout Neck	206
Provincetown	278
Provincetown Harbor	277
Pulpit Harbor	134
Pulpit Rock, Englishman Bay	69
Penobscot Bay	134
Pumpkin Cove Ledge	160
Pumpkin Island lighthouse	113

Q.

Quaker Head	64
Quarantine	26, 203, 253
Quincy	264
Quincy Bay	263
Quincy Great Hill	263
Quincy Point	264
Quoddy Roads	54, 61
Quohog Bay	192

R.

Race Point lighthouse	278
Radio service	30
Ragged Island, Casco Bay	192
Penobscot Bay	123
Rainsford Island	245
Ram Head	244
Ram Head Flats	244
Ram Island, Blue Hill Bay	101
Boothbay Harbor	169
Cape Elizabeth	205
Casco Bay	192
Kennebec River	182
Machias Bay	65
Mericoneag Sound	193
Moosabec Reach	48, 72
Muscongus Bay	163
Penobscot Bay	128
Saco Bay	206
Ram Island Ledge, Penobscot Bay	128
Saco Bay	206
Sheepscot River	177
Lighthouse	200
Ram Island lighthouse	169
Ram Islet, Marblehead Neck	233
Penobscot Bay	142
Randolph	183
Raspberry Island	76
Reach, The	133
Red Beach	58
Red Rock	239
Repairs, see name of port and	27
Reporting stations	252
Reserved Channel	246
Resolution Island	129
Revere	241, 249
Richmond	183
Richmond Island Harbor	205
Ridley Cove	191
Riggs Cove	173
Riggsville	174
Ringtown Island	103
Ripley Neck	77
Riverview	223
Roaring Bull, Boston Harbor	244
Marblehead Neck	233
off Penobscot Bay	126
Prospect Harbor	86
Roaring Bull Ledge, Head Harbor	127
Robbinston	58
Robert Harbor	133
Robin Hood Cove	173
Robin Hood Landing	174
Robinson Cove	165
Robinson Rock	136
Rockland	141
Rockland Harbor	141
Rockport, Me	143
Mass	225
Rockport Harbor, Me	142
Mass	225
Rocks Nose	211
Rocky Neck	227
Rocky Point	274
Rodericks Cove	95
Rogue Island, Casco Bay east	190
Casco Bay west	195
Roque Bluff	69
Roque Island Harbor	69
Ross Island	160
Round Pond	161
Round Porcupine Island	95
Round Rock, Casco Bay	192
Eastport Harbor	55
Shoal	226
Rowley	221
Rowley River	221
Roxbury	246
Rules of the road	25
Rumells Hub	104
Rye Beach	217
Rye Harbor	217
Rye Ledge	217

S.

Sabbath Day Harbor	138
Saco	206
Saco Bay	205
Saco River	206
Saddle Island	137
Saddleback Ledge	192
Saddleback Ledge lighthouse	127
Sagadahoc Bay	181
Sagamore	274, 283
Sagamore Beach	274
Sagamore Head	267
Sail Rock	55
Sailing directions, Philippine Islands	285
St. Andrew	58
St. Croix River	54, 58, 61
St. George	156
St. George River	155
St. Georges Island	244
St. Stephens	59

Digitized by Google

	Page.
Salem Harbor	231, 234, 236
Salisbury Beach	218
Salisbury Cove	94
Sally Islands	83
Salt Pond	107
Salt Rock	229
Salter Island	181
Sammy Rock	233
Sand Cove, Prospect Harbor	85
Vinal Haven	133
Winter Harbor	89
Sand Island, Casco Bay	195
Moosabec Reach	74
Sandwich	274
Sandwich Harbor	274
Sandy Bay	224
Sandy Bay Ledge	225
Sandy Cove	63
Sandy Neck	275
Sandy Neck lighthouse	275
Sandypoint	149
Saquish Head	270
Sargentville	114
Sassanoa River	173
Satan Rock	232
Saturday Cove	144
Saugus River	241
Sauli Rock	230
Sawyer Cove	104
Sawyer Island	173
Sawyers Ledge	127
Scabby Island Ledge	68
Scabby Islands	68
Scarboro Beach	206
Scarboro River	206
Scargo Hill	276
Schoodic Harbor	86
Schoodic Island	86
Schoodic Ledge	86
Schoodic Mountain	87
Schooner Brook	63
Schooner Head	96
Schooner Ledge	96
Scituate Harbor	268
Scorton Harbor	275
Scorton Ledge	275
Scorton Neck	275
Scrag Island	103
Scraggy Island	120
Scraggy Ledge	128
Sculpin Ledge	108
Sculpin Ledge Channel	242
Sea Horse Rock	74
Seal Bay	128
Seal Cove, Blue Hill Bay	104
Cape Elizabeth	205
Damariscotta River	167
Merchants Row	121
Seal Harbor, Blue Hill Bay	99
Muscle Ridge Channel	140
Penobscot Bay	138
Seal Island, off Penobscot Bay	123
Seal Ledge, Blue Hill Bay	108
Englishman Bay	69
Rockland	141
Seal Rocks, Kennebec River	182
Linekin Bay	170
Sears Island	146
Sears Island Ledge	146
Searsport	146
Searsport Harbor	145
Seavey Island, St. George River	156, 163
Seavey Ledges	152
Seaville	107
Seavys Island, Portsmouth	213
Sebasco	190
Sebasco Harbor	190
Second Cliff	268
Sedgwick	114
Seguin Island	181
Seguin Island lighthouse	181
Seguin Ledges	181
Seguin SSW Ledge	181
Sesuit Harbor	276
Seven Hundred Acre Island	137
Seward Neck	57
Shabbit Island	72
Shabbit Island Ledge	72
Shabby Island	117
Shag Islet	77
Shag Ledge, Englishman Bay	68
Penobscot Bay	124
Shag Rock, Englishman Bay	69
Kennebec River	182
Rockland	141
Shag Rocks, Boston Harbor	243
Nahant	240
Shank Painter Bar	278
Sharps Rocks	206
Sheep Island	48, 72
Sheep Island Ledge	135
Sheep Porcupine Island	95
Sheepscot	178
Sheepscot River	175, 179
Sherman Cove	143
Ship and Barges Ledge	107
Ship Island	107
Shipstern Island	78
Shirley Gut	241
Shoppee Island	69
Shorey Cove	70
Signals for surveying vessels	27
Simons Gurnet	194
Sister Island, Blue Hill Bay	101
Casco Bay	196
Ledge	196
Sisters, The, St. George River	156
Sheepscot River	175
Skillings River	93
Small Point	189
Small Point Harbor	189
Smith Cove, Gloucester	227
Penobscot Bay	128
Smutty Nose Island, Eggemoggin Reach	113
Smuttynose Island, Isles of Shoals	216
Somes Harbor	98
Somes Sound	98
Somesville	98
Sorrento	92

Digitized by Google

	Page.
Sorrento Harbor	92
Sounding tubes, use of	17
South Bay	246
South Blue Hill	107
South Boston	246, 250
South Breaker, Matinicus Island	124
Whitehead	141
South Bristol	166
South Brooksville	114
South Bunker Ledge	97
South Channel, Kingston Bay	270
Marblehead	232, 238
South Deer Isle	117
South Freeport	196
South Gardiner	183
South Gooseberry	232
South Gouldsboro	91
South Hancock	94
South Harpswell	194
South Ledge, Blue Hill Bay	108
Casco Bay	192
South Portland	201
South River, New Inlet	269
Salem	234
South Sugar Loaf	181
South Thomaston	140
South Trescott	63
Southeast Breaker	126
Southeast Harbor, Deer Island	117
Gloucester	226
Southern Harbor	121
Southern Mark Island	119
Southern Mark Island Ledge	119
Southern Triangles	126
Southport	173
Southwest Harbor	96, 99
Southwest Harbor, Penobscot Bay	128
Sparrow Island	120
Spectacle Island, Boston Harbor	245
Winter Harbor	89
Spectacle Islands, Eggemoggin Reach	115
Sheepscot River	177
Spirit Ledge	112
Spoon Ledge	128
Sprague Ledge	139
Sprague River	180
Spring Hill Beach	275
Spring Point Ledge lighthouse	201
Spruce Island	137
Spruce Point	170
Sprucehead	140
Spurling Cove	97
Spurwink River	206
Squaw Point	146
Squirrel Cove	170
Squirrel Island	170
Stage Island	207
Stage Island Bay	181
Stage Island Harbor	208
Stage Island Shoal	207
Stage Neck	211
Standish Monument	271
Stanley Ledge	74
Staple Ledge	101
Star Island	217
Starboard Cove	65
Starboard Island	65
Starboard post office	65
Stave Island, Casco Bay	195
Frenchman Bay	90
Harbor	90
Ledge	195
Steel Harbor Island	73
Steel Ledge	145
Stellwagen Bank	39
Stellwagen Ledges	268
Stellwagen Rock, Manomet Point	274
Steuben	84
Steuben Harbor	84
Stevens Island	74
Stinson Neck	117
Stockman Island	195
Stockton Harbor	145
Stockton Springs	146
Stone Horse Rocks	274
Stone Island	65
Stone Island Ledge	65
Stonington	117
Storm-warning displays	30
Straitsmouth Island	225
Straitmouth lighthouse	225
Stratten Island	206
Strawberry Hill	267
Strout Island	77
Strout Island Ledges	77
Sturdivant Island	197
Sturdivant Island Ledge	197
Suboffices, Coast and Geodetic Survey	253, 285
Sugar Loaves	121
Sullivan	93
Sullivan Falls	93
Sullivan Harbor	92
Summer Harbor	91
Sunken Duck Rock	155
Sunken Ledge	263
Sunken Money Ledge	101
Supplies, see name of port and	27
Surry	109
Sutton	99
Sutton Island	99
Swampscott	239
Swan Island, Blue Hill Bay	101
Kennebec River	183
System of buoyage	24

T.

Tarbox Cove	178
Tarbox Landing	178
Taunton Bay	93
Temple Heights	144
Ten Pound Island	123
Tenants Harbor	152
Tenants Harbor lighthouse	153
Tenpound Island	227
Thatcher Island	226
Thieves Ledge	243
Thomaston	155, 157
Thompson Island	156
Thoroughfare, The	69
Thread of Life	165

Digitized by Google

	Page.
Thread of Life Ledges	165
Three Fathom Ledge	123
Thrumb Cap, Casco Bay	194
Thrumbcap, Flanders Bay	91
Frenchman Bay	96
Thrumbcap Island, Eggemoggin Reach	115
Thrumbcap Ledge, Johns Bay	165
Eggemoggin Reach	115
Thumper, The	97
Thurston Ledges	164
Tidal currents. *See* Currents.	
Tide tables	8, 34
Tides, see name of port and	33
Tillsons Wharf	142
Time ball	253
Time signals	31
Tinker Island, Blue Hill Bay	107
Tinker Ledges	114
Tinkers Island, Marblehead	233
Todd Bay	182
Tom Moores Rock	233
Tommy Island	78
Torry Islands	114
Towboats, see name of port and	25
Town River Bay	264
Townsend Gut	173
Trafton Island	78
Trafton Island Ledge	78
Treat Island	56
Trefethen	200
Triangle Ledges	134
Triangles, The, Blue Hill Harbor	108
Casco Passage	106
Trumpet Island	107
Truro	277
Tuckanuck Ledge	124
Tumbler Island	170
Turkey Cove	156
Turnip Island, Casco Bay	193
Johns Bay	165
Turtle Head	139
Turtle Head Cove	139
Turtle Island	89
Turtle Island Ledge	89
Two Bush Channel	139
Two Bush Island lighthouse	139
Two Bush Islands, Deer Island	119
Two Bush Islet, Eggemoggin Reach	115
Matinicus Island	125
Two Bush Ledge, Casco Bay	192
Penobscot Bay	125

U.

Ultonia Ledge	243
Union River	109
Union River Bay	109
United States Navy Yard, Boston	246
Portsmouth	213
Upper Barket Ledge	197
Upper Flag Island	194
Upper Goose Island	195
Upper Hell Gate	174
Upper Mark Island	177
Use of charts	7
Use of oil	16
Use of sounding tubes	17

V.

Variation of the compass	33
Verona Park	149
Vinal Haven	133
Vinal Haven Island	132

W.

Waldoboro	160
Wall Point	170
Wallace Cove	63
Wallis Sands	217
Warren	157
Warren Cove	274
Warren Island	137
Warren River	157
Washman Rock	208
Waterman Cove	120
Waterman Ledge	120
Watertown	247
Watts Cove	157
Weaver Ledge	104
Webb Cove	117
Webber Dry Ledge	160
Webhannet River	210
Webster Head	134
Weir River	264, 266
Wellfleet	276
Wellfleet Harbor	276
Wells	210
Wells Beach	210
Weskeag River	140
West Barge	107
West Branch, Kennebec River	183
West Brooksville	132
West Brown Cow	195
West Deer Isle	128
West Georgetown	182
West Gouldsboro	91
West Halibut Ledges	128
West Halibut Rock	119
West Hogshead Rock	267
West Penobscot Bay	142, 147
West Quoddy Head	47, 55
West Quoddy Head lighthouse	55
West River	72
West Shag Rock	267
West Southport	176
West Sullivan	93
West Tremont	104
West Trenton	105
West Willies	267
Western Bay, Blue Hill Bay	105
Great Wass Island	74
Western Black Ledge	124
Western Branch, Johns River	165
Western Channel, Cohasset	267
Western Ear	127
Western Ear Ledge	127
Western Egg Rock	74
Western Island	115
Western Passage, Gouldsboro Bay	84
Passamaquoddy Bay	58

Digitized by Google

	Page.
Western Reef	78
Western Way, Boston Harbor	263
Frenchman Bay	97
Westport	174
Westport Island	174
Weymouth	264
Weymouth, Back River	264, 265
Weymouth Fore River	264
Whale Ledge	79
Whale Rock	192
Whaleback	125
Whaleback lighthouse	212
Whaleboat Island	195
Whales Back, Kennebec River	181
Manchester	230
Wheaton Island	124
Wheeler Big Rock	126
Wheeler Point	223
Wheeler Rock	126
Wheelers Bay	152
White Bull	189
White Head, Boston Harbor	267
Portland Harbor	200
White Horse Beach	274
White Island, Isles of Shoals	217
White Islands, Boothbay Harbor	169
White Ledge	230
Whitehead Island	140
Whitehead lighthouse	140
Whitehead Passage	200
Whiting	57
Whitmore Cove	109
Whitmore Island	149
Whitmore Neck	117
Whittum Island	177
Widows Island	121
Wills Straits	193
Windmill Point	263
Winds	28
Winnegance	182
Winnegance Bay	190
Winnegance Creek	182
Winter Harbor Cove	90
Winter Harbor, Frenchman Bay	89
Lighthouse	89
Vinal Haven	128
Winterport	149
Winthrop	241
Winthrop Beach	246
Winthrop Head	241
Wire-drag surveys	22, 27
Wiscasset	178
Wollaston Channel	263
Wood End lighthouse	278
Wood Island, Casco Bay	189
Harbor	207
Kennebec River	181
Lighthouse	206
Saco Bay	206
Wooden Ball Island	123
Woolwich	183
Wormell Ledges	55
Wrecks, Coast of Maine	41
Portland to Cape Cod	44
Wyman	79
Y.	
Yarmouth	196
Yarmouth Island Ledges	192
Yarmouth River	196
Yarmouthport	275
Yellow Birch Head	83
Yellow Island	91
Yellow Ledge, Jericho Bay	103
Muscle Ridge Channel	141
Yellow Rock	192
York Beach	210
York Harbor	210
York Ledge	211
York Narrows	106
Z.	
Zephyr Ledges	125
Zephyr Rock	125

69358°—18——20

Digitized by Google

Digitized by Google

Digitized by Google

Digitized by Google

Digitized by Google

Digitized by Google

Digitized by Google

Digitized by Google

Digitized by Google

Digitized by Google

YC 62625


386029
U.S.
VK 981
A6
Sect.A
1918
UNIVERSITY OF CALIFORNIA LIBRARY



Digitized by Google

DEPARTMENT OF COMMERCE
UNITED STATES OF AMERICA